Total Maximum Daily Loads for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou

Contract No. 582-0-80121 Work Order No. 582-0-80121-01

Final Report

Prepared by
University of Houston
PBS&J
Principal Investigators
Hanadi Rifai
Paul Jensen

Prepared for

Total Maximum Daily Load Program
Texas Natural Resource Conservation Commission
P.O. Box 13087, MC - 150
Austin, Texas 78711-3087

TNRCC Contact

Andrew Sullivan TMDL Team P.O. Box 13087, MC - 150 Austin, Texas 78711-3087 asulliva@tnrcc,state.tx.us

TABLE OF CONTENTS

TABI	LE OF CONTENTS	ii
LIST	OF TABLES	v
LIST	OF FIGURES	vii
CHA	PTER 1 - INTRODUCTION	1
1.1	Problem Statement	1
1.2	Description of the Project	2
1.3	Description of the Report	4
1.4	Definitions	5
CHA	PTER 2 - ASSESSMENT OF CURRENT LEVELS AND TH	RENDS OF
	BACTERIA DATA IN BUFFALO AND WHITEOAK BAYOUS.	10
2.1	Review of Historical Indicator Bacteria Data	10
2.1.1	Data Compilation	11
2.1.2	Flow Conditions	13
2.1.3	Statistical Tests	17
2.1.4	Data Comparison Conclusions	20
2.1.5	Data on other Conventional Water Quality Parameters	21
2.2	Temporal Trends and Spatial Patterns	21
2.2.1	Temporal Trends	23
2.2.2	Spatial Patterns	45
2.2.3	Data Collected at Flows above Median	51
2.2.4	High vs Low Flow Data Analyses	78

82
ENT OF MAJOR SOURCES, TRANSPORT AND FATE BUFFALO AND WHITEOAK BAYOUS
.89
90
93
94
95
98
101
109
11(
117
118
126
130
142
144
146
147
153
153
159
163
172
1 7 3
1

4.1	Model Review174
4.2	Preliminary Recommendations
4.3	Modeling Activities182
CHAI	PTER 5 - MONITORING PLAN FOR ADDITIONAL DATA COLLECTION .186
5.1	Point Source Monitoring
5.2	Illicit Discharges
5.3	Runoff Event Monitoring
5.4	Concentration Dynamics in the Bayous
CHAI	PTER 6 - STAKEHOLDER/PUBLIC EDUCATION AND INVOLVEMENT208
6.1	Summary of Support Activities
6.2	Technical Presentations at Stakeholder Meetings
6.3	Response to Stakeholders' Comments/Questions
CHAI	PTER 7 - CONCLUSIONS216
REFE	RENCES
APPE	NDICES

LIST OF TABLES

Table	Title Pa	age
1.1	Pathogenic Organisms of Concern to Water Quality	6
1.2	Texas Standards for Fecal Pathogens	9
2.1	Percentages of FC Data Collected under Different Flow Conditions	16
2.2	Number of Samples at each Sampling Station	18
2.3	Statistical Comparison of Means and Variances between Data Sets	
	Collected by Different Agencies	19
2.4	Selected Parameters in Buffalo and Whiteoak Bayous	22
2.5	Statistical Test of Trends in Low Flow FC Data Since 1992	44
2.6	Statistical Comparison of Means between Datsets Collected during	
	The First and Second Half on the 90's	46
2.7	Coefficients of Variation of FC Data	54
2.8	1992 to 1999 FC Data Collected at Flow Above 90 th Percentile	56
2.9	Statistical Test of Trends in High Flow FC Data Since 1992	77
2.10	Statistical Comparison of Means between Data Sets with Different	
	High-flow Definition	80
2.11	Statistical Tests of Trends for Various Data Subsets	83
2.12	Statistical Comparison of Means between Data Sets for Dry and Wet Weather	86
2.13	Statistical Comparison of Means between Data Sets for Winter and Summer	88
3.1	Wastewater Dischargers in Study Area	122
3.2a	Dischargers to Buffalo and Whiteoak Bayous Reporting FC Data	123

Table	Title	Page
3.2b	Fecal Coliform Self-Reporting Data for Dischargers to Buffalo and	124
	Whiteoak Bayous	
3.3	Point Source Fecal Coliform Load Calculation	125
3.4	Health and Human Services Department Sewer Leak Reports in	132
	Watersheds	
3.5	Public Works and Engineering Department Sewer Leak Reports in	133
	Watersheds 1989 – 1996	
3.6	Fecal Coliform Load from Untreated Discharges	141
3.7	Wastewater Dischargers Upstream of Monitoring Points	145
3.8	Average Year Total Non-Point Source Loads	148
3.9	Stormwater Bacteria Data Collected for MS4 Permit	150
3.10	Sampling Locations for SSO Impact Study	151
3.11	SSO Stormwater Bacteria Data	152
3.12	High-Flow Data in Bayous Collected by USGS	154
4.1	Data Requirements for HSPF (NPSM in BASINS)	180
5.1	Monitoring Sites and Frequencies	190
5.2	Data Quality Objectives for Measurement Data	194

LIST OF FIGURES

Figure	Title	Page
2.1	Locations of Sampling Stations on Buffalo Bayou and Whiteoak Bayou	12
2.2	Cumulative Flow Frequency Curves for Buffalo Bayou at West Belt	15
2.3	Cumulative Flow Frequency Curves for Whiteoak Bayou at Heights Blvd.	15
2.4	Time Series of Buffalo Bayou FC Data at Flow < 100 cfs	24
2.5	Time Series of Whiteoak Bayou FC Data at Flow < 50 cfs	36
2.6	Geometric Means (+/- Standard Deviation) of 1992 to 1999 FC Data along	
	Buffalo Bayou (Flow less than 100 cfs)	47
2.7	Geometric Means (+/- Standard Deviation) of 1992 to 1999 FC Data along	
	Whiteoak Bayou (Flow less than 100 cfs)	48
2.8	FC Concentration of Buffalo Bayou in Intensive Survey of July 1985	50
2.9	FC Concentration of Whiteoak Bayou in Intensive Survey of Nov 1980	50
2.10	Geometric Means (+/- Standard Deviation) of 1992 to 1999 FC Data along	
	Buffalo Bayou (Flow greater than or equal 100 cfs)	52
2.11	Geometric Means (+/- Standard Deviation) of 1992 to 1999 FC Data along	
	Whiteoak Bayou (Flow greater than or equal to 50 cfs)	53

Figure	Title	Page
2.12	Time Series of Buffalo Bayou FC Data at High Flow (100 <q<1000)< td=""><td>57</td></q<1000)<>	57
2.13	Time Series of Whiteoak Bayou FC Data at High Flow (50 <q<300)< td=""><td>69</td></q<300)<>	69
2.14	Observed Trends in FC Data Series at Low and High Flows	79
3.1	Permitted Wastewater Dischargers Buffalo and Whiteoak Bayous	120
3.2	Effect of Point Sources on FC Levels in Buffalo Bayou	127
3.3	Effect of Point Sources on FC Levels in Whiteoak Bayou	128
3.4	Effluent and Mixing Zone k Values Plotted against BOD ₅	129
3.5	Reported Sewer Leaks Buffalo and Whiteoak Bayous	140
3.6	Unsewered Areas Buffalo and Whiteoak Bayous	143
3.7	Land Use Distribution Buffalo Watershed (GBNEP-15)	155
3.8	Land Use Distribution Whiteoak Watershed (GBNEP-15)	156
3.9	Land Use Distribution Addicks Reservoir Watershed (GBNEP-15)	157
3.10	Land Use Distribution Barker Reservoir Watershed (GBNEP-15)	158
3.11	Population Distribution in Buffalo and Whiteoak Watersheds	160
3.12	Distribution of Wastewater Dischargers by Subwatershed	161
	Buffalo and Whiteoak Bayous	
3.13	Contribution to FC Load by Source Type (Data from year 2000)	162
3.14	TMDL Curves for Buffalo Bayou	165
3.15	TMDL Curves for Whiteoak Bayou	169
4.1	Subwatersheds for Buffalo and Whiteoak Bayous	184

Figure	Title	Page
5.1	Monitoring Locations for Point Source Sampling	189
5.2	Pilot Areas for Illegal Discharges Monitoring	199
5.3	Sampling Locations for Runoff Monitoring	201
5.4	Monitoring Locations for Dynamics Testing	204
5.5	Monitoring Locations for Sediment Sampling	206

CHAPTER 1

INTRODUCTION

Microorganisms are always present in terrestrial and aquatic ecosystems. Most types are beneficial, aiding in the synthesis of some chemicals, as essential components of the nitrogen cycle and other biogeochemical cycles, and as food sources for larger animals. However, there is a small subset of microorganisms that is harmful to human health. These disease-causing organisms are known as pathogens (U. S. EPA, 2001).

Over 55% of all stream segments listed on the 2000 303(d) list for Texas are threatened or impaired due to high pathogen concentrations. Bacteria contamination of a water body is an issue of serious concern for water managers. High pathogen concentrations can impair water bodies for uses such as recreational, public water supply, and aquatic life and fishing (U. S. EPA, 2001).

Because of pathogens' small size, they can easily be carried by runoff or other discharges into natural waters. Once in a stream, pathogens can infect humans through water ingestion, skin contact or consumption of contaminated food.

1.1 PROBLEM STATEMENT

Section 303(d) of the Clean Water Act requires that states develop a listing of all stream segments that do not meet surface water quality standards for their designated uses. Surface water quality standards for Texas are defined in 30 Texas Administrative Code, Chapter 307. The two bayous that are the subject of this TMDL Study, Buffalo Bayou and Whiteoak Bayous, are designated for contact recreation.

The State of Texas has recently adopted new standards based upon *Escherichia coli* (*E. coli* or EC) rather than the previously employed fecal coliform indicator bacteria. Fecal coliform is an acceptable indicator until a baseline can be assessed with the *E. coli*. For fecal coliform, no sample should exceed 400 colony-forming units (cfu) per 100 mL for contact recreation. In addition, the geometric mean should be less than 200 cfu/100 mL to meet contact recreation criteria. For *E. coli*, no sample should exceed 394 cfu/ 100 mL and the geometric mean should be less than 126 cfu/100 mL (30 Texas Administrative Code 307.7(b)(A)).

1.2 DESCRIPTION OF THE PROJECT

Description of Study Area

Buffalo Bayou (segments 1013 and 1014) and Whiteoak Bayou (segment 1017) are both included on the 303(d) for pathogens. Buffalo Bayou meanders from the outlying, less-developed portions of Harris County joining Whiteoak Bayou in the highly urbanized central part of the Houston business district. All three segments (1013, 1014 and 1017) lie within the San Jacinto River Basin and eventually discharge to Galveston Bay. Segment 1013, Buffalo Bayou tidal watershed, has a drainage area of 7 square miles and the length of the segment is only 4 miles. Buffalo Bayou above tidal, segment 1014, is shorter in length (4 miles) but has a much larger watershed, a total of 358 square miles. The Whiteoak Bayou watershed has an area of 105 square miles and the stream segment is 23 miles long (H-GAC, 2001).

Scope of the Project

Segments 1013 and 1014 of Buffalo Bayou and Segment 1017 of Whiteoak Bayou in Houston, Texas are among the most fecal contaminated water bodies in Texas as indicated by the frequency and magnitude of exceedances of fecal coliform-based water quality criteria for contact recreation. This project will result in the completion of a Total Maximum Daily Load (TMDL) and load allocation analysis, which will be submitted to TNRCC for approval by the Commission. This total maximum daily load will address violations of water quality criteria for contact recreation in these Houston bayous.

The scope of the TMDL for Fecal Pathogens Project (hereafter called the Bacteria Project) encompasses an assessment of current fecal pathogen levels and trends in Buffalo Bayou and Whiteoak Bayou, an assessment of major sources, and fate and transport of fecal contamination in the environment, assessment of a transport model for the scope area, development of a quality assurance project plan for the project, collection of additional monitoring data, participation and support in stakeholder/public education and developing a total maximum daily load for bacteria in the affected area as well as an assessment of allocation scenarios for the implementation plan. The deliverable from the Bacteria Project is a final report that presents the maximum daily load as well as the various load allocation scenarios.

There are six main tasks in this project as follows:

- 1. Stakeholder/Public Education and Involvement
- Assess Current Levels and Trends of Bacterial Indicators of fecal
 Pathogens in Buffalo Bayou and Whiteoak Bayou

- Assess Major Sources, Transport and Fate of Bacterial Indicators of Fecal Contamination
- Apply Models to Elucidate the Sources and Major Processes Controlling
 Observed Levels of Bacterial Indicators of Bacterial Contamination
- 5. Develop a quality assurance project plan for additional data collection
- 6. Bi-Weekly Project Management Meetings

1.3 DESCRIPTION OF THE REPORT

This document constitutes the final report of the TMDL Bacteria Project for Work Order No. 582-0-80121-01 (Contract Number 582-0-80121) and summarizes the activities undertaken by the University of Houston and PBS&J during the period June 26, 2000 to June 30, 2001.

This report compiles the three quarterly reports submitted to TNRCC in compliance with the Work Order and reflects the changes made to respond to stakeholders' and TNRCC's comments. The topics in the report are organized according to the tasks specified in Work Order 582-0-80121-01.

Chapter 2 presents a summary of the reviewed historical indicator bacteria data in Buffalo Bayou and Whiteoak Bayou as well as an analysis of the spatial and temporal trends exhibited by the data.

Chapter 3 contains a summary of the literature pertaining to sources, fate, kinetics and indicators of fecal pathogens in water reviewed for the purposes of this project. An assessment of the sources of fecal coliforms in Buffalo and Whiteoak Bayous is also presented in this chapter.

An analysis of the existing numerical models as well as a description of modeling activities to simulate fecal coliform concentrations in Buffalo and Whiteoak Bayous is presented in Chapter 4 of this report.

Chapter 5 presents a monitoring plan for additional data collection in support of this TMDL and describes the quality assurance program plan for the sampling activities to be conducted starting on July 2001.

Chapter 6 summarizes the support activities conducted by the project team as part of the stakeholder involvement. This chapter includes the presentations given by members of the team at stakeholder meetings and a summary of questions and answers.

Finally, chapter 7 presents the conclusions obtained from the project activities conducted under Work Order No. 1.

1.4 **DEFINITIONS**

Pathogens: subset of microorganisms that are harmful to living organisms. They can cause diseases or even death when introduced into the body. Pathogens most commonly identified and associated with waterborne diseases are grouped into three general categories: bacteria, protozoans, and viruses (U. S. EPA, 2001). Table 1.1 lists potential waterborne disease-causing organisms and the diseases associated with them.

Indicator Organisms

Because the number of pathogens relative to other microorganisms in water can be very small and difficult to identify, indicator organisms are generally used to measure the quality of the water. The majority of the disease causing organisms found in water are associated with the deposition of human or animal waste in those waters. Consequently, indicator organisms must be easily sampled and measured nonpathogenic bacteria that

are usually associated with pathogens transmitted by fecal contamination so that their presence in water is an evidence of fecal contamination from warm-blooded animals.

Table 1.1 Pathogenic organisms of concern to water quality

Name of organism or group	Major disease	Major reservoirs and primary			
Bacteria		sources			
Salmonella typhi	Typhoid fever	Human feces			
Salmonella paratyphi	Paratyphoid fever	Human feces			
Other Salmonella	Salmonellosis	Human and animal feces			
Shigella	Bacillary dysentery	Human feces			
Vibrio cholerae	Cholera	Human feces			
Enteropathogenic E. coli	Gastroenteritis	Human feces			
Yersinia enterocolitica	Gastroenteritis	Human and animal feces			
Campylobacter jejuni	Gastroenteritis	Human and animal feces			
Legionella pneumophila and related bacteria	Acute respiratory illness (legionellosis)	Thermally enriched waters			
Mycobacterium tuberculosis	Tuberculosis	Human respiratory exudates			
Other (atypical) mycobacteria	Pulmonary illness	Soil and water			
Opportunistic bacteria	Variable	Natural waters			
Enteric viruses					
Enteroviruses					
Polioviruses	Polioyelitis	Human feces			
Coxsackieviruses A	Aseptic meningitis	Human feces			
Coxsackieviruses B	Aseptic meningitis	Human feces			
Echoviruses	Aseptic meningitis	Human feces			
Other enteroviruses	Encephalitis	Human feces			
Reoviruses	Mild upper respiratory and gastrointestinal illness	Human and animal feces			
Rotaviruses	Gastroenteritis	Human feces			
Adenoviruses	Upper respiratory and gastrointestinal illness	Human feces			
Hepatitis A virus	Infectious hepatitis	Human feces			
Norwalk and related GI viruses	Gastroenteritis	Human feces			
Protozoans					
Acathamoeba castellani	Amoebic meningoencephalitis	Soil and water			
Balatidium coli	Balantidosis (dysentery)	Human feces			
Cryptosporidium	Cryptosporidiosis	Human and animal feces			
Entamoeba histolytica	Amoebic dysentery	Human feces			
Giardia lambia	Giardiasis (gastroenteritis)	Human and animal feces			
Naegleria fowleri	Primary amoebic meningoencephalitis	Soil and water			

Source: (American Water Works Association, 1990)

For a microorganism (or group of microorganisms) to be an indicator organism, it should (AWWA, 1990): (i) be always present when the pathogen of concern is present,

and absent in uncontaminated water; (ii) be present in large numbers in fecal matter; (iii) have a response to environmental conditions that is similar to that of the pathogens of concern; (iv) be easy to isolate, identify, and enumerate; (v) be present in much larger numbers than the pathogen of interest; (vi) should come from the same source than the pathogens do.

A number of microorganisms have been evaluated as indicator organisms, including total coliforms, fecal coliforms, *E. coli*, fecal streptococci, enterococci, Heterothrophic plate count (HPC), *Pseudomonas aeruginosa*, and yeast.

Total Coliforms

This group of organisms is defined as all the aerobic and facultatively anaerobic, gram-negative, non-spore-forming, rod-shaped bacteria that are able to ferment lactose with gas formation (AWWA, 1990).

Fecal Coliforms

Fecal coliforms are a subset of total coliforms, which includes several species of coliform bacteria that are present in the intestines and feces of warm-blooded animals (U. S. EPA, 2001).

Escherichia coli (E. coli)

A subgroup of the fecal coliform bacteria. *E. coli* is part of the normal intestinal flora in humans and animals and is, therefore, a direct indicator of fecal contamination in a waterbody. The O157 strain, sometimes transmitted in contaminated waterbodies, can cause serious infection resulting in gastroenteritis (U. S. EPA, 2001).

Water Uses

Section 303(c) of the Clean Water Act lists the designated uses of a specific water body. These uses include recreation, domestic water supply, and aquatic life.

Recreational use consists of two categories: contact recreation and noncontact recreation waters. A segment is designated for contact recreation unless elevated concentrations of indicator bacteria occur due to sources of pollution that can not be reasonably controlled by existing regulations or contact recreation is considered unsafe for other reasons such as ship traffic (TNRCC, 2000). Table 1.2 includes the numerical criteria for fecal pathogens in recreational waters in Texas.

Domestic water supplies consist of two use categories: public water supply and aquifer protection. Segments designated for public water supply include those known to be used or have potential to be used as the supply source for public water systems. On the other hand, segments designated for aquifer protection are those that infiltrate into and recharge an aquifer. Table 1.2 shows the Texas standards for fecal pathogens in domestic water supplies.

Finally, a segment is designated aquatic life use when fish, shellfish, oyster, and mussels inhabiting the water body are fished to be consumed by humans. Table 1.2 includes the Texas numerical criteria for fecal pathogens in waters designated for aquatic use.

Table 1.2 Texas Standards for Fecal Pathogens

TYPE OF WATER	LIMIT
Recreation *	
Freshwater	
Contact	The geometric mean of <i>Escherichia coli</i> must be less than 126 colony forming units (cfu)/100 mL. A single sample should never exceed 394 cfu / 100 mL.
Noncontact	The geometric mean of <i>E. coli</i> must be less than 605 cfu / 100 mL.
Salt Water	
Contact	The geometric mean of <i>Enterococci</i> must be less than 35 cfu / 100 mL. A single <i>Enterococci</i> sample should never exceed 89 cfu / 100 mL.
Noncontact	The geometric mean of <i>Enterococci</i> must be less than 168 cfu / 100 mL.
Domestic Water Supply	
Public Water Supply	For public water supplies collecting less than 40 bacteriological samples per month (cities less than 41,000), must have less than the MCL of 5.0% positive total coliform samples. For systems collecting more than 40 bacteriological samples per month, the MCL is one positive total coliform sample per month. **
Aquatic Life	There are five designations: limited, intermediate, high, and exceptional aquatic life and oyster waters. Of these designations, only oyster waters have a specific pathogen requirement. Pathogen requirements for the other designations are applied in a site-specific manner according to the 30 TAC §307.10. Appendices A. In general, the contact and non-contact recreation limits are applied. *
Oyster Water	The median fecal coliform concentration must not be above 14 cfu / 100 mL, with no more than 10% of all samples exceeding 43 cfu / 100 mL.

^{* 30} Texas Administrative Code (TAC) ' 307.7(b) **30 TAC ' 290.109

CHAPTER 2

ASSESSMENT OF CURRENT LEVELS AND TRENDS OF BACTERIA DATA IN BUFFALO AND WHITEOAK BAYOUS

2.1 REVIEW OF HISTORICAL INDICATOR BACTERIA DATA

This section describes the analysis of historical monitoring data performed as a component of the total maximum daily load (TMDL) study for fecal coliform (FC) for Buffalo Bayou and Whiteoak Bayou. The analysis focused on data collected by four major sources – the Texas Natural Resource Conservation Commission (TNRCC), the U. S. Geological Survey (USGS), the City of Houston Health and Human Services Department (H&HS), and the City of Houston Public Works and Engineering Department (PW&E). Other bacteria data have probably been collected in these bayous. However, the four listed agencies are the major sources that have performed continuous monitoring of the bayous.

An evaluation was first conducted to determine if there is any significant difference between data collected by the different agencies. This evaluation is important in deciding whether the data could be combined for analysis or they should be treated separately. Then the data were analyzed for temporal trends and spatial patterns. Analyses were also performed on the effect of flow. While the main emphasis was on bacteria data, other water quality parameters were tabulated.

2.1.1 Data Compilation


A total of five sets of FC bacteria data were obtained. Two of these five sets were downloaded from the web site of the Houston-Galveston Area Council (H-GAC). One of the H-GAC data sets is described as San Jacinto River Basin data. This is TNRCC and USGS data from 1992 through 1999. The other set is described as local monitoring data. The period for the local data is 1997 through 1999. The third set of data was downloaded from the TNRCC web site and consists of data from 1993 to 1999 from all sources.

In addition, the H&HS had supplied their bayou monitoring data from 1995 to 1998 to H-GAC. The H-GAC then made these data available to the project. The last set of data is PW&E data from 1983 to 1996 compiled by PBS&J in a previous study supplemented with 1997 data retrieved during this project.

As would be expected, there are overlaps of records among these five data sets. The duplicates were first identified and removed and the data were sorted according to the source agency, i.e. TNRCC, USGS, H&HS and PW&E. Figure 2.1 shows the locations of the sampling stations. It is noted that there are more TNRCC sampling stations in the two watersheds than those shown in Figure 2.1. Some are upstream of Barker Dam. However, the figure only shows stations with FC data in the databases described above.

The data collected from tributaries of the two bayous are mainly from H&HS. Therefore, when performing the comparison of data sources, only data from the main stems were considered.

The compiled database can be found in Appendix A of this report (electronic version). Table A.1 in Appendix A summarizes the data. It can be seen in Figure 2.1 that



data were collected from 20 locations in the Buffalo Bayou and from 17 locations in Whiteoak Bayou. Fecal coliform concentrations in Buffalo Bayou range between 1 and 250,000 cfu/100 mL, with geometric means between 607 and 9,374 cfu/100 mL. On the other hand, concentrations in Whiteoak Bayou are within the range 9-1,000,000 cfu/100 mL and the geometric means vary between 4 and 11,387 cfu/100 mL. In general, Whiteoak Bayou is more contaminated than Buffalo Bayou as indicated by an average geometric mean of fecal coliform concentration of 3,701 cfu/mL compared to 2,568 cfu/100 mL for Buffalo Bayou.

2.1.2 Flow Conditions

Because runoff can carry high FC levels from non-point sources, flow conditions under which samples were collected were considered in the comparison between data sets. There are three USGS flow gages on Buffalo Bayou with relatively complete flow records. These gages are located at Dairy Ashford Road (USGS Station 08073500), West Belt Drive (USGS Station 08073600) and Piney Point Road (USGS Station 08073700). The gages are not located far apart and their flow records have essentially the same flow patterns. The record at West Belt Drive was used since it is complete for the period that bacteria data are available. There are two USGS gages on Whiteoak Bayou, one at Alabonson Road (USGS Station 08074020) and the other at Heights Blvd (USGS Station 08074500). The gage at Alabonson Road appears to be defective since its record shows a consistent base flow of about 400 cfs. Therefore the record at Heights Blvd was used. This record is also complete for the period that bacteria data are available. The gages are shown in Figure 2.1.

Figures 2.2 and 2.3 show the cumulative flow frequency curves for Buffalo Bayou at West Belt and Whiteoak Bayou at Heights Blvd respectively. In each figure, the curve for the complete period of bacteria data (1983 to 1999) and the curves for the earlier half and latter half of the period are shown. The flow regime for Whiteoak Bayou appears to be the same for the whole period whereas some changes appear to have occurred in the flow regime for Buffalo Bayou at higher flows.

To facilitate data analysis, flow screening levels were defined for each bayou. Screening levels selected for Buffalo Bayou are 100 cfs and 1000 cfs and those for Whiteoak Bayou are 50 cfs and 300 cfs. It can be seen from Figures 2.2 and 2.3 that for each bayou, the lower screening level corresponds to approximately the median of the flow data and the higher level corresponds to approximately the 90th percentile of non-exceedance.

Table 2.1 shows the percentages of FC data remaining after data sampled at flows above the selected values have been screened out. The percentages of data remaining after screening are shown for the whole period of data record for the various collection agencies as well as for the recent period starting from 1995. The year 1995 was chosen because the H&HS data set starts from 1995.

The USGS has contributed a relatively small amount of data, a total of only 45 samples for the two bayous. Over half of the samples were collected before 1995 and appear to be predominantly wet weather samples. The percentages of H&HS data remaining after screening match roughly with the percentiles of the flow screening levels. This observation indicates that the H&HS sampling program followed a regular pattern and that weather conditions were not a consideration in the decision to sample. On the




TABLE 2.1
PERCENTAGES OF FC DATA COLLECTED UNDER DIFFERENT FLOW CONDITIONS

			All data		Data since 1995						
	PW&E	H&HS	USGS	TNRCC	TOTAL	PW&E	H&HS	USGS	TNRCC	TOTAL	
Buffalo Bayou											
Period of data	'83-'99	'95-'99	'93-'98	'92-'99	83-'99	'95-'99	'95-'99	'95-'98	'95-'99	'95-'99	
Total number of samples	2655	770	24	84	3533	990	770	6	51	1817	
Data with flow < 1000 cfs	91.1%	87.1%	91.7%	84.5%	90.1%	92.0%	87.1%	100.0%	92.2%	90.0%	
Data with flow < 100 cfs	54.5%	48.6%	12.5%	57.1%	53.0%	63.3%	48.6%	50.0%	82.4%	57.6%	
White Oak Bayou											
Period of data	'88-'99	'95-'99	'92-'98	'92-'99	'88-'99	'95-'99	'95-'99	'95-'98	'95-'99	'95-'99	
Total number of samples	1143	151	21	51	1366	436	151	12	30	629	
Data with flow < 300 cfs	94.8%	90.7%	85.7%	86.3%	93.9%	94.7%	90.7%	75.0%	96.7%	93.5%	
Data with flow < 50 cfs	59.9%	53.0%	38.1%	60.8%	58.9%	68.3%	53.0%	50.0%	73.3%	64.5%	

USGS gauges:

08073600 Buffalo Bayou at West Belt

08074500 White Oak Bayou at Heights Blvd

other hand, all the PW&E and TNRCC data in the more recent period (1995 to 1999) appear to be geared toward dry weather sampling. For example, the TNRCC data from '92-'99 has a markedly lower percentage of data collected below the median flow than the data from '95-'99. It appears that there has been a greater emphasis by TNRCC on dry weather sampling of bacteria levels in recent years, while PW&E has maintained this emphasis in all its monitoring.

2.1.3 Statistical Tests

Table 2.2 shows the number of samples at each station. The stations with a significant amount of data from more than one collection agency were identified and are highlighted in Figure 2.1. Statistical tests for comparing means and variances between data sets collected by different agencies were performed and the results are listed in Table 2.3. In a few cases, data from two nearby stations were used for the tests if there were no large data sets to compare at exactly the same station.

The tests were performed on the geometric means of the data, i.e. comparison was made using the mean of the log data and the variance of the log data. For the statistical tests the null hypothesis is that there is no significant difference between the means or the variances of the log data. The level of confidence selected was 95%. The 1997 PW&E data were not available at the time of the tests, therefore, whenever the PW&E data were involved, the comparison was made separately for pre-1997 data and post-1997 data.

For the Whiteoak Bayou data in Table 2.3, the null hypotheses of equal mean and equal variance are accepted in all tests for data collected at low flow. For the Buffalo Bayou data, the null hypotheses are accepted in most of the tests for data collected at low flow. However, including data collected at higher flow in the right portion of the table

TABLE 2.2
NUMBER OF SAMPLES AT EACH SAMPLING STATION

St	ation ID	Location	Total	Num	ber of s	amples	from		Start	date		End date			
		(from upstream to downstream)	number	ir	ndividua	l agency	/								
		,	of samples	TNRCC	USGS	H&HS	PW&E	TNRCC	USGS	H&HS	PW&E	TNRCC	USGS	H&HS	PW&E
	11142	Barker Dam	269			132	137			01/04/95	07/21/87			12/31/98	12/05/96
	11364	SH 6	198			30	168			02/01/99	02/24/86			06/29/99	09/27/99
	11363	Eldridge Rd	71				71				04/26/94				09/27/99
	11362	Dairy Ashford Rd	229	33			196	02/06/92			01/19/83	05/05/99			09/27/99
В	11361	Wilcrest Dr	71				71				03/23/83				09/27/99
U	11360	West Belt	349		2	152	195		08/03/98	01/04/95	01/19/83		08/22/98	06/29/99	09/27/99
F	11359	Gessner Dr	159				159				03/23/83				09/27/99
F	15846	Briar Forest Ave	181				181				02/28/85				09/27/99
Α	11358	Piney Point Rd	11	11				02/08/94				08/06/96			
L	11357	San Felipe St	186				186				01/19/83				09/27/99
0	11356	Voss Rd	154			154				01/04/95				06/29/99	
	15845	Chimney Rock Rd	168				168				04/11/83				09/27/99
В	11354	Woodway Dr	191	4			187	11/19/92			03/23/83	08/16/93			09/27/99
Α	11353	IH 610	123				123				03/06/89				09/27/99
Υ	15844	Westcott Ave	124				124				01/19/83				12/16/98
0	11351	Shepherd Dr	451	3	20	153	275	02/24/92	05/05/93	01/04/95	01/19/83	08/03/92	08/22/98	06/29/99	09/27/99
U	15843	Sabine Ave	199				199				01/19/83				09/27/99
	11347	Main St	149			149				01/04/95				06/29/99	
	15842	San Jacinto Ave	98				98				10/11/83				09/27/96
	11345	McKee St	152	33	2		117	02/24/92	08/03/98		01/19/83	08/03/99	08/22/98		09/27/99
	15841	Jensen Dr	163				163				01/19/93				11/03/97
	15840	Turning Basin	115				115				01/19/93				11/03/97
		Total	3533	84	24	770	2655								
	11398	Jones Rd	17	17				02/06/92				08/07/96			
W	15831	W. Tidwell Ave	95				95				12/20/89				09/15/99
Н	15830	Watonga	96				96				12/20/89				09/15/99
1	15829	W. 43rd St	86				86				12/20/89				09/02/98
Т	16637	W. T C Jester Ave (nr W. 34th St)	10				10				02/13/98				09/15/99
Е	11390	W. 34th St	96				96				12/20/89				09/15/99
	11391	Ella Blvd	91				91				12/20/89				09/15/99
0	15828	W. T C Jester Ave (nr W. 12th St)	71				71				12/20/89				05/07/97
Α	15827	N. Durham St	101				101				12/20/89				12/05/96
K	11387	Heights Blvd	203	31	21	151		11/19/92	02/26/92	02/03/95		08/03/99	08/11/98	06/29/99	
	15826	Studemont Ave	111				111				12/20/89				09/21/99
В	11388	Houston Ave	3	3				02/24/92				08/03/92			
Α	11385	Wrightwood St	79				79				08/07/90				05/07/97
Υ	15825	Crocket Ave	77				77				12/20/89				09/15/99
0	15824	Girard Ave	210				210				07/07/88				11/03/97
U	16647	S. Pacific RR Crossing	17				17				02/04/98				09/15/99
	16646	Confluence with Buffalo Bayou	3				3				02/13/98				09/02/98
		Total	1366	51	21	151	1143								

TABLE 2.3
STATISTICAL COMPARISON OF MEANS AND VARIANCES BETWEEN DATA SETS COLLECTED BY DIFFERENT AGENCIES

Station	Source Flow		Flow <	< 100 cfs for Buffalo Bayou or flow < 50 cfs for White Oak Bayou						Flow < 1000 cfs for Buffalo Bayou or flow < 300 cfs for White Oak Bayou										
	of data		Period Number of		Data set 1		Data set 2		Null hy	oothesis	Period	Number of		Data set 1		Data set 2		Null hypothesis		
	1	2		sam	ples	Geom	Stdev	Geom	Stdev	Same	Same		sam	ples	Geom	Stdev	Geom	Stdev	Same	Same
				1	2	Mean	(log)	Mean	(log)	mean	variance		1	2	Mean	(log)	Mean	(log)	mean	variance
BU 11142	H&HS	PW&E	05/95 - 12/96	36	11	345	0.42	2,138	0.93	Reject	Reject	01/95 - 12/96	61	19	792	0.78	1,547	0.84	Accept	Accept
BU 11362	TNRCC	PW&E	07/93 - 12/96	9	35	1,410	0.69	1,698	0.63	Accept	Accept	05/92 - 12/96	16	55	1,671	0.81	1,542	0.60	Accept	Accept
BU 11362	TNRCC	PW&E	02/98 - 09/99	8	13	640	0.39	1,072	0.69	Accept	Accept	02/98 - 09/99	9	16	686	0.38	1,509	0.72	* (Note 7)	Reject
BU 11360	H&HS	PW&E	01/95 - 12/96	35	19	2,001	0.75	2,249	0.65	Accept	Accept	01/95 - 12/96	57	29	2,833	0.81	1,698	0.76	Accept	Accept
BU 11360	H&HS	PW&E	02/98 - 09/99	30	13	2,745	0.66	1,153	0.33	Reject	Reject	01/98 - 09/99	46	16	3,709	0.69	1,632	0.50	Reject	Accept
BU 11356 & 11357	H&HS	PW&E	02/95 - 12/96	37	21	1,681	0.68	1,558	0.52	Accept	Accept	01/95 - 12/96	60	30	2,974	0.80	1,830	0.56	Accept	Reject
BU 11356 & 11357	H&HS	PW&E	02/98 - 09/99	28	13	2,514	0.70	816	0.54	Reject	Accept	01/98 - 09/99	43	16	3,312	0.73	1,254	0.64	Reject	Accept
BU 11351	H&HS	PW&E	02/95 - 12/96	40	36	3,928	0.70	2,869	0.63	Accept	Accept	01/95 - 12/96	62	51	5,014	0.69	2,617	0.63	Reject	Accept
BU 11351	H&HS	PW&E	02/98 - 06/99	25	24	3,845	0.56	2,191	0.70	Accept	Accept	01/98 - 06/99	39	31	4,244	0.56	1,974	0.70	Reject	Accept
BU 11347 & 15843	H&HS	PW&E	02/95 - 12/96	38	22	5,416	0.59	3,624	0.58	Accept	Accept	01/95 - 12/96	61	32	9,176	0.67	3,418	0.57	Reject	Accept
BU 11347 & 15843	H&HS	PW&E	02/98 - 09/99	23	13	3,760	0.56	3,718	0.74	Accept	Accept	01/98 - 09/99	36	16	4,642	0.53	4,295	0.72	Accept	Accept
BU 11345	TNRCC	PW&E	06/93 - 12/96	9	43	7,164	0.63	3,035	0.68	Accept	Accept	06/92 - 12/96	16	64	11,411	0.57	3,338	0.62	Reject	Accept
BU 11345	TNRCC	PW&E	03/98 - 09/99	9	12	1,271	0.71	3,004	0.78	Accept	Accept	02/98 - 09/99	10	15	1,316	0.67	4,279	0.79	Accept	Accept
WO 11387 & 15826	H&HS	PW&E	02/95 - 12/96	26	15	4,718	0.67	6,067	0.66	Accept	Accept	02/95 - 12/96	38	22	6,188	0.71	6,521	0.77	Accept	Accept
WO 11387 & 15826	H&HS	PW&E	01/98 - 09/99	31	17	4,781	0.51	3,422	0.57	Accept	Accept	01/98 - 09/99	50	25	5,606	0.62	2,842	0.57	Reject	Accept
WO 11387 & 15826	TNRCC	USGS	02/93 - 11/98	17	8	3,992	0.67	1,842	0.41	Accept	Accept	02/93 - 11/98	25	15	6,578	0.68	2,617	0.36	Reject	Reject
WO 11387 & 15826	H&HS	TNRCC	02/95 - 08/99	80	16	3,925	0.60	3,406	0.71	Accept	Accept	02/95 - 08/99	137	22	5,164	0.64	5,568	0.73	Accept	Accept
WO 11387 & 15826	H&HS	USGS	02/95 - 08/98	70	6	3,996	0.63	2,040	0.43	Accept	Accept	02/95 - 08/98	119	9	5,345	0.66	2,399	0.39	Reject	Accept

Notes

- 1. When comparing means, the null hypothesis is that the means of the two data sets are equal. When comparing variances, the null hypothesis is that the variances of the two data sets are equal.
- 2. Null hypothesis is tested at the 95% confidence level.
- 3. Reference: Statistical Analysis for Engineers by J. Wesley Barnes, 1988.
- 4. A general assumption is that the data are log normally distributed. However, when the total number of data of the two data sets minus two is greater than 30, the normality assumption is not necessary for tests comparing two means (Barnes, 1988).
- 5. When the total number of data of the two data sets minus two is less than 30, the test comparing two means requires the assumption of equal variance, a pooled estimate of the variance of the two data sets combined and the t-distribution are used; otherwise, estimate for the standard deviation of each data set is made and the normal distribution is used.
- 6. The test for equal variance employs the F-statistic.
- 7. * In this case, the test requires equal variance. Since the null hypothesis for equal variance is rejected, the test comparing means is not performed.
- 8. Locations of stations:

08074500

11142	Buffalo Bayou at Barker Dam
11362	Buffalo Bayou at Dairy Ashford Road
11360	Buffalo Bayou at West Belt
11357	Buffalo Bayou at San Felipe Street
11356	Buffalo Bayou at Voss Road
11351	Buffalo Bayou Tidal at Shepherd Drive
15843	Buffalo Bayou Tidal at Sabine Avenue
11347	Buffalo Bayou Tidal at Main Street
11345	Buffalo Bayou Tidal at Mckee Street
11387	White Oak Bayou at Heights Blvd
15826	White Oak Bayou at Studemont Avenue
9. USGS gauges:	•
08073600	Buffalo Bayou at West Belt

White Oak Bayou at Heights Blvd

causes rejection of the null hypothesis in many more cases. This observation is apparently related to the above discussion that the collection agencies have different sampling strategies with respect to weather conditions. This result also reflects the nature of wet weather samples where higher variability can be expected.

2.1.4 Data Comparison Conclusions

If data obtained under all flow conditions are included in the analysis, there appears to be significant differences between data sets. Considering data collected at flows less than the 90th percentile which eliminates the largest flow events, the null hypothesis is rejected in 9 out of 17 data set comparisons for the means. For low flow data (i.e. days where the daily average flow at selected gages was below the median value), there does not appear to be statistically significant differences between data sets collected by different agencies. There are a few cases where the null hypotheses of equal mean and/or equal variance have been rejected. Nevertheless, such apparent differences might well be caused by the inherently high variability of bacteria data and the fact that a relatively small amount of data is being considered.

Based on this analysis, it would appear that data from all agencies could be grouped so long as the data are first screened to eliminate data at higher flow where runoff is more likely to be a factor. Even then care will need to be taken to assure proper comparisons because at least one agency, the TNRCC, appears to have changed monitoring strategies in recent years.

2.1.5 Data on other Conventional Water Quality Parameters

To give a general characterization of the water quality in the two bayous, Table 2.4 lists the statistics of selected conventional parameters at a downstream station of each bayou. These two stations have been more frequently sampled and the parameters listed are those with larger amount of data. The mean values of the parameters appear to be within typical ranges.

A few points are worth noting in the data for the two bayous. The first is that the Buffalo Bayou conductivity is markedly lower than that for Whiteoak Bayou. The difference in dissolved oxygen is substantial probably reflecting the physical differences, with Buffalo being a natural channel and Whiteoak being concrete lined in this reach. The difference between the BOD and CBOD data in Buffalo Bayou is roughly what would be expected. The overall BOD levels are influenced by the 4 mg/L reporting limit for the H&HS data. Many of these values were "<" results. The differences in TSS results, with Buffalo over twice as high as Whiteoak, may also reflect the differences in the channel bottom. Both bayous have low ammonia-N levels reflecting an overall high level of wastewater treatment.

2.2 TEMPORAL TRENDS AND SPATIAL PATTERNS

This section analyzes the data obtained at lower flows to evaluate temporal trends and spatial patterns.

TABLE 2.4
SELECTED PARAMETERS IN BUFFALO AND WHITE OAK BAYOUS

Parameter	Unit	Number of	Start date	End date	Mean	Standard					
		data	of data	of data		Deviation					
Station 11351, Buffalo Bayou at Shepherd Dr, River Km 7.0											
Conductivity	μmhos/cm	149	09/04/83	06/29/99	522	444					
Dissolved Oxygen	mg/L	443	01/19/83	09/27/99	6.50	1.57					
BOD ₅ ¹	mg/L	186	07/30/85	09/27/99	4.36	1.66					
CBOD ₅	mg/L	169	01/19/83	02/15/99	3.55	2.74					
TSS	mg/L	245	07/30/85	06/29/99	84.6	104.9					
NH ₃ -N	mg/L	342	01/19/83	09/27/99	0.29	0.53					
SO ₄	mg/L	173	02/24/92	06/29/99	20.3	11.6					
Station 11387, White Oak Bayou at Heights Blvd, River Km 5.2											
Conductivity	μmhos/cm	165	11/19/92	11/09/99	678	252					
Dissolved Oxygen	mg/L	234	02/26/92	11/09/99	12.41	3.50					
BOD ₅ ¹	mg/L	184	02/26/92	06/29/99	4.69	4.42					
TSS	mg/L	232	02/26/92	08/03/99	38.1	83.3					
NH ₃ -N ²	mg/L	187	02/26/92	08/03/99	0.27	0.39					
SO ₄ ²	mg/L	232	02/26/92	08/03/99	32.2	29.3					

¹ H&HS, which has contributed significantly to this data set, has a detection limit of 4 mg/L for BOD₅

 $^{^2}$ Two samples on 3/3/97 have unusually high values of NH₃-N (> 40 mg/L) and SO₄ (> 600 mg/L). These high values are excluded.

³ There are no data for CBOD₅ at Station 11387.

2.2.1 Temporal Trends

Figures 2.4 and 2.5 show time series plots of FC data for each station on Buffalo Bayou and Whiteoak Bayou respectively. The data shown are samples from all agencies collected at low flow, i.e. below 100 cfs for Buffalo Bayou and below 50 cfs for Whiteoak Bayou. As mentioned in Section 2.1, the reference USGS flow gages are the gage at West Belt for Buffalo Bayou and the gage at Heights Blvd for Whiteoak Bayou. On the plots, different symbols are used to distinguish between samples collected by different agencies. For the tributaries, the data of all except two of the stations are from 1997 to 1999. Since tributary data are generally available only for a few recent years, the analysis of temporal trends was focused on the main stems.

In general, there do not appear to be significant data gaps in the plots. As is common in water quality data and especially for data sets that are combinations of data collected from different monitoring programs, the density of data varies somewhat throughout the period of record. Some of the data were obtained from monitoring programs that roughly sampled once a month while some data are 5-times-in-30-days samples. Moreover, some stations have been sampled more often than others. There are some stations with very few samples.

Trend Analysis for 1992-1999 Data


At a number of stations on both Buffalo Bayou and Whiteoak Bayou, some of the PW&E data from late 1980s to 1991 have very low values. There are also high FC values during the same period. The low FC values are likely due to high chlorine residuals in

FIGURE 2.4

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS

STN 11142 - BARKER DAM, KM 45.3



STN 11142 - BELOW BARKER DAM, KM 45.1





FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS

STN 11364 - SH 6, KM 45.0







FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS

STN 11362 - DAIRY ASHFORD RD, KM 40.2



STN 11361 - WILCREST DR, KM 36.7





FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS











FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS

STN 15846 - BRIAR FOREST AVE, KM 29.7









FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS

STN 11357 - SAN FELIPE ST, KM 25.3



STN 11356 -VOSS RD, KM 23.5





FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS











FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS











FIGURE 2.4 (CONTINUED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS









FIGURE 2.4 (CONTINUED) TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS • H&HS × PW&E ■ TNRCC • USGS

STN 11347 -MAIN ST, KM 1.7








FIGURE 2.4 (CONCLUDED)

TIME SERIES OF BUFFALO BAYOU FC DATA AT FLOW < 100 CFS

• H&HS × PW&E ■ TNRCC • USGS






FIGURE 2.5

TIME SERIES OF WHITE OAK BAYOU FC DATA AT FLOW < 50 CFS


○ H&HS × PW&E ■ TNRCC + USGS


STN 11398 - JONES RD, KM 35.3







STN 15830 - WATONGA, KM 15.4







STN 16637 - W. T C JESTER AVE, KM 12.7







STN 11391 - ELLA BLVD, KM 10.5






STN 15827 - N. DURHAM ST, KM 7.0







STN 15826 - STUDEMONT AVE, KM 4.1







STN 15825 - CROCKET AVE, KM 1.4









FIGURE 2.5 (CONCLUDED) TIME SERIES OF WHITE OAK BAYOU FC DATA AT FLOW < 50 CFS

o H&HS x PW&E ■ TNRCC **LUSGS**









the effluent prior to the time when dechlorination had become a common practice in the wastewater treatment process. The presence of these low values complicates the trend analysis. Therefore, trend analysis was performed on the data since 1992, excluding the earlier data with the low FC values.

The major effort of upgrading the sewer system through the Greater Houston Wastewater Program (GHWP) was completed in 1997. The major effort towards the end of the GHWP dealt with capacity to handle high flow conditions and minimize wet weather overflows. Work on the sewer system correcting dry weather overflows occurred very early and was substantially complete by 1990. If there were a change in bacteria levels resulting from this work, it should be present in the data before 1990.

A visual examination of the time series plots indicates that for most of the stations, there does not appear to be a trend in the data since 1992. Statistical testing was performed to confirm this visual observation. The results are shown in Table 2.5. The null hypothesis of zero slope in the temporal trend is rejected at the 95% confidence level at five stations on Buffalo Bayou and two stations on Whiteoak Bayou. The slopes of the data at these stations are all negative, indicating that bacteria levels have been decreasing over time. For most of the stations, the slope was negative but the null hypothesis could not be rejected, indicating that the change in bacteria levels has not been strong in the last decade. This may be a reasonable result. Most of the improvements to the collection system that would be a factor at lower flows were completed by the early 1990s. With these two bayous there may have been no major changes in the period from 1992 to 1999.

TABLE 2.5 STATISTICAL TESTS OF TRENDS IN LOW FLOW FC DATA SINCE 1992

Station ID	Location	River km	Num of data	Start date	End date	Slope ²	P-value 3	Null hypothesis 4
Buffalo Ba								
11142	Barker Dam	45.3	85	07/06/92	12/31/98	-0.00018	0.1486	Accept
11142	Below Barker Dam	45.1	20	10/05/93	12/05/96	0.00003	0.9204	Accept
11364	SH 6	45.0	71	07/06/92	09/27/99	-0.00011	0.2015	Accept
11363	Eldridge Rd	42.4	45	04/26/94	09/27/99	-0.00006	0.6330	Accept
11362	Dairy Ashford Rd	40.2	76	07/06/92	09/27/99	-0.00021	0.0459	Reject
11361	Wilcrest Dr	36.7	43	04/26/94	09/27/99	-0.00006	0.6711	Accept
11360	West Belt	34.6	127	07/06/92	09/27/99	-0.00005	0.5989	Accept
11359	Gessner Dr	31.5	54	07/06/92	09/27/99	-0.00022	0.0271	Reject
15846	Briar Forest Ave	29.7	56	07/06/92	09/27/99	-0.00028	0.0033	Reject
11358	Piney Point Rd	28.9	7	02/08/94	08/06/96	-0.00054	0.5668	Accept
11357	San Felipe St	25.3	53	09/22/92	09/27/99	-0.00015	0.1694	Accept
11356	Voss Rd	23.5	73	02/09/95	06/17/99	0.00014	0.4771	Accept
15845	Chimney Rock Rd	18.2	57	07/06/92	09/27/99	-0.00033	0.0024	Reject
11354	Woodway Dr	15.7	55	07/06/92	09/27/99	-0.00017	0.1268	Accept
11353	IH 610	14.2	55	07/06/92	09/27/99	-0.00004	0.6732	Accept
15844	Westcott Ave	8.7	37	09/22/92	07/13/98	-0.00005	0.8289	Accept
11351	Shepherd Dr	7.0	184	07/06/92	09/27/99	0.00000	0.9694	Accept
15843	Sabine Ave	3.8	56	07/06/92	09/27/99	0.00002	0.8297	Accept
11347	Main St	1.7	72	02/09/95	06/17/99	-0.00012	0.4424	Accept
15842	San Jacinto Ave	1.5	8	03/30/94	06/05/96	0.00015	0.8303	Accept
11345	McKee St	0.6	84	07/06/92	09/27/99	-0.00026	0.0197	Reject
White Oak	k Bayou							
11398	Jones Rd	35.3	11	11/17/92	08/07/96	0.00038	0.3706	Accept
15831	W. Tidwell Ave	16.5	44	06/18/92	09/15/99	-0.00007	0.4692	Accept
15830	Watonga	15.4	45	06/18/92	09/15/99	-0.00010	0.4523	Accept
15829	W. 43rd St	14.9	38	06/18/92	09/02/98	0.00014	0.3236	Accept
16637	W. T C Jester Ave (nr W. 34th St)	12.7	8	02/13/98	09/15/99	-0.00031	0.7887	Accept
11390	W. 34th St	12.5	47	07/07/92	09/15/99	-0.00007	0.4887	Accept
11391	Ella Blvd	10.5	41	06/18/92	09/15/99	-0.00001	0.9624	Accept
15828	W. T C Jester Ave (nr W. 12th St)	8.5	28	06/18/92	05/07/97	0.00012	0.4648	Accept
15827	N. Durham St	7.0	48	06/18/92	12/05/96	0.00018	0.3611	Accept
11387	Heights Blvd	5.2	108	02/08/93	08/03/99	-0.00002	0.8531	Accept
15826	Studemont Ave	4.1	53	06/18/92	09/21/99	-0.00001	0.9055	Accept
11385	Wrightwood St	2.0	35	06/18/92	05/07/97	-0.00019	0.2531	Accept
15825	Crocket Ave	1.4	41	06/18/92	09/15/99	-0.00027	0.0065	Reject
15824	Girard Ave	0.3	77	06/18/92	11/03/97	-0.00026	0.0370	Reject
16647	S. Pacific RR Crossing	0.1	12	02/04/98	09/15/99	-0.00153	0.0802	Accept
16646	Confluence with Buffalo Bayou	0.0	3	02/13/98	09/02/98	0.00415	0.2600	Accept

¹ For Buffalo Bayou, 0 km is at boundary of Segment 1013 with Segment 1007. For White Oak Bayou, 0 km is at confluence with Buffalo Bayou.

² Slope of temporal trend is calculated with log data.

³ If P-value is less than 0.05, the null hypothesis is rejected.

⁴ Null hypothesis is that the slope of the temporal trend in the data is zero. Null hypothesis is tested at the 95% confidence level.

⁵ Reference: Statistical Analysis for Engineers by J. Wesley Barnes, 1988.

Comparison of Data for Different Periods

Some of the various maintenance and recovery programs were implemented in the early part of the time frame between 1990 and year 2000, while others took place in the latter half of the period. Therefore, a comparison of the data obtained during the two periods (i.e. 1991-1995 and 1996-1999) was completed to evaluate if significant differences could be observed. Table 2.6 summarizes the results of this analysis. Two sets of comparisons were made: one for moderate flow data (flow<100 cfs and 50 cfs for Buffalo and Whiteoak Bayous, respectively) and the other for high flow data. Results shown in Table 2.6 indicate that the moderate flow data did not show significant differences (α =0.05) between the two time periods, with the exception of stations 15845, 11358, and 11345 in Buffalo Bayou. Significant differences between the two datasets were observed more frequently on the high flow data (5 stations). However, in general, the FC data did not show discernible differences for the period 1991-1999 and the impact of the various recovery programs cannot be assessed by this means.

2.2.2 Spatial Patterns

Figures 2.6 and 2.7 show the geometric means of the low flow FC data from 1992 to 1999 for Buffalo Bayou and Whiteoak Bayou respectively. The standard deviation is also shown to give an indication of the spread of the data. For those stations that have statistically significant temporal trends, the geometric means would be slightly lower if only recent data were used. The geometric means of the tributary data that were mainly collected by H&HS are also shown in the figures. All the stations have geometric means significantly above the contact recreation criterion of 200 cfu/dL. Most of the stations on

TABLE 2.6
STATISTICAL COMPARISON OF MEANS BETWEEN DATASETS COLLECTED DURING THE FIRST AND
SECOND HALF OF THE 90'S

Station		Moderate flow	data ^a		High flow data ^a				
Station	t Stat	t crit. two-tail	Null hypothesis	t Stat	t crit. two-tail	Null hypothesis			
Buffalo Bayo	u								
11142	1.47731	2.003239	Accept	-2.50559	1.990848	Reject			
11364	1.403814	2.005745	Accept	-1.2827	2.03011	Accept			
11363	0.921728	2.019542	Accept	-1.20378	2.068655	Accept			
11362	1.806157	1.996564	Accept	-2.2354	2.032243	Reject			
11361	0.195409	2.131451	Accept	-1.49316	2.073875	Accept			
11360	-0.633	2.004044	Accept	-3.21205	1.980993	Reject			
11359	1.689671	2.022689	Accept	-1.09714	2.068655	Accept			
15846	1.818635	2.007582	Accept	-1.00812	2.063898	Accept			
11358	4.848573	2.776451	Reject						
11357	0.632167	2.006645	Accept	-1.33669	2.039515	Accept			
11356	-0.25834	2.160368	Accept	0.211994	2.160368	Accept			
15845	3.185935	2.000297	Reject	-1.6489	2.04227	Accept			
11354	1.383579	2.004044	Accept	-1.66112	2.051829	Accept			
11353	0.83239	2.004881	Accept	-1.929	2.055531	Accept			
15844	0.728027	2.068655	Accept	-0.65021	2.079614	Accept			
11351	0.250409	1.978237	Accept	-0.97785	1.973535	Accept			
15843	-0.18715	2.003239	Accept	-1.34742	2.063898	Accept			
11347	-0.95516	2.160368	Accept	0.742856	2.131451	Accept			
15842	0.019698		·	-0.04736					
11345	2.31331	1.997137	Reject	0.032496	2.028091	Accept			
Vhite Oak Ba	ayou								
11398	0.088932	3.182449	Accept						
15831	0.524723	2.01894	Accept	-0.96382	2.200986	Accept			
15830	-0.32263	2.036932	Accept	-1.14938	2.178813	Accept			
15829	-1.90233	2.028091	Accept	-3.00531	2.178813	Reject			
16637									
11390	-0.9126	2.03011	Accept	-1.79829	2.055531	Accept			
11391	-1.21573	2.032243	Accept	-2.07854	2.051829	Reject			
15828	-1.766278	2.079614	Accept	-1.01702	2.228139	Accept			
15827	-1.48787	2.079614	Accept	-0.45468	2.306006	Accept			
11387	1.050811	2.045231	Accept	-0.18042	2.02619	Accept			
15826	-1.3101	2.015367	Accept	-0.82528	2.055531	Accept			
11385	1.044336	2.059537	Accept	-0.16224	2.364623	Accept			
15824	0.052834	1.992103	Accept	0.59792	2.051829	Accept			
16647			•			•			
16646									


^a variable 1 - 1991-1995 data; variable 2 - 1996-1999 data


The null hypothesis is rejected if $|t_{stat}| < t_{crit}$

The null hypothesis is tested at the 95% confidence level

^b the null hypothesis is that the two datasets are not statistically different


The test performed was the t-test assuming unequal variances





Buffalo Bayou have geometric means between 1000 and 3000 cfu/dL whereas most of the stations on Whiteoak Bayou have geometric means between about 3000 to 5000 cfu/dL. For both bayous, the bacteria level appears to be lower at the upstream end and higher at the downstream end. Most of the tributaries seem to have about the same bacteria level as the bayou, but there are a few that have higher bacteria levels. The bacteria level in Whiteoak Bayou is generally higher than that in Buffalo Bayou.


Figures 2.8 and 2.9 show the FC concentrations of samples collected under low flow conditions in an intensive survey of Buffalo Bayou in July 1985 and in an intensive survey of Whiteoak Bayou in November 1980 respectively. Samples were collected in the main stem and tributaries of each bayou and also from wastewater treatment plant (WWTP) outfalls. Almost all of the tributaries have bacterial levels close to that in the main stems. Except for one plant in the Whiteoak Bayou watershed, all the effluents from WWTPs have very low FC values because of chlorination. Given the fact that bacteria data are generally highly variable, the levels in the 1985 intensive survey of Buffalo Bayou appear to be consistent with that shown in Figure 2.6 for data in the '90s. This is not the case for Whiteoak Bayou. Except at a few locations, the FC values in the 1980 intensive survey of Whiteoak Bayou are below 1000 cfu/dL. However, the geometric means for the '90s data are all above 1000 cfu/dL as shown in Figure 2.7.



2.2.3 Data Collected at Flows above Median

Figures 2.10 and 2.11 show the geometric means of the FC data collected on days where the flow was at or above the screening values (approximately the median flows) from 1992 to 1999 for Buffalo Bayou and Whiteoak Bayou respectively. It should be noted that although a sample is associated with a higher flow, it might not be collected during the early stage of the runoff event when the bacteria level is usually very high. Moreover, as noted earlier, different agencies have different sampling strategies with respect to weather conditions and some of them are actually geared toward dry weather sampling. Nevertheless, this analysis of the high flow data gives a general indication of the effect of flow on the bacteria level.

Similar to the low flow data, the bacteria level appears to be lower at the upstream end and higher at the downstream end. For Buffalo Bayou, the geometric means of the high flow data are generally similar to those of the low flow data. On the other hand, for Whiteoak Bayou, the geometric means of the high flow data are generally higher than those of the low flow data. For both bayous, the high flow data have higher variability than the low flow data in terms of standard deviations. Table 2.7 shows the coefficients of variation (standard deviation divided by mean) for both the high and low flow data. For most of the stations on Buffalo Bayou, the coefficients of variation are higher for the high flow data. For Whiteoak Bayou, with both higher geometric means and larger standard deviations, the resulting coefficients of variation are about the same level as the low flow data. For the tributaries of Buffalo Bayou and Whiteoak Bayou, the high flow data do not seem to have consistently higher coefficients of variation than the low flow data.






TABLE 2.7
COEFFICIENTS OF VARIATION OF FC DATA

Sufficiol Bayou	Station ID	Location	River Km		Low flo	w data ¹			High flo	w data ²	
11142 Barker Dam				Number	logGM ³	logStdev 4	C _V ⁵	Number	logGM ³	logStdev 4	C _V ⁵
11142 Balow Barker Dam	Buffalo Ba	ауои									
11364 SH 6	11142	Barker Dam	45.3	85	2.68	0.58	0.22	85	3.22	0.89	0.28
11936 Eluridge Rd								12			
11362 Dairy Äshford Rd											
11361 Wilcrest Dr											
11360 West Belt											
11359 Gessner Dr											
1584 Briar Forest Ave 29.7 66 3.06 0.51 0.17 34 2.98 0.69 0.23											
11368 Piney Point Rd											
11355 San Falipe St 25.3 53 3.11 0.51 0.17 33 3.16 0.71 0.22 15845 Chinney Rock Rd 18.2 57 3.10 0.58 0.19 36 3.23 0.62 0.19 11354 Woodway Dr 15.7 55 3.15 0.55 0.17 38 3.19 0.66 0.21 11353 H 610 14.2 55 3.09 0.54 0.17 37 3.16 0.62 0.20 11351 Shepherd Dr 7.0 184 3.52 0.61 0.17 37 3.16 0.62 0.20 11351 Shepherd Dr 7.0 184 3.52 0.61 0.17 161 3.60 0.72 0.20 11354 Wastott Awe 3.8 56 3.50 0.59 0.17 37 3.34 0.68 0.20 11354 Main St 1.7 72 3.71 0.60 0.16 77 4.01 0.70 0.17 11342 San Jajorito Ave 1.5 8 3.68 0.49 0.13 9 3.60 0.53 0.15 11345 McKee St 7.4 2.62 0.52 0.20 51 3.71 0.68 0.18 11345 McKee St 7.4 2.62 0.52 0.20 57 2.92 0.74 0.25 11368 Rummel Creek at Memorial Dr 42.7 74 2.62 0.52 0.20 57 3.31 0.76 0.23 11188 Rummel Creek at Memorial Dr 34.6 2.7 3.30 0.84 0.26 2.7 3.31 0.76 0.23 11689 Spring Branch Ck at Wirt Rd 18.7 13 3.27 0.84 0.26 6 3.02 3.43 0.87 0.25 16592 Spring Branch Ck at Wirt Rd 18.7 13 3.27 0.84 0.26 6 3.02 3.43 0.87 0.25 16593 Spring Branch Creek at Chimney Rock Rd 18.7 13 3.27 0.84 0.26 6 3.02 0.29 0.25 16894 White Oak Bayou at Memorial Dr 17.9 2.6 3.61 0.97 0.27 2.94 4.14 0.80 0.13 190007** Procedus Creek at Long Point Rd 18.7 13 3.27 0.84 0.26 6 3.38 0.20 0.25 18831 W. Tidwell Ave 16.5 44 3.12 0.50 0.10 15 4.09 0.73 0.18 1899018** Spring Branch Creek at Chimney Rock Rd 18.7 13 3.43 0.86 0.25 17 3.93 0.80 0.25 18832 Watonga 15.4 4.7 4											
11368 Voss Rd											
15844 Chimney Rock Rd		· ·									
11353 Mocodway Dr											
11584 Westott A/Ve											
15844 Westcott Ave											
11315 Shepherd Dr											
18843 Sabine Ave											
11347 Main St		· ·									
18842 San Jacinto Ave 1.5											
11345 McKee St											
11163 South Mayde Creek at Memorial Dr											
15847 Turkey Creek at Memorial Dr	Tributarie	s of Buffalo Bayou									
15847 Turkey Creek at Memorial Dr	11163	South Mayde Creek at Memorial Dr	42.7	74	2.62	0.52	0.20	57	2.92	0.74	0.25
16591 Spring Branch Ck at Long Point Rd	15847		42.3	71	2.87	0.70	0.24	57	3.31	0.76	0.23
Spring Branch Ck at Wirt Rd	11188	Rummel Creek at Memorial Dr	34.6	27	3.30	0.84	0.26	27	3.67	0.90	0.25
90007 6 Proetzls Creek at Long Point Rd 18.7 13 3.43 0.86 0.25 17 3.93 0.83 0.21 90013 6 Spring Branch Creek at Chimney Rock Rd 18.7 11 4.15 0.95 0.23 24 4.42 0.60 0.13 90012 6 Spring Branch Creek at Chimney Rock Rd 18.7 11 4.15 0.95 0.23 24 4.42 0.60 0.13 90012 6 Spring Branch Creek at Chimney Rock Rd 18.7 11 4.15 0.95 0.23 24 4.42 0.60 0.13 90012 6 Spring Branch Creek at Chimney Rock Rd 18.7 11 4.15 0.95 0.23 24 4.42 0.60 0.13 90012 6 Spring Branch Creek at Chimney Rock Rd 17.9 26 3.61 0.97 0.27 29 4.14 0.87 0.21 90012 6 Spring Branch Creek at Chimney Rock Rd 4.5 22 4.37 0.73 0.17 29 4.12 0.82 0.20 Whods Bayou at Memorial Dr 4.5 22 4.37 0.73 0.17 29 4.12 0.82 0.20 11398	16591	Spring Branch Ck at Long Point Rd	18.7	22	3.42	0.90	0.26	30	3.43	0.87	0.25
Spring Branch Creek at Chimney Rock Rd 18.7 11 4.15 0.95 0.23 24 4.42 0.60 0.13		Spring Branch Ck at Wirt Rd	18.7	13	3.27	0.84	0.26	6	3.62	0.92	0.25
Neimans Bayou at Memorial Dr		Proetzls Creek at Long Point Rd	18.7	13	3.43	0.86	0.25	17	3.93	0.83	0.21
90012 6 16675 Unnamed tributary at Glenwood Cemetary Rd 4.5 2.2 4.37 0.73 0.10 1.5 4.09 0.73 0.18	90013 ⁶	Spring Branch Creek at Chimney Rock Rd	18.7	11	4.15	0.95	0.23	24	4.42	0.60	0.13
Mile Oak Bayou		Neimans Bayou at Memorial Dr	17.9	26	3.61	0.97	0.27	29	4.14	0.87	0.21
White Oak Bayou	90012 ⁶	Woods Bayou at Memorial Dr	17.9	4	4.78	0.50	0.10	15	4.09	0.73	0.18
11398 Jones Rd 35.3 11 2.60 0.62 0.24 6 3.38 0.92 0.27	16675	Unnamed tributary at Glenwood Cemetary Rd	4.5	22	4.37	0.73	0.17	29	4.12	0.82	0.20
15831 W. Tidwell Ave 16.5 44 3.12 0.52 0.17 29 3.31 0.88 0.26											
15830 Watonga 15.4 45 3.18 0.67 0.21 29 3.35 0.84 0.25											
15829 W. 43rd St 14.9 38 3.10 0.61 0.20 26 3.35 0.85 0.25											
16637 W. T C Jester Ave (nr W. 34th St) 12.7 8 3.61 0.61 0.17 2 3.89 0.56 0.14		<u> </u>									
11390 W. 34th St 12.5 47 3.42 0.60 0.17 27 3.68 0.56 0.15											
11391 Ella Blvd 10.5 41 3.53 0.57 0.16 28 3.72 0.57 0.15 15828 W. T C Jester Ave (nr W. 12th St) 8.5 28 3.55 0.60 0.17 21 3.66 0.68 0.19 15827 N. Durham St 7.0 48 3.72 0.68 0.18 32 3.80 0.60 0.16 11387 Heights Blvd 5.2 108 3.56 0.59 0.17 95 3.95 0.63 0.16 15826 Studemont Ave 4.1 53 3.61 0.67 0.19 36 3.57 0.67 0.19 11388 Houston Ave 2.2 0 3 4.52 0.66 0.15 11385 Wrightwood St 2.0 35 3.57 0.64 0.18 31 4.24 0.73 0.17 15825 Crocket Ave 1.4 41 3.93 0.51 0.13 23 3.93 0.64 0.16 15825 Girard Ave 0.3 77 3.91 0.63 0.16 46 4.11 0.60 0.15 16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12 16648 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 Unnamed tributary at W. 14th St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0											
15828 W. T C Jester Ave (nr W. 12th St) 8.5 28 3.55 0.60 0.17 21 3.66 0.68 0.19 15827 N. Durham St 7.0 48 3.72 0.68 0.18 32 3.80 0.60 0.16 11387 Heights Blvd 5.2 108 3.56 0.59 0.17 95 3.95 0.63 0.16 15826 Studemont Ave 4.1 53 3.61 0.67 0.19 36 3.57 0.67 0.19 11388 Houston Ave 2.2 0 3 4.52 0.66 0.15 11385 Wrightwood St 2.0 35 3.57 0.64 0.18 31 4.24 0.73 0.17 15825 Crocket Ave 1.4 41 3.93 0.51 0.13 23 3.93 0.64 0.16 15824 Girard Ave 0.3 77 3.91 0.63 0.16 46 4.11 0.60 0.15 16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12 16646 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0 16593 Cole Creek at Bolivia Blvd 17.1 21 3.13 0.67 0.21 25 4.23 0.62 0.15 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 6											
15827 N. Durham St 7.0 48 3.72 0.68 0.18 32 3.80 0.60 0.16 11387 Heights Blvd 5.2 108 3.56 0.59 0.17 95 3.95 0.63 0.16 15826 Studemont Ave 4.1 53 3.61 0.67 0.19 36 3.57 0.67 0.19 11388 Houston Ave 2.2 0 3 4.52 0.66 0.15 11385 Wrightwood St 2.0 35 3.57 0.64 0.18 31 4.24 0.73 0.17 15825 Crocket Ave 1.4 41 3.93 0.51 0.13 23 3.93 0.64 0.16 15824 Girard Ave 0.3 77 3.91 0.63 0.16 46 4.11 0.60 0.15 16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12 16648 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0 16593 Cole Creek at Bolivia Blvd 17.1 21 3.13 0.67 0.21 25 4.23 0.62 0.15 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at WJ290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 6											
11387 Heights Blvd		` ,									
15826 Studemont Ave											
11388 Houston Ave 2.2 0 35 3.57 0.64 0.18 31 4.24 0.73 0.17 15825 Crocket Ave 1.4 41 3.93 0.51 0.13 23 3.93 0.64 0.16 15824 Girard Ave 0.3 77 3.91 0.63 0.16 46 4.11 0.60 0.15 16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12 16646 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0 16593 Cole Creek at Bolivia Blvd 17.1 21 3.13 0.67 0.21 25 4.23 0.62 0.15 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 6											
11385 Wrightwood St 2.0 35 3.57 0.64 0.18 31 4.24 0.73 0.17 15825 Crocket Ave 1.4 41 3.93 0.51 0.13 23 3.93 0.64 0.16 15824 Girard Ave 0.3 77 3.91 0.63 0.16 46 4.11 0.60 0.15 16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12 16646 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0 16593 Cole Creek at Bolivia Blvd 17.1 21 3.13 0.67 0.21 25 4.23 0.62 0.15 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 6					0.01	0.07	0.13				
15825 Crocket Ave 1.4 41 3.93 0.51 0.13 23 3.93 0.64 0.16 15824 Girard Ave 0.3 77 3.91 0.63 0.16 46 4.11 0.60 0.15 16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12 16646 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0 16593 Cole Creek at Bolivia Blvd 17.1 21 3.13 0.67 0.21 25 4.23 0.62 0.15 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 Girand Ave 0.3 0.62 0.447 0.74 0.17 25 4.53 0.77 0.17 93151 Girand Ave 0.3 0.62 0.447 0.74 0.17 25 4.53 0.77 0.17 16596 Unnamed tributary at Wynwood 8.5 13 3.43 0.35 0.10 18 4.38 0.69 0.16 16596 Unnamed tributary at W. 14th St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0					3.57	0.64	0.18				
15824 Girard Ave 0.3 77 3.91 0.63 0.16 46 4.11 0.60 0.15 16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12 16646 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0 16593 Cole Creek at Bolivia Blvd 17.1 21 3.13 0.67 0.21 25 4.23 0.62 0.15 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 Gold Unnamed tributary at Wynwood 8.5 13 3.43 0.35 0.10 18 4.38 0.69 0.16 16596 Unnamed tributary at W. 14th St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0		o a									
16647 S. Pacific RR Crossing 0.1 12 3.67 0.60 0.16 5 3.85 0.45 0.12											
16646 Confluence with Buffalo Bayou 0.0 3 3.41 0.46 0.13 0											
Tributaries of White Oak Bayou 16593 Cole Creek at Bolivia Blvd 17.1 21 3.13 0.67 0.21 25 4.23 0.62 0.15 16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 6 Unnamed tributary at Wynwood 8.5 13 3.43 0.35 0.10 18 4.38 0.69 0.16 16596 Unnamed tributary at W. 14th St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0	16646		0.0	3		0.46	0.13	0			
16594 Brickhouse Gully at US290 14.3 20 3.62 0.74 0.21 26 4.36 0.87 0.20 16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 6 Unnamed tributary at Wynwood 8.5 13 3.43 0.35 0.10 18 4.38 0.69 0.16 16596 Unnamed tributary at W. 14th St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0 0											
16595 Unnamed tributary at US290 11.5 20 4.47 0.74 0.17 25 4.53 0.77 0.17 93151 6 16596 Unnamed tributary at Wynwood 8.5 13 3.43 0.35 0.10 18 4.38 0.69 0.16 16596 11148 1148 1149 White Oak Bayou at Trimble St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 1149 White Oak Bayou at Maufred 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15	16593		17.1	21	3.13	0.67	0.21	25	4.23	0.62	0.15
93151 ⁶ Unnamed tributary at Wynwood 8.5 13 3.43 0.35 0.10 18 4.38 0.69 0.16 16596 Unnamed tributary at W. 14th St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0	16594	Brickhouse Gully at US290	14.3		3.62	0.74	0.21		4.36		0.20
16596 Unnamed tributary at W. 14th St 8.3 6 4.08 0.86 0.21 6 4.02 0.79 0.20 11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0 0		Unnamed tributary at US290	11.5	20	4.47	0.74	0.17	25	4.53	0.77	0.17
11148 Little White Oak Bayou at Trimble St 2.1 84 4.45 0.65 0.15 68 4.57 0.71 0.15 16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0 0	93151 ⁶	Unnamed tributary at Wynwood	8.5	13	3.43	0.35	0.10	18	4.38	0.69	0.16
16636 Little White Oak Bayou at Maufred 2.1 9 3.60 0.70 0.20 0	16596	Unnamed tributary at W. 14th St	8.3	6	4.08	0.86	0.21	6	4.02	0.79	0.20
	11148	Little White Oak Bayou at Trimble St	2.1	84	4.45	0.65	0.15	68	4.57	0.71	0.15
16648 Little White Oak Bayou at White Oak Dr 2.1 10 3.49 0.60 0.17 22 4.32 0.85 0.20											
	16648	Little White Oak Bayou at White Oak Dr	2.1	10	3.49	0.60	0.17	22	4.32	0.85	0.20

¹ For Buffalo Bayou, flow at USGS gage no. 08073600 < 100 cfs. For White Oak Bayou, flow at USGS gage no. 08074500 < 50 cfs.

² For Buffalo Bayou, flow at USGS gage no. 08073600 >= 100 cfs.
For White Oak Bayou, flow at USGS gage no. 08074500 >= 50 cfs.

³ Log of geometric mean, i.e. average of log data. ⁴ Standard deviation of log data.

⁵ Coefficient of variation = LogStdev/LogGM.

⁶ These stations do not have TNRCC Station ID.

Table 2.8 shows the geometric means of the FC data collected on days where the flow was above the screening levels approximating the 90th percentile values from 1992 to 1999. The number of data at each station is relatively small so that only overall geometric means for the main stem and tributaries of each bayou are presented. With this high flow screening level, the overall geometric mean of Buffalo Bayou is slightly less than most of the geometric means for the low flow data of the individual stations. On the other hand, the overall geometric mean of Whiteoak Bayou is higher than most of the geometric means for the low flow data of the individual stations. For both bayous, the bacteria levels in the tributaries are higher than that in the main stem.

A further analysis of high flow data was undertaken to determine differences, if any, when compared to low flow data. High-flow data were also analyzed on a station-by-station basis to evaluate if the data exhibit temporal trends and to compare these data sets with those for moderate-flow conditions. Figures 2.12 and 2.13 show time series plots of FC data at high flows for each station in the main stem on Buffalo Bayou and Whiteoak Bayou, respectively. The data shown are samples from all agencies collected at high flow, i.e. between 100 and 1,000 cfs for Buffalo Bayou and between 50 and 300 cfs for Whiteoak Bayou.


Visual inspection of the time series plots indicates that for most of the stations, there does not appear to be a trend in the data since 1992. Statistical testing, however, was performed to confirm this observation. The results are shown in Table 2.9. The null hypothesis of zero slope in the temporal trend is rejected at the 95% confidence level at 7 stations (out of 20) on Buffalo Bayou and 3 stations (out of 14) on Whiteoak Bayou. The slopes of the data for 7 of these 10 stations are positive, indicating that bacteria levels at

TABLE 2.8 1992 TO 1999 FC DATA COLLECTED AT FLOW ABOVE 90TH PERCENTILE $^{\rm 1}$

	Number of data	Geometric Mean (cfu/dL)	Stdev of log data
Buffal Bayou			
Main stem	298	997	0.84
Tributaries	94	2997	1.05
White Oak Bayou			
Main stem	67	9711	0.63
Tributaries	47	36372	0.67

Screening levels are 1000 cfs for Buffalo Bayou and 300 cfs for White Oak Bayou. These are approximately the 90th percentiles.

FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)







FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)






FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)




FIGURE 2.12
TIME SERIES OF BUFFALO BAYOU FC DATA AT HIGH FLOW (100<Q<1000)





FIGURE 2.13
TIME SERIES OF WHITEOAK BAYOU FC DATA AT HIGH FLOW (50<Q<300)







FIGURE 2.13
TIME SERIES OF WHITEOAK BAYOU FC DATA AT HIGH FLOW (50<Q<300)







FIGURE 2.13
TIME SERIES OF WHITEOAK BAYOU FC DATA AT HIGH FLOW (50<Q<300)









FIGURE 2.13
TIME SERIES OF WHITEOAK BAYOU FC DATA AT HIGH FLOW (50<Q<300)











FIGURE 2.13
TIME SERIES OF WHITEOAK BAYOU FC DATA AT HIGH FLOW (50<Q<300)







FIGURE 2.13
TIME SERIES OF WHITEOAK BAYOU FC DATA AT HIGH FLOW (50<Q<300)






FIGURE 2.13
TIME SERIES OF WHITEOAK BAYOU FC DATA AT HIGH FLOW (50<Q<300)




TABLE 2.9
STATISTICAL TESTS OF TRENDS IN HIGH FLOW FC DATA SINCE 1992

Station ID	Location	River km 1	Num of data	Slope ²	P-value 3	Null hypothesis 4
Buffalo Ba	ayou					
11142	Barker Dam	45.3	94	0.000195	0.009806	Accept
11142a	Barker Dam	46.3	11	0.000819	0.004157	Reject
11364	SH 6	45.0	73	0.000031	0.5304799	Accept
11363	Eldridge Rd	42.4	20	0.000437	0.1132252	Accept
11362	Dairy Ashford Rd	40.2	84	0.000171	0.0210579	Reject
11361	Wilcrest Dr	36.7	20	0.000077	0.4283258	Accept
11360	West Belt	34.6	136	0.000346	4.026E-10	Reject
11359	Gessner Dr	31.5	57	0.000247	0.0044567	Reject
15846	Briar Forest Ave	29.7	69	0.000154	0.0535205	Accept
11358	Piney Point Rd	28.9	3	0.000986	0.8106723	Accept
11357	San Felipe St	25.3	72	0.000052	0.5249048	Accept
11356	Voss Rd	23.5	62	-0.000018	0.9442713	Accept
15845	Chimney Rock Rd	18.2	62	-0.000045	0.5342534	Accept
11354	Woodway Dr	15.7	73	-0.000056	0.3432523	Accept
11353	IH 610	14.2	42	0.000040	0.6721385	Accept
15844	Westcott Ave	8.7	47	-0.000066	0.3856283	Accept
11351	Shepherd Dr	7.0	167	-0.000081	0.0249978	Reject
15843	Sabine Ave	3.8	75	-0.000134	0.0065644	Reject
11347	Main St	1.7	58	-0.000369	0.0650282	Accept
15842	San Jacinto Ave	1.5	44	-0.000174	0.0354753	Reject
11345	McKee St	0.6	42	-0.000062	0.4143361	Accept
White Oal	k Bayou					
11398	Jones Rd	35.3	4	0.001090	0.267321	Accept
15831	W. Tidwell Ave	16.5	34	0.000312	0.138083	Accept
15830	Watonga	15.4	34	0.000573	0.006044	Reject
15829	W. 43rd St	14.9	33	0.000789	0.000348	Reject
16637	W. T C Jester Ave (nr W. 34th St)	12.7	5	-0.000647	0.729380	Accept
11390	W. 34th St	12.5	31	0.000287	0.079971	Accept
11391	Ella Blvd	10.5	34	0.000332	0.038996	Reject
15828	W. T C Jester Ave (nr W. 12th St)	8.5	28	0.000289	0.181623	Accept
15827	N. Durham St	7.0	35	0.000356	0.062545	Accept
11387	Heights Blvd	5.2	1			
15826	Studemont Ave	4.1	42	-0.000036	0.751478	Accept
11385	Wrightwood St	2.0	33	-0.000120	0.473357	Accept
15825	Crocket Ave	1.4	24	-0.000135	0.385423	Accept
15824	Girard Ave	0.3	65	0.000060	0.550006	Accept
16647	S. Pacific RR Crossing	0.1	4	-0.000194	0.946355	Accept
16646	Confluence with Buffalo Bayou	0.0				

¹ For Buffalo Bayou, 0 km is at boundary of Segment 1013 with Segment 1007. For White Oak Bayou, 0 km is at confluence with Buffalo Bayou.

² Slope of temporal trend is calculated with log data.

³ If P-value is less than 0.05, the null hypothesis is rejected.

⁴ Null hypothesis is that the slope of the temporal trend in the data is zero. Null hypothesis is tested at the 95% confidence level.

⁵ Reference: Statistical Analysis for Engineers by J. Wesley Barnes, 1988.

high flows have been increasing over time. For most of the stations, the null hypothesis could not be rejected, indicating that the change in bacteria levels has not been strong in the last decade. Figure 2.14 shows a comparison of the observed trends between low and high flow data.

2.2.4 High vs Low Flow Data Analyses

Statistical analysis of the moderate- and high-flow FC datasets for selected monitoring stations showed that the two datasets were not significantly different (P values greater than 0.05), even though the geometric mean FC values for higher flows were higher than those for moderate flow (see Table 2.10).

The data analyses were expanded by looking at different flow quantiles to see if statistical differences could be found if the high flow data definition changed (i.e. the limit between moderate and high flow data was somewhere between 10th and 50th percentiles). Table 2.10 includes a summary of results for all the stations in the Buffalo and Whiteoak Bayous.

It can be observed that for Buffalo Bayou, 15 out of 20 stations showed no statistical difference (α =0.05) between low and high flow datasets, when the limit was set to the median flow (i.e. 100 cfs). This number decreased to 13 when the limit was lowered to the flow corresponding to the 40^{th} percentile and remained the same for the remaining flow limits (30^{th} , 20^{th} , and 10^{th} percentiles). These results confirm that, overall, the high flow data are not statistically different from the low flow data in Buffalo Bayou. Stations 11142, 11345, 11347, 11356, and 11358 exhibited significant differences between the low and high flow data.




TABLE 2.10
STATISTICAL COMPARISON OF MEANS BETWEEN DATA SETS WITH DIFFERENT HIGH-FLOW DEFINITION

Ctation	Deta Denga		<10% vs <u>></u> 10	%		<20% vs >2	0%		<30% vs >3	0%
Station	Date Range	t Stat	t crit. two-tail	Null hypothesis	t Stat	t crit. two-tail	Null hypothesis	t Stat	t crit. two-tail	Null hypothesis
Buffalo Bayou	1									
11142	7/92-12/98	-5.19184	1.992544	Reject	-5.27246	1.976578	Reject	-5.30501	1.974272	Reject
11364	4/92-9/99	-1.70157	2.085962	Accept	-1.72535	2.000297	Accept	-1.00743	1.988269	Accept
11363	4/94-9/99	-1.57657	2.100924	Accept	-1.42996	2.004044	Accept	-0.91364	1.995468	Accept
11362	2/92-9/99	-0.10155	2.048409	Accept	-1.12636	1.98761	Accept	0.62339	1.979765	Accept
11361	4/94-9/99	1.70236	2.085962	Accept	0.388351	2.000297	Accept	1.726002	1.998969	Accept
11360	4/92-9/99	0.171707	1.992544	Accept	-0.92425	1.974622	Accept	-0.84591	1.97011	Accept
11359	4/92-9/99	0.258535	2.048409	Accept	0.32997	1.993462	Accept	1.478017	1.989688	Accept
15846	4/92-9/99	-0.16043	2.059537	Accept	0.233975	1.996009	Accept	1.375725	1.98896	Accept
11358	2/94-8/96			•	-3.73404	2.364623	Reject	-3.88174	2.446914	Reject
11357	4/92-9/99	-0.15588	2.100924	Accept	0.22312	2.003239	Accept	0.671695	1.990848	Accept
11356	1/95-6/99	-2.95075	2.00297	Reject	-3.38666	1.986377	Reject	-3.06229	1.979124	Reject
15845	4/92-9/99	-2.4179	2.068655	Reject	-0.79462	2.005745	Accept	-0.48304	1.986673	Accept
11354	4/92-9/99	-0.94831	2.068655	Accept	-0.07367	2.004044	Accept	0.256549	1.986377	Accept
11353	4/92-9/99	-0.60036	2.059537	Accept	0.620419	2.005745	Accept	-0.04863	1.986978	Accept
15844	5/92-12/98	-0.305155	2.02619	Accept	0.038647	2.005745	Accept	-0.37216	2.003239	Accept
11351	2/92-9/99	-1.16877	1.980625	Accept	-1.15844	1.970566	Accept	-1.69108	1.967114	Accept
15843	4/92-9/99	0.838586	2.085962	Accept	2.287609	1.997137	Reject	1.368582	1.98933	Accept
11347	1/95-6/99	-3.18721	1.997137	Reject	-3.04661	1.9858	Reject	-2.52015	1.979765	Reject
15842	4/92-9/96	3.167971	2.131451	Reject	3.167971	2.131451	Reject	0.643744	2.160368	Accept
11345	2/92-9/99	-1.54354	2.048409	Accept	-2.59088	1.990065	Reject	-2.50806	1.978524	Reject
Whiteoak Bay	ou									
11398	2/92-8/96	-0.39669		Reject	0.61625	2.364623	Accept	-0.8804	2.131451	Accept
15831	4/92-9/99	-3.14726	2.04227	Reject	-0.8422	2.028091	Accept	-0.68015	2.004044	Accept
15830	4/94-9/99	-1.45089	2.131451	Accept	-1.10965	2.021075	Accept	-0.7404	2.004044	Accept
15829	4/92-9/98	-0.77514	2.262159	Accept	-1.04001	2.045231	Accept	-0.95496	2.018082	Accept
16637	2/98-9/99	0.310754	12.70615	Accept	0.310754	12.70615	Accept	0.036256	3.182449	Accept
11390	4/92-9/99	-1.46914	2.178813	Accept	-0.49964	2.039515	Accept	-0.59992	2.016691	Accept
11391	4/92-9/99	-0.60035	2.228139	Accept	-0.22993	2.051829	Accept	0.109065	2.021075	Accept
15828	4/92-5/97	-2.117233	2.178813	Accept	-0.680199	2.119905	Accept	0.017117	2.055531	Accept
15827	4/92-12/96	-1.10599	2.20986	Accept	-0.31678	2.048409	Accept	0.663585	2.024394	Accept
11387	2/92-8/99	-0.64938	2.055531	Accept	-0.53209	2.005745	Accept	-1.53971	1.982385	Accept
15826	4/92-9/99	0.046599	2.262159	Accept	-0.05882	2.055531	Accept	0.189493	2.032243	Accept
11385	4/92-5/97	-0.91323	2.570578	Accept	-3.2135	2.079614	Reject	-3.99506	2.009574	Reject
15825	4/92-9/99	-0.03094	2.306006	Accept	0.932192	2.012894	Accept	0.219589	2.012894	Accept
15824	4/92-11/97	0.392259	2.364623	Accept	0.201756	2.019542	Accept	-1.63308	1.98861	Accept
16647	2/98-9/98	-0.21387	2.776451	Accept	0.051202	2.228139	Accept	-0.74147	2.200986	Accept
16646	2/98-9/98	0.146978			0.146978			0.146978		

^a variable 1 - low-flow data; variable 2 - high-flow data

The null hypothesis is rejected if $|t_{stat}| < t_{crit}$

The null hypothesis is tested at the 95% confidence level

^b the null hypothesis is that the two datasets are not statistically different

The test performed was the t-test assuming unequal variances

TABLE 2.10
STATISTICAL COMPARISON OF MEANS BETWEEN DATA SETS WITH
DIFFERENT HIGH-FLOW DEFINITION (CONT'D)

Station	Deta Dens		<40% vs >40°	%		<50% vs <u>></u> 50)%
Station	Date Range	t Stat	t crit. two-tail	Null hypothesis	t Stat	t crit. two-tail	Null hypothesis
Buffalo Bayo	u						
11142	7/92-12/98	-4.242175	1.9747176	Reject	-4.68796	1.976578	Reject
11364	4/92-9/99	-0.18356	1.990848	Accept	0.344429	2.001716	Accept
11363	4/94-9/99	-0.88027	2.005745	Accept	-0.72517	2.022689	Accept
11362	2/92-9/99	1.209805	1.981566	Accept	0.385491	1.990452	Accept
11361	4/94-9/99	0.772946	2.004881	Accept	0.592677	2.022689	Accept
11360	4/92-9/99	-0.43804	1.969984	Accept	-0.28159	1.971007	Accept
11359	4/92-9/99	1.336072	1.996564	Accept	0.998727	2.007582	Accept
15846	4/92-9/99	1.393344	1.996009	Accept	0.278072	2.004044	Accept
11358	2/94-8/96	-3.88174	2.446914	Reject	-6.18686	2.776451	Reject
11357	4/92-9/99	0.40118	1.995468	Accept	-0.31892	2.005745	Accept
11356	1/95-6/99	-2.86519	1.976346	Reject	-2.19616	1.975695	Reject
15845	4/92-9/99	-0.33854	1.989688	Accept	-0.95234	1.993944	Accept
11354	4/92-9/99	0.279887	1.98896	Accept	-0.27543	1.994435	Accept
11353	4/92-9/99	0.052691	1.98861	Accept	-0.056854	1.994435	Accept
15844	5/92-12/98	-0.34027	2.000997	Accept	-1.01774	2.007582	Accept
11351	2/92-9/99	-1.98661	1.96701	Reject	-1.02692	1.967524	Accept
15843	4/92-9/99	2.050698	1.990065	Reject	1.345751	1.995468	Accept
11347	1/95-6/99	-2.73726	1.976459	Reject	-2.7946	1.976346	Reject
15842	4/92-9/96	0.329286	2.131451	Accept	0.329286	2.131451	Accept
11345	2/92-9/99	-2.53948	1.978524	Reject	-2.16414	1.982385	Reject
Whiteoak Bay	/ou		•			•	·
11398	2/92-8/96	-1.28376	2.262159	Accept	-1.87543	2.306006	Accept
15831	4/92-9/99	-0.60497	1.994945	Accept	-1.07241	2.019542	Accept
15830	4/94-9/99	-0.79314	1.994945	Accept	-0.94486	2.007582	Accept
15829	4/92-9/98	-1.67254	1.999624	Accept	-1.27873	2.018082	Accept
16637	2/98-9/99	0.053183	2.306006	Accept	-0.612711	4.302656	Accept
11390	4/92-9/99	-1.74383	1.993462	Accept	-1.88302	2.002466	Accept
11391	4/92-9/99	-1.4094	1.997728	Accept	-1.32146	2.001716	Accept
15828	4/92-5/97	-0.041265	2.016691	Accept	-0.571543	2.021075	Accept
15827	4/92-12/96	-0.05508	1.992544	Accept	-0.54096	1.993462	Accept
11387	2/92-8/99	-3.65272	1.97253	Reject	-4.45761	1.972267	Reject
15826	4/92-9/99	0.51298	1.992998	Accept	0.302866	1.991675	Accept
11385	4/92-5/97	-4.4755	2.000297	Reject	-3.93897	2.000297	Reject
15825	4/92-9/99	0.27286	1.999624	Accept	-0.02404	2.024394	Accept
15824	4/92-11/97	-1.3242	1.98118	Accept	-1.76171	1.984467	Accept
16647	2/98-9/98	0.055755	2.131451	Accept	-0.68056	2.28139	Accept
16646	2/98-9/98	-0.25087					•

^a variable 1 - low-flow data; variable 2 - high-flow data

^b the null hypothesis is that the two datasets are not statistically different

The test performed was the t-test assuming unequal variances

The null hypothesis is rejected if $|t_{stat}| < t_{crit}$

The null hypothesis is tested at the 95% confidence level

For Whiteoak Bayou, only two stations (11385 and 11387) showed statistically significant differences between low and high flow data when the limit was set to the median and 40th percentile. Similarly to Buffalo Bayou, Whiteoak Bayou high flow data are not statistically different from the low flow data.

In addition, a test was performed to investigate if there were a statistically significant trend in the data subsets since 1992. The results are shown in Table 2.11. The null hypothesis of zero slope in the temporal trend was rejected at the 95% confidence level at five stations on Buffalo Bayou and one station on Whiteoak Bayou for the high flow data. For the other data subsets no trend was observed with very few exceptions. The data corresponding to extreme low flow conditions (10th percentile) was totally random as indicated by zero rejections of the null hypothesis.

2.2.5 Seasonal Trends

The possible impact of seasonal variations on bacteria levels was evaluated by comparing datasets under two different scenarios: (i) dry- vs. wet-weather data, and (ii) winter vs summer data.

Dry- vs Wet-weather Data

Precipitation data for the period 1961-1990 were obtained from the National Weather Service Webpage. Averaged monthly precipitation data for Houston were used to differentiate between dry- and wet-weather data. Those months whose average values of rainfall were greater than the total average precipitation over the entire period of data

TABLE 2.11
STATISTICAL TESTS OF TRENDS FOR VARIOUS DATA SUBSETS

			1	0%				20%			3	30%				10%	
Station	Date Range	# of	-	7.5	Nuli	# of			Null	# of		. • , , ,	Null	# of			Null
	g .	observation	Slope ¹	P-value ²	hypothesis ³	observation	Slope ¹	P-value ²	hypothesis ³	observation	Slope ¹	P-value ²	hypothesis ³	observation	Slope ¹	P-value ²	hypothesis ³
Buffalo Bayou																	
11142	7/92-12/98	33	-0.00037	0.1581764	Accept	17	-0.00011	0.650068	Accept	13	-2.40E-05	0.935823	Accept	14	-6.10E-05	0.8679012	Accept
11364	4/92-9/99	14	-1.00E-04	0.722095	Accept	14	-0.00018	0.480529	Accept	15	-0.00021	0.166459	Accept	6	0.00071	0.082976	Accept
11363	4/94-9/99	13	-0.00027	0.405151	Accept	12	-0.00014	0.716737	Accept	10	7.04E-05	0.773483	Accept	5	-7.40E-05	0.55921	Accept
11362	2/92-9/99	20	-0.00038	0.163504	Accept	18	0.00025	0.286904	Accept	18	-7.40E-05	0.670485	Accept	9	-8.40E-05	0.822522	Accept
11361	4/94-9/99	13	-0.00048	0.067711	Accept	13	4.64E-05	0.888933	Accept	8	7.59E-05	0.691578	Accept	4	-0.00034	0.455161	Accept
11360	4/92-9/99	47	-0.00031	0.137315	Accept	26	2.63E-05	0.901705	Accept	22	-8.40E-06	0.945024	Accept	19	0.000243	0.455903	Accept
11359	4/92-9/99	15	-0.00019	0.356498	Accept	14	-0.00054	0.037515	Reject	13	-5.15E-05	0.779905	Accept	7	-0.00044	0.246386	Accept
15846	4/92-9/99	15	-0.00024	0.274384	Accept	14	-0.00037	0.167346	Accept	15	-0.0002	0.19565	Accept	7	-0.0005	0.167749	Accept
11358	2/94-8/96					3	0.000171	0.743787	Accept								
11357	4/92-9/99	14	-0.00034	0.259282	Accept	14	-0.00018	0.51965	Accept	15	-2.00E-05	0.866202	Accept	5	0.000565	0.496468	Accept
11356	1/95-6/99	36	-0.0001	0.715026	Accept	9	0.000552	0.291405	Accept	11	5.71E-05	0.920031	Accept	8	0.000931	0.018264	Reject
15845	4/92-9/99	15	-0.00035	0.115666	Accept	14	-0.0004	0.215474	Accept	16	-0.00032	0.011428	Reject	7	-0.00012	0.819048	Accept
11354	4/92-9/99	15	-0.00023	0.332076	Accept	14	-0.00035	0.302365	Accept	15	-6.70E-05	0.6795	Accept	6	-0.00025	0.620195	Accept
11353	4/92-9/99	14	-0.00026	0.223646	Accept	13	0.000115	0.0733933	Accept	16	-5.80E-05	0.678795	Accept	7	-0.00011	0.859399	Accept
15844	5/92-12/98	12	8.98E-05	0.724748	Accept	13	-0.00014	0.772216	Accept	4	0.00011	0.804496	Accept	4	-0.00054	0.789416	Accept
11351	2/92-9/99	63	8.72E-05	0.445714	Accept	37	-0.00016	0.306424	Accept	38	0.00014	0.226526	Accept	23	-1.40E-05	0.927926	Accept
15843	4/92-9/99	15	0.000375	0.209349	Accept	14	0.000219	0.293039	Accept	15	-2.60E-07	0.998464	Accept	7	-0.00029	0.652911	Accept
11347	1/95-6/99	33	-0.00023	0.271231	Accept	10	-0.0005	0.395616	Accept	10	0.000113	0.833225	Accept	9	8.28E-05	0.808882	Accept
15842	4/92-9/96	2	-0.00011			2	-0.00011			5	5.17E-05	0.960976	Accept				
11345	2/92-9/99	20	-0.00025	0.35224	Accept	20	1.77E-06	0.995085	Accept	20	-0.00028	0.168307	Accept	14	-0.00044	0.151511	Accept
Whiteoak Bayou																	
11398	2/92-8/96					3	0.000666	0.43949	Accept	4	-8.10E-05	0.918693	Accept	2	0.000893		
15831	4/92-9/99	6	0.000118	0.150656	Accept	12	0.000455	0.198826	Accept	4	-0.00021	0.496655	Accept	12	-0.00043	0.056504	Accept
15830	4/94-9/99	7	-7.50E-05	0.68307	Accept	12	0.000153	0.388887	Accept	4	-0.00079	0.055991	Accept	12	-0.0002	0.397074	Accept
15829	4/92-9/98	5	-0.00015	0.500079	Accept	12	0.0003	0.50184	Accept	3	0.000787	0.063879	Accept	9	0.000104	0.549235	Accept
16637	2/98-9/99	2	-0.002882											3	0.003799	0.059584	Accept
11390	4/92-9/99	8	3.67E-05	0.849716		12	0.000155	0.723337		5	-0.00083	0.106675		13	-0.0001	0.571342	
11391	4/92-9/99	6	3.61E-07	0.998325	Accept	12	8.85E-05	0.829024	Accept	5	-0.00102	0.055874	Accept	9	4.07E-05	0.82101	Accept
15828	4/92-5/97	4	-1.05E-06	0.995943	Accept	8	0.000121	0.812805	Accept	4	-0.000298	0.597378	Accept	5	-0.000138	0.722004	Accept
15827	4/92-12/96	4	-2.70E-05	0.910379	Accept	17	0.000291	0.525766	Accept	5	-9.50E-05	0.886399	Accept	13	-0.00016	0.700917	Accept
11387	2/92-8/99	22	0.000153	0.673349	Accept	14	0.000834	0.005202	Reject	21	-0.00039	0.265759	Accept	26	-0.00018	0.204304	Accept
15826	4/92-9/99	7	8.37E-05	0.692358	Accept	13	-0.0002	0.61484	Accept	4	-0.00065	0.436737	Accept	14	0.000172	0.374763	Accept
11385	4/92-5/97	5	0.000143	0.859524	Accept	7	1.38E-05	0.966072	Accept	7	0.000331	0.15764	Accept	8	-0.00081	0.20256	Accept
15825	4/92-9/99	6	-0.00012	0.554273	Accept	12	-0.00019	0.424627	Accept	4	-0.00094	0.34905	Accept	10	-9.80E-05	0.681716	Accept
15824	4/92-11/97	7	0.000311	0.598889	Accept	22	-0.00016	0.601275	Accept	17	-9.50E-05	0.724793	Accept	14	-0.00085	0.00587	Reject
16647	2/98-9/98	4	-0.00095	0.649748	Accept	2	0.00537							2	-0.00111		
16646	2/98-9/98																

Slope of temporal trend is calculated with log data.
 If P-value is less than 0.05, the null hypothesis is rejected.
 Null hypothesis is that the slope of the temporal trend in the data is zero. Null hypothesis is tested at the 95% confidence level.
 Reference: Statistical Analysis for Engineers by J. Wesley Barnes, 1988.

TABLE 2.11 STATISTICAL TESTS OF TRENDS FOR VARIUOS DATA SUBSETS

		50% >50%					>	50%				75%				90%				100%	
Station	Date Range	# of			Null	# of			Null	# of		_	Null	# of		_	Null	# of			Null
		observation	Slope ¹	P-value ²	hypothesis ³	observation	Slope ¹	P-value ²	hypothesis ³	observati	Slope ¹	P-value ²	hypothesis ³	observati	Slope ¹	P-value ²	hypothesis ³	observati	Slope ¹	P-value ²	hypothesis ³
Buffalo Bayou																					
11142	7/92-12/98	8	-0.00041	0.258686	Accept	85	0.000383	0.077587	Accept	43	0.000231	0.488453	Accept	24	0.000654	0.104987	Accept	18	0.000685	0.127869	Accept
11364	4/92-9/99	7	0.000872	0.006527	Reject	33	0.000312	0.032525	Reject	16	0.000121	0.579959	Accept	8	0.0004	0.080432	Accept	9	0.000254	0.33793	Accept
11363	4/94-9/99	5	0.0038	0.546192	Accept	26	0.000139	0.597597	Accept	15	0.000523	0.122188	Accept	6	0.000744	0.180761	Accept	5	-0.00052	0.356173	Accept
11362	2/92-9/99	11	-0.00038	0.231599	Accept	47	0.00023	0.121694	Accept	21	0.000345	0.10311	Accept	14	0.000153	0.6266	Accept	12	0.000149	0.415627	Accept
11361	4/94-9/99	24	0.000191	0.391175	Accept	24	0.000191	0.391175	Accept	13	0.00027	1.272995	Accept	6	0.00089	0.095905	Accept	5	0.00011	0.597224	Accept
11360	4/92-9/99	13	-0.00011	0.808548	Accept	115	0.000343	0.007762	Reject	57	0.00034	0.023227	Reject	31	0.000497	0.143471	Accept	27	0.000205	0.353495	Accept
11359	4/92-9/99	5	0.00022	0.703633	Accept	34	0.000205	0.227056	Accept	17	0.000111	0.635233	Accept	6	0.0004	0.442086	Accept	11	2.77E-05	0.891623	Accept
15846	4/92-9/99	5	0.000253	0.686692	Accept	34	0.000217	0.179063	Accept	16	0.000425	0.06877	Accept	9	0.000277	0.424972	Accept	9	-0.0001	0.667127	Accept
11358	2/94-8/96	3	7.15E-05	0.650559	Accept	4	-0.00039	0.757894	Accept	2	0.000256										
11357	4/92-9/99	5	0.000137	0.692019	Accept	33	0.000232	0.155942	Accept	17	0.000201	0.442279	Accept	7	0.000592	0.197566	Accept	9	7.87E-06	0.962227	Accept
11356	1/95-6/99	9	-0.00024	0.700165	Accept	81	-7.75E-06	0.973412	Accept	46	1.38E-04	0.613855	Accept	18	-5.80E-04	0.353383	Accept	17	7.45E-04	0.162816	Accept
15845	4/92-9/99	5	-0.00046	0.62184	Accept	36	0.000204	0.137238	Accept	16	-5.00E-06	0.978064	Accept	9	0.000344	0.29891	Accept	11	0.000135	0.522903	Accept
11354	4/92-9/99	5	0.000732	0.208138	Accept	38	0.000227	0.097954	Accept	18	0.000321	0.145974	Accept	9	5.45E-05	0.885839	Accept	11	0.000177	0.236787	Accept
11353	4/92-9/99	5	0.000398	0.366313	Accept	37	0.000283	0.035552	Reject	17	0.000378	0.091438	Accept	9	0.000237	0.363785	Accept	11	0.000159	0.522733	Accept
15844	5/92-12/98	4	-0.00019	0.76356	Accept	25	0.000386	0.044885	Reject	12	0.000445	0.233921	Accept	6	0.000452	0.300842	Accept	7	0.000277	0.47879	Accept
11351	2/92-9/99	21	-0.00059	0.070937	Accept	161	-6.30E-05	0.396085	Accept	81	-1.60E-04	0.114113	Accept	41	9.95E-05	0.48131	Accept	39	-1.30E-05	0.931294	Accept
15843	4/92-9/99	5	-0.001	0.144813	Accept	36	0.000281	0.062813	Accept	17	7.74E-05	0.722844	Accept	9	0.008709	0.92501	Accept	9	0.000631	0.054697	Accept
11347	1/95-6/99	10	-0.00033	0.583807	Accept	77	-0.00044	0.019341	Reject	42	-0.00048	0.052566	Accept	20	-1.60E-05	0.961507	Accept	15	-0.00017	0.767695	Accept
15842	4/92-9/96					9	0.000184	0.64621	Accept	4	0.000503	0.049946	Reject				Reject	4	0.001398	0.401282	Accept
11345	2/92-9/99	10	-0.00021	0.673147	Accept	51	-5.70E-05	0.641305	Accept	24	-1.20E-04	0.494821	Accept	13	-5.75E-05	0.813514	Accept	14	-1.10E-04	0.635704	Accept
Whiteoak Bayou																					
11398	2/92-8/96					6	0.000434	0.648228	Accept	3	0.001896	0.346991	Accept	2	0.000555		Reject				
15831	4/92-9/99	10	-4.30E-05	0.740058	Accept	29	0.000239	0.226833	Accept	18	0.00116	0.731067	Accept	7	0.000131	0.745276	Accept	4			
15830	4/94-9/99	10	-9.20E-05	0.781776	Accept	29	0.000154	0.417704	Accept	18	0.000187	0.558049	Accept	7	-8.43E-05	0.834589	Accept	4	-9.59E-06	0.985836	Accept
15829	4/92-9/98	9	0.000236	0.454495	Accept	26	0.000559	0.015505	Reject	18	0.000427	0.119133	Accept	6	0.000552	0.383827	Accept	2	0.000946		Reject
16637	2/98-9/99	2	-0.000914			2	-0.031496														
11390	4/92-9/99	9	1.09E-05	0.959081		27	3.95E-05	0.732273	Accept	16	2.31E-05		Accept	7	-0.000206	0.536842	Accept	4	-0.00013	0.139949	Accept
11391	4/92-9/99	9	0.000143	0.465577	Accept	28	0.000119	0.352521	Accept	19	7.72E-05	0.646871	Accept	6	-0.00014	0.744313	Accept	3	0.000103	0.191583	Accept
15828	4/92-5/97	7	0.000351	0.128735	Accept	21	8.18E-05	0.69415	Accept	14	-1.21E-04	0.604578	Accept	5	4.26E-04	0.493878	Accept	2	8.66E-05		
15827	4/92-12/96	9	0.000164	0.668631	Accept	32	8.79E-05	0.622517	Accept	20	-8.10E-05	0.725216	Accept	8	1.19E-04	0.740309	Accept	4	-7.40E-04	0.254742	Accept
11387	2/92-8/99	25	-9.70E-05	0.6652	Accept	95	9.58E-05	0.362784	Accept	50	2.89E-05	0.841301	Accept	27	1.41E-04	0.442893	Accept	18	1.06E-04	0.657136	Accept
15826	4/92-9/99	15	-3.90E-05	0.780937	Accept	36	-2.90E-05	0.797211	Accept	22	-1.30E-04	0.301116	Accept	11	-1.80E-04	0.462065	Accept	3	1.45E-04	0.67034	Accept
11385	4/92-5/97	8	-0.00034	0.365565	Accept	31	-0.00016	0.445077	Accept	21	-9.80E-05	0.690795	Accept	6	-0.00019	0.655113	Accept	4	-0.00047	0.700617	Accept
15825	4/92-9/99	9	-0.00037	0.030112	Reject	23	-0.00011	0.481957	Accept	15	-0.00047	0.065546	Accept	5	-9.20E-05	0.771549	Accept	3	-0.00018	0.516423	Accept
15824	4/92-11/97	17	-0.00023	0.079597	Accept	46	-3.70E-05	0.768767	Accept	28	-1.80E-04	0.275954	Accept	12	1.99E-04	0.472466	Accept	6	-2.00E-04	0.346658	Accept
16647	2/98-9/98	3	-0.00351	0.254777	Accept	5	0.000585	0.775638	Accept	2	0.003619			2	-0.00299	-					
16646	2/98-9/98																				

Slope of temporal trei¹ Slope of temporal trend is calculated with log data.
 If P-value is less than² If P-value is less than 0.05, the null hypothesis is rejected.
 Null hypothesis is tha³ Null hypothesis is that the slope of the temporal trend in the data is zero. Null hypothesis is tested at the 95% confidence level.
 Reference: Statistical⁴ Reference: Statistical Analysis for Engineers by J. Wesley Barnes, 1988.

were considered "wet weather" and the remaining ones were considered "dry weather".

The wet and dry months are shown below.

Wet	Dry
May	January
June	February
July	March
August	April
September	October
November	December

Table 2.12 includes the results of this analysis. Data in Table 2.12 show that four stations in Buffalo and three in Whiteoak exhibited statistically significant differences (α =0.05) between dry- and wet-weather datasets. This seems to indicate that bacterial levels (wet data) in Buffalo and Whiteoak Bayous are slightly impacted by the wet weather conditions (20% of the stations showed wet data that are higher than the dry data with a 95% confidence level). These higher values may be the result of runoff and/or higher temperatures that favor microbial growth. To assess the influence of the latter, an analysis of data for two seasonal periods was conducted as presented below.

Winter vs Summer Data

Historical temperature datasets were obtained from the National Weather Service Webpage. Averaged monthly temperature data for Houston during the period 1961-1990 were used to differentiate between summer and winter data. If a month presented an averaged monthly temperature higher than the total average temperature, it was classified as a "summer" month, otherwise it was considered a "winter" month. The winter and summer months are shown below.

TABLE 2.12 STATISTICAL COMPARISON OF MEANS BETWEEN DATA SETS FOR DRY AND WET WEATHER

Station	Date Range	t Stat	t crit. two-tail	Null hypothesis	Geometri	c mean
Buffalo Bayou					wet	dry
11142	7/92-12/98	-1.510493	1.976123	Accept	2.7833557	2.9406420
11364	4/92-9/99	2.712683	1.994945	Reject	2.7324311	2.3933341
11363	4/94-9/99	1.696404	2.012894	Accept	2.8630793	2.5516319
11362	2/92-9/99	0.820164	1.986086	Accept	3.0849315	2.9668956
11361	4/94-9/99	1.920563	2.006645	Accept	3.2320846	2.9650489
11360	4/92-9/99	-0.262827	1.970197	Accept	3.2355306	3.2715329
11359	4/92-9/99	1.889643	1.990848	Accept	3.1614148	2.9202952
15846	4/92-9/99	2.460429	1.988269	Reject	3.0969990	2.8155037
11358	2/94-8/96	2.360087	2.262159	Reject	2.2720810	1.8058450
11357	4/92-9/99	2.89883	1.989688	Reject	3.2225059	2.8845600
11356	1/95-6/99	-0.287017	1.975695	Accept	3.4106485	3.4624211
15845	4/92-9/99	1.500158	1.991675	Accept	3.1711918	2.9790386
11354	4/92-9/99	0.117811	1.993944	Accept	3.1223258	3.0947413
11353	4/92-9/99	1.086175	1.987291	Accept	3.1131021	3.0077205
15844	5/92-12/98	0.408694	2.000997	Accept	3.1728984	3.1147176
11351	2/92-9/99	-1.197839	1.967337	Accept	3.4574927	3.5423924
15843	4/92-9/99	-0.751411	1.988610	Accept	3.3378506	3.4459118
11347	1/95-6/99	-0.334619	1.976346	Accept	3.7901799	3.8263351
15842	4/92-9/96	-1.2170	2.178813	Accept	3.4527834	3.7557945
11345	2/92-9/99	-0.4523	1.982171	Accept	3.4562586	3.5305442
Whiteoak Bayon	u	•			•	
11398	2/92-8/96	2.669991	2.160368	Reject	3.0256786	2.2504311
15831	4/92-9/99	3.142662	2.004881	Reject	3.3045001	2.8115988
15830	4/94-9/99	3.123909	2.00297	Reject	3.3385609	2.8600612
15829	4/92-9/98	1.359383	2.021075	Accept	3.2292369	2.9328550
16637	2/98-9/99	-0.046193	12.70615	Accept	3.6303502	3.6061161
11390	4/92-9/99	0.508544	2.014103	Accept	3.4929481	3.4107538
11391	4/92-9/99	1.249443	2.005745	Accept	3.6177204	3.4541800
15828	4/92-5/97	0.566872	2.028091	Accept	3.5792511	3.4654924
15827	4/92-12/96	1.726941	2.024394	Accept	3.8129875	3.4602464
11387	2/92-8/99	-1.238698	1.972267	Accept	3.6219088	3.7594991
15826	4/92-9/99	1.309009	1.999624	Accept	3.6073553	3.4053911
11385	4/92-5/97	0.685761	2.036932	Accept	3.8520537	3.7041645
15825	4/92-9/99	-0.332097	2.005745	Accept	3.8658688	3.9289380
15824	4/92-11/97	-0.294833	1.980097	Accept	3.9152356	3.9770959
16647	2/98-9/98	-1.780169	2.178813	Accept	3.5256923	3.9927876
16646	2/98-9/98				3.6705600	2.8920946

^a variable 1 - wet-weather data; variable 2 - dry-weather data

The null hypothesis is tested at the 95% confidence level

^b the null hypothesis is that the two datasets are not statistically different

The test performed was the t-test assuming unequal variances

The null hypothesis is rejected if $|t_{\text{stat}}| < t_{\text{crit}}$

Winter	Summer					
November	May					
December	June					
January	July					
February	August					
March	September					
April	October					

Table 2.13 includes the results of the comparison between winter and summer data. Data in Table 2.13 indicates that 7 out of 20 stations in Buffalo Bayou showed differences between summer and winter data with a significance level of 95%; whereas 5 out of 15 stations in Whiteoak Bayou exhibited statistically significant differences between the two datasets. Overall, 35% of the FC data showed seasonal variation. A possible explanation for this variation is that FC bacteria find the lysis of macrophytes a suitable environment and the macrophyte population has been found to be greater at higher temperatures. Further analysis of this variation will be pursued in future stages of the project.

In a further analysis, FC levels were plotted against temperature to investigate trends in the data. However, no significant correlation between FC and this parameter was found.

TABLE 2.13
STATISTICAL COMPARISON OF MEANS BETWEEN DATA SETS FOR WINTER AND SUMMER

Station	Date Range	t Stat	t crit. two-tail	Null hypothesis	Geomet	ric mean
Buffalo Bayou	I				wet	dry
11142	7/92-12/98	1.578241	1.978378	Accept	2.957314559	2.784865487
11364	4/92-9/99	-2.254039	1.999624	Reject	2.407891896	2.722206993
11363	4/94-9/99	-2.382813	2.009574	Reject	2.503962164	2.908569154
11362	2/92-9/99	-2.410936	1.984217	Reject	2.859685505	3.164371315
11361	4/94-9/99	-2.506242	2.003239	Reject	2.927843478	3.275974498
11360	4/92-9/99	-0.946336	1.97897	Accept	3.212435786	3.284777939
11359	4/92-9/99	-3.090529	1.992103	Reject	2.83532993	3.229866342
15846	4/92-9/99	-3.030494	1.989688	Reject	2.771609456	3.132765499
11358	2/94-8/96	-0.318736	2.306006	Accept	2.068063601	2.705749821
11357	4/92-9/99	-3.689897	1.990452	Reject	2.827112836	3.262283259
11356	1/95-6/99	0.588173	1.9758	Accept	3.484017135	3.395636096
15845	4/92-9/99	-0.857677	1.996564	Accept	3.010629892	3.149166444
11354	4/92-9/99	0.194218	1.998342	Accept	3.109992266	3.112200824
11353	4/92-9/99	-0.783583	1.987933	Accept	3.02403931	3.101790653
15844	5/92-12/98	-0.609863	2.004044	Accept	3.089493186	3.188306846
11351	2/92-9/99	-1.068701	1.969538	Accept	3.504764101	3.48749762
15843	4/92-9/99	-1.277454	2.021075	Accept	3.37986037	3.382783955
11347	1/95-6/99	0.4473	1.9763	Accept	3.839996822	3.779586872
15842	4/92-9/96	1.2170	2.178813	Accept	3.755794536	3.452783356
11345	2/92-9/99	-1.8302	1.979602	Accept	3.562297228	3.557983587
Whiteoak Bay	ou					
11398	2/92-8/96	-3.772476	2.144789	Reject	2.229362787	3.231422136
15831	4/92-9/99	-3.653375	2.019542	Reject	2.730733811	3.279218944
15830	4/94-9/99	-3.741897	2.005745	Reject	2.796158808	3.308417105
15829	4/92-9/98	-1.042317	2.048409	Accept	2.976973334	3.174770185
16637	2/98-9/99	0.046193	12.70615	Accept	3.606116142	3.630350244
11390	4/92-9/99	-0.882412	2.012894	Accept	3.395527678	3.492574978
11391	4/92-9/99	-2.271066	2.014103	Reject	3.368477377	3.630132888
15828	4/92-5/97	-1.33814	2.011739	Accept	3.438800759	3.58566843
15827	4/92-12/96	-1.369016	2.039515	Accept	3.510427807	3.75807293
11387	2/92-8/99	0.786326	1.972016	Accept	3.730720846	3.646683298
15826	4/92-9/99	-1.55001	2.016691	Accept	3.362607264	3.60568662
11385	4/92-5/97	0.798291	2.073875	Accept	3.951665885	3.767880241
15825	4/92-9/99	-0.164013	2.039515	Accept	3.877750384	3.89396839
15824	4/92-11/97	-0.294833	1.980097	Accept	3.915707038	3.95244084
16647	2/98-9/98	2.3373	2.228139	Reject	4.076010079	3.486243059
16646	2/98-9/98			,	2.892094603	3.670560011

^a variable 1 - wet-weather data; variable 2 - dry-weather data

The test performed was the t-test assuming unequal variances

The null hypothesis is rejected if $|t_{\text{stat}}| < t_{\text{crit}}$

The null hypothesis is tested at the 95% confidence level

^b the null hypothesis is that the two datasets are not statistically different

CHAPTER 3

ASSESSMENT OF MAJOR SOURCES, TRANSPORT AND FATE OF BACTERIA IN BUFFALO AND WHITEOAK BAYOUS

One of the main requirements of this TMDL effort is to identify sources of indicator bacteria within the Buffalo and Whiteoak watersheds (task 1.3 in Work Plan 582-0-80121-01). This chapter summarizes the available literature on sources and fate of fecal pathogens and bacterial indicators of fecal contamination in the environment; presents a summary of source assessments for other bacteria TMDLs conducted in recent years; and analyzes the potential sources of high bacteria levels in the bayous with the data that are currently available. The analysis is intended to aid in the identification of data gaps and support the development of a TMDL sampling plan.

3.1 LITERATURE REVIEW ON SOURCES, FATE AND TRANSPORT OF BACTERIA

This section provides a summary of the literature associated with sources, transport and fate of fecal pathogens and bacterial indicators of fecal contamination in the environment. Most of the discussion is focused on water contamination by fecal pathogens with the exception of a brief discussion on fecal coliforms in sediments. The first three sections deal with three elusive, poorly quantified sources of fecal pathogens: sediments, bird droppings and regrowth in riverine environments. Section 3.1.4 summarizes the literature on die-off rates of fecal coliforms (FC) and fecal streptococci

(FS). The remaining subsections in section 3.1 describe the various methods that have been used to distinguish between the sources of FC and FS (human or animal, etc) as well as a detailed discussion on bacterial indicators and DNA studies.

3.1.1 Sediments

Stream sediments have been shown to contain fecal coliforms at concentrations higher than those observed in the overlying water column. Ashbolt *et al.* (1993), Van Donsel and Geldreich (1971) and (Buckley *et al.*, 1998), for example, suggested that sediments may contain 100 to 1,000 times the number of fecal indicator bacteria contained in the overlying water.

Crabill *et al.* (1999) analyzed FC in water and sediment samples from Oak Creek, AZ. They found sediment samples with up to 2,200 times the FC counts of the water column. Results showed that resuspension of sediments due to agitation by recreational activities and storm events during summer season negatively impacted the water quality.

Studies on the survival of bacteria indicate that sediments present an environment favorable for growth. Fecal bacteria have been shown to survive and, to a certain extent, even to grow in sediments. Hood and Ness (1982) reported on the survival of *Vibro cholerae* and *Escherichia coli* in sediments and work by Gerba and McLeod (1976) and LaLiberte and Grimes (1982) showed evidence of survival and growth of *E. coli* in sediments.

Davies *et al.* (1995) studied the survival of fecal coliforms (FC), fecal streptococci (FS), and *Clostridium perfringens* spores in freshwater and marine sediments from sites near sewage outfalls. They observed that, in the absence of predators, fecal coliforms may grow in both freshwater and marine sediments, while under natural

conditions (presence of predators) a net die-off occurs. Authors also studied viable but nonculturable (VCN) formation of *E. coli* in aquatic sediments associated with sewage outfalls. Throughout the duration of the experiment (68 days), the same proportion of *E. Coli* organisms remained culturable, which suggests that sediment provide a favorable environment for bacterial growth. Furthermore, some studies show that sediments allow an extended survival of bacteria in comparison with water environments (Goyal and Adams, 1984; Hendricks, 1971; LaBelle *et al.*, 1980; Van Donsel and Geldreich, 1971).

Burton *et al.* (1987) tested four human-associated bacteria (*Pseudomonas aeruginosa*, *Salmonella newport*, *E. coli* and *Klebsiella pneumaniae*) for survival in five freshwater sediments. They found differences of up to 5 orders of magnitude in die-off rates among the different species. Results indicated that the levels of FC and other pathogens are higher in sediments than in the overlying water. The mechanisms contributing to high FC concentrations in sediments include adsorption, sedimentation, and extended survival. This study suggested that the sediment reservoir allowed the survival of enteric and pathogenic bacteria for several months; therefore, resuspension of bacteria may impact levels of FC in the overlying water.

Pommepuy *et al.* (1992) documented the accumulation of indicator bacteria and viruses in sediments and associated it to the sorption of the microorganisms to particles suspended in water, which sediment out. Furthermore, because light penetration is prevented by suspended matter, survival in sediments may be longer.

Marino and Gannon (1991) noted that balance between predation and growth could be reached and afterwards the bacteria levels would persist at fairly constant levels.

They concluded that storm drain sediments serve as reservoirs of high concentrations of FC and FS during warm, dry weather periods.

Analysis of sediment samples from recreational waters in UK by Obiri-Danso and Jones (2000) showed no obvious seasonal trend in FC numbers. Fecal indicators were found predominantly in surface layers and numbers decreased with depth. Results of experiments to study the *in situ* deposition of bacteria onto clean surfaces from the water column during tidal cover showed a deposition rate of 0.1% of the total population of FC. Results indicated that sediments act as a reservoir for fecal indicators.

Work by Erkenbrecher (1981) in an urban shellfishing subestuary also confirmed that sediments act as reservoirs of microorganisms in aquatic environments. Furthermore, Grimes (1975 and 1980) stated that sediments act as reservoirs of FC in aquatic environments and with turbulence they resuspend and increase water concentrations.

Baudart *et al.* (2000) compared *Salmonella* and fecal coliform loads to coastal water from a river and a wastewater treatment plant (WWTP) outfall. They found that bacterial loads from the river were higher than those from the outfall and were associated with small clay particles ($< 2\mu m$) originating from different reservoirs. The bacteria trapped in the particles-sediment accumulated in the downstream part of the river during the lowest water levels and were resuspended during storm events.

Pettibone *et al.* (1996) noted that ship traffic resuspends contaminated bottom river sediments, which may impact water quality. They observed increases in FC, heterotrophic plate count (HPC) and total suspended solids (TSS) immediately after the ship passed with the largest increases at the mid-channel sites. The authors determined that FC levels were strongly correlated with TSS in the water column suggesting re-

entrainment of particle-bound bacteria. They called attention to the fact that since flocculation affects the hydrodynamic properties of particles and their transport, the characteristics of flocculated sediment should be considered in water quality modeling.

Finally, results from laboratory experiments conducted by Howell *et al.* (1996) to measure FC and FS mortality rates at three different temperatures and in three fecesamended sediments with different particle size showed that rates declined as sediment particle size decrease and as temperature decreased. However, they found no interaction between these two factors and fecal bacteria persistence. Finally, they concluded that the FC/FS ratio was influenced by temperature, the presence of sediment, and sediment particle size.

3.1.2 Birds as Sources of FC

A number of papers in the general literature have indicated that bird droppings are a source of FC to recreational waters, presenting the possibility of disease transmission (Butterfield *et al.*, 1983; Furness and Monaghan, 1987; Gilliland and Baxter-Potter, 1987; PBS&J, 2000).

Levesque *et al.* (1993) investigated the effect of gull droppings on fecal coliforms in water by measuring fecal coliform concentrations before and after the presence of a significant number of gulls near a monitoring point in the St. Lawrence river, Quebec. They found that the concentration of FC in water increased rapidly as a consequence of an increase in the number of gulls and demonstrated that these two variables were closely related. An increase in the number of gulls presents a potential for health impacts as gull droppings have been shown to contain fecal material. For instance, gull droppings have shown the presence of *Salmonella* (Girdwood *et al.*, 1985; Kapperud and Rosef, 1983;

Kirkpatrick, 1986Butterfield, 1983 #3); *Campylobacter fetus* (Kapperud and Rosef, 1983; Whelan *et al.*, 1988); and *Yersinia* (Kapperud and Rosef, 1983).

3.1.3 Regrowth

After inactivation or injury of bacteria by disinfection processes (chlorination, UV, ozone addition), microorganisms may eventually reactivate and regrow, generating an increase in concentrations in the receiving stream. A number of studies in the general literature have shown evidence of regrowth, most of them, however, have been conducted in drinking water distribution systems and only two studies reported here report on reactivation in a WWTP effluent.

Hancock and Davis (1999) investigated photoreactivation and regrowth of FC in effluents of WWTP using UV as disinfectant. Authors reported that "shielding of bacteria ingested in *Daphnia sp* in the plant outfalls was shown to be a major contributor to increased fecal coliform, *E. coli*, fecal streptococci and enterococci after fragmentation of the Daphnia due to normal dieoff."

Sanchez-Ruiz *et al.* (1995) investigated the potential regrowth of bacteria in wastewater disinfected with peracetic acid (PAA) after discharge of the treated water to the ocean. After disinfection and mixing with seawater in laboratory experiments, total coliforms presented higher T90 values and disappearance times and showed increased concentrations in darkness.

Joret *et al.* (1991) reported a strong relationship between biodegradable dissolved organic carbon (BDOC) values and the regrowth potential of bacteria in samples inoculated with a natural biomass, fixed on sand particles.

Mechsner *et al.* (1991) pointed out that bacteria damaged by UV could undergo repair and regain activity. Their paper showed evidence of regrowth of sublethally UV-injured bacteria. This is relevant as exposure to light is warranted in surface waters.

Muyima and Ngcakani (1998) investigated the quality of drinking water in Alice, Eastern Cape. They measured regrowth of heterotrophic bacteria, total and injured coliforms in the chlorinated water. Results showed remarkable regrowth of these bacteria associated with high biodegradable dissolved organic carbon content.

Power and Nagy (1999) reported bacterial regrowth within Sydney's drinking water distribution system. The presence of high bacterial numbers correlated to turbidity and distance from the initial treatment point.

Springthorpe *et al.* (1993) compared the survival of *E. coli*, *Enterococcus durans*, MS-2 phage, poliovirus type 1, and hepatitis A virus (HM-175) in river water under identical conditions. Results showed that the survival patterns of *E. coli* in nutrient rich river water were highly variable and a 10-fold or greater increase in numbers of E. coli was sometimes observed. In addition, no regrowth was observed for *E. durans* and the phage survival was similar to that of the human pathogenic viruses.

3.1.4 Factors Affecting Survival/Die-Off

Several studies have focused on the factors affecting the survival of bacterial microorganisms in water and some have even provided rates of loss for such organisms.

This section presents a summary of the literature reviewed to date pertaining to this topic.

Auer and Niehaus (1993) conducted field and laboratory studies to develop and verify the kinetic expressions required to simulate the loss of FC in lakes due to die-off and sedimentation. They observed no consistent relationship between the dark die-off rate

(0.73/day) and temperature. The irradiance-mediated death rate was shown to be proportional to irradiance. They also estimated a settling loss rate of 1.38 m/d.

Burkhardt *et al.* (2000) investigated the effect of various factors on the survival of FC, *E. coli, Clostridium perfringens*, and male-specific bacteriophage (MSB) in estuarine waters. They found that sunlight and/or temperature have the greatest impact on indicator decay rates. Exposure to sunlight accounted for a reduction of up to 99% of the FC density, being the indicator affected the most by this parameter. For FC the effect of sunlight was most pronounced in winter than during summer.

Research conducted by Dan *et al.* (1997) showed that the survival of bacteria (*E. coli* and enterococci) was highly dependent on environmental conditions. Inactivation of *E. coli* appeared to be initiated by light, even though the presence of sulfide also made the cells non-culturable.

El-Sharkawi et al. (1989) investigated the effects of certain environmental factors on the die-off of Salmonella typhi, Salmonella wein, Shigella flexneri, and E. coli in different types of water. Results showed no great difference in the survival times of the organisms tested at temperatures between 25-35°C, but the rate of die-off was higher at 40°C. Salmonella bacteria were not affected by salinity, however Sh. flexneri and E. coli appeared to survive longer in freshwater than in seawater. Sunlight was shown to have a negative impact on the survival of all the tested organisms, but artificial light had a smaller effect.

Esham and Sizemore (1998) conducted an intensive monitoring of fecal coliforms in Futch Creek, NC in an attempt to determine sources of pollution. Effects of various environmental factors were evaluated. Results showed higher FC levels in warmer

temperatures as well as an inverse relationship between FC counts and salinity. Tidal cycles also affected FC counts with substantially higher counts during low tide; tidal effect appeared to be more important than rain events.

Results from laboratory experiments conducted by Howell *et al.* (1996) to measure FC and FS mortality rates at three different temperatures and in three fecesamended sediments with different particle size showed that rates declined as sediment particle size decrease and as temperature decreased. However, they found no interaction between these two factors and fecal bacteria persistence. Finally, they concluded that the FC/FS ratio was influenced by temperature, the presence of sediment, and sediment particle size.

Nasser and Oman's (1999) work indicated that the inactivation of viral agents in water depends on the water quality, temperature and microorganism type. The effect of temperature was found to be microorganism type dependent but, in general, virus inactivation increased with increased temperature. The inactivation rate of E. coli was higher than that of hepatitis A virus (HAV) and poliovirus 1 at lower temperatures. The effect of temperature was significant in GW and less significant in raw wastewater (enhanced virus persistence). Male-specific bacteriophages persisted for the longest time in the various water types, whereas *E. coli* inactivation was the fastest in GW at 4°C and 37°C. F+ bacteriophages were shown to be more suitable than *E. coli* for predicting inactivation of pathogenic viruses in natural waters. The inactivation of male-specific bacteriophages was lower than that of *E. coli* under all experimental conditions, suggesting greater persistence in water and, consequently, the possibility of being a more suitable indicator.

Olson *et al.* (1999) found that oocysts could survive at -4 and 4°C in water and soil for more than 12 weeks but degradation was accelerated at 25°C, which suggests a strong relationship between die-off rates and temperature. On the other hand, Pathak and Bhattacherjee (1994) stated that microbial survival is highly dependent upon the trophic state and concentration of different pollutants.

FC, FS and salmonella were measured from water and sand samples to evaluate the extent of marine pollution due to occasional untreated wastewater discharges. Samples were taken 5 and 10 m away from an emergency outfall. It was found that the intensity of accumulation of fecal indicators was reduced 50% from the 5 to the 10 m locations. Bacteria showed inactivation due to solar radiation (Shatti and Abdullah, 1999).

Sinton *et al.* (1999) compared sunlight inactivation rates of somatic coliphages, F-specific RNA bacteriophages (F-RNA phages), and FC using sewage-seawater mixtures. They found sunlight inactivation rates higher than dark inactivation rates for all the tested organisms, being the greatest for FC. They observed that raw sewage FC were inactivated faster than pond effluent FC. In addition, inactivation rates decreased with the increase in spectral cutoff wavelength.

3.1.5 Indicators

Extensive research has been conducted over the years to find an organism that serves as quantitative indicator of the extent of fecal contamination in water. This section presents a summary, by no means comprehensive, of such studies.

Burkhardt *et al.* (2000), while investigating the effect of various factors on the survival of FC, *E. coli*, Clostridium perfringens, and male-specific bacteriophage (MSB)

in estuarine waters, found that FC was the indicator affected the most by sunlight and that the effect was most pronounced in winter than during summer. Overall, FC decay rates were very different to those found for MSB. Therefore, authors concluded that FC may not be a good indicator of viruses in estuarine waters.

Crane and Moore (1986) called attention to the fact that fecal streptococci provide information on relative age of contamination since streptococci die-off more rapidly in the environment than do coliform organisms.

Elmund *et al.* (1999). after conducting a study to correlate *E. coli*, TC and FC in WWTP effluent and a receiving stream, suggested that *E. coli* is a good indicator of fecal contamination in water and would provide greater health protection for contact recreation and human consumption than the traditional FC group.

Furuse (1987) concluded that male-specific RNA coliphage are better indicators of human sewage where they are commonly found than animal feces where they have shown a low and sporadic recovery rate

Hadas *et al.* (2000) conducted an interdisciplinary biological, physical and chemical approach to determine the distribution of bacteria and river alluvium at the mouth of the Jordan river, Israel. Results from the distribution of FC analysis showed that the maximal longitudinal gradient was at the bar, so FC can be used as indicator of fecal contamination coming from the river and entering the lake. FC varied accordingly to attenuation of flow velocity. At the entrance to the bar, sedimentation was found to dominate, while dilution was the process dominating beyond the bar.

Huysman et al. (1993) pointed out that C. perfringens is a very specific indicator of pollution of manure origin. Kay et al. (1994) conducted research at beaches in the

United Kingdom and found enterococcus a better indicator than coliform for predicting the likelihood of gastroenteritis. They demonstrated a mathematical relationship between gastroenteritis and fecal streptococcus.

Miyabara *et al.* (1994) pointed out that urobilin indicates fecal contamination over long period of time, while NH4-N and total coliforms indicate more recent contamination. This study attempted to classify urban rivers on the basis of these parameters to estimate the origin of water pollution.

Nasser and Oman (1999) research's results showed that F+ bacteriophages are more suitable than *E. coli* to predict inactivation of pathogenic viruses in natural waters. In their experiments, the inactivation of male-specific bacteriophages was lower than that of *E. coli* under all experimental conditions, suggesting greater persistence in water and, consequently, the possibility of being a more suitable indicator.

Nuzzi and Burhans (1997) conducted a water quality study of bathing beaches in the Suffolk County, NY. This study was conducted to compare the total- and fecal coliform standards to a proposed enterococcus standard. Results showed that enterocuccus values correlated well with coliform values but enterococcus standard would result in increased beach closures.

Puig et al. (1997) found that strains HSP40 and RYC4023 of *Bacteroides fragilis* selectively detect bacteriophages excreted by humans. The authors performed tests on the specificity of detection using slaughterhouse wastes and found that the procedures may be useful for fingerprinting human fecal pollution.

Sinton *et al.* (1999) compared sunlight inactivation rates of somatic coliphages, F-specific RNA bacteriophages (F-RNA phages), and FC using sewage-seawater mixtures.

They found that inactivation rates decreased with the increase in spectral cutoff wavelength and indicated that FC and F-RNA phages are more susceptible than somatic coliphages to longer solar wavelengths, which suggested that the later could be a better indicator of fecal contamination in seawater.

Sobsey *et al.* (1998) conducted a study on alternative indicators where a wide range of indicators of fecal contamination were evaluated. The studied indicators include Coliphages, Bacteri-phages, Male-specific (F+) coliphages, *Bacteroides fragilis* phages, Salmonella phages, Fecal coliforms, Enterococci, and *Clostridium perfringens* spores. The authors reported that conventional indicators (FC, EN) did not adequately represent the degree of fecal contamination of water and did not predict the presence of viruses in oysters. Results showed that F+ coliphages and *C. perfringens* are good predictors of the degree of wastewater input and of enteric viruses. *B. fragilis* and *Salmonella* phages were reported to be relatively unsuitable.

Springthorpe *et al.* (1993), as discussed in section 2.4, compared the survival of *E. coli, Enterococcus durans*, MS-2 phage, poliovirus type 1, and hepatitis A virus (HM-175) in river water under identical conditions. The observations concerning *E. coli* (variable survival and potential for regrowth) questioned the suitability of *E. coli* as water quality indicator; MS-2 appeared to be a good indicator.

3.1.6 Source Identification

It is well known that contamination by FC in recreational waters is caused by a number of sources that may or may not be of human origin. For example, Conboy and Goss (1999) sampled over 300 rural drinking water wells throughout Southern Ontario and 148 wells in rural Zimbabwe for bacteriological water quality. The bacteriological

quality was assessed measuring TC, FC, and FS and determining the presence or absense of *Clostridium perfringens*. They found that a significant percentage of the bacteria of fecal origin in rural wells came from animal manure and human waste disposal systems (septic tanks or latrines). Therefore, the use of only one or two bacterial indicators is not always effective to locate the source of contamination due to the multiple pollution sources.

Several methods have been suggested to attempt distinguishing the sources of contamination as will be summarized in the following paragraphs.

Atypical colonies

Brion and Mao (2000) conducted research on the relationships between atypical colonies (AC) from total coliforms (TC) tests and other bacterial indicators in a watershed impacted by agricultural and urban animals. TC, FC and coliphage (CP) were monitored at eight locations including sites impacted by raw sewage, agricultural runoff, urban runoff, and a mixture of urban and agricultural runoff. Results showed a clear relationship among AC concentrations, fecal pollution sources, and pollution levels. AC concentrations correlated well with FC but did not do so with total CP. The ratio of AC to CP correlated well with the degree of fecal pollution. The authors concluded that the AC, when used in conjunction with other indicators, may provide an additional tool for monitoring fecal contamination. Specifically, data from their study suggested that the ratio AC (coliforms, possible coliforms, and noncoliform opportunistic pathogens) to TC might help in identifying urban runoff from agricultural sites. Furthermore, this ratio may provide insight into the age of fecal pollution although more research is needed to confirm this conclusion.

Bile acids

Elhmmali *et al.* (1997) studied the use of bile acids as an indicator of sewage contamination. They found the major bile acids to be more resistant to decay during wastewater treatment than coprostanol. He was able to differentiate between the bile acids of humans and pigs, which makes this method potentially adequate for indicating human sewage. It was pointed out that further research would be needed prior to implementing this method, though.

Elhmmali *et al.* (2000) combined the use of bile acids, stanols and sterols to assess the sources of fecal matter into the Avon River, Bristol, UK. The concentrations of fecal bile acids increased along the course of the river in agreement with the results obtained for coprostanol, the traditional indicator of fecal pollution and other related stanols and sterols. On the contrary, non-fecal sterols and stanols decreased in concentration as compared to coprostanol and other fecal indicators in the lower reaches of the river. Results of bile acid analyses supported their use as sewage contamination markers. Authors concluded that a combined multimolecular approach provided an improved tool to assessing fecal matter inputs into aquatic environments.

DNA Analysis - Polymerase Chain Reaction (PCR)

Polymerase Chain Reaction (PCR) is an enzymatic reaction that is used to amplify DNA for very sensitive detection of DNA sequences. After amplification, a variety of methods and probes can be used to visualize the presence or absence of the targeted sequence. Amplification of the *uidA* gene, which codes for a specific enzyme in *Eschericia coli*, and subsequent Southern blotting has been used to successfully identify *E. coli* in polluted river water (Iqbal *et al.*, 1997). Oberst *et al.* (1998) used Multiplex

PCR to target multiple genes simultaneously. They noted that once the DNA has been amplified, the amplified product must be detected in order to confirm its presence. This can be done through gel electrophoresis, Southern blots or dot blot hybridizations with probes, and more recently 5' nuclease assays. Oberst *et al.* (1998) investigated the applicability of 5' nuclease assays to detecting PCR products, specifically *E. coli* 0157:H7. A fluorogenic TaqMan probe was designed and used in the automated amplification/detection process. The assay Obert *et al.* proposed was successful in detecting *E. coli* 0157:H7 in a specific, rapid manner.

Nested PCR has also been used amplify the *uidA* gene. Nested PCR increases sensitivity by using the product of the first PCR cycle as a template for the second cycle of PCR. The amplified DNA is visualized on an agarose gel stained with ethidium bromide. This method provides rapid results with detection of 1-10 cells/50 mL, as contrasted by the two to three days required for Southern blotting and biochemical detection methods (Juck *et al.*, 1996).

Arias *et al.* (1998) combined cultural-based methods and PCR, as well as comparing primers and PCR versus nested PCR to differentiate *Vibrio vulnificus* (an important pathogen that causes primary septicemia and necrotizing wound infection in addition to gastroenteritis). The PCR based methods of detection proved to have fewer positives than the cultural based methods, presumably providing more accurate results since they overcome the viable but non-cultural problems posed by this organism.

Fricker and Fricker (1994) conducted a study to determine the potential use of two sets of primers (*uid A* gene and *lac Z* gene) for the simultaneous detection of *E. coli* and coliforms. They concluded that the polymerase chain reaction (PCR) can be used for

the rapid identification of *E. coli* using these primers, with a substantial reduction in time when compared conventional analytical methods.

Work by Gilgen *et al.* (1995) looked at using reverse transcription PCR (RT-PCR) to detect enteroviruses in water samples from rivers and lakes. Gilgen *et al.* (1995) noted that traditional methods of detection are often time consuming and labor intensive. The detection system Gilgen *et al.* developed did detect enteroviruses, but also found significant amounts of non-specific amplification products. The authors compared PCR detection of *Escherichia coli*, *Salmonella* spp. with the RT-PCR for enterovirus. All samples that tested positive for *E. coli* also tested positive for enterovirus.

McDaniels *et al.* (1996) tested various bacteria for *gadA/B*, the gene that the glutamate decarboxylase which is specific to *E. coli*, and compared phenotypic and genotypic detection methods. Bacterial DNA was amplified using polymerase chain reaction (PCR) and visualized using slot blot hybridization. Genotypic assays using PCR and gene probes provide a higher degree of accuracy for *E. coli* detection than simple enzymatic assays. Both the *gadA/B* and *uid* gene are highly specific to *E. coli* and either will provide accurate detection.

E. faecium has several different strains which are different to resolve with cultural and PCR techniques. Quednau et al. (1999) proposed restriction endonuclease analysis as a method to separate the strains. Although there is some question as to whether Enterococcus strains and/or antibiotic resistance can differentiate between human and non-human sources, the findings of Quednau et al. (1999) suggested that they may be good indicators.

Tani *et al.* (1998) have shown that direct in situ PCR can be performed to detect *E. coli* with highly reliable results using the HNPP (2-hydroxy-3-naphtonic acid-2'phenylanilide phosphate)-Fast Red TR system. The authors used fluorescence to visualize the PCR amplified sequences that are specific for various bacterial strains, including *Escherichia coli*. In-situ PCR (inside the cell as opposed to lysing the cell to release the DNA) was performed with EUB and ECOL primers. The technique used by Tani *et al.* (1998) was found to be effective at differentiating *E. coli* from other bacteria. Tani *et al.* also employed image analysis to assist in distinguishing bacterial cells from background fluorescence. The method described was found to be an effective technique for evaluation of bacterial presence in natural waters and an also determine the relative number of *E. coli* in the sample.

Ribotyping

Ribotyping is a methodology that can be used to identify and classify bacteria based upon differences in DNA, specifically the rRNA genes. Ribotyping was successfully used to discriminate *E. coli* from different sources (Parveen *et al.*, 1996; Tarkka *et al.*, 1994).

Parveen *et al.* (1999) studied 238 *E. coli* isolates from human sources (HS) and nonhuman sources (NHS) collected from the Apalachicola National Estuarine Research Reserve associated with WWTP discharges and animal wastes. The isolates were examined for differences by ribotype (RT) profile analysis. Discriminant analysis (DA) of RT showed that 97% of the NHS and 100% of the animal fecal isolates were classified correctly and the average rate of correct classification for HS and NHS isolates was 82%, which suggested that this method is appropriate for distinguishing between human and

animal fecal contamination. DA of antibiotic resistance patterns of fecal streptococci is useful in differentiating human vs. animal sources of fecal pollution in water. However, this method has some disadvantages including the fact that the antibiotic resistance patterns of bacteria are influenced by selective pressure and, consequently, may vary according to geographical location and over time.

Fecal Coliform to Fecal Streptococci Ratio (FC/FS)

Analyses of water samples collected from the lower Buffalo River, NY for a 2-year period showed evidence of the importance of runoff as a source of bacteria into the river. Average FC concentrations significantly increased with the increase in urbanization. Ratios of FC/FS were successfully used to identify human sewage sources (Irvine and Pettibone, 1996). Pourcher *et al.* (1991) successfully used the ratio between FC and FS as a method for source determination.

However, Toranzos and McFeters (1997) showed that the ratio of FC to fecal streptococci depended upon animal type and time in the environment. Thus, this ratio is an inadequate indicator of fecal contamination in watersheds where the polluting source is far away from the area of use. Brion and Lingireddy (1999) also reported that the analysis of FC/FS ratios in seven different sites representing different degrees of fecal contamination was not able to differentiate between urban and agricultural sources

Sediment bags

Nix *et al.* (1993) used sediment bags (porous bags filled with sand) suspended in the water to identify sources of fecal contamination. Authors pointed out that these bags integrate water quality data with respect to FC concentrations and retain coliform bacteria

after their initial sorption to the sand substrate. Therefore, they can identify contaminant sources even if sampling is carried out after the pollution event.

Nix *et al.* (1994) used sediment bags suspended from buoys and organized in a grid pattern around the beach to assess sources of fecal contamination. The bags eliminated the difficulty in documenting the occurrence of episodic contaminant sources and, consequently, were appropriate in tracing the pattern of the pollution plume and revealing the source. The authors found that fecal contamination of a local beach in North Vancouver, BC, Canada mainly came from storm sewers.

Antibiotic resistance

Multiple antibiotic resistance (MAR) was shown to be appropriate in differentiating point and nonpoint sources of *E. coli* in an estuarine environment (Parveen *et al.*, 1997).

Wiggins (1996) demonstrated that discriminant analysis (DA) of antibiotic resistance patterns of FS is a useful tool for differentiating human and animal sources of fecal pollution in water. He correctly classified 92% of human source (HS) isolates with an average rate of correct clasification (ARCC) of 84%.

Wiggins *et al.* (1999) conducted an antibiotic resistance analysis for identifying the sources of fecal pollution in surface and ground water. Individual classification of isolates yielded an average rate of correct classification (ARCC) into four possible types (human, cattle, poultry, and wild) ranging between 64 and 78%. Higher ARCC (96-100%) were obtained when the resistance patterns of all isolates from each sample were averaged and the resulting sample-level resistance patterns were classified. Results

demonstrated that antibiotic resistance analysis can be used to classify and identify these sources.

Neural network

A neural network model was successfully implemented to distinguish between urban and agricultural fecal contamination in inputs to a drinking water reservoir. The model used bacterial (FC, FS, TC, and coliphage) and weather data to differentiate between three site classifications: urban, agricultural, and a mixture of these. Analysis of coprostannol and serotyping of male-specific coliphage demonstrated the absence of human sewage (Brion and Lingireddy, 1999).

3.1.7 Summary of Literature Review Findings

The literature review to date resulted in several findings which are relevant to this TMDL project:

- 1. Previous research indicates that stream sediments have higher FC levels than the overlying water column and that sediments provide a favorable environment for regrowth. Additionally, and subject to perturbations, resuspension of FC from sediments may occur and negatively impact water quality.
- 2. Birds have been confirmed as potential sources of FC into streams.
- 3. A limited number of studies (2) reported regrowth of bacteria from WWTP effluent in laboratory conditions. Other regrowth studies indicated a dependency on BOD levels to promote regrowth.
- 4. Bacterial die-off rates appeared to be influenceed by sunlight, temperature, sulfide levels and salinity.

- 5. Numerous tests have been evaluated as indicators of bacterial contamination including fecal streptococci, *E. coli, Clostridium. perfringens*, urobilin, F+ bacteriophages, *Bacteroides fragilis*, Coliphages, *Salmonella*, and *Enterococcus durans*.
- 6. Several methods have been suggested for source identification including atypical colonies, bile acids, Polymerase Chain Reaction (PCR), Fecal Coliform to Fecal Streptococci Ratio (FC/FS), sediment bags, antibiotic resistance analysis, ribotyping, an neural networks.
- 7. Source identification (specially DNA studies) are useful to locate the main sources contributing to FC contamination at a given watershed.

3.2 LITERATURE REVIEW ON SOURCE ASSESSMENT IN OTHER TMDL PROJECTS

TMDLs on pathogens have been completed throughout the United States. Within these projects, numerous sources of bacterial contamination have been identified. Some of these projects have been summarized below to give an overview of the findings.

Choctawhatchee River, Florida (3 segments)

The US EPA Region 4 office prepared a proposed TMDL for three segments in the Choctawhatchee River for the designated uses of primary contact recreation and fishing (US EPA Region 4, 2000b). The watershed for the Choctawhatchee river covers a total of 5,362 square miles and the primary land uses are forest (44%), agricultural (22%), pasture (15%) and wetlands (16%). The only point sources that were considered in the TMDL development were wastewater treatment plants (WWTPs) with flow greater

than 1 MGD. This resulted in a total of 9 WWTPs being included, and their total combined flow was 24.715 MGD. Non-point sources (NPS) identified were pasture runoff from grazing livestock, cropland runoff, failing septic systems, wildlife contributions, cattle in streams, and urban and residential storm water runoff. BASINS and NPSM were used to link the water quality target and the source loadings. Load allocations were obtained from either literature values or calculations based upon land use, density, and fecal coliform production rates. The total load allocation for NPS was 9.8035×10^{16} cfu/30 days.

Choctawhatchee River, Florida (4 segments)

Four additional segments in the Choctawhatchee River, FL were also identified for TMDL development (US EPA Region 4, 2000a). These segments have impairments that impact their designated uses of PCR and fishing. Within these watersheds, the primary land use is agriculture, forested land and cropland comprising the main agricultural uses. Only 3 WWTPs are found within this watershed, and there have been documented permit exceedances for all of them. NPS sources include pasture runoff from grazing livestock, cropland runoff, failing septic systems, wildlife contributions, cattle in streams, urban and residential storm water runoff. Poultry and land-application of sludge are also potential sources of FC bacteria.

BASINS and NPSM were used to determine the loading reductions for each segment. Cattle in the streams and failing septic systems were modeled as direct sources to the river. Based upon model calculations, the following reductions were recommended: Alligator creek: 2.79%, Camp Branch: .78%, and Fish Branch: 20.66%. No loading reductions were recommended for Bruce Creek.

Ravine Lake, SD

Ravine Lake in South Dakota had water quality impairments due to non-point source inputs from livestock grazing runoff, livestock feeding operations, and storm sewer discharge to the lake (SDDENR Department of Environment & Natural Resources, 1999). No point sources were identified in the study. Ravine Lake is designated for warm water semi-permanent fish life, immersion recreation, and limited primary contact recreation. Modeling was performed using AGNPS and the end point for the TMDL was determined to be when every grab sample taken meets the 400 cfu / 100 mL water quality standard. Best Management Practices (BMPs) were implemented to meet the TMDL, including fencing of the lake shore to prevent direct livestock access. Follow-up monitoring showed that the fecal coliform levels had been reduced to below the water quality standard.

Aucilla River, Georgia

Aucilla River in Georgia has a designated use for fishing. In the 87 square mile watershed, 17% of the land use is forested, 29% is crop land, and 15% is woody wetland. No point sources were identified, but non-point sources were determined to be agricultural runoff from grazing, leaking septic systems, wildlife, and urban development (US EPA Region 4, 2000c). This TMDL includes detailed information regarding the NPSM/HSPF model assumptions. High fecal coliform values are not simulated in the model because the rainfall at the meteorological station did not always reflect the rainfall that was occurring in the watershed. A 58% reduction of FC concentrations is required to meet the load allocation of 3.24x10¹² cfu/30 days.

Duck Creek, Alaska

The 1080 acre watershed in Duck Creek in Mendenhall Valley, Alaska has a primary land use of residential (50%) followed by commercial (26%) and recreation/wetland (16%) (US EPA Region 10, 2000). No point sources were identified in the watershed, but NPS of fecal coliform were urban runoff and domestic animals. Also, there was an impounded portion of the creek that was impounded that could also be a source of elevated FC since it attracts wildlife such as ducks. No flow data were available for the impoundment, and consequently no downstream impacts could be calculated. Overall, very little data was available for the TMDL modeling. A load allocation of 2.23x10¹¹ FC per year, which translates into a reduction of 38%, was recommended through modeling with SWMM. Control mechanisms such as storm drain stenciling and public education on proper handling of pet waste were recommended to help meet the recommended reduction in FC.

Bayou Teche, Louisiana

Three segments in Bayou Teche, Lousiana were targeted for FC TMDL development (US EPA Region 6, 2000b). The stream segments were listed for impairment of primary contact recreation. The primary land use in the watershed is agriculture, followed by urban land use as well as some wetland and forested areas. Point sources were identified to be 30 WWTPs that have a combined flow of 3.9 MGD. Nonpoint sources include agriculture and urban runoff and possibly leaking septic tanks. A loading curve was used to calculate the loading capacity of the watershed. The total waste load allocation for point sources was 2.99x10¹⁰ cfu/day while the total load allocation for NPS was 1.84x10¹² cfu/day. These allocations result in a 738% reduction of FC in the bayou. In order to achieve these reductions, the LADEQ (Louisiana

Department of Environmental Quality) proposed to stringently enforce WWTP permits and work with stakeholders to implement BMPs.

Bayou Plaquemine Brule, LA

Bayou Plaquemine Brule in Louisiana (segment 050201) was targeted for FC TMDL development (US EPA Region 6, 2000a). The stream segment was listed for impairment of primary contact recreation. The watershed of Bayou Teche receives 57 inches of rainfall per year. Agriculture is the primary land use within the watershed comprising 89% of the total area. Seventeen WWTPs discharge into Bayou Plaquemine Brule for a total combined flow of 5.3 MGD. Suspected NPS are agriculture and urban runoff, as well as possibly leaking septic tanks. Loading curves were used to calculate the loading capacity of the waterbody. In May through October, the loading capacity was found to be 1.4x10¹³ cfu/day and in November through April it was 7.98x10¹³ cfu/day. To meet water quality standards would require a 481% reduction in FC concentrations in May through October and 272% reduction in November through April.

Ochlockonee River, Florida

A TMDL for FC has been developed for two segments on the Ochlockonee River in Florida (US EPA Region 4, 2000d). The designated use for the segments is fishing. The land use in the watershed includes row crops, pasture and forest. One point source was identified as a water pollution control plant with a permitted flow of 4 MGD. In addition, leaking sewer lines, animals in the stream and leaking septic systems were considered point sources for modeling purposes. Agricultural and urban runoff were the NPS of fecal contamination. After modeling with NPSM/HSPF, a 66% reduction in fecal coliform concentration was recommended.

Vermilion River, Louisiana

In Louisiana, a TMDL for primary contact recreation was developed on Vermilion River, segments 060801 and 060802 (US EPA Region 6, 2000c). This area receives approximately 60 inches of rainfall per year and the primary land uses in the watershed are cropland and pasture (78%) and urban (10%). Within the Vermilion River watershed, there are 149 wastewater treatment plants (WWTP) with a total flow of 30.8 million gallons per day (MGD). Nonpoint sources (NPS) were identified as agricultural and urban runoff in addition to leaking septic tanks, sanitary sewer leaks and wild and domesticated animals. Following modeling with loading curves based upon in-stream bacterial counts and stream flow, a reduction of 733% was recommended for May-October and 225% reduction was recommended for November – April.

Lake Chelan, Washington

Lake Chelan in Washington was targeted for TMDL development for phosphorous and fecal coliform to protect it as a special resource (US EPA, 1994). The 924 square mile watershed surrounding Lake Chelan is largely forested and undisturbed. The lake is 50 miles long, with an average width of 1 mile and a maximum depth of at least 1,486 feet. The population in the surrounding areas of the lake fluctuates based upon seasonality but was approximately 6,600 in 1987. Control mechanisms recommended to decrease fecal coliform concentrations included encouraging individuals to change to public sewerage, boat sewage pump-outs and agricultural and storm water management.

Okatoma Creek, Mississippi

The Okatoma Creek was selected for TMDL development so that the creek would meet its designated uses of primary contact recreation. The main land use of the watershed is forest (62%), followed by pasture (31%). Several sources were identified, including two of four WWTPs that regularly exceed their permitted effluent limit, and leaking septic systems and cattle defecating directly into streams. After modeling different scenarios with BASINS and NPSM, the researchers concluded that a 75% reduction in cattle in the stream and a 50% reduction in the leaking septic system load would be adequate to reduce the nonpoint source contributions. In addition, all WWTPs are required to meet the 200 cfu / 100 mL water quality standard.

Blackwater River, Florida

A TMDL for bacteria was developed for six segments in the Blackwater River Watershed (U. S. EPA Region 4, 2000e). The 853 square mile watershed of the Blackwater River in Florida is 65% forested, 12% cropland, and 9% wetlands. Only wastewater treatment plants with flows of greater than 1 million gallons per day were considered point sources for the TMDL. In the Blackwater River watershed there is only one such plant. Nonpoint sources of fecal pathogens include pasture runoff from grazing livestock, cropland runoff, failing septic systems, wildlife contributions, cattle in streams, and urban and residential storm water runoff. The load allocation was calculated using BASINS and NPSM to be 5.08x10¹⁷ cfu/100 mL and the waste load allocation was calculated to be 2.63x10¹¹ cfu/100 mL. Management strategies for the nonpoint sources include BMP implementation for the agricultural sources.

Republican River, Kansas

The Kansas Department of Health and Environment developed a TMDL Curve as their methodology for assessing the loading capacity of the Republican River (KDHE, 1999). This method allows the loading capacity to vary as the flow changes. To obtain the curve, first a flow duration curve is developed, where the flow is graphed versus the percent of days where the flow exceeded. From this information, a load duration curve is calculated. This is done by multiplying the concentration of the target constituent by the average daily flow. This approach allows researchers to pinpoint the sources of the contamination, whether point source or non-point source.

3.3 SOURCES OF BACTERIA IN BUFFALO AND WHITEOAK

As discussed in Chapter 2, both Buffalo and Whiteoak bayous have indicator bacteria levels that are higher than the contact recreation criteria all the way from the most upstream to downstream stations. The bacterial indicator employed to date is the Fecal Coliform (FC) test. The FC geometric means appear to increase from upstream to downstream, indicating potential inputs of FC bacteria from tributaries, point source outfalls, non-point and other possible sources along the bayou channels. While the density of monitoring stations on the bayous is very good compared to many streams in the state, the data collected on these stations are in general not sufficient to identify specific FC sources in the watershed. Thus, additional sampling specifically designed to identify sources will ultimately be needed. Therefore, this analysis of possible sources using existing watershed data, as well as the analysis of bayou data, will be the technical

basis for specifying the additional sampling described in the Bayou Monitoring Plan section of this quarterly report.

The potential sources of high indicator bacteria levels observed in the bayou include (in no particular order):

- 1. Treated effluent from point sources not disinfected completely,
- 2. Regrowth or reactivation of bacteria after point source discharge,
- 3. Discharge of untreated sewage due to sewer leaks or blockage,
- 4. Bacteria inputs from illicit dischargers,
- 5. Discharge of untreated sewage from failed on-site wastewater systems located in un-sewered areas,
- 6. Bacteria from upstream sources,
- 7. Bacteria from birds concentrated at bridges,
- 8. Bacteria from runoff, and
- 9. Bacteria associated with stream sediments.

This list of potential sources may not be exhaustive. If any additional sources are identified they will be added to the list.

The following sections provide a more detailed discussion of data collected and conclusions drawn for each of the potential sources listed above.

3.3.1 Incomplete Disinfection of Point Sources

In dry weather essentially all of the flow in both Buffalo and Whiteoak bayous is from point source discharges. Any search for understanding of water bacteria levels must start with this source of water. These discharges are required by their discharge permits to maintain a chlorine residual of 1 mg/L for at least 20 minutes at the design maximum

permitted flow. If the permitted capacity is 1 MGD or larger than, plants are required to dechlorinate down to a concentration of <0.01 mg/L. In practice, the chlorine contact time is much longer in dry weather and low flows. If all of these requirements were met, in theory there should be very low levels of indicator bacteria in the effluents. Since the effluents essentially are the entire bayou flows in dry weather, low bacteria levels should be the norm.

The practice appears to be very different from the theory since high FC levels have been recorded in the bayous during dry weather. Sampling done as part of a recent Greens Bayou Intensive Survey revealed that 5 of 12 samples from the smaller Wastewater Treatment Plants (WWTPs) had FC concentrations > 200 cfu/dL (colony forming units per deciliter), and that 2 of 12 samples were near 10,000 cfu/dL (City of Houston Public Works and Engineering Department, 1999). One of the problems with smaller plants may be poor control over the chlorination process. While the City of Houston treatment plants in these stream segments have a sophisticated system to regulate the dosage of disinfectant and the sodium bisulfite dechlorination agent, that is not true for many of the smaller facilities. The lack of automatic control, plus the fact that these plants are checked infrequently, may mean that high levels of indicator bacteria are not at all uncommon.

Figure 3.1 shows the locations of permitted wastewater dischargers in the two watersheds. There are 9 major WWTPs (≥ 1 MGD) in Buffalo and 5 in Whiteoak Bayous, respectively and 80 and 48 minor ones, respectively. Domestic discharges with a permitted flow of 1 MGD or more are shown with a larger symbol because they are in general required to dechlorinate their wastewater in addition to chlorination.




Table 3.1 lists all the dischargers to each bayou along with their permitted and self-reported ('98-'99) average flows. It can be seen that these dischargers provide a substantial flow to the bayous. For example the average flow from point sources in Whiteoak Bayou is 21.62 MGD or 33.5 cfs. This is close to the median flow determined for this stream of approximately 45 cfs.

Out of the 124 permitted dischargers located in the study area, only 18 had a fecal coliform standard and reporting requirement (see Table 3.2a for a list of such facilities). Historical self-reporting monitoring fecal coliform data from the plants listed in Table 3.2a were obtained from the EPA Permit Compliance System (PCS) and included in Appendix B. Table 3.2b includes a summary of the FC data for the last three years for the facilities shown in Table 3.1. It can be seen that the reported effluent FC concentrations meet the 200 cfu/dL standard in more than 95% of the cases in Whiteoak Bayou (3.5% exceedance) and in 100% of the Buffalo Bayou data. This may be explained by the fact that the reporting facilities are all major dischargers (flow > 1 MGD) that usually have good disinfection controls.

An estimate of the annual FC load to Buffalo and Whiteoak Bayous from point sources was completed using the total flow discharged to the bayous and the average concentrations reported in the self-reporting data from major dischargers. The FC load due to minor dischargers was calculated assuming that they discharge much higher levels of FC as suggested by the Greens Bayou Intensive Survey (City of Houston Public Works and Engineering Department, 1999). The average concentration for minor dischargers (< 1 MGD) was assumed to be equal to the average concentration from the Greens Bayou Study (2,114 cfu/dL). Table 3.3 includes an estimate of the FC point source load (PSL) to

TABLE 3.1 WASTEWATER DISCHARGERS IN STUDY AREA

Permit name	Permit	Permitted	'98-'99 Solf reported	Permit name	Permit	Permitted	'98-'99 Solf reported
	number	flow (MGD)	Self-reported average flow (MGD)		number	flow (MGD)	Self-reported average flow (MGD)
BUFFALO BAYOU			(IVIGD)	WHITE OAK BAYOU			(IVIGD)
TOSHIBA INTERNATIONAL	03153-002	0.05		AQUASOURCE DEVELOPMENT	13433-001	0.50	
VARCO SHAFFER PETERSEN, JAMES	03994-001 12398-001	0.05 0.02		HARRIS CO METRO UD KONECRANES LANDEL	13673-001 13912-001	0.20 0.20	
HARRIS CO MUD 166,257,276	12474-001	0.63		TRAMMELL CROW	13996-001	0.05	
HARRIS-FORT BEND COS MUD ADAMOLI, JAMES	12498-001 12811-001	0.43 0.01		WEST HARRIS CO MUD 010 NCI BUILDING SYSTEMS	14072-001 12552-002	1.50 0.01	0.00
HARRIS CO MUD 276	12927-001	0.50		SMITH, WILLIAM	12573-002	0.01	0.00
HARRIS CO MUD 284	12949-001	0.10		MCDONALDS CORP.	13807-001	0.00	0.00
RLG REALTY HOLDINGS REMINGTON MUD 001	13218-001 13328-001	0.35 1.10		RIEDEL, ANTHONY RESTAURANT SERVICE	13939-001 13983-001	0.00 0.00	0.00
HARRIS COJUVENILE BOOT CAMP	13921-001	0.02		SUPERIOR DERRICK SERV	12443-001	0.00	0.00
GINTER REAL ESTATE	14011-001	0.15		PILOT INDUSTRIES	01899-001	0.03	0.01
WEATHERFORD U.S. ICO WORLDWIDE, INC.	14070-001 02104-001	0.01 0.04	0.00	TEXAS ARAI INC. QUALITY PRODUCT FINISHING	03014-001 03223-001	0.04 0.03	0.01 0.01
GRANT PRIDECO	03022-001	0.01	0.00	HANOVER LAND CO.	11797-001	0.03	0.01
BAYOU CLUB OF HOUSTON ASEP AMERICA, INC.	12233-001 12355-001	0.01 0.01	0.00 0.00	DANIEL INDUSTRIES TIFCO INDUSTRIES	12397-001 12465-001	0.01 0.04	0.01 0.01
TRANSWESTERN KATY FREEWAY	12406-001	0.01	0.00	NCI BUILDING SYSTEMS	12552-001	0.01	0.01
COOPER CAMERON CORP	12412-001	0.01	0.00	SMITH, BOB	13509-001	0.03	0.01
AIVAZIAN, GEORGE ROBINSON, J. WAYNE	12427-001 12830-001	0.00 0.01	0.00 0.00	COOPER CAMERON CORP. MOORPARK VILLAGE	13578-001 13727-001	0.01 0.04	0.01 0.01
FRIEDMAN, STEPHEN	13778-001	0.01	0.00	C&P UTILITIES	12342-001	0.03	0.02
AIR LIQUIDE AMERICA OCEANEERING	13959-001 12466-001	0.00 0.01	0.00	DOMCO INC. VANCOUVER MANAGEMENT	00785-001 11051-001	0.02 0.03	0.03 0.03
WEST HOUSTON AIRPORT	12516-001	0.00	0.00	ABB VETCO GRAY INC	11651-001	0.03	0.03
IGLOO PRODUCTS	02229-001	0.03	0.01	FAIRBANKS PLAZA SHOPPING	12139-001	0.04	0.03
TOSHIBA INTERNATIONAL VERRY, RICHARD	03153-001 12310-001	0.05 0.03	0.01 0.01	CBI NA-CON INC. WHITE OAK OWNERS ASSOC.	11389-001 12132-001	0.05 0.06	0.04 0.04
HARRIS CO MUD 216	12682-001	0.40	0.01	AQUASOURCE UTILITY	12222-001	0.25	0.05
HARRIS COUNTY-CULLEN	12858-001	0.03	0.01	TOWER MANAGEMENT SERV	13764-001	0.15	0.05
HARRIS-FT BEND CO MUD GRAND LAKES MUD #4	12805-001 13245-001	0.25 0.90	0.02 0.02	HARRIS CO MUD 130 CREEKSIDE UTILITIES	12574-001 11375-001	0.50 0.64	0.08 0.10
HARRIS COUNTY-BEAR CK	10932-001	0.04	0.03	NORTHW HARRIS CO MUD 029	12795-001	0.57	0.12
WESTON MUD ROLLING CREEK UD	11632-001 12841-001	0.10 0.90	0.03 0.03	WEST HARRIS CO MUD CHAMP'S WATER CO.	13623-001 11005-001	2.00 0.28	0.12 0.14
529 #35, LTD	13484-001	0.90	0.03	HARRIS CO MUD #119	12714-001	0.25	0.14
NOTTINGHAM COUNTRY MUD (WTP)	13674-001	0.05	0.03	WHITE OAK BEND MUD	11979-002	0.40	0.20
HOUSTON AREA DEVELOPMENT SASSON, ELI	13775-001 11414-001	0.25 0.06	0.03 0.04	HARRIS CO MUD 247 ROLLING FORK PUD	12681-001 11188-001	0.80 0.49	0.20 0.26
KATY ISD	12110-001	0.10	0.04	WEST HARRIS CO MUD 011	13689-001	1.50	0.32
FT BEND CO MUD 050 TEX-SUN PARKS	13228-001	0.70 0.09	0.04 0.05	SUNBELT FWSD	11670-001	0.99 0.75	0.34 0.43
HARRIS CO MUD 167	12189-001 12834-001	0.60	0.05	HARRIS CO MUD 006 HARRIS CO MUD 023	11273-001 11485-001	0.75	0.43
FORT BEND CO MUD 034	12298-001	0.20	0.07	HOUSTON-WESTWAY UD	10495-139	1.00	0.50
HARRIS CO MUD 196 HARRIS CO MUD 250	12447-001 12685-001	0.50 0.10	0.07 0.07	AQUASOURCE UTILITY REID ROAD MUD 001	11193-001 11563-001	1.00 1.75	0.54 0.63
NORTHWEST HARRIS CO MUD 16	11935-001	0.99	0.08	HARRIS CO MUD 170	12121-001	2.50	0.94
ADDICKS UD	11696-002	0.40	0.09 0.11	HARRIS CO FWSD 061	10876-001	1.60	0.95 1.06
WYMAN-GORDON FORGINGS HARRIS CO MUD 105	01402-002 11792-002	0.45 1.25	0.11	WHITE OAK JOINT POWERS HARRIS CO FWSD 061	11538-001 10876-002	4.50 3.00	1.28
NORTHW HARRIS CO MUD 012	11991-001	0.16	0.11	HARRIS CO WCID 133	11153-001	3.00	1.36
HARRIS CO. MUD #345 FORT BEND CO MUD 037	12356-001 12370-001	0.71 0.18	0.11 0.11	HOUSTON-WHITE OAK MUD HOUSTON-NORTHWEST	10495-099 10495-076	4.00 21.00	1.69 9.27
BIG OAKS MUD	13021-001	0.20	0.11	Total flow	10475-070	56.67	21.62
WEST HARRIS CO MUD 007	12140-001	0.50	0.12				
WEST HARRIS CO MUD #15 HARRIS CO MUD 238	12223-001 12802-001	0.35 0.70	0.14 0.15				
WEST HARRIS CO MUD 017	12247-001	0.28	0.16				
CINCO MUD 001 WEST PARK MUD	13172-002 12346-001	0.91 0.50	0.17 0.19				
HARRIS CO MUD 127	12209-001	0.33	0.17				
HARRIS CO MUD 071	11917-001	0.45	0.21				
HARRIS CO MUD 155 FRY ROAD MUD	12726-001 11989-001	2.00 0.80	0.23 0.24				
HARRIS CO MUD 157	11906-001	1.50	0.25				
HARRIS CO MUD 185 SPENCER ROAD PUD	12124-001	0.68 0.98	0.27				
HARRIS CO MUD #149	11472-001 11836-001	0.93	0.33 0.33				
CHIMNEY HILL MUD	12304-001	0.90	0.34				
HOUSTON-PARK TEN NOTTINGHAM COUNTRY MUD	10495-135 12479-001	3.50 1.30	0.39 0.40				
CASTLEWOOD MUD	11883-001	1.37	0.47				
GREEN TRAILS MUD	12289-001	0.99	0.51				
LANGHAM CREEK UD HORSEPEN BAYOU MUD	11682-001 12128-001	3.00 0.95	0.54 0.55				
WESTLAKE MUD 001	11284-001	1.20	0.58				
MAYDE CREEK MUD	11969-001	2.00	0.60				
CINCO MUD 001 WILLIAMSBURG REGIONAL	13558-001 11598-001	1.69 2.00	0.64 0.74				
HARRIS CO MUD 102	11523-001	1.30	0.85				
MEMORIAL MUD	11893-001	3.00	1.19				
KATY WEST MEMORIAL MUD	10706-001 11152-001	3.45 6.48	1.27 1.58				
HARRIS CO MUD 208	11947-001	6.70	1.78				
JACKRABBIT ROAD PUD MEMORIAL VILLAGES WA	11290-001 10584-001	5.10 3.05	2.29 2.39				
HOUSTON-TURKEY CREEK	10384-001	12.00	3.89				
HARRIS CO MUD 070	11486-001 10495-030	1.50 26.40	5.81 11.06				
HOUSTON-WEST DISTRICT							

TABLE 3.2a
DISCHARGERS TO BUFFALO AND WHITEOAK BAYOUS REPORTING FC DATA

TNRCC PERMIT No	EPA PERMIT	PERMIT NAME	PERMITTED	SELF-	RECEIVING
			EL 014 (140E)	REPORTED	DAYOU
			FLOW (MGD)	FLOW (MCD)	BAYOU
WQ0011792-002	TX0070971-000	HARRIS COUNTY MUD NO.	1.25	0.11	BUFFALO
WQ0011947-001	TX0075884-000	HARRIS CO MUD NO. 208	6.7	1.78	BUFFALO
WQ0012189-001	TX0082830-000	TEX-SUN PARKS, L.C.	0.09	0.05	BUFFALO
WQ0012474-001	TX0089494	HARRIS COUNTY MUD NO.	0.63		BUFFALO
		166 257			
WQ0012834-001	TX0094307-000	HARRIS CO MUD NO. 167	0.6	0.05	BUFFALO
WQ0010495-139	TX0026875	HOUSTON, CITY OF	1	0.5	WHITEOAK
WQ0011188-001	TX0026697	ROLLING FORK PUD	0.49	0.26	WHITEOAK
WQ0011273-001	TX0026352	HARRIS CO MUD NO. 6	0.75	0.43	WHITEOAK
WQ0011375-001	TX0026247	CREEKSIDE UTILITIES INC.	0.64	0.1	WHITEOAK
WQ0011485-001	TX0062235-000	HARRIS CO MUD NO. 23	0.75	0.48	WHITEOAK
WQ0011563-001	TX0053325-000	REID ROAD MUD NO. 1	1.75	0.63	WHITEOAK
WQ0011979-002	TX0076651-000	WHITE OAK BEND MUD	0.4	0.2	WHITEOAK
WQ0012552-001	TX0090115	NCI BUILDING SYSTEMS L.P.	0.01	0.01	WHITEOAK
WQ0012573-001	TX0090735-000	SMITH, WILLIAM D.	0.01	0	WHITEOAK
WQ0012714-001	TX0092908	HARRIS COUNTY MUD NO.	0.25	0.19	WHITEOAK
WQ0012795-001	TX0093726-000	NW HARRIS CO MUD NO. 29	0.57	0.12	WHITEOAK
WQ0013509-001	TX0092746	SMITH BOB	0.03	0.01	WHITEOAK

TABLE 3.2b FECAL COLIFORM SELF-REPORTING DATA FOR DISCHARGERS TO BUFFALO AND WHITEOAK BAYOUS

			O BAYOU Daily Maximum (cfu/dL)	WHITEAOAK BAYOU Daily average (cfu/dL) Daily Maximum (cfu/dL)		
4000	Maximum	10	10	437	437	
1998	Average	7	7	17	22	
1999	Maximum	28	40	96	154	
1999	Average	12	15	17	28	
2000	Maximum	2	2	40	211	
2000	Average	2	2	17	54	
Total # samples			45		260	
# samples > 200 cfu/dL			0		9	

Notes: See Table 3-2a for list of dischargers

Data source: EPA Permit Compliance System (PCS) accessed via Internet (www.epa.gov/enviro)

TABLE 3.3 POINT SOURCE FECAL COLIFORM LOAD CALCULATION

	(1)	(2)	(3)	(4)	(5)		(6)			(7)	
	Total flow	Total volume	Total flow	Total volume	Average conc	Average	e concen	tration	Total Point Source load (cfu)		load (cfu)
	major	major	minor	minor	minor	majo	r dischar	gers			
Bayou	dischargers	dischargers	dischargers	dischargers	dischargers		fu/100ml			1	1
	(MGD)	(gal)	(MGD)	gal	(cfu/100mL) ^a	1998	1999	2000	1998	1999	2000
Buffalo	31.26	1.14E+10	11.13	4.06E+09	2,114	10	40	2	3.29E+14	3.42E+14	3.26E+14
Whiteoak	14.66	5.35E+09	6.96	2.54E+09	2,114	437	154	211	2.92E+14	2.35E+14	2.46E+14

Notes:


- (1) Data from wastewater permit files (Table 3.1 reported flow <= 1 MGD)
- (2) Calculated by multiplying total flow in (1) by 365 days
- (3) Data from wastewater permit files (Table 3.1, reported flow < 1 MGD)
- (4) Calculated by multiplying total flow in (3) by 365 days
- (5) Average of concentrations reported in the Greens Bayou Intensive Survey (City of Houston PW&E, 1999)
- (6) Average of maximum daily concentrations from self-reporting data for each year (Table 3.2b)
- (7) Calculated by adding the product of the average concentration in major sources by the total volume in (2) plus (4) times (5)

the Buffalo and Whiteoak Bayous for the years 1998-2000. As can be seen in Table 3.3, total annual FC loads from point sources ranged between 2.35x10¹⁴ and 3.42x10¹⁴ for this period.

Additionally, FC concentrations at monitoring stations located upstream and downstream of point dischargers were compared to evaluate the impact of these sources on water quality in the bayous. This analysis is shown in Figures 3.2 and 3.3 for Buffalo and Whiteoak Bayous, respectively. As can be seen, FC levels are generally higher at the downstream locations than at the upstream locations for median flows and high flows in both bayous, with the exception of one location in Whiteoak Bayou at high flow. However, it should be noted that this type of analysis tends to be inconclusive because of the different sampling agencies and times involved.

3.3.2 Regrowth or Reactivation of Bacteria in Disinfected Wastewater

If disinfected wastewater is discharged with essentially no viable indicator bacteria but quickly takes on higher concentrations in the receiving stream, regrowth or reactivation may be occurring. Distinguishing between the two processes is difficult and may not be necessary. An example of the process is shown in Figure 3.4, taken from an older study (Jensen, 1980). Samples of primary, secondary and industrial effluents were placed in sterile containers and kept in the dark at room temperature for four days. Each day subsamples were analyzed for total and fecal coliform bacteria with the 5-tube MPN method. The plot shows the average rate of change in bacteria concentration (per hour) over the period versus the initial BOD₅ concentration. The shifts shown are adjustments in the BOD₅ values based on total organic carbon results made necessary because the







FIGURE 3-2 EFFECT OF POINT SOURCES ON FC LEVELS IN BUFFALO BAYOU AT

(a) Low Flow (b) High Flow







FIGURE 3-3 EFFECT OF POINT SOURCES ON FC LEVELS IN WHITEOAK BAYOU AT

(a) Low Flow (b) High Flow



Source: Jensen, P.A. 1980. Regrowth of Coliform Bacteria as influenced by Wastewater Treatment. Paper presented at Texas Section ASCE Conference. El Paso. September 25-27, 1980.

BOD₅ samples had not been dechlorinated like the bacteria samples. This study found that on average, a BOD₅ concentration of 5 mg/L or less would not result in regrowth over the four-day period, but a concentration of 10 mg/L would yield an average growth rate of 0.0375/hr. This would be an increase in concentration by a factor of 2.46 in a 24-hr period.

In practice today effluents rarely reach such BOD concentrations and there is little evidence that regrowth/reactivation exists at the low levels common today.

3.3.3 Direct Sewage Discharges

A potential major source of indicator bacteria to the bayous includes sewer leaks and illicit sewage discharges. These are grouped and discussed together because they come from the same source and enter the bayou by the same method.

Sewer leaks happen for a variety of reasons including broken lines, blockages, or insufficient hydraulic capacity. Some releases only occur during wet weather conditions when infiltration and inflows cause the sewage flows to exceed the line capacity. Excess flow will find an outlet (manhole, etc.) and flow into the storm drain system to the bayou.

Of greater concern from a bayou bacteria concentration standpoint is a sewage flow during dry weather. These typically happen from a broken or blocked line. A broken line that is not visible may be very difficult to detect, particularly if the sewage flows to the bayou underground in a covered storm drain. When a sewer blockage occurs, the sewage that can no longer flow through the line backs up and finds a path that ultimately leads to the bayou. Leaks from sewer blockages are typically detected more rapidly by

those affected. While dry weather leaks tend to be small in volume, this discharge of raw sewage could contribute substantially to the high FC levels in the bayous.

To investigate the extent of sewer leakage and blockage, the TMDL team contacted the City of Houston's Health and Human Services (H&HS) and Public Works and Engineering (PW&E) departments. The H&HS provided a database containing citizens' complaints related to sanitary sewer or sewage problems. Table 3.4 lists the reports provided by H&HS that are in the study area watersheds. There were 12 incidents reported in Buffalo Bayou and 4 in Whiteoak Bayou during April 99 and June 2000. This list only covers a 15-month period and only those that elected to contact the H&HS hotline number.

The PW&E has provided a database that contains older sewer leak detection and repair information. Table 3.5 summarizes the findings during the period 1989 to 1996. The PW&E database in Table 3.5 covered a substantial period of time and found a significant number of leaks. Most appear to be caused by a blockage (Code 23) but broken lines also figure prominently.

Another set of data that was requested is the database maintained by the PW&E's Sewer Maintenance Quadrants, which actually conduct sewer repair work in the city. This database includes leaks and overflows between 1995 and 2000 as can be seen in Appendix C.

Additionally, overflows and bypasses to the Buffalo and Whiteoak Bayous reported to the TNRCC were compiled by looking at the individual wastewater discharge permit files and included in Appendix C.

TABLE 3.4
HEALTH AND HUMAN SERVICES DEPARTMENT SEWER LEAK REPORTS IN WATERSHEDS

Date	Time	Location	Nature of Complaint	Flow to	NH3-	FC	Watershed	Remarks
				Street/	N	(cfu/100 ml.)		
04/08/99		4726 Richmond Ave	City manhole backup				Buffalo	
04/22/99		1500 Memorial Dr	Sewer leak to storm drain	yes			Buffalo	
05/21/99	14:30	1500 Memorial Dr	Sewer leak to storm drain	yes	3		Buffalo	
06/17/99	08:40	5800 Bellaire	Sewer leak to storm drain from apartm	yes			Buffalo	
10/07/99	15:18	3754 Westheimer	Broken city sewerline	yes			Buffalo	
02/17/00		4094 Westheimer	Sewer overflow from a restaurant				Buffalo	
03/29/00	15:50	3326 Travis	Sewer overflow from a restaurant				Buffalo	
04/05/00		9310 Long Point	SSO to storm ditch	yes	3	Sampled	Buffalo	
05/30/00	12:30	9348 Long Point	Broken private sewerline	no			Buffalo	
06/07/00	09:30	14555 Grisby	Sewage in storm ditch	yes	2	Low	Buffalo	FC too low to be sewer leal
06/29/00	08:12	722 Riedel	Broken private sewerline	yes	3	21,000	Buffalo	Source from 727 Bunker Hi
07/05/00	08:15	727 Bunker Hill Place #78	Broken private sewerline	yes	3	480,000	Buffalo	FC sampled 7/7/00
11/01/99	08:38	1003 W. 34th	Illicit dumping of feces from buses	yes	> 3		White Oak	
12/07/99		2407 Airline Dr.	Illicit discharge from a restaurent	yes	0	High	White Oak	
04/28/00	11:55	1003 W. 34th	Illicit dumping of feces from buses	yes	1		White Oak	
07/05/00		6240 Antoine	Sewer blockage				White Oak	

Source: City of Houston Health and Human Services Department, Citizen Complaint Database.

TABLE 3.5
3LIC WORKS AND ENGINEERING DEPARTMENT SEWER LEAK REPORTS IN WATERSHEDS 1989 - 1

Date	Location	Flow (gpm)	Problem description	Watershed
03/30/89	Tiel Way Gully	50	SS discharging to gully.	Buffalo
03/30/89		30	Code 23. SS backed up to storm.	Buffalo
04/12/89	Waugh St. Outfall	50	Prvt-Milk (1930 mg/l BOD)	Buffalo
04/19/89	1111 Post Oak	10	Prvt-Laundry room to storm	Buffalo
04/19/89	Sage/Delmonte*	15	Code 23. SS plugged to storm.	Buffalo
04/19/89	Post Oak/SnFlpe-TomCtfsh	0	Prvt-GT full. Grease in storm	Buffalo
04/24/89	Broad Oak Circle	30	SS to storm 24". Not shown on map.	Buffalo
04/26/89	Post Oak/San Felipe	20	SS to storm 24".	Buffalo
04/26/89	5600 San Felipe	0	Overflow inactive. NH3=16.	Buffalo
05/03/89	1410 Hyde Park	5	CO-From apt. overflowing to storm.	Buffalo
05/10/89	3128 Mt. Vernon	5	Code 23. SS plugged to storm.	Buffalo
05/12/89	Stanford/Oakley	5	SS to storm 2-12".	Buffalo
05/12/89	California/Montrose	3	SS to storm 15".	Buffalo
05/12/89	Schuler/Sandman	20	Code 23. SS plugged to storm.	Buffalo
05/12/89	Reinerman/Dickson	20	Code 23. SS plugged to storm.	Buffalo
05/23/89	Wilson/Robin	5	Code 23.MH-Andrews/Genesse holding	Buffalo
05/23/89	Valentine/Cleveland	2	Code 23.MH-Cleveland/Cushing hold	Buffalo
05/23/89	Calhoun/Baldwin	2	SS to storm.	Buffalo
05/25/89	San Jacinto/Tuam	2	Appeared to be user connect. prob.	Buffalo
05/25/89	Fannin/Tuam	2	Code 23. MH holding. SS to storm.	Buffalo
05/25/89	McGowen/Bagby	5	Dye+ into 24"&14" storm lines	Buffalo
05/25/89	Dennis/Albany	2	SS 8" to storm 60".	Buffalo
05/25/89	1900 Bailey	2	CO-Abandoned in vacant lot	Buffalo
05/25/89	Hyde Park/Hopkins	1	SS to storm. Visual verification.	Buffalo
05/25/89	McGowen/Albany*	5	Dye+ SS into storm	Buffalo
05/25/89	602 Welch	1	SS 8" to storm. CO's suspected.	Buffalo
05/25/89	Dennis/Genesse	1	SS 8" to storm. CO's suspected.	Buffalo
06/21/89	Sul Ross/Yoakum	10	Brkn line. Yoakum/Graustark	Buffalo
06/21/89		35	SS to storm MH from lines/sides	Buffalo
06/21/89	Elgin/Smith	3	Code 23. 12" SS line. MH hold 1 ft	Buffalo
06/21/89	Elgin/Brazos	2	SS to storm 18".	Buffalo
07/13/89	Louisiana/Gray	10	SS to storm MH	Buffalo
07/13/89	Smith/Hadley*	2	Code 23. SS to Storm MH	Buffalo
07/13/89	Victor/GilletteBail	5	SS to storm.	Buffalo
07/16/89	Louisiana/McGowen	3	SS to storm. S side of MH	Buffalo
07/16/89	Anita/Fannin	3	SS to storm MH	Buffalo
07/16/89	Anita/Main	2	SS to storm 18". SW side of MH	Buffalo
07/16/89	Elgin/Milam	10	Dye+ 24"&15" Cajun Rest	Buffalo
07/16/89	Westheimer/Whitney	2	SS to storm 18". S side of MH	Buffalo

Source: City of Houston Public Works & Engineering Department. SS Sanitary Sewer

SS Sanitary Sewel
CO Cleanout
Code 23 Blockage

Dye+ Dye test performed

TABLE 3.5 (CONTINUED)
3LIC WORKS AND ENGINEERING DEPARTMENT SEWER LEAK REPORTS IN WATERSHEDS 1989 - 1

Date	Location	Flow (gpm)	Problem description	Watershed
07/16/89	Westheimer/Stanford	1	SS to storm Westheimer system.	Buffalo
07/16/89	Avondale/Stanford	0	Code 23. Holding about 1 ft	Buffalo
07/19/89	100ydsE WDist WWTP	15	Prvt-4" prvt main 2 bayou/pipe brk	Buffalo
07/23/89	Rusk/Bagby	3	Dye+ SS to storm from 100'away	Buffalo
07/30/89	Post Oak/Westbrier	3	Code 23. MH holding. SS to storm.	Buffalo
	Waugh/Pierce*	4	Code 23. MH holding. SS to storm.	Buffalo
	Alabama/SJacntoMilam	10	SS to storm.	Buffalo
08/25/89	Fondren/Richmond	0	Code 23. NH3=8 on storm.	Buffalo
09/27/89	5151 San Felipe	4	MH base leaking to storm ditch.	Buffalo
09/27/89		3	SS along 2 gas lines to 72" storm	Buffalo
09/27/89	SanFelipe/Sherbrook	4	SS 10" to storm 24".	Buffalo
10/04/89	Bremond/Brazos	3	SS to storm 12".	Buffalo
10/04/89	W Loop/Hwy59-NE fdr	5	Code 23. SS MH to street to storm	Buffalo
10/11/89	Stanford/Woodrow	1	SS to storm 18".	Buffalo
10/12/89	San Jacinto/Hadley	30	SS 8" main to storm.	Buffalo
	Fannin/Alabama	5	SS to storm. Marked.	Buffalo
10/16/89	Fannin/Alabama	4	CO-Circle K to storm.	Buffalo
10/16/89	Gillette/Robin	3	Code 23. Dallas/Gillette	Buffalo
10/17/89	California/Grant	1	D-type drain to storm. Marked.	Buffalo
10/18/89	Clarkcrest/Jeanetta	10	Dye+ 12" SS to storm	Buffalo
10/18/89	9001 Clarkcrest	2	SS line crossing to storm	Buffalo
	2929 Fondren (Luby's)	10	Code 23. SS to storm	Buffalo
10/24/89	Westheimer/Fondren	5	SS 4" to storm. CBOD=518	Buffalo
	Travis/Pease*	5	Prvt-18" cast iron storm frm condo	Buffalo
10/27/89	McKinney at CHA	500	Combo-PeaseTravis>Louis.Lamar	Buffalo
11/02/89		1	SS to storm 45". Marked.	Buffalo
11/06/89	· · · · · · · · · · · · · · · · · · ·	2	Dye+ 8" SS to storm	Buffalo
	Fannin/Alabama	5	Code 23. SS Circle-K/StopNGo.TV	Buffalo
	Dallas/Gillette*	0	Code 23. SS line to storm	Buffalo
11/16/89		0	Code 23. SS to storm. Marked	Buffalo
11/20/89		1	Code 23. SS to storm. Marked.	Buffalo
11/20/89		5	Code 23. SS>Briargrove.Plug end	Buffalo
12/02/89		1	SS to storm. Marked.	Buffalo
	Post Oak/San Felipe	20	SS 21" force main to storm.	Buffalo
	California/Grant	10	Code 23. SS to storm. Marked.	Buffalo
12/07/89	2502 Westerland	30	Prvt-Private line to storm.	Buffalo
	95 Block Tuam	1	Dye+ 0.5 gpm to storm	Buffalo
12/09/89	Smith/Gray	1	Code 23. SS to storm. Marked	Buffalo
12/12/89	Harold/Yupon	0	Overflow SS to storm. SEAL.	Buffalo

Source: City of Houston Public Works & Engineering Department.

SS Sanitary Sewer
CO Cleanout
Code 23 Blockage

Dye+ Dye test performed

TABLE 3.5 (CONTINUED)
3LIC WORKS AND ENGINEERING DEPARTMENT SEWER LEAK REPORTS IN WATERSHEDS 1989 - 1

Date	Location	Flow (gpm)	Problem description	Watershed
12/15/89	1400 Briar Hollow Ln	5	Dye+ SS to storm. Marked.	Buffalo
01/18/90	6300 Westheimer	5	SS 6" open backend to ditch.	Buffalo
01/22/90	Victor/Bailey	5	Dye+ SS to storm. Marked.	Buffalo
01/26/90	West Lane/Mid Lane	1	Dye+ SS to storm. Marked.	Buffalo
01/27/90	Westheimer/WestLane	10	Dye+ SS to storm. Marked.	Buffalo
01/29/90	Louisiana/McGowen	2	Dye+ SS to storm. Marked.	Buffalo
01/29/90	Cleveland/Bailey	5	Dye+ SS to storm. Marked.	Buffalo
01/30/90	1910 Indiana	5	SS overflow to storm. SEAL.	Buffalo
01/31/90	1502 Cleveland	3	Dye+ SS to storm. Marked.	Buffalo
02/01/90	Mockingbrd/Larchmnt	10	Code 23. 8" line holding.	Buffalo
02/12/90	Mockingbird/Delmont	10	Dye+ SS to storm. Marked.	Buffalo
	Fountnview/Woodway	50	Prvt-Dye+ 2 twmhomes to storm.	Buffalo
02/23/90	Driscoll/Indiana	1	Dye+ 8" SS to storm. Marked.	Buffalo
02/23/90	2101 Hazard	4	Dye+ 6" serv main. Marked.	Buffalo
03/01/90	6300 San Felipe	30	Overflow (known) to storm ditch.	Buffalo
03/05/90		7	Code 23. MH to storm inlet.	Buffalo
03/06/90	1913 Bailey Street	5	Community line to storm inlet	Buffalo
03/13/90	Fairview/Converse	10	Community 6" to storm.	Buffalo
03/14/90	1705 Waugh Dr.	5	Dye+ SS to storm.	Buffalo
	Vermont/Morse	2	Dye+ SS to storm. Marked.	Buffalo
03/17/90	Greely/Oakley	4	Dye+ SS to storm. Marked.	Buffalo
	Welch/Hopkins	5	Dye+ SS to storm. Marked.	Buffalo
03/26/90		3	Code 23. SS to storm. Marked.	Buffalo
04/03/90		5	Code 23. SS trunk. Seal MH walls.	Buffalo
04/03/90	5840 Bayou Glen	0	Overflow frm 15" SS Main.MHcst/cvr	Buffalo
04/12/90	Victor/Wilson	3	Comm 6" to 42" strm Dye+on4"CO	Buffalo
04/19/90	6226 VIIy Forge	5	SS 8" to storm.	Buffalo
04/27/90		0	Dye+ Pinpoint Seal MH wall	Buffalo
07/09/90		5	SS 6" to storm.	Buffalo
07/11/90		1	Dye+ 8" SS to storm.	Buffalo
07/11/90		10	Dye+ 6" comm to storm.	Buffalo
07/12/90		3	Prvt-Dye+ Church line to storm MH.	Buffalo
	1925 Milam	3	Prvt-Dye+ Car Wash SW to storm MH.	Buffalo
	3535 W. Dallas	10	Prvt-Dye+ Apartments to storm.	Buffalo
	W. Dallas/Eberhard	1	SS 8" to storm. Marked.	Buffalo
08/02/90	6360 Richmond	20	Code 23. SS > storm/Tony Romas Rst	Buffalo
08/02/90		20	Code 23. SS to storm/BEST Store	Buffalo
08/15/90	306 Walnut Bend	1	SS 8" to storm. Marked.	Buffalo
08/28/90	6360 Skyline Drive	15	Prvt-SS>15"prvt strm>36"Cty strm	Buffalo

Source: City of Houston Public Works & Engineering Department. SS Sanitary Sewer

SS Sanitary Sewer
CO Cleanout
Code 23 Blockage

Dye+ Dye test performed

TABLE 3.5 (CONTINUED)
3LIC WORKS AND ENGINEERING DEPARTMENT SEWER LEAK REPORTS IN WATERSHEDS 1989 - 1

Date	Location	Flow (gpm)	Problem description	Watershed
08/28/90	O'Neil/Gillette	15	SS to storm. Stopped up to house.	Buffalo
09/05/90	4126 Southwest Freeway	30	Prvt-SS to storm. 12 Oaks Hospital	Buffalo
09/19/90	W. Dallas/Eberhard	30	Code 23. (1) SS overflow to storm.	Buffalo
09/24/90		5	SS leak to street/strm inlet NH3>3	Buffalo
09/24/90	800 Anita	10	Code 23. SS frm MH to street	Buffalo
10/16/90	3007 Crossview (3008)	7	SS leak to storm/Fajitas Flats	Buffalo
10/18/90	1916 Baldwin	5	Community 6" stopped up.	Buffalo
11/06/90	W. Dallas/Eberhard	30	Code 23. (2) SS overflow to storm.	Buffalo
11/16/90	Dennis/Genesse	20	SS 8" to storm. Marked.	Buffalo
11/26/90	W. Dallas/Eberhard	30	Code 23. (3) SS overflow to storm.	Buffalo
11/27/90	4827 S. Main/Rosedale	5	SS leak to street/strm inlet (2)	Buffalo
11/29/90	600 Elgin/Smith	5	Code 23. SS to storm.	Buffalo
12/07/90		10	MH wall leaking to storm.	Buffalo
12/07/90	700 Elgin/Louisiana	20	Code 23. SS to storm.	Buffalo
03/26/91	6300 San Felipe	75	Overflow (known) to storm ditch.	Buffalo
03/26/91	6300 Fairdale	60	Overflow (known) to storm.	Buffalo
04/18/91	10722 Meadow Lake	10	SS leak to storm.	Buffalo
05/07/91	600 Elgin/Smith	20	Code 23. SS to storm/rqst to TV.	Buffalo
05/07/91	5200 Richmond	50	Code 23. SS MH to street to storm.	Buffalo
05/08/91	4211 Southwest Freeway	15	2 yr old contract SS to storm.	Buffalo
05/21/91	2502 Westerland	40	Prvt-Private line to storm.	Buffalo
05/24/91	1925 Milam	3	Prvt-Dye+ Car Wash SW to storm MH.	Buffalo
08/01/91	600 Crestbend	200	Contractors TVing lines in area.	Buffalo
08/29/91	Gessner/Cedardale	15	SS leak to storm.	Buffalo
09/12/91	10110 Westview	15	Prvt-Westview Forest Apts.	Buffalo
10/01/91	West Belt/I-10 (Petmart)	15	SS leak to storm in parking lot.	Buffalo
10/08/91	West Belt/I-10 Sportstwn	15	SS conn to storm in parking lot.	Buffalo
03/18/92	6350 Beverly Hills	75	Overflow (known) to Bering Ditch	Buffalo
	W. Dallas/Peveto	25	Code 23. SS to storm.	Buffalo
	W. Dallas/Peveto	20	Code 23. SS to storm.	Buffalo
09/24/92		100	12" SS line to storm.	Buffalo
	Avalon/Westgate	30	Code 23. SS to storm.	Buffalo
10/19/92		100	12" force main to bayou.	Buffalo
12/02/92	Westview/Aldrich	30	SS to storm.	Buffalo
	6150 Chevy Chase	15	SS to Bering Ditch.	Buffalo
07/23/93	Richmond at Greenridge	20	SS to Bering Ditch.	Buffalo
08/09/93		5	Dye+ SS to storm.	Buffalo
08/19/93	6345 Windswept	5	SS to Bering Ditch.	Buffalo
08/19/93	Woodway at Bering Ditch	5	SS to Bering Ditch.	Buffalo

Source: City of Houston Public Works & Engineering Department. SS Sanitary Sewer

SS Sanitary Sewe
CO Cleanout
Code 23 Blockage

Dye+ Dye test performed

TABLE 3.5 (CONTINUED)
3LIC WORKS AND ENGINEERING DEPARTMENT SEWER LEAK REPORTS IN WATERSHEDS 1989 - 1

Date	Location	Flow (gpm)	Problem description	Watershed
09/09/93	6350 Beverly Hills	35	SS to Bering Ditch.	Buffalo
10/24/93	6146 Doliver	0.5	SS to Bering Ditch.	Buffalo
10/24/93	1403 Winrock	3	SS to Bering Ditch.	Buffalo
10/24/93	6224 Cedar Creek	2	SS to Bering Ditch.	Buffalo
11/23/93	Westheimer/Greenridge	25	SS to Bering Ditch.	Buffalo
12/06/93	10950 Briar Forest	5	Prvt-Park at Lakeside	Buffalo
01/24/94	Woodway/Buffalo Bayou	1	SS seepage from joint to bayou.	Buffalo
03/31/94	Bering Ditch/Woodway	NA	High fecal result: 510000	Buffalo
03/31/94	Fondren Outfall/Woodway	NA	Fecal result: 50000	Buffalo
04/05/94	Waco/Providence	7	SS to 30" storm.	Buffalo
04/05/94	Waco/Gunter	7	SS to 30" storm.	Buffalo
04/08/94	Pagewood	5	SS to storm.	Buffalo
04/12/94	Briarmead/Valley Forge	5	SS to storm.	Buffalo
04/26/94	Bering Ditch/Longmont	35	SS to Bering Ditch.	Buffalo
07/12/94	2710 Mason	25	Overflow active to storm.	Buffalo
	Arthur/Robin	20	SS to storm.	Buffalo
08/29/94	100 Dairy-Ashford	20	SS to 60" storm.	Buffalo
09/23/94	14520 Memorial	?	Code 23. SS to 60" storm.	Buffalo
11/18/94	Westheimer/Mid Lane	20	SS to Briarhollow Ditch.	Buffalo
05/12/95	Sage/St. James Place	5	Code 23. SS to storm.	Buffalo
11/29/95		?	Not Given	Buffalo
11/29/95		?	Code 23. SS to storm.	Buffalo
12/12/95	Not Given	?	Not Given	Buffalo
01/23/96	Not Given	? ?	Code 23. SS to storm.	Buffalo
04/11/96	6300 Fairdale		Overflow (known) to storm.	Buffalo
04/11/96	6350 Beverly Hills	?	Overflow (known) to Bering Ditch	Buffalo
04/11/96	Fairdale at Voss	?	Prvt-Apartments broken sewer line.	Buffalo
05/13/96		?	SS to Storm.	Buffalo
10/02/96	Not Given	?	Not Given	Buffalo
	Hickory/Summer	2	SS to storm 2-18". Test CO's	White Oak
08/24/89	2002 White	4	SS 4" to storm. NH3=37.1/CBOD>2490	White Oak
08/24/89	1216 Houston St.	80	SS to storm. pH=11.3/CBOD=727.	White Oak
03/21/90	WhiteOakBayou/Moody Pk	100	Brkn frce mn 24" to bayou.	White Oak
09/18/90	1600 W. T. C. Jester	20	Prvt-Timbergrove Apt. R. Alexander	White Oak
05/02/91	Reagan and Pizer	10	6" comm to storm	White Oak
06/24/91	122 E. Crosstimbers	10	Prvt-Apt to storm manhole.	White Oak
06/26/91		25	Code 23-6" main to storm ditch.	White Oak
07/16/91	E. 14th at Norhill	30	Code 23-10" main to storm.	White Oak
07/22/91	810 E. Whitney	20	Code 23-6" main to storm ditch.	White Oak

Source: City of Houston Public Works & Engineering Department. SS Sanitary Sewer

SS Sanitary Sewe
CO Cleanout
Code 23 Blockage

Dye+ Dye test performed

TABLE 3.5 (CONCLUDED)
3LIC WORKS AND ENGINEERING DEPARTMENT SEWER LEAK REPORTS IN WATERSHEDS 1989 - 1

Date	Location	Flow (gpm)	Problem description	Watershed
07/26/91	122 E. Crosstimbers	10	Prvt-Apt to storm manhole.	White Oak
09/12/91	122 E. Crosstimbers	10	Prvt-Apt to storm manhole.	White Oak
09/25/91	500 Walton	30	Code 23-10" main to storm.	White Oak
10/24/91	810 E. Whitney	20	Code 23-6" main to storm ditch.	White Oak
10/24/91	Crosstimbers/Airline	70	SS to 36" storm to LWO Bayou.	White Oak
01/08/92	508 E. 20th Street	40	SS to street to storm to LWO Bayou	White Oak
03/03/92	Outfall #143-029	175	Overflow active in dry weather	White Oak
03/13/92	12" Plug-Union Pacific	3	12" plug leak from sewer stoppage	White Oak
03/16/92	Kiam & Reinerman	75	SS to storm.	White Oak
04/03/92	Hays and Booth	80	SS to LWO Bayou from brkn main	White Oak
07/16/92	Woodland Park	80	SS to LWO Bayou from brkn main	White Oak
09/10/92	122 E. Crosstimbers	10	Prvt-Dye ck to LWO from Apt CO	White Oak
10/28/92	Glebe & LaMonte	5	SS to storm.	White Oak
04/02/93	Woodland Park	80	SS to LWO Bayou from brkn main	White Oak
12/01/93	Crockett & Hickory	250	SS to storm.	White Oak
01/05/94	,	50	SS to storm.	White Oak
03/17/94	LWO Bayou/Cavalcade	35	SS to LWO Bayou from overflow	White Oak
04/04/94	Hogan Bridge Outfall	75	SS to 72" storm to White Oak Bayou	White Oak
04/05/94	Turkey Creek at W 16th	NA	High fecal count: 94000	White Oak
04/07/94	2300 N Shepherd	7	Prvt-Fiesta dumpster to storm.	White Oak
04/18/94	Michaux/Winston	?	Code 23. SS to storm	White Oak
04/22/94	1505 Hemphill	?	Code 23. SS to 72" storm.	White Oak
05/26/94	Holly/Summer	?	Prvt-Contractor plug. SS to 72" storm.	White Oak
06/20/94	Holly/Shearn	20	SS to 72" storm.	White Oak
08/01/94	Vincent/Fugate	?	Code 23. SS to storm	White Oak
08/30/94	9005 Long Point	50	SS to Spring Creek.	White Oak
09/28/94	Summer/Hemphill	?	Code 23. SS to 72" storm.	White Oak
10/14/94	Summer/Taylor	20	Code 23 & Repair. SS to 72" storm.	White Oak
10/31/94	Summer/Taylor	50	Prvt-Riviana Foods spill to 72" storm.	White Oak
12/07/94	Vincent/Fugate	?	FC=2000000. SS to storm.	White Oak
08/11/95	Vincent/Fugate	?	FC=940000. Contractor plugging line.	White Oak
10/23/95	Vincent/Fugate	?	FC=2000000. SS to storm. Broken line.	White Oak
05/03/96	Vincent/Fugate	?	FC=2000000. SS to storm. Code 23.	White Oak
09/27/96	Vincent/Fugate	?	FC=1600000. SS to storm. Code 23.	White Oak
10/28/96	Vincent/Fugate	?	FC=1400000. SS to storm. Code 23.	White Oak

Source: City of Houston Public Works & Engineering Department. SS Sanitary Sewer

SS Sanitary Sewer
CO Cleanout
Code 23 Blockage

Dye+ Dye test performed

Figure 3.5 shows the area together with reported sewer leak or blockage locations in the watersheds. As can be seen from the figure, there is a very busy and complicated sewer system in Houston area and there are many opportunities for sewer leaks to enter the bayous. However, a sewage leak must be substantial in quantity and persistence for it to impact bayou FC levels significantly. The locations of sewer leak complaints and repairs indicate that most of the leaks occurred in the older part of the city that has an aged sewer system. This situation is expected to continue and it has been and will be a long-term effort for the city to detect and repair sewer leaks as they occur.

Illicit discharges are a more complicated issue because there is no clear definition of an illicit discharge. Examples that have been discussed range from the obvious such as direct sanitary sewage connection to a storm drain, to washdown from areas around trash containers, and discharges from vehicle wash areas. Other discharges that are questionable include cooling tower blowdown and air conditioning condensate discharges. In some cases these can have significant bacteria (Glanton, 1999), but the total amount of flow that might be involved is probably fairly small.

The total volume of sewage flow discharged to the bayous (leaks, bypasses and overflows) during the last three years is summarized in Table 3.6. To estimate annual FC loads from untreated sewage, an estimate of FC concentration of 500,000 cfu/dL was used. This assumption was based on the rationale that this flow is primarily stormwater mixed with some smaller proportion of sanitary sewage; the exact proportion will vary considerably but will probably be at least five parts stormwater to one part sewage (Jensen and Su, 1992). Table 3.6 presents the estimated loads of FC from leaks and




TABLE 3.6 FECAL COLIFORM LOAD FROM UNTREATED DISCHARGES

Bayou		me bypasse overflows (ga	4	Conc of dissolved sewage					
	1998	1999	2000	(cfu/100mL) ²	1998	1999	2000		
Buffalo Whiteoak	417,868 154,881	701,792 407,495	1,735,818 701,435	,	7.908E+12 2.931E+12	1.328E+13 7.712E+12	3.285E+13 1.327E+13		

Notes:

¹ Total volume calculated by adding the volume of all the reported overflows, leaks and bypassess for each year (Appendix II)

² Jensen, 1992 (GBNEP-21)

³ Calculated by multiplying the total volume for each year by the concentration of dissolved sewage


overflows. The calculated loads range from 2.93×10^{12} and 3.28×10^{13} between 1998 and 2000.

The common element to both dry weather sewer leaks and illicit discharges is that they result in flows to the stormwater system in dry weather that are transported to the bayous. These discharges enter to the bayous during a time when high concentrations of bacteria have been documented. Addressing these discharges and assessing their size and relevance to the overall problem is possible by monitoring storm drains near the point where they enter the bayous, as will be seen in the monitoring section of the report.

3.3.4 Discharge from Un-Sewered Areas

Although most of metropolitan Houston is served by sanitary sewer systems, there are still small areas within the watersheds that are on on-site systems. Sewage discharged from failed on-site systems may enter the stormsewers and increase the FC levels in receiving bayous.

The Houston-Galveston Area Council (H-GAC, 1999) has conducted a study that provided background information on 26 areas of concern previously identified by an earlier 319(h) Nonpoint Source Project. While these areas are not all unsewered and there are probably hundreds of unsewered locations in the region that have had some type of trouble with conventional septic systems, these 26 areas represent the worst cases of problem on-site systems. Among the 26 areas identified, as shown in Figure 3.6, three areas (#21- Recreation Farms; #24-Timber Lake Estates; and #25-Tower Oaks) appeared to be in the Whiteoak bayou watershed. However, on closer examination, two of the three are actually in the Cypress Creek watershed. Only Recreation Farms is in the study area.



Most of this area was reported to have adequate lot size for on-site systems, but several trailer parks and apartments were noted to need additional land area for alternative systems. Several alternatives for these situations were described.

The net effect at this time appears to be that with only one area identified in the watersheds, failed on-site systems do not appear to represent a major source of bacteria loading to the two bayous. This conclusion may need to be modified if additional information becomes available.

3.3.5 Loadings from Upstream Sources

As discussed in the first quarterly report, the most upstream routine sampling stations on Buffalo and Whiteoak bayous are the ones on Barker Dam and Jones Road, respectively. Both stations show consistently high FC levels over time, indicating potential FC sources upstream.

For Buffalo Bayou, the area upstream of Barker Dam includes Barker Reservoir, the City of Katy and other small communities. Table 3.7 shows that there are 25 permitted wastewater outfalls upstream of Barker Dam with a total 09/98 – 08/99 self-reporting flow of 7.6 MGD. A good portion of this area is also served by septic systems.

For Whiteoak Bayou upstream of Jones Road Table 3.7 lists four permitted wastewater outfalls with a total 09/98 - 08/99 self-reporting flow of 3.2 MGD. Some of this area is served by on-site systems.

The main purpose of the Addicks and Barker reservoirs is flood control, and stormwater is stored in the reservoirs for extended period of time after a storm event. The stored stormwater is discharged to the bayous gradually, typically for several weeks

TABLE 3.7
WASTEWATER DISCHARGERS UPSTREAM OF MONITORING POINTS

Permit name	Permit number	Permitted flow (MGD)	'98-'99 Self-reporte average flow (MGD)
BUFFALO BAYOU DISCHARGERS	UPSTREAM OF B	ARKER DAM	/
IGLOO PRODUCTS	02229-001	0.03	0.01
KATY	10706-001	3.45	1.27
WEST MEMORIAL MUD	11152-001	6.48	1.58
WILLIAMSBURG REGIONAL	11598-001	2.00	0.74
WESTON MUD	11632-001	0.10	0.03
CASTLEWOOD MUD	11883-001	1.37	0.47
MEMORIAL MUD	11893-001	3.00	1.19
GREEN TRAILS MUD	12289-001	0.99	0.51
FORT BEND CO MUD 034	12298-001	0.20	0.07
WEST PARK MUD	12346-001	0.50	0.19
HARRIS CO. MUD #345	12356-001	0.71	0.11
FORT BEND CO MUD 037	12370-001	0.18	0.11
COOPER CAMERON CORP	12412-001	0.01	0.00
NOTTINGHAM COUNTRY MUD	12479-001	1.30	0.40
HARRIS-FORT BEND COS MUD	12498-001	0.43	
HARRIS-FT BEND CO MUD	12805-001	0.25	0.02
HARRIS COUNTY-CULLEN	12858-001	0.03	0.01
CINCO MUD 001	13172-002	0.91	0.17
RLG REALTY HOLDINGS	13218-001	0.35	
FT BEND CO MUD 050	13228-001	0.70	0.04
GRAND LAKES MUD #4	13245-001	0.90	0.02
CINCO MUD 001	13558-001	1.69	0.64
NOTTINGHAM COUNTRY MUD (W	13674-001	0.05	0.03
HOUSTON AREA DEVELOPMENT	13775-001	0.25	0.03
GINTER REAL ESTATE	14011-001	0.15	
Total flow		26.03	7.64
WHITE OAK BAYOU DISCHARGER	S UPSTREAM OF	JONES ROAD	
HARRIS CO FWSD 061	10876-001	1.60	0.95
HARRIS CO FWSD 061	10876-002	3.00	1.28
HARRIS CO MUD 170	12121-001	2.50	0.94
TIFCO INDUSTRIES	12465-001	0.04	0.01
Total flow		7.14	3.18

after a significant event. Therefore, the sources of this upstream and background FC are most likely to include stormwater and discharges from domestic outfalls and septic systems. More targeted monitoring may be necessary to identify any specific source upstream of these stations.

3.3.6 Bacteria from Birds at Bridges

In the recent Bacterial Indicator Study (PBS&J, 2000) some indications of significant avian contributions to surface waters were noted. Data collected by the Upper Guadalupe River Authority documented levels under major bridges that routinely exceeded contact recreation criteria by a substantial margin. Exhaustive searches revealed no wastewater sources and levels away from the bridges were markedly lower. There were high bird populations living along and under the bridges leading the UGRA staff to conclude they were the most likely source of the high concentrations observed.

Another finding of the study was that direct measurement of fecal matter mixed in a standard concentration with buffered laboratory water found pigeon droppings to be relatively high in indicator bacteria. Levels were comparable with dogs, and markedly higher than cat or horse droppings.

Whether birds (or other wildlife) can make a significant difference in the Houston bayous is unknown. However, essentially all of the data in the area are obtained by sampling from bridges, and bridges do tend to support substantial bird populations. Further investigation of this contribution may be warranted.

3.3.7 Bacteria from Runoff

Runoff has long been documented to be high in bacteria. The precise reasons have not been defined in many cases. Newell *et al.* (1992) calculated FC loads to Galveston Bay from Buffalo and Whiteoak Bayous. Table 3.8 summarizes the calculated loadings for FC as well as runoff volumes for an average year and includes the event mean concentrations used in the calculation. The data in Newell *et al.* (1992) are useful for describing the magnitude of the overall non-point source contribution. However, and because of the dynamic nature of runoff events, additional non-point data collection and calculation would be needed for this TMDL.

As described in the first quarterly report (University of Houston and PBS&J, 2000a), many of the bayou data were collected when flows were above the median level. In theory, the difference between high- and low-flow FC data would be the runoff loads. However, as shown in Figures 3.2 and 3.3, this may not be a straightforward calculation. Also, as described above, the Barker and Addicks reservoirs store stormwater during storm events and discharge the water for an extended period of time after the events. Therefore, a precise divide between dry- and wet-weather flows is hard to define.

Statistical analysis of the moderate- and high-flow FC datasets for selected monitoring stations showed that the two datasets were not significantly different (section 2.2.3). This confirms the earlier assessment that it would be difficult to isolate the contribution of non-point sources by looking at FC data for high flows.

In addition to the FC data collected during high flows, as those reported in the first quarterly report, there are other sets of runoff data. As a part of the MS4 permit requirements, the City of Houston, Harris County and TxDOT have been collecting wet-

TABLE 3.8 AVERAGE YEAR TOTAL NON-POINT SOURCE LOADS

Watershed	Subwatershed	Area (sq mi)	Runoff volume	Average year FC	Total NPS load
			(thousands acre-ft) ^a	Concentration	(x10 ¹⁵ cfu)
Buffalo	BF01	40.13	33		7
	BF02	29.43	34		9
	BF03	16.57	20		5
	BF04	8.05	12		3
	BF05	10.72	17		4
	Total	104.9	116	19,178	27
Whiteoak	WO01	43.98	45		9
	WO02	11.35	14		3
	WO03	23.66	29		7
	WO04	21.25	26		6
	WO05	10.09	14		4
	Total	110.33	128	18,332	29

^a Case 1-Average annual rainfall

Source: Newell et al., 1992 (GBNEP-15)

weather samples from selected watersheds and analyzing them for bacteria and other parameters. Table 3.9 lists data collected in the last year as part of the program. The values shown are grab samples collected during runoff events. Most samples show high bacteria levels, in general agreement with other runoff data.

As part of an effort to quantify the effect of Sanitary Sewer Overflows (SSO), the City undertook a major effort to monitor stormsewers upstream and downstream of known overflow locations (Espey Huston and Associates Inc., 1994a). Table 3.10 lists the sampling stations monitored. At each site there is a stormsewer manhole upstream (U) and downstream (D) of a known overflow point. Five rain events were sampled at the ten sites (U&D) and the data are presented in Table 3.11. The composite samples were obtained by mixing individual samples in proportion to the flow that was estimated from the water level in the manhole. Bacteria analyses were performed by Dr. Ernst Davis of the UT School of Public Health.

One of the expectations of the study was that a systematic increase in bacteria concentrations could be found downstream of the SSOs, and that this increase could be used to quantify the impact on bayou water quality. This expectation was not met. Taken together, the data indicated higher concentrations on average in the upstream locations than downstream (Espey Huston and Associates Inc., 1994a). It was concluded that a combination of the high overall concentrations and large variability in stormwater bacteria data with no overflows, combined with the relative rarity of overflow events made the SSO "signal" too weak to detect above the background noise. A separate modeling analysis (Espey Huston and Associates Inc., 1994b) indicated that the SSO contribution was far too small to be detected by monitoring.

TABLE 3.9 STORMWATER BACTERIA DATA COLLECTED FOR MS4 PERMIT 1

Sampling site	Site location	Sampling date	Fecal Coliform	Fecal Streptococc	Enterococci
			(mpn/dL)	(mpn/dL)	(mpn/dL)
BUFFALO BAYO	U WATERSHED				
Tanglewilde	Manhole on Tanglewilde approximately 600 ft north of Ella Lee,	2/17/99	16,000	> 16,000	
	near a 30 ft ditch draining to the east.	3/12/99 ²	140	> 16,000	130
	Ů	4/14/99	90,000	90,000	90,000
Memorial City Mal	Manhole in the parking lot of Memorial City Mall, approximately	2/20/99	9,000	> 16,000	
	600 ft east-southeast of the corner of Gessner and the I-10	4/14/99	7,000	28,000	17,000
WHITE OAK BAY	OU WATERSHED				
Lazybrook	Former USGS substation east side of West T.C. Jester across	2/17/99	16,000	> 16,000	
	from Lazybrook Drive.	3/19/99	50,000		90,000
Eleventh Street	Manhole on south side of West Eleventh Street, approximately	1/28/99 ²	270	500	1
	500 ft west of Ella Blvd.	3/13/99	140	> 16,000	9,000
		3/19/99	1,700		13,000
Steeplechase	Manhole located on Bridgedown Drive approximately 700 ft west	2/11/99	5,500		< 2
	of Jones Road in the Steeplechase Corners Shopping Center.	6/15/99	260,000	350,000	90,000

Source: Annual Report for National Pollutant Discharge Elimination System Permit No. TXS001201, Reporting Period: October 1, 1998 - July 31, 1998. City of Houston/Harris County/Harris County Flood Control District/Texas Department of Transportation Storm Water Management Joint Task Force

¹ All values are grab samples.
² Event did not meet the EPA criterion that requires the minimum rainfall amount to be 0.10 in.

TABLE 3.10 SAMPLING LOCATIONS FOR SSO IMPACT STUDY

Site No.	Location
143-018U	Rosslyn Road @ Ebony Lane
143-018D	Rosslyn Road between W. 34th Street and the railroad
143-019U	Ella Blvd. @ East T.C. Jester Blvd.
143-019D	East T.C. Jester Blvd. east of Ella Blvd.
143-030U	W. 14th Street @ Herkimer Street
143-030D	W. 14th Street @ Alexander Street
143-037U	Hamilton Street @ Tidwell Road
143-037D	Hamilton Street @ Whiteoak Bayou (east of Harvard Street)
143-042U 143-042D	W. 6th Street @ Leafton Street (north side) 600 N. Shepherd Drive (parking lot between 6th Street and White Oak Bayou)
143-043U	Center Street @ Silver Street
143-043D	White Street @ Memorial Drive
143-047U 143-047D	Paschall Street @ Keene Street Paschall Street @ Marie Street
143-065U 143-065D	Detering Street @ Floyd Street Detering Street @ Lacy Street
143-090U	W. 13th Street @ Tulane Street
143-090D	Yale Street @ W. 7th Street
237-010U	Brittmore Road @ Perthshire Road
237-010D	Memorial Drive @ Rummel Creek

Source: Analysis of Sanitary Sewer Overflows Effects on Surface Water Quality Volume II Monitoring Overflow Effects on Urban Runoff Espey, Huston & Associates, Inc., 1994.

TABLE 3.11 SSO STORMWATER BACTERIA DATA

Date	Site 1		Fecal colifo	orm (cfu/dL)			E. Coli	(cfu/dL)		F	ecal Strepto	cocci (cfu/dL	_)		Enterocoo	cci (cfu/dL)	
		Upstrea	ım (U) ²	Downstre	am (D) 2	Upstrea	am (U) ²	Downstr	eam (D) 2	Upstrea		Downstre		Upstrea	am (U) ²	Downstre	eam (D) 2
	•	Composite	Grab	Composite	Grab	Composite	Grab	Composite	Grab	Composite	Grab	Composite	Grab	Composite	Grab	Composite	Grab
5-05-93	143-018	•															
5-23-93	143-018	29,000	> 50,000	< 1	500	22,000	500	< 1	< 1	4,300	485	180	60	4,950	2,400	500	520
6-19/20-93	143-018	12,000	15,000	4,400	2,000	4,000	2,000	600	1,000	900	1,100	300	500	300	700	100	100
10-20-93	143-018	19,500	30,000	115,000	4,000	5,000	15,000	60,000	2,000	9,000	11,000	18,000	17,500	< 1	4,000	6,500	6,000
11-16-93	143-018	245,000	310,000	340,000	450,000	130,000	6,500	140,000	25,000	107,500	131,500	48,500	49,500	24,000	17,000	14,500	26,500
5-05-93	143-019		150	> 38,000			< 1	19,000			500	3,350			< 1	1,000	
5-23-93	143-019																
6-19/20-93	143-019			1,000	7,000			< 1	3,000			350	420			550	< 1
10-20-93	143-019																
11-16-93	143-019	6,000	3,000	960,000	910,000	< 1	2,000	360,000	3,000	9,500	4,500	59,000	76,000	4,000	2,500	53,000	55,000
5-05-93	143-030																
5-23-93	143-030																
6-19/20-93																	
10-20-93	143-030	2,000		1,500		1,500		500		3,500		8,000		1,000		< 8,000	
11-16-93	143-030	270,000	480,000	305,000	540,000	105,000	250,000	120,000	230,000	26,500	35,500	51,000	59,500	< 26,500	24,000	41,000	21,500
5-05-93	143-037	350				150				200				< 1			
5-23-93	143-037		< 1		100		< 1		50		< 1		5		50		105
6-19/20-93			1,000		1,000		200		< 1		200		100		100		12
10-20-93	143-037	12,000	13,500	14,000	12,000	10,500	10,000	13,500	8,500	3,000	9,000	2,500	4,500	< 1	< 1	< 2,500	500
11-16-93	143-037																
5-05-93	143-042																
5-23-93	143-042		50		100		< 1		50		35		100		200		95
6-19/20-93			2,000		500		200		200	_	60		50		20		< 1
10-20-93	143-042	3,000	1,500	1,000	500	500	< 1	1,000	< 1	< 1	4,000	2,500	1,500	2,000	500	1,000	500
11-16-93	143-042	43,000	190,000	23,000	13,500	6,500	20,000	16,000	6,500	22,000	20,500	11,500	14,500	6,500	4,000	2,500	5,000
5-05-93 5-23-93	143-043			11,000	0.000			1,750				< 1	30			< 1	130
5-23-93 6-19/20-93	143-043				6,000				< 1				30				130
10-20-93				15,500		. 4		15,000		< 1		11,000		500		2,000	
11-16-93	143-043 143-043	< 1		15,500		< 1		15,000		< 1		11,000		500		2,000	
5-05-93	143-043											-					
5-23-93	143-047	2,500	1,000	3,000	100	750	500	200	< 1	250	95	300	15	170	600	2,500	125
6-19/20-93		200	200	3,000	100		< 1	200	100	90	500	300	1,000	50	< 1	2,300	< 1
10-20-93	143-047	200	200		100	100	'		100	30	300		1,000	30	'		' '
11-16-93	143-047	#######	250,000	50,000	100,000	210,000	50,000	40,000	50.000	28,000	24,000	21,000	56,000	< 28,000	13,000	21,000	28,000
5-05-93	143-047	8,500	200,000	4,050	100,000	2,000	50,000	2,000	50,000	< 1	24,000	650	50,000	< 1	10,000	< 1	20,000
5-23-93	143-065	0,000		1,000		2,000		2,000		l				l			
6-19/20-93												1					
10-20-93	143-065			45,000	45,000			40,000	40,000			17,500	19,500			8,500	11,000
11-16-93	143-065			.0,000	.0,000			.0,000	10,000			,000	.0,000			0,000	,000
5-05-93	143-090																
5-23-93	143-090		4,000		2,000]	< 1		< 1	1	215	I	20	1	1,400		300
6-19/20-93			550		2,000]	300		< 1	1	200	I	190	1	45		100
10-20-93	143-090	22,500	39,000	19,500	6,500	15,000	5,000	5,000	5,500	8,500	4,000	6,000	5,500	1,500	< 4,000	1,500	1,500
11-16-93	143-090	,	99,500	44,500	-,	.,.,.	10,000	31,000	-,	-,	32,000	25,000	-,	,	< 32,000	23,000	,
5-05-93	237-010										, , , , , , , , , , , , , , , , , , , ,	,			,	,	
5-23-93	237-010		250		550		< 1		< 1		10	1	30		135		65
6-19/20-93			1,000	100	1,650		100	50	1,000		160	110	300		30	90	200
10-20-93	237-010	30,000	50,000	44,000	31,000	30,000	15,000	19,000	17,500	24,000	16,000	15,500	17,500	10,500	10,500	7,500	12,000
11-16-93		150,000	145,000	210,000	170,000	105,000	30,000	50,000	50,000	45,000	27,000	35,000	22,000	28,000	13,000	19,000	20,000
		,	,	,	,		,		,		, , , , , , ,	,	,				

Source: Analysis of Sanitary Sewer Overflows Effects on Surface Water Quality, Volume II Monitoring Overflow Effects on Urban Runoff, Espey, Huston & Associates, Inc., 1994.

1 See Table 2-6 for site locations.

² Upstream/downstream of sanitary sewer overflow locations.

Another set of high flow data in study area bayous was collected by the USGS in 1993-1994. Table 3.12 lists the results of the sampling effort. FC levels during the high bayou flows were approximately ten times higher than in dry weather.

While runoff may be the most significant source of bacteria in Buffalo and Whiteoak bayous, its impact when bayou flows are low enough to support contact recreation is yet to be determined. Monitoring of smaller runoff events may be needed to address this issue.

3.3.8 Bacteria from Stream Sediments

Stream sediments contain bacteria that have shown positive on both the FC and EC tests (PBS&J, 2000). A review of the general literature indicated that the levels of FC and other pathogens are higher in sediments than in the overlying water column. Furthermore, it has been shown that sediments present appropriate conditions for an extended survival of bacteria. It is possible that such sediments function as a reservoir for bacteria, maintaining a near continuous source to the water through resuspension. To understand this possible mechanism will require field and laboratory monitoring, as described in the monitoring plan section of the report.

3.3.9 Relationships between Observed Fecal Coliform Levels and other Factors

Figures 3.7 and 3.8 show land use from the GBNEP non-point source study for Galveston Bay (Newell *et al.*, 1992). Both figures show the watersheds are mostly urban with some agriculture/open/pasture areas in the upper watersheds. The GBNEP study also included land use maps for Addicks and Barker Reservoirs (Figures 3.9and 3.10). The

TABLE 3.12 HIGH FLOW DATA IN BAYOUS COLLECTED BY USGS

DATE	Flow	Fecal	Fecal	DATE	Flow	Fecal	Fecal	DATE	Flow	Fecal	Fecal
	(cfs)	coliform	Streptococci		(cfs)	coliform	Streptococci		(cfs)	coliform	Streptococci
		(cfu/dL)	(cfu/dL)			(cfu/dL)	(cfu/dL)			(cfu/dL)	(cfu/dL)
BUFFALO BAYO	U AT SHE	PHERD DRIVE		BUFFALO BAYO	U AT MC	KEE STREET		WHITE OAK BAY	OU AT MA	IN STREET	
May 5 - 6, 1993				May 5 - 6, 1993				May 5 - 6, 1993			
5/5/93 11:20	476	6,700	18,000	5/5/93 11:26	1,800	920	2,200	5/5/93 11:05	500	700	2,800
5/5/93 13:35	925	8,700	19,000	5/5/93 11:49	2,500	19,000	25,000	5/5/93 12:12	520	6,000	50,000
5/5/93 15:22	1,100	9,300	25,000	5/5/93 13:22	3,850	55,000	46,000	5/5/93 14:52	1,950	17,000	60,000
5/5/93 23:10	1,290	23,000	30,000	5/5/93 16:16	4,400	35,000	32,000	5/5/93 17:12	1,470	31,000	62,000
5/6/93 1:10	1,200	20,000	27,000	5/5/93 20:17	3,400	26,000	54,000	5/5/93 20:18	1,300	38,000	84,000
5/6/93 13:47	806	9,300	20,000	5/6/93 2:29	1,880	13,000	41,000	5/6/93 0:03	1,000	26,000	35,000
May 23 - 24, 1993				May 23 - 24, 1993	}			May 23 - 24, 1993			
5/23/93 12:45	325	2,900	39,000	5/23/93 13:16	2,350	3,100	2,600	5/23/93 13:10	600	2,100	9,300
5/23/93 13:55	482	3,300	7,700	5/23/93 15:15	1,950	30,000	11,000	5/23/93 14:46	610	25,000	34,000
5/23/93 18:44	656	10,000	15,000	5/23/93 18:52	3,500	41,000	30,000	5/23/93 19:21	1,820	39,000	41,000
5/24/93 7:00	1,690	25,000	41,000	5/23/93 21:06	5,900	52,000	40,000	5/23/93 21:30	2,300	55,000	52,000
5/24/93 8:46	1,450	34,000	25,000	5/23/93 23:23	5,300	31,000	36,000	5/23/93 22:50	1,820	29,000	40,000
5/24/93 10:35	1,090	12,000	24,000	5/24/93 1:23	2,800	25,000	31,000	5/24/93 0:30	1,550	31,000	42,000
June 19 - 21, 1993	3			June 20 - 21, 199	3			June 19 - 21, 1993	3		
6/19/93 23:48	4,260	7,000	35,000	6/20/93 0:55	11,500	3,900	38,000	6/19/93 23:55	4,700	1,000	21,000
6/20/93 2:55	5,280	16,000	41,000	6/20/93 4:48	10,700	11,000	120,000	6/20/93 3:35	5,200	4,400	25,000
6/20/93 6:00	5,760	29,000	65,000	6/20/93 7:38	12,400	14,000	48,000	6/20/93 9:14	5,100	8,300	20,000
6/21/93 8:35	4,160	1,000	7,000	6/20/93 10:03	13,000	26,000	44,000	6/20/93 11:22	5,400	15,000	32,000
6/21/93 14:20	2,160	8,000	3,800	6/21/93 10:28	5,000	2,000	9,000	6/20/93 9:57	1,650	3,600	9,300
6/21/93 19:06	1,270	11,000	3,100	6/21/93 17:40	2,480	5,800	9,700	6/21/93 17:35	1,620	5,400	11,000

Source: Analysis of Sanitary Sewer Overflows Effects on Surface Water Quality, Volume III Overflow Modeling and Effects Quantification, Espey, Huston & Associates, Inc., 1994.




Figure 3.7 Buffalo Bayou Watershed Land Use (from GBNEP-15)





Figure 3.8 Whiteoak Bayou Watershed Land Use (from GBNEP-15)



by Intera Aero Service. Figure 3.9 Addicks Reservoir Watershed Land Use (from GBNEP-15)




Figure 3.10 Barker Reservoir Watershed Land Use (from GBNEP-15)


land use in the two reservoirs seems to be predominantly agriculture/open/pasture. It is noted that the GBNEP data are from 1990 and may require updating for use in this project. An analysis of the correlation between land use patterns and observed FC levels in the bayous is underway.


In addition to land use patterns, population data were gathered. The data in Figure 3.11 show the population distribution for the study area. An analysis of possible correlation between population and observed FC levels is underway.

Figure 3.12 shows the location of dischargers to Buffalo and Whiteoak Bayous on a subwatershed basis. It can be seen in Figure 3.12 that a significant number of major dischargers are located in the Addicks Reservoir and in the upper part of Whiteoak Bayou, which suggests that FC levels in the bayous are very influenced by upsteam sources, as discussed earlier in this report. The first monitoring stations in both Whiteoak and Buffalo Bayous include the effect of PS dischargers upstream (high FC values as shown by the monitoring data). The Addicks Reservoir, however, is classified as agricultural land (see Figure 3.9) and not as urban area. There is an area within Addicks Reservoir that is highly populated (8137) and two with moderate population (3334 and 2170), that explains the location of numerous WWTPs in an area classified as agricultural land.

3.3.10 Relative Importance of the Major Sources of Fecal Coliform to the Bayous

An evaluation of the relative importance of point sources (PS), non-point sources (NPS), and overflows from a loading perspective showed that the non-point sources are the major contributor of fecal coliform to Buffalo and Whiteoak Bayous. As shown in Figure 3.13, the NPS loads are one order of magnitude greater than those from PS and up








FIGURE 3.13 Contribution to FC load by source type (data from year 2000)

to three orders of magnitude greater than the loads from overflows and bypasses. However, it should be kept in mind that runoff is a shorter term dynamic phenomenon that affects FC conditions in the bayou on an intermittent basis.

3.3.11 Assessment of TMDL Curves

The Kansas TMDL Curve Methodology (KDHE, 1999) was followed to determine the issues surrounding the high bacteria levels at the Buffalo and Whiteoak Bayous and to differentiate between point and nonpoint sources. The TMDL Curve is a plot of the concentration of fecal coliform per day vs. the percent of days the load is exceeded at a specific monitoring station. Those points above the curve represent violations to the water quality standard, while the points below the curve represent compliance with the standards. The methodology followed to build the TMDL curves for the project area is described below (KDHE, 1999).

- Development of a flow duration curve for the gages located in Buffalo and Whiteoak Bayous (average daily flow values were used for this purpose).
- 2. Multiplication of the daily flows by the FC standard (200 cfu/day) and by a conversion factor to obtain a Load Duration (TMDL) Curve (i.e. daily load in cfu/day vs. percent days load exceeded).
- 3. Conversion of a FC concentration to a load by multiplying it by the flow measured when the sample was taken. Then, these points are plotted on the TMDL Curve.
- 4. Loads that plot above the curve in the flow regime defined as being exceeded 85-99% of the time are likely indicative of point source impacts on the water quality.

 Those points that fall above the curve over the range 10-70% flow exceedance

likely reflect nonpoint contributions. Points falling above the curve over the transition zone (70-85% flow exceedance) represent a combination of point and nonpoint source contributions. Those plotting above the curve at exceedances less than 10% or more than 99% reflect extreme hydrologic conditions of flood or drought.

Figures 3.14 and 3.15 present the TMDL Curves for the different stations along Buffalo and Whiteoak Bayous. It is important to note that since data from only one gage in Buffalo Bayou (West Belt) were available, loadings at all stations were compared to the same TMDL Curve built with the average daily flow data from the West Belt station. There are two USGS gages in Whiteoak Bayou, therefore, two different TMDL curves were developed for this bayou and data at a given station were compared to the TMDL curve that corresponds to the closer USGS gage.

Data in Figures 3.14 and 3.15 show that the water quality standard is violated most of the time, with a few points falling above the TMDL curve for both Buffalo and Whiteoak Bayous. These load exceedances are up to three order of magnitude higher than the load that supports contact recreation for a given flow value. It can also be observed that for both bayous the load points are distributed all over the range 10-99% of flow exceedance, which makes it difficult to differentiate between point and nonpoint source impacts. There are also some points falling above the curve over the flow range 0.1-10%, which reflect effects of very high flow events. The needed load and wasteload reductions to meet contact recreation standards will be quantified in the future.




Figure 3.14 TMDL Curves for Buffalo Bayou




Figure 3.14 TMDL Curves for Buffalo Bayou (Continued)





Figure 3.14 TMDL Curves for Buffalo Bayou (Continued)






Figure 3.14 TMDL Curves for Buffalo Bayou (Continued)




Figure 3.14 TMDL Curves for Whiteoak Bayou Stations







Figure 3.14 TMDL Curves for Whiteoak Bayou Stations (Continued)










Figure 3.14 TMDL Curves for Whiteoak Bayou Stations (Continued)

3.3.12 Conclusions and Recommendations

While there is a great deal of bacteria monitoring data available to characterize bayou levels, there appears to be very little available to identify specific sources of bacteria. More monitoring efforts targeted to testing specific sources will be needed to achieve the overall TMDL objectives.

Among the types of targeted monitoring that appear to be needed are: point source effluent testing, monitoring for sewer leaks and illicit discharges, special studies to address mechanisms such as regrowth/reactivation, sediment and avian sources, and monitoring of smaller runoff events.

CHAPTER 4

MODELING SOURCES AND MAJOR PROCESSES CONTROLLING OBSERVED LEVELS OF BACTERIA IN BUFFALO AND WHITEOAK BAYOUS

A major component of the Fecal Pathogen TMDL study will be the application of a suitable model to quantify the fate and transport of the indicator bacteria and to determine the maximum permissible loading to Buffalo and Whiteoak Bayous that will meet contact recreation criteria (Task 1.4). The modeling will also have to elucidate the effects of various sources and examine the effects of specific control measures. As part of the first work order for this contract (Work Order No. 582-0-80121-01), an in-depth model review was undertaken to evaluate the suitability of the existing Buffalo and Whiteoak Bayou SWWM models for meeting the goals of the project.

This chapter summarizes the findings from the review and provides justification for selecting the HSPF model for the study, as well as describes the activities needed to complete the modeling task. HSPF model development and calibration will be accomplished using the historical data gathered to date and the additional data that will be collected in this TMDL project. The EPA BASINS GIS interface will be used in this effort to the extent that is practical.

4.1 MODEL REVIEW

As discussed in the Source Analysis section, there are a number of sources of indicator bacteria and several important processes to be considered. The bacteria levels in the bayous are a combined result of inputs from the watersheds as well as processes in the bayous. A number of sources may have significant effects in dry weather conditions. These include point sources, direct sewage inputs from collection system leaks, and seepage or leaks from un-sewered areas. In addition, runoff is also a significant source of bacteria during wet weather periods. Of particular interest are the small to moderate rain events that result in moderate flow conditions under which contact recreation is still practical. Given that runoff from such events would impact the fate and transport of bacteria in the bayous for a period following the events, the modeling must include runoff simulations. Therefore, a dynamic model is required instead of a steady-state model. An additional requirement is the capability of the model to represent data sets collected along the bayou over a short time span following a wide range of antecedent conditions. To achieve this goal efficiently, a continuous model is a practical necessity.

Ward and Benaman (1999) have conducted a survey and review of models for TMDL application in Texas. They concluded that the following are the most appropriate existing models for watershed simulation:

- Hydrologic Simulation Program Fortran (HSPF) by the U.S. Environmental Protection Agency (EPA).
- Soil and Water Assessment Tool (SWAT) by the Agricultural Research Service of the U.S. Department of Agriculture.
- Precipitation-Runoff Modeling System (PRMS) by the U.S. Geological Survey.

They noted that while these were recommended, each has significant weaknesses and limitations for Texas application. They also identified the EPA Storm Water Management Model (SWMM) as a specialized model that may be applicable for some TMDL problems in urban areas.

Since PRMS does not include a water-quality capability, it is not further considered in this evaluation. Ward and Benaman commented that the greatest weakness of SWAT is its reliance on the empirical formulations of the curve number method and the universal soil loss equation. Between SWAT and HSPF, the deterministic basis of HSPF hydrology and sediment loading is preferred.

For this review, SWMM and HSPF are short-listed for further evaluation for the following reasons. They are readily available in the public domain. They have undergone years of development. They have been used extensively for various purposes and are widely accepted professionally. Various forms of technical support are available such as limited support from the model developers and Internet discussion groups.

SWMM simulates storm events with rainfall input, other meteorological inputs and system characterization to predict runoff quantity and quality. It is capable of modeling the rainfall/runoff process, including surface and subsurface flows, runoff quality, the transport routing through the drainage networks or channel systems, and through a set of storage and treatment units. Either the Horton or the Greens-Ampt equations can be used for estimating infiltration in SWMM. The kinematic wave method is used for flow routing. Alternatively, one of the modules, the EXTRAN block, can perform in-stream flow routing by solving the St. Venant's equations. However, the EXTRAN block does not have water quality simulation capability.

HSPF simulates the hydrologic and water quality processes on pervious and impervious land surfaces as well as streams. It uses a conceptual framework to account for the fluxes and storage involved in interception, infiltration, overland flow, interflow, groundwater and evapotranspiration. The model performs fate and transport of water quality constituents in one-dimensional channels. The kinematic wave method is used to obtain the land segment flows and to perform channel routing.

Both SWMM and HSPF are capable of modeling the following processes that are relevant in the TMDL study:

- Build-up and washoff of water quality constituents in the watershed.
- Quality routing by means of advection and mixing in the stream.
- In-stream first-order decay of water quality constituents.
- Scour and deposition of sediments in the stream.

SWMM was originally developed for event simulation. A continuous simulation capability has been added in a later version. In order to perform continuous simulation, the model needs to account explicitly for antecedent conditions. In the case of the Horton model, SWMM uses a hypothetical drying curve to regenerate infiltration capacity during dry weather. For the Green-Ampt model, recovery of infiltration capacity is by means of a simple empirical procedure. In contrast, HSPF was developed as a continuous model. It computes a continuous moisture balance within a watershed, taking into account evapotranspiration and other long-term hydrologic abstractions that are responsible for the change in moisture during dry periods. It appears that HSPF is the better choice for continuous simulation.

Ward and Benaman (1999) also recommended QUAL-TX for steady-state, low-flow-dominated problems. QUAL-TX is a one-dimensional steady-state water quality model developed by the predecessor agencies to the TNRCC. It is a modified version of the EPA QUAL-II. The model has been widely used in the field of water quality modeling, especially for stream waste load allocation for meeting dissolved oxygen criteria. The model solves the one-dimensional mass transport equation which describes the effects of advection, dispersion, decay, sources and sinks of the constituents being modeled. The hydraulics is handled by solving the continuity equation for flow and then obtaining the depth from stage-discharge relationship. While the representation of sources, sinks and biochemical processes is good, the inability of the QUAL-TX model to simulate runoff or dynamic flow conditions eliminates it from consideration at this point. Nevertheless, if future events in the project show that only steady-state low flow conditions are important, QUAL-TX may be reconsidered.

For time varying problems, Ward and Benaman suggested that the DYNHYD/WASP combination (Dynamic Hydrodynamics Program and Water-quality Analysis Simulation Program by EPA) is the best option available for modeling streams and rivers. However, there is indication that DYNHYD may not be able to handle the abrupt storm events common in Texas. Moreover, a disadvantage of WASP is that it requires user-supplied kinetics.

Ward and Benaman (1999) recommended that the receiving water component of HSPF not be used in TMDL evaluations for two reasons. First, the flow routing in HSPF is very simplistic and depends on a user-defined relation between discharge and depth, in

principle similar to the approach in QUAL-TX. Second, the resolution of the watercourse is limited by the delineation of the subwatershed segments.

The above limitations do not appear to be severe enough to preclude the use of the stream module in HSPF for TMDL application. A recent TMDL application of HSPF for fecal coliform in Idaho appears to have satisfactory results (EPA, 2000). As the model will only be used for conditions where contact recreation is practical (i.e. low to moderate flows), the lack of sophisticated hydraulics does not pose a limitation. Adequate resolution of the bayous could easily be obtained by delineating smaller subwatersheds and reaches in the areas of interest while still keeping the total number of subwatersheds to a manageable level. On the other hand, there does not appear to be a distinctively better alternative to using the HSPF stream module. As noted above, the DYNHYD/WASP combination recommended by Ward and Benaman (1999) has its own limitations. Moreover, linking HSPF to DYNHYD/WASP, or any other receiving water model, will significantly increase the complexity of the modeling effort.

4.2 PRELIMINARY RECOMMENDATIONS

Based on a review of various water quality models by the project team and consideration of the recommendations in Ward and Benaman (1999), HSPF with both its watershed and stream modules appears to be the best option and is recommended for the bacteria TMDL study. The project team has discussed the above model evaluation with Dr. George Ward. He basically concurred with the recommendation (Ward, 2000). Nevertheless, he cautioned that there might be stability problem in the HSPF stream module when the stream is finely divided into small reaches. This particular aspect will

be investigated in the early stage of the modeling effort. In the event that there are indeed problems with the HSPF stream module, depending on the seriousness of the problems, necessary precautionary and/or remedial measures will be developed, or a suitable receiving water model may have to be linked with the watershed module of HSPF.

A list of model requirements as well as the availability of the data to date is included in Table 4.1.

The project team may consider using the HSPF model built in the BASINS platform (i.e. NPSM). The reason for this is that the use of an integrated modeling system will allow the comprehensive management of water resources, while taking advantage of GIS capabilities. The Better Assessment Science Integrating Point and Nonpoint Sources (BASINS) system was developed under the direction of EPA's Office of Science and Technology, Standards and Applied Science Division and in cooperation with an interdisciplinary team from Tetra Tech, Inc. (Lahlou et al., 1998). BASINS is an interface designed within the GIS platform, ArcView 3.x that provides a more efficient way to approach watershed and water quality management. It integrates several environmental data sets with analysis techniques and environmental models, and assists in various stages of environmental management and planning. The user interface is designed to facilitate data input using GIS capabilities. In addition, BASINS was partially designed as a tool to support TMDL development (Lahlou et al., 1998).

Table 4.1 DATA REQUIREMENTS FOR HSPF (NPSM in BASINS)

<u>Data type</u>	Available?
Land use-land cover data	Yes (GBNEP, BASINS)
Estimated number of swine and beef and dairy cows	Needs to be prepared
% annual manure production applied to cropland	Needs to be prepared
Assumed number of wildlife per square mile	Needs to be prepared
Cattle in streams/other point sources	Needs to be prepared
Watershed delineation	Yes (Flood Control, PBS&J)
Stream networks – river reach files	Yes (EPA R1 and R3)
Stream geometry/cross sections	Needs to be prepared
(depth, channel lengths and slopes, cross-sectional area,	1 1
wetted perimeter, flow rate)	
Digital elevation data	Yes (TNRIS)
Soils data	Yes (TNRIS)
Weather data	Yes (USGS)
Precipitation data (hourly)	
Temperature (daily max and min, daily dewpoint)	
Wind (total daily wind movement)	
Evapotranspiration (daily pan evapotranspiration)	
Total daily solar radiation	
Average daily cloud cover	
Population/areas served by septic systems	Yes
Point sources	Yes
Estimated/actual concentration in runoff	From TMDL Sampling Plan
Sediment concentrations and mass losses in runoff	From TMDL Sampling Plan
Resuspension from sediment	From TMDL Sampling Plan
Measured concentrations of FC	Yes (TNRCC, USGS, PWE)
Flow	Yes (USGS)
Rates during monitored storm events	
Flow volume (daily, monthly, annual)	

The BASINS system combines six components for performing watershed and water quality analysis:

National databases with local data import tools

Assessment tools (TARGET, ASSESS, and Data Mining) that address needs ranging

from large-scale to small-scale basins

Watershed Characterization Reports

Utilities including Data Import, Land Use Re-Classification, DEM Reclassification, and Watershed Delineation

Watershed and water quality models including NPSM/HSPF, TOXIROUTE, and QUAL2E

Post-processing output tools.

The BASINS system includes, in addition to the NPSM model (which is the Windows version of HSPF), two other watercourse models to predict the impact of different point and nonpoint source loading scenarios on surface water bodies. These models are TOXIROUTE and QUAL2E. The use of QUAL2E is restricted to steady-state flow conditions, but if future research in the project shows that only steady-state low flow conditions are important, this could be the model of choice (see previous discussion on the QUAL-TX model).

As discussed by Ward and Benaman (1999), the usefulness of BASINS consists largely on the fact that it is a starting point for the modeler. It provides a varied array of data files and it allows the user to perform model runs and calibrations with minimal time spent on data management itself. The postprocessor supports daily, monthly, and annual NPSM output. The postprocessor displays NPSM simulation output, BASINS water quality observation data, and USGS flow data in a graphical format. It also performs basic statistical calculations and data comparison. However, Ward and Benaman (1999) cautioned the fact that this software is too easily accessible to the inexperienced user: it does require certain degree of knowledge and experience in order to use it correctly and make sense of the results. They concluded that while BASINS as a model shell offers some potentially important advantages, in facilitating set-up of a watershed model, and in

allowing preliminary simplified model evaluations, its use could be limited due to bugs in the present model (version 2.1) that will have to be worked through. In addition, better receiving water models could be needed for final TMDL determinations than afforded by BASINS.

As of this writing a new version of BASIN has been released (i.e. version 3.0-beta). This version includes updates related to the year 2000 compliance as well as improvements to existing functions and models. It is likely that this new version corrects some of the bugs reported in the previous one. In addition, case studies reporting the successful use of BASINS for the development of fecal coliform TMDLs in Idaho (EPA, 2000) and Florida (EPA Region 4, 2000) may support the use of this platform in our project.

4.3 MODELING ACTIVITIES


The goal of this task is to use models to elucidate the sources and major processes controlling observed levels of fecal pathogens in Buffalo and Whiteoak Bayous and to identify the maximum permissible loading. The models will also be used to examine the effects of specific control measures. This modeling effort will use fecal coliform and/or the current *Escherichia coli* (*E. coli*) criteria (TNRCC, 2000), as applicable, as the basis of evaluation.

Key steps in the modeling effort include the following:

Delineation of the Buffalo and Whiteoak Bayou watersheds to define subwatersheds.
 The intersections of the boundaries of these subwatersheds and the bayous and tributaries then define the reaches in the model. Factors to be considered in the

delineation include locations of stream gages, locations of bacteria monitoring stations, locations of confluences with major tributaries, variation of channel characteristics, and desired spatial resolution for scenario simulations. Figure 4.1 shows a preliminary delineation of the watersheds. This will be refined as part of the modeling task.

- Compilation and preparation of water quality, sources, and other data on fecal pathogens from previous stages of the project and additional data collection conducted as part of the TMDL. This step also includes the preparation of precipitation and meteorological data, watershed land use/land cover characteristics, hydrography and channel characterization, and other data needed to set-up the HSPF model for Buffalo and Whiteoak Bayous (See Table 4.1).
- *Model calibration* to existing conditions using the collected data. Model calibration will be refined through the following steps:
 - develop an overall water mass balance that compares well with observed data by adjusting overall gains and losses of water in the watershed from precipitation, evapotranspiration, and loss to deep groundwater;
 - match the monitoring data by adjusting the rates at which water percolates through the soil, enters groundwater, and recharges streams in a trial-and-error fashion;
 - match peak storm volumes and reproduce the number of days required for flow to return to normal levels;
 - fit the seasonal distribution of flows based on seasonal variation in evapotranspiration, soil moisture, etc.; and



match the observed fecal coliform/*E. coli* concentrations by iteratively adjusting the point and non-point sources on a subwatershed-by-subwatershed basis.

- Sensitivity analyses to show the extent of variation or uncertainty in the model to changes in various parameters in the model.
- Model runs to predict required bacteria load reduction for the studied bayous to meet
 the water quality standards, and how long it would take to meet these targets. The
 model will also be run under specific bacteria discharge reduction scenarios.

CHAPTER 5

MONITORING PLAN FOR ADDITIONAL DATA COLLECTION

The Buffalo and Whiteoak Bayou systems have been and continue to be monitored for a range of conventional water quality parameters. The monitoring data have been analyzed (Chapter 2) and indicate that the bayous maintain relatively high concentrations of indicator bacteria even under dry weather conditions when essentially all of the flow is composed of treated and disinfected wastewater. The expectation for disinfected wastewater would be low bacteria levels.

The main reasons for monitoring under the TMDL project are to understand and document the sources of these elevated bacteria levels so that development of appropriate control measures that can be implemented to bring bacteria levels into compliance with the contact recreation criteria. A second reason is to better understand the processes affecting bacteria concentrations in the bayous, such as survival in the water and sediment, possible regrowth/reactivation, and inputs from the sediments. A third reason for monitoring is to obtain better data to calibrate a water quality model of the system.

A quality assurance project plan (QAPP) for the monitoring activities in support of the bacteria TMDL was developed and is included in Appendix D. Monitoring activities will include four major components:

- Monitoring of point sources,
- Searches for illicit discharges in both sewered and unsewered areas, and
- Moderate runoff event sampling

Analyses of concentration dynamics in the bayous.

5.1 POINT SOURCE MONITORING

In dry weather essentially all of the flow in these urban bayous is from point source discharges. Therefore, our search for understanding of water bacteria levels will start with these water sources. These discharges are required to maintain a chlorine residual of 1 mg/L for at least 20 minutes and plants larger than 1 MGD are required to dechlorinate down to a concentration of <0.01 mg/L. These requirements must be met in wet weather conditions when the plants are at maximum permitted flows (these requirements must be met at all times, although they are most difficult to meet during wet weather events). In practice, the chlorine contact time is much longer in dry weather and low flows. If all of these requirements were met, in theory there should be very low levels of indicator bacteria in the effluents. Since the effluents essentially are the bayou flows in dry weather, low bacteria levels should be the norm. However, sampling done as part of a recent Greens Bayou Intensive Survey (City of Houston Public Works and Engineering Department, 1999) showed discharged FC concentrations higher than 200 cfu/dL, with 2 of 12 samples exhibiting FC counts near 10,000 cfu/dL. Similarly, data from inspections conducted by HCPC between 1998 and 2000 showed that 25 out of 29 measurements (for a total of 18 small plants in the Buffalo and Whiteoak Bayous) exceeded the limit of 200 cfu/dL, with 14 samples showing FC levels higher than 10,000 cfu/dL.

One of the problems with smaller plants may be poor control over the chlorination process. While the City of Houston (COH) plants in these stream segments have a sophisticated system to regulate the dosage of disinfectant and the sodium bisulfite dechlorination agent, that is not true for many of the smaller facilities. That lack of

automatic control, plus the fact that these plants are checked infrequently, may mean that high levels of indicator bacteria are not at all uncommon. In Whiteoak and Buffalo, there are 76 and 44 domestic WWTP with flows lower than 1 MGD, respectively releasing close to 38 and 12% of the median flow in these bayous (45 and 90 cfs, respectively).

To investigate and document this situation a program of point source monitoring that will include early morning and mid-morning sampling of a broad range of plants over the course of a 6-month period is proposed. This sampling effort will cover all the minor domestic wastewater treatment plants (flow less than 1 MGD) discharging to Buffalo and Whiteoak Bayous. A total of 120 wastewater dischargers will be sampled (see Figure 5.1 and Table 5.1 for sampling location and scheduling)

A sampling crew (2 people) will leave early in the morning to sample two small plants by 0800, and then will deliver the samples to the lab. This round of samples will characterize the discharge at the low point in the diurnal flow cycle. Samples will be collected at a point following the chlorine contact chamber as it is flowing over the weir. The sampling will include doing a field measurement of residual chlorine, estimating the flow, estimating conventional chemical parameters (see Table 5.2) and collecting water samples for laboratory analyses. Each of the samples will be analyzed for FC and *E. coli* along with TSS

The *E. coli* analyses will be performed using the IDEXX Colilert method that is a separate test from the FC analysis, which may result in *E. coli* counts higher than the FC data.

To sample the high flow period, the crew will repeat the trip in mid-morning, getting the samples to the lab by early afternoon. This process will continue during dry




Table 5.1 Monitoring Sites and Frequencies

Sampling	1	Permit SC1/ Prog					Monitoring	g frequencie	es (per monitoring program)									
Jumpung	Segment	Site description	number/	Sample ID	Start Date	End Date	501,	1105	Flow	FC	EC	TSS	TOC	Wet		Ammonia	CBOD ₅	Grain size
Component ^a	Segment	Site description	Station ID	Sumple 12	Start Date	Ziiu Ziiie	SC2	Code						chemistry ^b	chlorine			
I.1	1017	HARRIS CO FWSD 061	10876-001	S1	7/2/01		UH/UH	DL	2 ^c	2 ^e	2 ^c	2°		2°	2 ^e			
	1017	TIFCO INDUSTRIES	12465-001	S2	7/2/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^c			
	1017	DANIEL INDUSTRIES	12397-001	S3	7/3/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	NORTHW HARRIS CO MUD 029	12795-001	S4	7/3/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	WHITE OAK BEND MUD	11979-002	S5	7/4/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	HARRIS CO MUD 170	12121-001	S6	7/4/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	REID ROAD MUD 001	11563-001	S7	7/5/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	WEST HARRIS CO MUD 010	14072-001	S8	7/5/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	AQUASOURCE DEVELOPMENT	13433-001	S9	7/9/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	WEST HARRIS CO MUD	13623-001	S10	7/9/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	SUPERIOR DERRICK SERV	12443-001	S11	7/10/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	RIEDEL, ANTHONY	13939-001	S12	7/10/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	ABB VETCO GRAY INC	11651-001	S13	7/11/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	SMITH, WILLIAM	12573-001	S14	7/11/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	HANOVER LAND CO.	11797-001	S15	7/12/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	CHAMP'S WATER CO.	11005-001	S16	7/12/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^e		2 ^e	2 ^e			
	1017	HARRIS CO MUD #119	12714-001	S17	7/16/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^e		2 ^e	2 ^e			
	1017	CBI NA-CON INC.	11389-001	S18	7/16/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	KONECRANES LANDEL	13912-001	S19	7/17/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2°		2°	2 ^c			
	1017	C&P UTILITIES	12342-001	S20	7/17/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^e	2 ^e			
	1017	SMITH, BOB	13509-001	S21	7/18/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	HARRIS CO METRO UD	13673-001	S22	7/18/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	MOORPARK VILLAGE	13727-001	S23	7/19/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	ROLLING FORK PUD	11188-001	S24	7/19/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	CREEKSIDE UTILITIES	11375-001	S25	7/23/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	HARRIS CO MUD 006	11273-001	S26	7/23/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	HARRIS CO MUD 023	11485-001	S27	7/24/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^e		2 ^e	2 ^e			
	1017	SUNBELT FWSD	11670-001	S28	7/24/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	MCDONALDS CORP.	13807-001	S29	7/25/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	RESTAURANT SERVICE	13983-001	S30	7/25/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^e		2 ^e	2 ^e			
	1017	VANCOUVER MANAGEMENT	11051-001	S31	7/26/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1017	WEST HARRIS CO MUD 011	13689-001	S32	7/26/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	HARRIS CO MUD 130	12574-001	S33	7/30/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	HARRIS CO MUD 247	12681-001	S34	7/30/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	NCI BUILDING SYSTEMS	12552-001	S35	7/31/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	NCI BUILDING SYSTEMS	12552-002	S36	7/31/01		UH/UH	DL	2 ^c	2°	2 ^c	2 ^c		2°	2°			
	1014	ADAMOLI, JAMES	12811-001	S37	8/1/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	COOPER CAMERON CORP.	13578-001	S38	8/1/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	OCEANEERING	12466-001	S39	8/2/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	ROBINSON, J. WAYNE	12830-001	S40	8/2/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	WEATHERFORD U.S.	14070-001	S41	8/6/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	AQUASOURCE UTILITY	11193-001	S42	8/6/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	AQUASOURCE UTILITY	12222-001	S43	8/7/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	HOUSTON-WESTWAY UD	10495-139	S44	8/7/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	FAIRBANKS PLAZA SHOPPING	12139-001	S45	8/8/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1017	TRAMMELL CROW	13996-001	S46	8/8/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD 157	11906-001	S47	8/9/01		UH/UH		2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	•	•	•	•	•	•		,	•	•	•	•	•	•	•	•	•	•

Table 5.1 Monitoring Sites and Frequencies

Sampling		Permit SC1/ Prog				Monitorin	frequencie	s (per monitoring program)										
Jumpung	Segment	Site description	number/	Sample ID	Start Date	End Date	501,	1105	Flow	FC	EC	TSS	TOC	Wet		Ammonia	CBOD ₅	Grain size
Component ^a	g		Station ID	~ .			SC2	Code						chemistryb	chlorine			
	1014	HARRIS COJUVENILE BOOT CAMP	13921-001	S48	8/9/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2°	2 ^e			
	1014	HARRIS CO MUD 196	12447-001	S49	8/13/01		UH/UH	DL	2 ^e	2 ^c	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	REMINGTON MUD 001	13328-001	S50	8/13/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	WYMAN-GORDON FORGINGS	01402-002	S51	8/14/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	WEST HARRIS CO MUD #15	12223-001	S52	8/14/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD 105	11792-002	S53	8/15/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	NORTHW HARRIS CO MUD 012	11991-001	S54	8/15/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD 127	12209-001	S55	8/16/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD 167	12834-001	S56	8/16/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	ROLLING CREEK UD	12841-001	S57	8/20/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD 284	12949-001	S58	8/20/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD #149	11836-001	S59	8/21/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD 155	12726-001	S60	8/21/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	SPENCER ROAD PUD	11472-001	S61	8/22/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	CHIMNEY HILL MUD	12304-001	S62	8/22/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	SASSON, ELI	11414-001	S63	8/23/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	VERRY, RICHARD	12310-001	S64	8/23/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	HARRIS CO MUD 250	12685-001	S65	8/27/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	PETERSEN, JAMES	12398-001	S66	8/27/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	529 #35, LTD	13484-001	S67	8/28/01		UH/UH	DL	2 ^e	2 ^c	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	VARCO SHAFFER	03994-001	S68	8/28/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	AIR LIQUIDE AMERICA	13959-001	S69	8/29/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	HORSEPEN BAYOU MUD	12128-001	S70	8/29/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	TOSHIBA INTERNATIONAL	03153-002	S71	8/30/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	HARRIS CO MUD 102	11523-001	S72	8/30/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	HARRIS CO MUD 185	12124-001	S73	9/3/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	HARRIS CO MUD 276	12927-001	S74	9/3/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	FRIEDMAN, STEPHEN	13778-001	S75	9/4/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	LANGHAM CREEK UD	11682-001	S76	9/4/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	NORTHWEST HARRIS CO MUD 16	11935-001	S77	9/5/01		UH/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	HARRIS CO MUD 166,257,276	12474-001	S78	9/5/01		UH/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	HARRIS CO MUD 071	11917-001	S79	9/6/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	WEST HARRIS CO MUD 007	12140-001	S80	9/6/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	TEX-SUN PARKS	12189-001	S81	9/10/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	WEST HARRIS CO MUD 017	12247-001	S82	9/10/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	MAYDE CREEK MUD	11969-001	S83	9/11/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	FRY ROAD MUD	11989-001	S84	9/11/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	KATY ISD	12110-001	S85	9/12/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	HARRIS CO MUD 238	12802-001	S86	9/12/01		UH/UH	DL	2 ^c	2 ^c	2 ^e	2 ^c		2 ^e	2 ^e			
	1014	WESTLAKE MUD 001	11284-001	S87	9/13/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	WEST PARK MUD	12346-001	S88	9/13/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	ADDICKS UD	11696-002	S89	9/17/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
	1014	WEST HOUSTON AIRPORT	12516-001	S90	9/17/01		UH/UH	DL	2 ^e	2 ^e	2 ^c	2 ^c		2 ^e	2 ^e			
	1014	WILLIAMSBURG REGIONAL	11598-001	S91	9/18/01		UH/UH	DL	2 ^e	2 ^e	2 ^c	2°		2 ^e	2 ^e		1	
	1014	WESTON MUD	12412-001	S92	9/18/01		UH/UH	DL	2 ^e	2 ^e	2 ^c	2 ^c		2 ^e	2 ^e			
	1014	HARRIS COUNTY-BEAR CK	11883-001	S93	9/19/01		UH/UH	DL	2 ^e	2 ^e	2 ^c	2 ^c		2 ^e	2 ^e			
	1014	TRANSWESTERN KATY FREEWAY	11632-001	S94	9/19/01		UH/UH		2°	2 ^c	2°	2°		2°	2 ^c		1	
		1						_								•	•	•

Table 5.1 Monitoring Sites and Frequencies

Sampling			Permit		I		SC1/	Prog		.		Monitoring	fraguancia	s (per monitorin	a program)			
Samping	Segment	Site description	number/	Sample ID	Start Date	End Date	301/	rrog	Flow	FC	EC	TSS	TOC	Wet		Ammonia	CBOD.	Grain size
Component ^a	Segment	Site description	Station ID	Sample 1D	Start Date	Liiu Date	SC2	Code	11011	10	LC.	155	100	chemistry ^b	chlorine	7 x minioma	свов,	Grain size
Component	1014	CASTLEWOOD MUD	12356-001	S95	9/20/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
		HARRIS CO. MUD #345	12682-001	S96	9/20/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
		HOUSTON-PARK TEN	10495-135	S97	9/24/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
		HARRIS CO MUD 216	12406-001	S98	9/24/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	1014	GREEN TRAILS MUD	10932-001	S99	9/25/01			DL	2°	2°	2°	2°		2°	2°			
	1014	NOTTINGHAM COUNTRY MUD	12427-001	S100	9/25/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	-	HARRIS COUNTY-CULLEN	12355-001	S101	9/26/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	1014	NOTTINGHAM COUNTRY MUD (WTP)	12233-001	S102	9/26/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	1014	ASEP AMERICA, INC.	12132-001	S103	9/27/01		UH/UH	DL	2 ^c	2 ^c	2 ^e	2 ^c		2°	2 ^c			
	1014	AIVAZIAN, GEORGE	13764-001	S104	9/27/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
		BAYOU CLUB OF HOUSTON	12289-001	S105	10/1/01		UH/UH	DL	2°	2°	2 ^c	2°		2°	2°			
	1017	TOWER MANAGEMENT SERV	12479-001	S106	10/1/01		UH/UH	DL	2 ^c	2 ^c	2 ^e	2 ^c		2°	2 ^c			
	1017	WHITE OAK OWNERS ASSOC.	12370-001	S107	10/2/01		UH/UH	DL	2 ^c	2 ^c	2 ^e	2 ^c		2°	2 ^c			
	1014	FORT BEND CO MUD 034	12498-001	S108	10/2/01		UH/UH	DL	2 ^c	2°	2 ^c	2°		2°	2°			
	1014	FORT BEND CO MUD 037	13775-001	S109	10/3/01		UH/UH	DL	2°	2°	2°	2°		2°	2 ^c			
	1014	COOPER CAMERON CORP	12805-001	S110	10/3/01		UH/UH	DL	2 ^c	2 ^c	2 ^e	2 ^c		2°	2 ^c			
		HARRIS-FORT BEND COS MUD	13228-001	S111	10/4/01		UH/UH	DL	2 ^c	2 ^c	2 ^e	2°		2°	2 ^c			
		HARRIS-FT BEND CO MUD	12298-001	S112	10/4/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
		BIG OAKS MUD	13674-001	S113	10/8/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	1014	CINCO MUD 001	12858-001	S114	10/8/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	1014	RLG REALTY HOLDINGS	13021-001	S115	10/9/01		UH/UH	DL	2 ^c	2°	2 ^c	2°		2°	2°			
	1014	FT BEND CO MUD 050	13245-001	S116	10/9/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	1014	GRAND LAKES MUD #4	13172-002	S117	10/10/01		UH/UH	DL	2°	2°	2°	2°		2°	2°			
	1014	CINCO MUD 001	13558-001	S118	10/10/01		UH/UH	DL	2°	2°	2°	2°		2°	2 ^c			
	1014	HOUSTON AREA DEVELOPMENT	14011-001	S119	10/11/01		UH/UH	DL	2 ^c	2 ^c	2 ^e	2 ^c		2°	2 ^c			
	1014	GINTER REAL ESTATE	13218-001	S120	10/11/01		UH/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.2		20 POINT SOURCES (HIGHEST LEVELS)	tbd		10/15/01	11/2/01	UH/UH	DL	2	2	2	2		2	2			
П	1017	PILOT AREA 1 - WHITEOAK	30 locations tbd	I1 to I30	9/3/01	2/1/02	UH/UH	DL	1 dry	1 dry	1 dry	1 dry		1 dry	1 dry	1 dry		
Ш	1014 1014	PILOT AREA 2 - BUFFALO DAIRY ASHFORD RD.	30 locations tbd 11362	I31 to I60 R1	9/3/01 7/2/01	2/1/02 8/31/01	UH/UH PB/PB	DL DL	1 dry 10 wet	1 dry 10 wet	1 dry 10 wet	1 dry 10 wet		1 dry 10 wet	1 dry	1 dry		
	1014	WEST BELT	11360	R2	7/2/01	8/31/01	PB/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet				
		WEST BELT	11360	R2	7/2/01	8/31/01	GS/GS	DL	10 wet									
		PINEY POINT RD	11358	R3	7/2/01	8/31/01	PB/PB	DL		10 wet	10 wet	10 wet		10 wet				
	1014 1014	PINEY POINT RD SHEPHERD DR.	11358 11351	R3 R4	7/2/01 7/2/01	8/31/01 8/31/01	GS/GS PB/PB	DL DL	10 wet 10 wet	10 wet	10 wet	10 wet		10 wet				
	1014	HEIGHTS BLVD.	11331	R5	7/2/01	8/31/01	PB/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet				
		HEIGHTS BLVD.	11387	R5	7/2/01	8/31/01	GS/GS	DL	10 wet	10 1101	10 1101	10 1101		10 1101				
	1017	JONES RD.	11398	R6	7/2/01	8/31/01	PB/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet				
TV/ 1	1017	W. TIDWELL AVE.	15831	R7	7/2/01	8/31/01	PB/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet				
IV.1	1014 1014	SAN FELIPE ST. WEST BELT	11357 11360	D1 D2	8/6/01 8/6/01	12/21/01 12/21/01	PB/PB PB/PB	DL DL			5 dry 5 dry			5 dry 5 dry				
	1017	JONES RD.	11398	D3	8/6/01	12/21/01	PB/PB	DL			5 dry			5 dry				
-	1017	WATONGA	15830	D4	8/6/01	12/21/01	PB/PB	DL			5 dry			5 dry				
IV.2	1017	HARRIS COUNTY MUD 170	12121-001	RG1	8/6/01	12/21/01	PB/PB	DL	3 dry		3 dry	1 dry	1 dry		3 dry		1 dry	
	1014 1017	HOUSTON-NORTHWEST WWTP MEMORIAL VILLAGES WA	10495-076 10584-001	RG2 RG3	8/6/01 8/6/01	12/21/01 12/21/01	PB/PB PB/PB	DL DL	3 dry 3 dry		3 dry 3 dry	1 dry 1 dry	1 dry 1 dry		3 dry 3 dry		1 dry 1 dry	
	1017	HOUSTON-WEST DISTRICT WWTP	10495-030	RG4	8/6/01	12/21/01	PB/PB	DL	3 dry		3 dry	1 dry	1 dry		3 dry		1 dry	
IV.3	1014	SAN FELIPE ST.	11357	RS1	8/6/01	12/21/01	PB/PB	DL	·		1 dry ^d			1 dry			-	
	1014	WEST BELT	11360	RS2	8/6/01	12/21/01	PB/PB	DL			1 dry ^d			1 dry				
	1017	JONES RD.	11398	RS3	8/6/01	12/21/01	PB/PB	DL			1 dry ^d			1 dry				
		WATONGA	15830	RS4	8/6/01	12/21/01	PB/PB	DL			1 dry ^d			1 dry				
	1017	WATUNGA	15850	K54	8/0/01	12/21/01	PB/PB	DL		l	1 ary	l		ı ary	l			

Table 5.1 Monitoring Sites and Frequencies

Sampling			Permit				SC1/	Prog				Monitoring	g frequencies	s (per monitorin	g program)			
	Segment	Site description	number/	Sample ID	Start Date	End Date			Flow	FC	EC	TSS	TOC	Wet	Residual	Ammonia	$CBOD_5$	Grain size
Component ^a		-	Station ID	_			SC2	Code						chemistryb	chlorine			
IV.4	1014	BARKER DAM	11142	SE1	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	ELDRIDGE RD.	11363	SE2	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
		DAIRY ASHFORD RD.	11362	SE3	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	WILCREST DR.	11361	SE4	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	WEST BELT	11360	SE5	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	BRIAR FOREST AVE.	15846	SE6	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	PINEY POINT RD.	11358	SE7	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	SAN FELIPE ST.	11357	SE8	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	SHEPHERD DR.	11351	SE9	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	VOSS RD.	11356	SE10	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1014	SAN JACINTO AVE.	15842	SE11	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1017	JONES RD.	11398	SE12	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1017	WATONGA	15830	SE13	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1017	ELLA BLVD.	11391	SE14	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1017	W. T C JESTER AVE.	15828	SE15	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1017	W. 43RD ST.	15829	SE16	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1017	HEIGHTS BLVD.	11387	SE17	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	1017	W.TIDWELL AVE.	15831	SE18	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	tbd	tbd		SE19	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry
	tbd	tbd		SE20	9/3/01	12/21/01	UH/UH	DL			1 dry							1 dry

a Monitoring components: I-Point Sources (1. First round, 2. Second round), II-Illegal Discharges, III-Runoff, IV-Dynamics (1. In-stream Dynamics, 2. Growth, 3. Resuspension, 4. Sediment baseline concentration)

 $^{^{\}rm b}$ Wet chemistry analyses include DO, pH, turbidity, conductivity, and PO $_{\rm 4}$ -P

c Two samples taken during the same day (one in the morning and the other at midday) for the first sampling round. If levels are high, then it may be monitored a second time

^d Sediment sample

Source codes need to be obtained prior to submission of data.

Table 5.2 Data Quality Objectives for Measurement Data

PARAMETER	UNITS	METHOD TYPE	METHOD	METHOD DESCRIPTION	STORET	MAL	PRECISION of laboratory duplicates (RPD)	ACCURACY of matrix spikes % Recovery	ACCURACY CRM	PERCENT COMPLETE
Field Parameters	•	•	•			·		•	•	
pH	pH units		EPA 150. land TNRCC SOP		00400	1.0	10	NA	NA	90
DO	mg/L		EPA 360. land TNRCC SOP		00300	1.0	10	NA	NA	90
Conductivity	mS/cm		EPA 120. land TNRCC SOP		00094	1	10	NA	NA	90
Temperature	° Celcius		EPA 170. land TNRCC SOP		00010	NA	10	NA	NA	90
Flow	cfs		TNRCC SOP		00061	NA	10	NA	NA	90
Flow Severity	1-no flow, 2-low, 3-normal, 4-flood, 5-high, 6-dry	TNRCC SOP	TNRCC SOP ²		01351	NA	NA	NA	NA	90
Conventional para	ameters									
TSS	mg/L	gravimetric	EPA 160.2		00530	4.0	20	NA	NA	90
TOC	mg/L	oxidation	EPA 415.2		00680	0.1	20	80-120	NA	90
Residual chlorine	mg/L	DPD colorimetric	Std. Methods 400-Cl G/ HACH Method 8021		50060	0.01	20	80-120		90
Ammonia-N	mg/L	Colorimetric, salicylate	HACH Methods 10023(low range) and 10031 (high range			0.02	20	80-120		90
o-Phosphorous	mg/L	colorimetric, absorbic acid	EPA 365.3/ HACH Method 8048		00671	0.01	20	80-120		90
Turbidity	NTU	nephelometric	EPA 180.1		82079		20	NA		90

PARAMETER	UNITS	METHOD TYPE	METHOD	METHOD DESCRIPTION	STORET	MAL	PRECISION of laboratory duplicates (RPD)	ACCURACY of matrix spikes % Recovery	ACCURACY CRM	PERCENT COMPLETE
Carbonaceous Biochemical Oxygen Demand	mg/L	potentiometric	Std. Methods 5210-B		80082		25	NA		90
FC in water	cfu/100 mL	membrane filter, mFC	Std. Methods 9222-D	membrane filter, mFC	31616	1	3.27* R _{log} /n	NA		90
EC in water	MPN/100 mL	Alternate Direct	IDEXX Colilert	IDEXX MPN Quantitray 2000	31699	1	3.27* R _{log} /n	NA		90
EC in sediment ³	cfu/100 g	Resuspension in water with subsequent mTEC		membrane filter, mTEC	31702	1	3.27* R _{log} /n	NA		90
Sediment grain size analysis	% dry weight 0.0039- 0.0625 mm	TNRCC SOP	Fract.separation /gravimetric determination		82008	NA	NA	NA		90
Sediment grain size analysis	% dry weight < 0.0039 mm	TNRCC SOP	Fract.separation /gravimetric determination		82009	NA	NA	NA		90
Sediment grain size analysis	% dry weight 0.0625-2 mm	TNRCC SOP	Fract.separation /gravimetric determination		89991	NA	NA	NA		90

Due to the dependence of rainfall occurrence at certain times, runoff samples will have a lesser percent of completeness

TNRCC. 1999. Surface Water Quality Monitoring Procedures, pp. 2.16-2.17

Bacteria will be transferred from the sediment sample to an aqueous phase and subsequently analyzed using membrane filtration.

weather until all the plants had been sampled and those plants that showed high bacteria values had been resampled (the highest 20).

5.2 ILLICIT DISCHARGES

This component will include sampling of stormsewers discharging into the bayous under dry-weather conditions to identify illicit discharges to the bayous via stormsewers that may come from a sanitary sewer problem of some type or outright unpermitted wastewater discharges. This work will include review of monitoring in the bayous to identify locations where a sudden increase in indicator bacteria occurs, and checking on stormsewers to find flow. In dry weather the stormsewers should be dry so flow could be an illicit discharge.

In general terms, this effort will be undertaken by two-person teams that will work in dry weather only. They will be equipped with maps of the stormsewer system and the locations of the outfalls. Prior to sampling the teams will walk along the bayous and main tributaries to perform reconnaissance of the stormsewer infrastructure. During this reconnaissance effort, the teams will identify how many outfalls are discharging into the bayous and confirm their presence in the GIMS database so that their properties can be determined (diameter, length, material, and age). If an outfall is not found in the GIMS maps, it will be noted with its diameter and material. Geographic locations will be verified using Global Positioning System (GPS) to the extent possible and practical. GPS activities will be conducted using a Motorola LGT 1000 equipped with Starlink MRB-2A radio beacon receiver to correct for selective availability. This equipment has a real time correction providing accuracy of 5 meters.

Once all the outfalls have been located and identified, the sampling activities will start. The sampling points will be based on locatable outfalls discharging under dryweather conditions. A maximum of 60 points will be sampled for this component. For sampling in the Buffalo Bayou, a canoe will be used to both expand the sampling area and insure detailed coverage. It is expected that in a seven-day period, the area from Eldridge Parkway Bridge to Shepherd Street Bridge could be covered and with a canoe to transport sampling equipment and personnel, 98% of all the outfalls could be located and sampled. Further, for sampling of the remaining segments of Buffalo Bayou as well as sampling of Whiteoak Bayous and the tributaries to both bayous, the crews will walk pilot areas determined after field reconnaissance. The criteria to select those areas include diameter of the stormsewers (sampling will focus mainly on large diameter lines since they represent large drainage areas and this should offer the most coverage for potential dry weather flow) and age of the lines.

The sampling crew will first determine if there is flow, and then determine if there is a residual chlorine level indicating a drinking water leak of some type. If it is chlorinated water, no further work will be done other than the flow estimate. If the flow is significant it should be reported as a water leak. If the water is not chlorinated, two different criteria will be applied to determine whether samples will be collected for bacterial and TSS analyses. First, the presence of ammonia using a field test kit will be assumed as an indicator of fecal contamination and, therefore, samples will be collected. Second, the observation of Sphaerotilus will be considered a trigger for sample collection. Sphaerotilus is a non-fungus aerobic bacteria that prefers habitats with slowly running fresh water contaminated with sewage and grows attached to submerged plants,


rods, and other solid objects. Sphaerotilus will appear submerged in the flow and attached to a hard surface. The color of the growth is a gray to white hue (see Standard Methods for additional information). The sampling crew will also measure the approximate dimensions of the flow and estimate the velocity. The samples will be iced and the team will move to the next stormsewer outfall. By 1400 the team will head to the University of Houston lab arriving in time for the bacteria samples to begin filtration.

Based on available data, two preliminary pilot areas have been identified (Figure 5.2); however, these sampling areas may change as the field reconnaissance is conducted. Table 5.1 includes the sampling schedule for the illicit discharges monitoring.

5.3 RUNOFF EVENT MONITORING

Concentrations of indicator bacteria in runoff tend to be very large, several orders of magnitude greater than the criteria developed for swimming areas in fair weather. For safety as well as bacteria reasons, the main project emphasis needs to be on lower flow conditions. However, there is also a need to consider some runoff events simply because they are often small enough to have a very small effect on flow in the main stem of the bayous, and thus become part of the "background" levels. Accordingly, this monitoring program will include at least three smaller rain events in each watershed.

Runoff event monitoring will be conducted at the USGS locations on each bayou (e.g. Whiteoak Bayou at Heights and Buffalo at West Belt or Piney Point) so that flow data will be available for acquisition. USGS Station 08074200 (Whiteoak at Alabonson) appears to be defective because its record shows a consistent base flow of about 400 cfs; therefore, this station is discarded for runoff sampling. Nor will Buffalo at Mckee




(08074610) and Whiteoak at Main (08074598) be sampled as they are stage record gages and flow is not monitored. The sampling crews will deploy to the USGS gages and collect samples with pre-sterilized buckets from the bridges. Two non-USGS stations on Whiteoak Bayou and one on Buffalo Bayou will also be sampled and flow will be measured. Samples will be analyzed for conventional parameters in the field and for FC and EC by North Water District Laboratory Services. In parallel, we will obtain rainfall data from the HCFCD network as well as the City stations.

Events will be limited to those that could be sampled during daylight hours. Samples will be collected as soon as possible on the rising limb of the hydrograph, and then at roughly 3-hr intervals till dark. To track the expected decline in bacteria levels on the falling limb, samples will be collected the next morning and then at 12-hr intervals for the next two days. See Figure 5.3 for the location of the monitoring sites and Table 5.1 for the schedule.

5.4 CONCENTRATION DYNAMICS IN THE BAYOUS

Once a disinfected discharge enters the bayous it becomes subject to a very different set of environmental conditions. After chlorine has been eliminated by contact with organic matter and sediments, it may be possible for indicator bacteria to either reactivate (assuming they were stunned but not killed by the disinfectant) or regrow (assuming some cells survived and there was sufficient nutrients to support growth of the cells that also perform well on the FC or EC tests). Either mechanism, or some other mechanism not well defined, can result in higher stream levels than are typically seen in wastewater effluents.




To study these regrowth or resupply dynamics, we propose a series of field and laboratory experiments where we seek to isolate various mechanisms and document changes and rates. There will be three main elements: in-stream dynamics (normal rates of change), rates of change influenced by freshwater (regrowth), and rates of change affected by resupply from stream sediments.

The in-stream dynamics tests will comprise a series of *in-situ* chambers placed in Buffalo and Whiteoak bayous. The chambers will be attached to round floats so the edge of the chamber is above the water surface, but the water inside the chamber will be exposed to the air and true ambient conditions. The floats will be tethered or anchored so that they could be easily sampled. To avoid contamination from bird droppings, the floats will be fitted with a clear plastic "umbrella". It is recognized that if a significant flow increase occurs, the containers will be lost. Duplicate EC subsamples will be collected from each chamber the first morning and evening after installation of the chambers and the morning and evening following installation. In addition, routine probe parameters will be monitored from the collected samples. Each set of chambers will have a control, either in the ambient water (water collected from the stream approximately tracking the water initially sampled as it moved downstream under the influence of sediment and intervening sources) or a chamber without additions. A DI water blank will be prepared for each batch of bags. Chamber conditions will be varied to further examine the exact dynamics occurring at the bayous. Some of the variations in chamber conditions are as follows: post-rain versus dry conditions, effluent mixes versus natural site water to assess regrowth, and effluent or site water mixed with channel sediments to obtain an indication of the effect of solids content on rates. Tracking the bagged and water samples will

provide an indication of the growth and dieoff rates as influenced by day-night light intensity, sediment levels, organic strength and isolation from the sediment. Figure 5.4 shows a map with the proposed locations for this component. We expect this testing process to evolve with model calibration and development, with model needs guiding the testing decisions.


For the regrowth studies, bayou water samples will be collected under dry weather conditions from upstream, effluent and from the mixing zone downstream from four large domestic wastewater treatment plants (preliminary locations are mapped on Figure 5.4). The samples will be collected in new plastic garbage sacks (presumed to be free of significant bacterial contamination). All samples will be checked in the field for residual chlorine. Dechlorination will be performed if necessary. An aliquot of each water sample will be analyzed for N and P forms, TOC, CBOD₅, and TSS by North Water District Laboratory Services. Duplicate subsamples will be collected at the start and tested for bacterial levels. The collected effluent and upstream water will be mixed together to simulate the downstream mixing zone. This would yield two sets of bottles, with one set from the downstream mixing zone and one simulating the same conditions. The samples will be taken back to the laboratory where conditions such as sunlight and temperature could be controlled and gentle mixing will be provided with a small flow of air. Subsamples will then be withdrawn after a one to two day period and analyzed for EC levels with IDEXX. If significant increases in bacteria concentrations are noted, regrowth of shocked cells may be occurring. If the mixing zone concentrations increases, and no bacteria are detected in the effluent, this might suggest that nutrients in the effluent were stimulating growth in bacteria from upstream.



Resupply of bacteria from sediments will be assessed by collecting sediment grab samples at locations removed from point sources (Figure 5.4) and mixing a predetermined amount (1 mL, 10 mL, and 100 mL) of sediment unconsolidated surface mud with 1L of previously collected and autoclaved stream water. Three aliquots will be made from each water-sediment mixture. A control using DI water will be used as well. The water-sediment mixtures will be shaken and then an initial portion of each sample will be poured off for EC analysis. The bottles will be maintained near bayou water temperatures in low light conditions and resampled after the first and second days for EC and routine probe parameters. It is expected that differences in the initial level of bacteria concentrations will be proportional to the initial sediment addition. Further increases in bacteria concentrations following incubation would be evidence of bacteria resupply. The results of the experiment should not be affected by low dissolved oxygen occurring after 1-2 days. Additional tests will be conducted by allowing the top of the bottles to be open to ensure DO similar to bayou levels, and EC analysis will be conducted again.

Standard statistical tests for means and variance using Excel spreadsheets will be used to analyze the data to identify significant trends in data obtained from the dynamics tests.

Finally, to determine baseline sediment concentrations, EC levels will be measured in up to 20 sediment samples. Analyses of sediment samples will be conducted only if the results from the dynamics test show that resuspension is a significant source of EC into the Buffalo and Whiteoak Bayous. Preliminary locations for sediment sampling are shown in Figure 5.5. This locations, however, may change depending on model



segmentation and needs. In addition to EC analysis, sediment samples will be analyzed to obtain particle size data.

CHAPTER 6

STAKEHOLDER/PUBLIC EDUCATION AND INVOLVEMENT

6.1 SUMMARY OF SUPPORT ACTIVITIES

In accordance with this task, the project team completed the following activities:

- Development of informational materials summarizing the technical aspects of the project for electronic or paper distribution at stakeholder meetings. These materials included a summary of the quarterly reports 1 and 2, maps, and a document with a draft monitoring plan as well as the proposed modeling activities.
- Participation in three stakeholder meetings (May 3,2000; January 25, 2001; and March 8, 2001).
- Preparation and presentation of technical information at stakeholder meetings.
 Responding to questions and information requests from stakeholders and providing rationale for whether or not certain requests by stakeholders for refinement in technical analysis can or cannot be achieved.
- Providing technical expertise on issues of microbiological public health, urban wastewater infrastructure and water quality.

6.2 TECHNICAL PRESENTATIONS AT STAKEHOLDER MEETINGS

Copies of the technical presentations given at the stakeholder meetings are included in Appendix E.

6.3 RESPONSE TO STAKEHOLDERS' COMMENTS/QUESTIONS

The project team modified reports and plans, when appropriate, according to stakeholder input. Below is a list of comments received from stakeholders during the meetings or via email and their respective responses.

Theo Glanton's comments on Work Plan

Comment Corrective Action		Response
Under the point source		Flow rate will be measured
monitoring section, the plan		every time a sample is
is to collect both low and		collected. Point source
high flow values from		sampling description reads:
WWTP of less than 1 MGD.		"The sampling will include
It is suggested that that some		doing a field measurement of
of the plant effluent flow		residual chlorine, corrected for
rates should also be recorded		manganese interference,
when the samples are		estimating the flow, estimating
collected. The data could		conventional chemical parameters (see Table 1) and collecting water
then be compared to reported		samples for laboratory
average flow values to verify		analyses"
that high and low flow		
conditions are being		
sampled.		
In the Illicit discharge	Field ammonia analysis is	The Illicit discharges
monitoring section it states	a good tool, but it is only	monitoring section was updated
that residual chlorine and	part of the toolbox used by	as follows:
ammonia testing will be the	the City of Houston and it	"If the water is not chlorinated,
determining factors for Fecal	requires field experience	two different criteria will be
Coliform (FC) analysis.	and good judgement to	applied to determine whether
Field experience has	obtain consistent results. I	samples will be collected for
demonstrated that ammonia	would like to suggest that	bacterial, TOC and TSS analyses. First, the presence of ammonia
analysis is an excellent	two criteria be added. One,	using a field test kit will be
tracking tool and an indicator	that some percentage of	assumed as an indicator of fecal
of fecal contamination.	any dry weather line flow	contamination and, therefore,
However, ammonia analysis	be considered for FC	samples will be collected. Second,
with a field test kit is reliable	bacteria sampling. Two,	the observation of Sphaerotilus
down to about .5 mg/l. Thus	the observation of any	will be considered a trigger for
the detection limit is	sewage fungus	sample collection. Sphaerotilus is
somewhere around an eight	(Sphaerotilus) should be	a non-fungus aerobic bacteria that
to ten percent sewage	considered a trigger for	prefers habitats with slowly
contamination level. By	sample collection.	running fresh water contaminated with sewage and grows attached to
contrast, FC bacteria can	Sphaerotilus will appear	submerged plants, rods, and other
indicate sewage	submerged in the flow and	solid objects. Sphaerotilus will
contamination down to a less	attached to a hard surface.	appear submerged in the flow and
than one percent	The color of the growth is	attached to a hard surface. The

Comment	Corrective Action	Response
contamination level.	a gray to white hue (see	color of the growth is a gray to
Experience has demonstrated	Standard Methods for	white hue (see Standard Methods
that FC may be present at the	additional information).	for additional information). "
100,000 C/dl concentration		
level and the field ammonia		
test value, in some cases,		
will not clearly indicate a		
contamination problem.		
The illicit discharge	It is suggested that the use	Point well taken. Text was
monitoring section identifies	of a canoe in the Buffalo	modified to reflect this
an outline of the pilot areas	Bayou watershed could	comment and different pilot
and both of the locations are	both expand the sampling	areas were suggested.
in sections where the sewer	area and insure detailed	" For sampling in the Buffalo
systems are comparatively	coverage. It is suggested	Bayou, a canoe will be used to both expand the sampling area and
new relative to age of the	that both equipment and	insure detailed coverage.
City of Houston. Further, the	guide services could be	[] Further, for sampling of the
plan indicates that the	obtained from either the	remaining segments of Buffalo
sampling points will be based on locatable outfalls.	Houston Canoe Club or	Bayou as well as sampling of
based on locatable outrails.	White Water Experience for a nominal fee. In a	Whiteoak Bayous and the
	seven-day period, the area	tributaries to both bayous, the
	from the upstream point of	crews will walk pilot areas determined after field recognition.
	the proposed location to	The criteria to select those areas
	Shepherd Street Bridge	include diameter of the
	could be covered and with	stormsewers (sampling will focus
	a canoe to transport	mainly on large diameter lines
	sampling equipment and	since they represent large
	personnel 98% of all the	drainage areas and this should
	outfalls could be located	offer the most coverage for potential dry weather flow) and
	and sampled. Further,	age of the lines. Appendix B
	some sampling be done	contains a map of the preliminary
	outside of the pilot areas,	pilot areas."
	specifically it is	
	recommended that outfalls	
	inside the loop in the down	
	town area be included. To	
	target these areas it is	
	recommended that only	
	the large diameter storm	
	sewers be examined. The	
	large diameter lines	
	represent large drainage	
	areas and this should offer	
	the most coverage for	
	potential dry weather flow	
	for the least amount of	
T [1 ']	effort.	
In [dynamics] section	It is recommended that the	In-stream dynamics test
regarding the in-situ testing,	bags be qualified as being	description now reads:
the use of plastic bags are	a clear plastic type.	"The samples will be collected

Comment	Corrective Action	Response	
identified.		in new plastic garbage sacks (presumed to be free of significant	
		bacterial contamination)"	

Theo Glanton's comments on Data Analysis and Modeling Plan

Comment Corrective Action		Response
Comment The flow and concentration data presented at the January TMDL Stakeholders meeting limited the flow relationship to greater than or less than 100 cubic feet per second. Based on a review of the charts, the analysis break point appears to be established on the 50% of the flow range value. Further, data analysis was limited to only two bridge locations; Shepard and West Belt.	The flow analysis should be expanded to look at the extreme low flow and high flow FC concentrations. It is suggested that one and two standard deviations boundary values be considered or the upper and lower 10% of the flow range values as an alternative. This approach could allow for the division of the data into six quartiles where each may have separate trends. The purpose is to get a definitive view of the bayou and FC relationship during the dry weather periods, wet weather periods and mixed dry and wet weather periods.	Low vs high flow data were compared assuming the boundary at 10%, 20%, 30%, 40%, 75% and 90% (Chapter 2)
	The data and data subsets should be analyzed for randomness. If a data set is not found to be random then some trend can and should be extrapolated. It is understood that the regression analysis correlation coefficient will most likely be rather poor, but as an interpretation of a generalized direction of the trend, it could be a useful tool. The data should be viewed with a focus towards three main areas; outside the City of Houston's jurisdiction (i.e. above	Trend analyses were performed on the quartiles defined above (Chapter 2). Agree. Model activities will definitely consider the differences among these three areas regarding source contributions, flow, and control

Comment	Corrective Action	Response
	Barker Dam), above tidal	actions and management
	(i.e. the Shepard Street	measures.
	bridge and above) and	
	below tidal. The	
	justification for these	
	boundaries is that in each	
	separate area represent a	
	section where a distinct	
	and separate solution will	
	most likely be required for	
	both the study and	
	resolution of the issues.	
	It is suggested that the data	Chapter 2 presents a
	trending analysis for	comparison of winter vs.
	seasonal periods be	summer data.
	included (i.e. winter and	balliller dam.
	summer). Past work has	
	looked at DO	
	concentrations in both	
	winter and summer	
	conditions and it showed	
	seasonal variation. The	
	data was normalized to	
	eliminate the temperature	
	effect by calculating DO	
	as a percent saturation. It	
	was found that	
	temperature was not the	
	controlling factor in the	
	season DO variations. It	
	was postulated that the	
	macrophyte population	
	was the controlling factor	
	for the seasonal changes in	
	DO concentration. It is	
	unknown whether FC	
	bacteria are an	
	opportunistic species;	
	however, limited testing	
	and field experiences	
	indicate that FC bacteria	
	propagate given the	
	appropriate conditions. If	
	the FC bacteria find the	
	lysis of macrophytes a	
	suitable environment then	
	some seasonal variations	
	in concentration should be	
	detectable.	

Kim Phillip's comments on QAPP

be the oject
l of this
be the
the
3
ours
is
ata
his
ent
the
ities
e
etc)
in
t be
any
,
from
ieous
lyzed

Comment	Corrective Action	Response
method? Suspending any		
sample in nutrient broth		
would invalidate the sample.		
I think the sediment testing		We were told by TNRCC that
is a very good idea and will		IDEXX was not recommended
yield some very interesting		for sediments (comments to
and hopefully helpful		QAPP revision 2). We checked
information. But, sediment		with North Water District
should not be analyzed using		Laboratory Services and they
membrane filtration. The		have successfully analyzed soil
MPN (most probable		samples using filtration (with
number) method is what is		high dilutions). We also found
recommended for sediment		some papers later reporting
testing. The MPN can be		sediment data (FC mainly)
obtained by using the		using membrane filtration.
traditional Multiple Tube		
Fermentation (MTF) method		
or IDEXX Colilert Quanti-		
tray.		
The name of the project		Fecal Pathogens is the name
infers that actual fecal		that appears in the contract with
pathogens other than		TNRCC.
coliforms will be monitored.		
This is misleading. The term		
"indicator bacteria" would be		
more appropriate.		
[In section A7] RPDs are not		The following statements were
applicable to microbiology.		added to the "Precision"
The correct method for		description:
calculating precision for		"For microbiological analyses, the
microbiological analysis can		method to be used for calculating
be found in Standard		precision is the one outlined in
Methods 20th Edition		Standard Methods 20th Edition
section 9020 B.8.b.		section 9020 B.8.b.
		$RPD_{bacteria} = (log X_1 - log X_2)$
		The RPD _{bacteria} should be lower
		than 3.27 R_{log}/n , where R_{log} is the
		difference in the natural log of
		duplicates for the first 15 positive
		samples."

Comments from stakeholder meeting on March 8

Comment	Corrective Action	Response
Sample point sources during		Out of the scope of this project.
wet weather conditions.		

Comment	Corrective Action	Response
Include bypasses in		•
monitoring plan		
Include bypasses in the		Model is dynamic so will
model.		include both high and low flow
		conditions.
Sample wet weather		Out of the scope of this project.
facilities		
11 out of 128 small WWTP		8 out of the 11 industrial
are industrial so it may not		WWTP do not treat domestic
be useful to sample them.		sewage, thus, they were
		removed from the list of plants
	T 1 1 1'	to be sampled (Table 6).
One sampling station in	Include more sampling	Two stations (11398 and
Whiteoak Bayou is not enough to calibrate the	stations (non-USGS) and estimate flow.	15831) were added to the runoff
enough to calibrate the model.	estimate now.	sampling sites. Flow will be
		estimated using a rating curve.
It was pointed out that the IDEXX method was going		EC will be analyzed using IDEXX Colilert.
to be used by the TNRCC		IDEAA Comert.
Statewide for the monitoring		
of E.coli and enterococcus.		
So, that should be the		
method to be used in this		
project.		
Run blanks for the in-stream		OK. See description of in-
dynamics tests and measure		stream dynamics studies
DO and temperature.		
In the chamber experiment,		Yes, samples will be taken from
will samples be taken from		ambient waters.
ambient waters. If yes, an		Conventional field parameters
"equipment control" for the		(including DO) will be
garbage bags should be used.		measured in the ambient water
It was suggested testing		as a control (see Section 5.4).
dissolved oxygen and		
temperature in ambient		
waters and in garbage bags.		TO 1 11 11 1
Are the samples for regrowth		The samples will remain
testing going to be capped -		uncapped.
if so, BOD may be a		
problem.		

CHAPTER 7

CONCLUSIONS

The following activities were conducted to complete the tasks listed in the Work Plan for Work Order No. 582-0-80121-01 for the Bacteria Project: literature review on the sources, and fate of bacteria and indicators of fecal contamination; assessment of levels and trends of fecal coliform in the Buffalo and Whiteoak Bayous; assessment of potential sources of bacteria to the project area; selection of numerical model to be used to aid in load allocations, development of a monitoring plan with its respective Quality Assurance Program Plan (QAPP); and participation in stakeholder/public outreach activities.

There have been four agencies collecting indicator bacteria data in the two bayous over the years. Almost all of these data have been collected from bridges with similar methods. The major differences appear to be in the decision of when to sample. The agency with the fewest samples is the USGS. A relatively high proportion of the samples reported by the USGS were obtained at higher flows, probably reflecting an involvement with stormwater event sampling.

The TNRCC ranks next in terms of number of samples, averaging about 10 individual samples per year in each bayou (typically quarterly sampling at 3 stations). Over the period 1992 to 1999 the distribution of sampling days is similar to the distribution of flows. However, in the period 1995 to 1999 a higher proportion of samples was collected during low flow periods. This would be consistent with TNRCC

monitoring guidance that suggests avoiding sampling for bacteria during and immediately after rains.

The H&HS arm of the City of Houston contributed a substantially higher number of samples. Their effort from 1995 to 1999 averaged 23 samples per month in Buffalo and 10 samples per month in Whiteoak bayou watersheds. Most of the samples were collected on the main stems of the bayous but about 47% were obtained from tributaries. These monitoring data appear to follow a regular schedule, with the distribution of flows on sampling days roughly equivalent to the distribution of flows overall.

The most populated data set in the historical record was that contributed by PW&E of the City of Houston. This unit operates the City's water and wastewater system. The Wastewater Operations portion of PW&E began bayou monitoring in 1983, primarily to help identify problems with treatment plants and the collection system. With that emphasis, the monitoring was specifically directed to lower flows because it is very difficult to detect point source effects at high flows when urban runoff dominates. The rate of sampling varied over the years, averaging 22 samples per month in the two systems.

In comparing the data it was found that all four data sources were comparable provided that only data obtained when the flow at major gages was less than a screening value that approximated the median flow. With that restriction, all the data were combined at each station to test for temporal and spatial trends.

The temporal trend analysis had to be limited to the period 1992 on because before that time the effect of residual chlorine in the bayous appeared to cause anomalous low values. With data from 1992 on, most stations had no significant trend. However,

several stations appear to show a downward trend in FC concentrations that is significantly different from zero with a confidence level of 95%. Even where a trend does not rise to the level of statistical significance, the slopes are almost always negative, further supporting the idea that there has been a reduction in the FC concentrations over time.

With spatial information there appear to be two broad ideas of interest. The first is that on both Buffalo and Whiteoak bayous the average concentrations appear to increase from upstream to downstream. The increase is on the order of a factor of two in both systems. While this is not huge on the log scale of FC data, it may be significant in interpreting causes. For example, going from upstream to downstream, the density and age of development increase in both bayou watersheds.

Another general observation is that long-term geometric means of Whiteoak Bayou appear to be higher than those of Buffalo Bayou, also by about a factor of two. These two observations may be useful in the investigative work needed to understand the causes of the dry weather FC concentrations.

Data at higher flows (collected on days where the reference gage flow was higher than the median value) are moderately higher than low flow data. Examining data where the flow was above the 90th percentile, the trend was for those data to be markedly higher in FC concentrations for Whiteoak Bayou but not for Buffalo Bayou.

Nine potential sources of the high indicator bacteria levels observed in the bayou were identified. These potential sources include effluent from point sources not disinfected completely, regrowth/reactivation of bacteria after point source discharge, untreated sewage, illicit dischargers, untreated sewage from failed on-site wastewater

systems located in un-sewered areas, bacteria from upstream sources, avian sources, runoff, and stream sediments.

Data gatherings and analysis of the nine identified potential sources indicated that point sources, illegal discharges, sediments, runoff, and upstream sources are relatively significant contributors to bacteria in the bayous. There were no data on contributions from avian sources and regrowth or reactivation of bacteria in disinfected water, so they could not be evaluated. A comparison of total annual loads from point sources, illegal discharges and runoff indicates that non-point sources are one order of magnitude greater than those from point sources and up to three orders of magnitude greater than loads from overflow and bypasses. It should be noted, however, that runoff is a shorter term dynamic phenomenon that affects FC conditions in the bayous on an intermittent basis.

Additional monitoring of the bayous would include four components as follows:

- Monitoring of point sources,
- Searches for illicit discharges in both sewered and unsewered areas,
- Moderate runoff event sampling. and
- Analyses of concentration dynamics in the bayous.

A review of suitable models to quantify the fate and transport of the indicator bacteria suggested that HSPF is the best model choice for the purposes of this TMDL study.

REFERENCES

- American Water Works Association. (1990). "Water Quality and Treatment. A Handbook of Community Water Supplies.", T. E. Frederick W. Pontius, ed., McGraw-Hill, Inc., New York, NY, 1194 p.
- Arias, C. R., Aznar, R., Pujalte, M. J., and Garay, E. (1998). "A Comparison of Strategies for the Detection and Recovery of *Vibro vulnificus* from Marine Samples of the Western Mediterranean Coast." *Systematic and Applied Microbiology*, 21, 128-134
- Ashbolt, N. J., Grohmann, G. S., and Kueh, C. (1993). "Significance of Specific Bacterial Pathogens in the Assessment of Polluted Receiving Waters of Sydney." *Water Science and Technology*, 27, 449-452.
- Auer, M. T., and Niehaus, S. L. (1993). "Modeling Fecal Coliform Bacteria I. Field and Laboratory Determination of Loss Kinetics." *Water Resources Research*, 27(4), 693-701.
- Baudart, J., Grabulos, J., Barusseau, J.-P., and Lebaron, P. (2000). "Salmonella spp. and Fecal Coliform Loads in Coastal Waters from Point vs. Nonpoint Source of Pollution." *Journal of Environmental Quality*, 29(1), 241-250.
- Brion, G. M., and Lingireddy, S. (1999). "Neural Network Approach to Identifying Non-point Sources of Microbial Contamination." *Water Research*, 33(14), 3099-3106.
- Brion, G. M., and Mao, H. H. (2000). "Use of Total Coliform Test for Watershed Monitoring with Respect to Atypicals." *Journal of Environmental Engineering*, 126(2), 175-181.
- Buckley, R., Warnken, W., Wild, C., and Clough, E. (1998). "Coliform bacteria in streambed sediments in a subtropical rainforest conservation reserve." *Water Resources*, 32(6), 1852-1856.
- Burkhardt, W., III, Calci, K. R., Watkins, W. D., Rippey, S. R., and Chirtel, S. J. (2000). "Inactivation of Indicator Microorganisms in Estuarine Waters." *Water Research*, 34(8), 2207-2214.
- Burton, G. A., Jr., Gunnison, D., and Lanza, G. R. (1987). "Survival of Pathogenic Bacteria in Various Freshwater Sediments." *Applied and Environmental Microbiology*, 53(4), 633-638.
- Butterfield, J., Coulson, J. C., Kearsey, S. V., and Monaghan, P. (1983). "The herring gull *Larrus argentatus* as carrier of *Salmonella*." *Journal of Hyg. Camb.*, 91, 429-436.
- City of Houston Public Works and Engineering Department. (1999). "Greens Bayou Intensive Survey and Wasteload Evaluation Final Report.", Prepared for the Texas Clean Rivers Program, Houston-Galveston Area Council, Houston, TX.
- Conboy, M. J., and Goss, M. J. (1999). "Contamination of Rural Drinking Water Wells by Fecal Origin Bacteria -- Survey Findings." *Water Quality Research Journal of Canada*, 34(2), 281-303.
- Crabill, C., Donald, R., Snelling, J., Foust, R., and Southam, G. (1999). "Impact of Sediment Fecal Coliform Reservoirs on Seasonal Water Quality in Oak Creek, Arizona." *Water Research*, 33(9), 2163-2171.

- Crane, S. R., and Moore, J. (1986). "Modeling Enteric Bacterial Die-off: A Review." *Water Air and Soil Pollution*, 27, 411-439.
- Dan, T. B.-B., Wynne, D., and Manor, Y. (1997). "Survival of Enteric Bacteria and Viruses in Lake Kinneret, Israel." *Water Research*, 31(11), 2755-2760.
- Davies, C. M., Long, J. A. H., Donald, M., and Ashbolt, N. J. (1995). "Survival of Fecal Microorganisms in Marine and Freshwater Sediments." *Applied and Environmental Microbiology*, 61(5), 1888-1896.
- Elhmmali, M. M., Roberts, D. J., and Evershed, R. P. (1997). "Bile Acids a New Class of Sewage Pollution Indicator." *Environmental Science and Technology*, 31, 332-339.
- Elhmmali, M. M., Roberts, D. J., and Evershed, R. P. (2000). "Combined Analysis of Bile Acids and Sterols/Stanols from Riverine Particulates to Assess Sewage Discharges and Other Fecal Sources." *Environmental Science and Technology*, 34(1), 39-46.
- Elmund, K. G., Allen, M. J., and Rice, E. W. (1999). "Comparison of *Escherichia coli*, Total Coliform, and Fecal Coliform Populations as Indicators of Wastewater Treatment Efficiency." *Water Environment Research*, 71(3), 332-339.
- El-Sharkawi, F., El-Attar, L., Abdel-Gawad, A., and Molazem, S. (1989). "Some Environmental Factor Affecting Survival of Fecal Pathogens and Indicator Organisms in Seawater." *Water Science and Technology*, 21(1), 115-120.
- Erkenbrecher, C. W. (1981). "Sediment Bacterial Indicators in an Urban Shellfishing Subestuary of the Lower Chesapeake Bay." *Applied and Environmental Microbiology*, 44, 1144-1149.
- Esham, E. C., and Sizemore, R. K. (1998). "Evaluation of Two Techniques: mFC and mTEC for Determining Distributions of Fecal Pollution in Small, North Carolina Tidal Creeks." *Water, Air and Soil Pollution*, 106(1-2), 179-197.
- Espey Huston and Associates Inc. (1994a). "Analysis of Sanitary Sewer Overflow Effects on Surface Water Quality, Volume II, Monitoring Overflow Effects on Urban Runoff.", *EH&A Document No. 93-0803*, Prepared for the City of Houston, Houston, TX.
- Espey Huston and Associates Inc. (1994b). "Analysis of Sanitary Sewer Overflow Effects on Surface Water Quality, Volume III, Overflow Modeling and Effects Quantification.", *EH&A Document No. 93-0803*, Prepared for the City of Houston, Houston, TX.
- Fricker, E. J., and Fricker, C. R. (1994). "Application of the Polymerase Chain Reaction to the Identification of *Escherichia coli* Coliforms in Water." *Letters in Applied Microbiology*, 19, 44-46.
- Furness, R. W., and Monaghan, P. (1987). "Seabirds as Pests." In *Seabird Ecology*, Chapman and Hall Ltd., London, 127-138.
- Furuse, K. (1987). "Distribution of coliphages in the Environment: General Considerations." In *Phage Ecology*, S. M. Goyal, C. P. Gerba, and G. Bitton, eds., John Wiley & Sons, New York, NY.
- Gerba, C. P., and McLeod, J. S. (1976). "Effects of Sediments on the Survival of *Escherichia coli* in Marine Waters." *Applied and Environmental Microbiology*, 32, 114-120.

- Gilgen, M., Wegmuller, B., Burkhalter, P., Buhler, H. P., Muller, U., Luthy, J., and Candrian, U. (1995). "Reverse transcription PCR to detect enteroviruses in surface water." *Applied and Environmental Microbiology*, 61(4), 1226-1231.
- Gilliland, M. W., and Baxter-Potter, W. (1987). "A Geographic Information System to Predict Non-Point Source Pollution Potential." *Water Resources Bulletin*, 23(2), 281-291.
- Girdwood, R. W. A., Fricker, C. R., Munro, D., Shedden, C. B., and Monaghan, P. (1985). "The Incidence and Significance of *Salmonella Carriage by Gulls (Larus spp.)* in Scottland." *Journal of Hyg. Camb.*, 05, 229-241.
- Glanton, T. (1999). "Personal Communication on FC Levels in Illicit Discharges.".
- Goyal, S. M., and Adams, W. N. (1984). "Drug-Resistant Bacteria in Continental Shelf Sediments." *Applied and Environmental Microbiology*, 48, 861-862.
- Grimes, D. J. (1975). "Release of Sediment Bound Faecal Coliforms by Dredging." *Applied Microbiology*, 29, 109-111.
- Grimes, D. J. (1980). "Bacteriological Water Quality Effects of Hydraulically Deredging Contaminated Upper Mississippi River Bottom Sediment." *Applied and Environmental Microbiology*, 39, 782-789.
- Hadas, O., Shteionman, B., and Pinkas, R. (2000). "Distribution of Fecal Coliforms in the Jordan River Mouth Originating from Anthropogenic Activities in the Watershed." *Water Science and Technology*, 42(1), 129-133.
- Hancock, G. G., and Davis, E. M. (1999). "Regrowth Potential of Coliforms after UV Disinfection of Municipal Wastewater." *Journal of Environmental Science and Health*, 34(9), 1737-1743.
- Hendricks, C. W. (1971). "Increased Recovery Rate of Salmonellae from Stream Bottom Sediments versus Surface Waters." *Applied Microbiology*, 21, 379-380.
- H-GAC. (1999). "On-Site Sewage Target Communities.", Houston, TX.
- Hood, M. A., and Ness, G. E. (1982). "Survival of *Vibro cholerae* and *Escherichia coli* in Estuarine Waters and Sediments." *Applied and Environmental Microbiology*, 43, 578-584.
- Houston-Galveston Area Council. (2001). "2001 Draft Basin Summary Report." . http://www.hgac.cog.tx.us/resources/crp/watersheds.html.
- Howell, J. M., Coyne, M. S., and Cornelius, P. L. (1996). "Effect of Sediment Particle Size and Temperature on Fecal Bacteria Mortality Rates and the Fecal Coliform/Fecal Streptococci Ratio." *Journal of Environmental Quality*, 25(6), 1216-1220.
- Huysman, F., Van Renterghem, B., and Verstraete, W. (1993). "Antibiotic Resistant Sulphide-reducing Clostridia in Soil and Groundwater as Indicator of Manuring Practices." *Water Air and Soil Pollution*, 69, 243-255.
- Iqbal, S., Robinson, J., Deere, D., Saunders, J. R., Edwards, C., and Porter, J. (1997). "Efficiency of Polymerase Chain Reaction Amplification of the uid Gene for Detection of *Escherichia coli* in Contaminated Water." *Letters in Applied Microbiology*, 24, 498-502.
- Irvine, K. N., and Pettibone, G. W. (1996). "Planning Level Evaluation of Densities and Sources of Indicator Bacteria in Mixed Land Use Watershed." *Environmental Technology*, 17(1), 1-12.

- Jensen, P. "Regrowth of Coliform Bacteria as Influenced by Wastewater Treatment." In *Proceedings of Texas Section ASCE Conference*, September 25-27, , ASCE, El paso, TX, .
- Jensen, P., and Su, Y.-C. (1992). "Characterization of Selected Public Health Issues in Galveston Bay.", *GBNEP-21*, Prepared for the Galveston Bay National Estuary Program, Austin, TX.
- Joret, J. C., Levi, Y., and Volk, C. (1991). "Biodegradable Dissolved Organic Carbon (BDOC) Content of Drinking Water and Potential Regrowth of Bacteria." *Water Science and Technology*, 24(2), 95-101.
- Juck, D., Ingram, J., Prevost, M., Coallier, J., and Greer, C. (1996). "Nested PCR Protocol for the Rapid Detection of *Escherichia coli* in Potable Water." *Canadian Journal of Microbiology*, 42, 862-866.
- Kansas Department of Health and Environment. (1999). "Kansas TMDL Curve Methodology." . http://www.kdhe.state.ks.us/tmdl/Data.htm.
- Kapperud, G., and Rosef, O. (1983). "Avian Wildlife Reservoir of *Campylobacter fetus* subsp. *jejuni*, *Yersinia* spp., and *Salmonella* spp. in Norway." *Applied and Environmental Microbiology*, 45, 375-380.
- Kay, D., Fleisher, J. M., Godfree, A. F., Jones, F., Salmon, R. L., Shore, R., Wyer, M. D., and Zelenauch-Jacquotte, R. (1994). "Predicting Likelihhod of Gastroenteritis from Sea Bathing: Results from Randomised Exposure." *The Lancet*, 344(8927), 905-909.
- Kirkpatrick, C. E. (1986). "Isolation of *Salmonella* spp. from a Colony of Wading Birds." *Journal of Wildlife Diseases*, 22, 262-264.
- LaBelle, R. L., Gerba, C. P., Goyal, S. M., Melnick, J. L., Cech, I., and Bogdan, G. F. (1980). "Relationships between Environmental Factors, Bacterial Indicators, and the Occurrence of Enteric Viruses in Estuarine Sediments." *Applied and Environmental Microbiology*, 39, 588-596.
- Lahlou, M., Shoemaker, L., Choudhury, S., Elmer, R., Hu, A., Manguerra, H., and Parker, A. (1998). "Better Assessment Science Integrating Point and Nonpoint Sources. BASINS Version 2.0, User Manual.", *EPA-823-B-98-006*, U. S. Environmental Protection Agency, Washington, D.C.
- LaLiberte, P., and Grimes, D. J. (1982). "Survival of *Escherichia coli* in Lake Bottom Sediments." *Applied and Environmental Microbiology*, 43, 623-628.
- Levesque, B., Brosseau, P., Simard, P., Dewailly, E., Meisels, M., Ramsay, D., and Joly, J. (1993). "Impact of the Ring-Billed Gull (*Larus delawarensis*) on the Microbiological Quality of Recreational Water." *Applied and Environmental Microbiology*, 59(4), 1228-1230.
- Marino, R. P., and Gannon, J. J. (1991). "Survival of Faecal Coliforms and Faecal Streptococci in Storm Drain Sediment." *Water Resources*, 25(9), 1089-1098.
- McDaniels, A. E., Rice, E. W., Reyes, A. L., Johnson, C. H., Haugland, R. A., and G. N. Stelma, J. (1996). "Confirmational identification of Escherichia coli, a comparison of genotypic and phenotypic assays of glutamate decrobxylase and B-D-glucuronidase." *Applied and Environmental Microbiology*, 62(9), 3350-3354.
- Mechsner, K., Fleischmann, T., Mason, C. A., and Hamer, G. (1991). "UV Disinfection. Short Term Inactivation and Revival." *Water Science and Technology*, 24(2), 339-342.

- Miyabara, Y., Suzuki, J., and Suzuki, S. (1994). "Classification of Urban Rivers on the Basis of Water Pollution Indicators in River Sediment." *Bulletin of Environmental Contamination and Toxicology*, 52(1), 52/1-52/8.
- Muyima, N. Y. O., and Ngcakani, F. (1998). "Indicator Bacteria and Regrowth Potential of the Drinking Water in Alice, Eastern Cape." *Water S. A.*, 24(1), 29-34.
- Nasser, A. M., and Oman, S. D. (1999). "Quantitative Assessment of the Inactivation of Pathogenic and Indicator Viruses in Natural Water Sources." *Water Resources Research*, 33(7), 1748-1752.
- Newell, C. J., Rifai, H. S., and Bedient, P. B. (1992). "Characterization of Non-Point Sources and Loadings to Galveston Bay.", *GBNEP-15*, Prepared for the Galveston Bay National Estuary Program, Houston, TX.
- Nix, P. G., Daykin, M. M., and Vilkas, K. L. (1993). "Sediment Bags as an Integrator of Fecal Contamination in Aquatic Systems." *Water Research*, 27(10), 1569-1576.
- Nix, P. G., Daykin, M. M., and Vilkas, K. L. (1994). "Fecal Pollution Events Reconstructed and Sources Identified Using a Sediment Bag Grid." *Water Environment Research*, 66(6), 814-818.
- Nuzzi, R., and Burhans, R. (1997). "The Use of Enterococcus and Coliform in Characterizing Bathing-Beach Waters." *Journal of Environmental Health*, 60, 16-22.
- Oberst, R. D., Hays, M. P., Bohra, L. K., Phebus, R. K., Yamashiro, C. T., Paszko-Kolva, C., Flood, S. J. A., Sargeant, J. M., and Gillespie, J. R. (1998). "PCR-Based DNA amplification and presumptive detection of *Escherichia coli* 0457:H7 with an internal fluorogenic probe and the 5' nuclease (TaqMan) assay." *Applied and Environmental Microbiology*, 64(9), 3389-3396.
- Obiri-Danso, K., and Jones, K. (2000). "Intertidal Sediments as Reservoirs for Hippurate Negative *Campylobacters, Salmonellae* and Fecal Indicators in Three Recognized Bathing Waters in North West England." *Water Research*, 34(2), 519-527.
- Olson, M. E., Goh, J., Phillips, M., Guselle, N., and McAllister, T. A. (1999). "Giardia Cyst and Cryptosporidium Oocyst Survival in Water, Soil, and Cattle Feces." *Journal of Environmental Quality*, 28(6), 1991-1996.
- Parveen, S., Murphree, R. L., Edmiston, L., Kaspar, C. W., Portier, K. M., and Tamplin, M. L. (1997). "Association of Multiple Antibiotic Resistance Profiles with Point and Nonpoint Sources of *Escherichia coli* in Apalachicola Bay." *Applied and Environmental Microbiology*, 63, 2607-2612.
- Parveen, S., Murphree, R. L., and Tamplin, M. L. "Differentiating Point and Nonpoint Sources of Escherichia coli in an Estuarine Environment by Multiple Antibiotic Resistance and Ribotype Profile." In *Proceedings of Abstracts of the 96th General Meeting of the American Society for Microbiology*, American Society for Microbiology, Washington D.C., 469.
- Parveen, S., Portier, K. M., Robinson, K., Edmiston, L., and Tamplin, M. L. (1999). "Discriminant Analysis of Ribotype Profiles of *Escherichia coli* for Differentiating Human and Nonhuman Sources of Fecal Pollution." *Applied and Environmental Microbiology*, 65(7), 3142-3147.
- Pathak, S. P., and Bhattacherjee, J. W. (1994). "Effect of pollutants on Survival of *Escherichia coli* in Microcosms of River Water." *Bulletin of Environmental Contamination and Toxicology*, 53(2), 198-203.

- PBS&J. (2000). "Bacterial Indicator Study Final Report.", *Document No. 000195*, Prepared for Guadalupe-Blanco River Authority and the TNRCC, Austin, TX.
- Pettibone, G. W., Irvine, K. N., and Monahan, K. M. (1996). "Impact of a Ship Passage on Bacteria Levels and Suspended Sediment Characteristics in the Buffalo River, New York." *Water Research*, 30(10), 2517-2521.
- Pommepuy, M., Guillaud, J. F., Dupray, E., Derrien, A., Le Guyader, F., and Cormier, M. (1992). "Enteric Bacteria Survival Factors." *Water Science and Technology*, 25(12), 93-103.
- Pourcher, A. M., Devrisse, L. A., Hernandez, J. F., and Delattre, J. M. (1991). "Enumeration by a Ministurized Method of *Escherichia coli, Streptococcus bovis* and Enterococci as Indicators of the Origin of Faecal Pollution of Waters." *Journal of Applied Bacteriology*, 70, 525-530.
- Power, K. N., and Nagy, L. A. (1999). "Relationship between Bacterial Regrowth and Some Physical and Chemical Parameters within Sydney's Drinking Water Distribution System." *Water Research*, 33(3), 741-750.
- Puig, A., Jofre, J., and Araujo, R. (1997). "Bacteriophages Infecting Various *Bacteroides fragilis* Strains Differ in their Capacity to Distinguish Human from Animal Faecal Pollution." *Water Science Technology*, 35(11-12), 359-362.
- Quednau, M., Ahrene, S., and Molin, G. (1999). "Genomic relationships between *Enterooccus faecium* strains from different sources and with different antibiotic resistance profiles evaluated by restriction endonuclease analysis of total chromosomal DNA using *EcoRI* and *PvuII*." *Applied and Environmental Microbiology*, 65(4), 1777-1780.
- Sanchez-Ruiz, C., Martinez-Royano, S., and Tejero-Monzon, I. (1995). "Evaluation of the Efficiency and Impact of Raw Wastewater Disinfection with Peracetic Acid Prior to Ocean Discharge." *Water Science and Technology*, 32(7), 159-166.
- SD Department of Environment & Natural Resources Watershed Protection Program TMDL. (1999). "Ravine Lake Watershed, Beadle County, South Dakota.", SD Department of Environment & Natural Resources Watershed Protection Program TMDL.
- Shatti, J. A., and Abdullah, T. H. A. (1999). "Marine Pollution Due to Wastewater Discharge in Kuwait." *Water Science and Technology*, 40(7), 33-39.
- Sinton, L. W., Finlay, R. K., and Lynch, P. A. (1999). "Sunlight Inactivation of Fecal Bacteriophages and Bacteria in Sewage-Polluted Seawater." *Applied and Environmental Microbiology*, 65(8), 3605-3613.
- Sobsey, M. D., Chung, Y., Freeman, A., and Lovelace, G. (1998). "Assessing the Microbial Quality of Marine Recreational Waters using New and Alternative Indicators of Fecal Contamination.", UNC, Department of Environmental Sciences and Engineering.
- Springthorpe, V. S., Loh, C. L., Robertson, W. J., and Sattar, S. A. (1993). "In Situ Survival of Indicator Bacteria, MS-2 Phage and Human Pathogenic Viruses in River Water." *Water Science and Technology*, 27(3-4), 413-420.
- Tani, K., Kurokawa, K., and Nasu, M. (1998). "Development of a Direct In Situ PCR Method for Detection of Specific Bacteria in Natural Environments." *Applied and Environmental Microbiology*, 64(4), 1536-1540.

- Tarkka, E., Ahman, H., and Siitonen, A. (1994). "Ribotyping as an Epidemiologic Tool for *Escherichia coli*." *Epidemiology of Infections*, 112, 263-274.
- Texas Natural Resource Conservation Commission. (2000). "Chapter 307 Texas Surface Water Quality Standards.", Austin, TX.
- Toranzos, G. A., and McFeters, G. A. (1997). "Detection of Indicator Organisms in Environmental Freshwaters and Drinking Waters." In *Manual of Environmental Microbiology*, ASM Press, Washington, D.C., 184-194.
- U. S. Environmental Protection Agency. (2000). "Fecal Coliform TMDL Modeling Report, Cottonwood Creek Watershed, Idaho County, Idaho.", EPA Office of Water, Office of Science and Technology, Standards and Applied Science Division, Exposure Assessment Branch, Washington, D. C.
- U. S. Environmental Protection Agency. (2001). "Protocol for Developing Pathogen TMDLs." First Edition, *EPA 841-R-00-002*, Office of Water, Washington D.C.
- University of Houston, and PBS&J. (2000a). "Total Maximum Daily Load for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou Quarterly Report No. 1.", Prepared for the Texas Natural Conservation Commission, Houston, TX.
- University of Houston, and PBS&J. (2000b). "Total Maximum Daily Load for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou Quarterly Report No. 2.", Prepared for the Texas Natural Conservation Commission, Houston, TX.
- US EPA. (1994). "TMDL Case Study Lake Chelan, Washington.", EPA841-F-94-001, US EPA.
- US EPA Region 4. (2000a). "Fecal Coliform TMDL Fecal Coliform TMDL Development for Three Segments in the Choctawhatchee River Watershed, Florida.", US EPA Region 4, Atlanta.
- US EPA Region 4. (2000b). "Fecal Coliform TMDL for Four Segments in the Choctawhatchee River Watershed, Florida.", US EPA Region 4, Atlanta.
- US EPA Region 4. (2000c). "TMDL Evaluation for Fecal Coliform in the Aucilla River Thomas County, Georgia.", US EPA Region 4.
- US EPA Region 4. (2000d). "TMDL Evaluation for Fecal Coliform in Two Segments of the Ochlockonee River Worth and Colquitt Counties, Georgia.", US EPA Region 4.
- U. S. EPA Region 4. (2000e). "Fecal Coliform TMDL Development for Six Segments in the Blackwater River Watershed, Florida.", USEPA Region 4, Atlanta, GA.
- US EPA Region 6. (2000a). "Bayou Plaquemine Brule TMDL for Fecal Coliform.", US EPA Region 6 and Louisiana Department of Environmental Quality.
- US EPA Region 6. (2000b). "Bayou Teche TMDL for Fecal Coliform.", US EPA Region 6 and Louisiana Department of Environmental Quality.
- US EPA Region 6. (2000c). "Vermilion River TMDL for Fecal Coliform.", US EPA Region 6 and Louisiana Department of Environmental Quality.
- US EPA Region 10. (2000). "TMDL for Fecal Coliform Bacteria in the Waters of Duck Creek in Mendenhall Valley, Alaska.", US EPA Region 10, Seattle.
- Van Donsel, D. J., and Geldreich, E. E. (1971). "Relationship of Salmonellae to Fecal Coliforms in Bottom Sediments." *Water Resources*, 5, 1079-1087.
- Ward, G., and Benaman, J. (1999). "A Survey and Review of Modeling for TMDL Application in Texas Watercourses (Draft Report).", Center for Research in Water Resources. University of Texas at Austin, Autsin, TX.

- Ward, G. H. (2000)., Bureau of Economic Geology, Austin, TX.
- Whelan, C. D., Monaghan, P., Girdwood, R. W. A., and Fricker, C. R. (1988). "The Significance of Wild Birds (*Larus* spp.) in the Epidemiology of *Campylobacter* Infections in Humans." *Epidemiology of Infections*, 101, 259-267.
- Wiggins, B. A. (1996). "Discriminant Analysis of Antibiotic Resistance Patterns in Fecal Streptococci, a Method to Differentiate Human and Animal Sources of Fecal Pollution in Natural Waters." *Applied and Environmental Microbiology*, 62, 3997-4002.
- Wiggins, B. A., Andrews, R. W., Conway, R. A., Corr, C. L., Dobratz, E. J., Dougherty,
 D. P., Eppard, J. R., Knupp, S. R., Limjoco, M. C., Mettenburg, J. M., Rinehardt,
 J. M., Sonsino, J., Torrizos, R. L., and Zimmerman, M. E. (1999). "Use of Antibiotic Resistance Analysis to Identify Nonpoint Sources of Fecal Pollution."
 Applied and Environmental Microbiology, 68(8), 3483-3486.

APPENDIX A RAW DATABASE AND SUMMARY OF COMPILED DATA

Table A.1 Fecal Coliform Database

Table A.1 Summary of compiled fecal pathogen data (cfu/100 mL)

	Station ID	Location (from upstream to downstream)	Minimum	Maximum	Geometric Mean
-	11142	Barker Dam	9	160,000	843
	11345	McKee St	100	200,000	3,990
	11347	Main St	400	160,000	7,323
	11351	Shepherd Dr	1	200,000	3,912
	11353	IH 610	99	99,000	1,507
	11354	Woodway Dr	1	223,000	2,054
	11356	Voss Rd	99	200,000	3,394
\supseteq	11357	San Felipe St	1	160,000	1,156
۸YC	11358	Piney Point Rd	110	60,000	2,498
BUFFALO BAYOU	11359	Gessner Dr	1	90,000	994
ALC	11360	West Belt	1	220,000	1,067
77.	11361	Wilcrest Dr	1	23,000	1,358
BL	11362	Dairy Ashford Rd	1	130,000	852
	11363	Eldridge Rd	9	22,000	641
	11364	SH 6	9	33,000	607
	15842	San Jacinto Ave	340	250,000	9,374
	15843	Sabine Ave	100	200,000	4,646
	15844	Westcott Ave	140	250,000	2,610
	15845	Chimney Rock Rd	9	150,000	1,741
	15846	Briar Forest Ave	1	130,000	799
	11385	Wrightwood St	230	350,000	8,123
	11387	Heights Blvd	72	160,000	5,540
	11388	Houston Ave	6,000	107,000	4
	11390	W. 34th St	9	200,000	1,892
	11391	Ella Blvd	9	200,000	2,494
\supseteq	11398	Jones Rd	45	60,000	746
EOAK BAYOU	15824	Girard Ave	9	1,000,000	11,387
(B/	15825	Crocket Ave	160	210,000	8,182
JAk	15826	Studemont Ave	9	200,000	3,294
	15827	N. Durham St	9	200,000	3,770
WHIT	15828	W.T.C. Jester Ave (nr W. 12th st)	9	200,000	2,307
>	15829	W. 43rd St	9	200,000	667
	15830	Watonga	9	250,000	796
	15831	W. Tidwell Ave	9	200,000	1,216
	16637	W.T.C. Jester Ave (nr W. 34th st)	770	35,000	4,626
	16646	Confluence with Buffalo Bayou	780	5,500	2,579
	16647	S. Pacific RR Crossing	590	47,000	5,293

APPENDIX B

SELF-REPORTED FC DATA FROM

PERMIT COMPLIANCE SYSTEM (PCS)

APPENDIX B
SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0070971	< 1	< 1	9/30/91
TX0070971	< 1	< 1	12/31/91
TX0070971	< 2	< 2	3/31/92
TX0070971	7	7	6/30/92
TX0070971	< 1	< 1	9/30/92
TX0070971	< 1	<1	12/31/92
TX0070971	< 1	<1	3/31/93
TX0070971	< 1	<1	6/30/93
TX0094307	< 1	<1	6/30/93
TX0094307	< 1	<1	6/30/93
TX0070971	< 1	< 1	9/30/93
TX0094307	< 1	<1	9/30/93
TX0094307	< 1	<1	9/30/93
TX0070971	< 1	<1	12/31/93
TX0094307	< 1	<1	12/31/93
TX0094307	< 1	< 1	12/31/93
TX0070971	< 1	< 1	3/31/94
TX0070971	5	5	6/30/94
TX0070971	5	5	9/30/94
TX0082830	4	4	9/30/98
TX0082830	4	4	9/30/98
TX0094307	10	10	9/30/98
TX0094307	10	10	9/30/98
TX0082830	< 2	< 2	12/31/98
TX0082830	< 2	< 2	12/31/98
TX0094307	10	10	12/31/98
TX0094307	10	10	12/31/98
TX0082830	28	28	3/31/99
TX0082830	28	28	3/31/99
TX0094307	15.87	40	3/31/99
TX0094307	15.87	40	3/31/99
TX0082830	18	18	6/30/99
TX0082830	18	18	6/30/99
TX0094307	10	10	6/30/99
TX0094307	10	10	6/30/99
TX0082830	12	12	9/30/99
TX0082830	12	12	9/30/99
TX0094307	10	10	9/30/99
TX0094307	10	10	9/30/99
TX0082830	< 2	< 2	12/31/99
TX0082830	< 2	< 2	12/31/99
TX0094307	2	2	12/31/99
TX0094307	2	2	12/31/99
TX0082830	< 2	< 2	3/31/00
TX0082830	< 2	< 2	3/31/00
TX0053325	6.74	40	4/30/91
TX0053325	7.94		6/30/91

APPENDIX B
SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0053325	18.61	535	7/31/91
TX0053325	130	274	9/30/91
TX0053325	20.79	35.4	11/30/91
TX0053325	25.67	147.74	12/31/91
TX0053325	30.48	45.52	1/31/92
TX0053325	22.8	39.51	2/29/92
TX0053325	49.02	79.47	3/31/92
TX0053325	32.45	132.53	4/30/92
TX0053325	43.58	81.44	9/30/92
TX0053325	37.28	63.75	12/31/92
TX0053325	63.91	100.68	1/31/93
TX0053325	25.64	38.24	2/28/93
TX0053325	89.37	200.29	3/31/93
TX0053325	60.16	143.88	5/31/93
TX0053325	37.5	73.46	6/30/93
TX0053325	46.16	122.25	7/31/93
TX0053325	15.73	40.99	8/31/93
TX0053325	13.59	20.79	9/30/93
TX0053325	15.46	23.43	10/31/93
TX0053325	30.06	97.62	11/30/93
TX0053325	38.47	69.22	12/31/93
TX0053325	27.81	47.17	1/31/94
TX0053325	21.76	50.34	3/31/94
TX0053325	16.49	21.67	4/30/94
TX0053325	12.49	13.91	5/31/94
TX0053325	19.38	30.08	6/30/94
TX0053325	38.08	63.08	7/31/94
TX0053325	26.74	58.79	8/31/94
TX0053325	41.05	91.9	9/30/94
TX0053325	40.59	63.02	10/31/94
TX0053325	31.91	45.6	11/30/94
TX0053325	52.27	74.46	12/31/94
TX0053325	50.44	94.78	4/30/95
TX0053325	34.34	190.96	5/31/95
TX0053325	34.34	190.96	5/31/95
TX0053325	58.07	108.86	6/30/95
TX0053325	58.07	108.86	6/30/95
TX0053325	16.89	25.53	7/31/95
TX0053325	16.89	25.53 25.53	7/31/95 7/31/95
TX0053325	28.08	25.55 44.4	8/31/95
TX0053325	28.08	44.4 44.4	8/31/95
TX0053325	27.83	36.08	9/30/95
TX0053325	27.83 27.83	36.08	9/30/95
TX0053325	27.63 38.67	48.65	9/30/95 10/31/95
	38.67	48.65	10/31/95
TX0053325			
TX0053325	49.46	123.22	11/30/95
TX0053325	49.46	123.22	11/30/95

APPENDIX B
SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0053325	25.86	37.45	12/31/95
TX0053325	25.86	37.45	12/31/95
TX0053325	17.48	25.22	1/31/96
TX0053325	17.48	25.22	1/31/96
TX0053325	17.95	40.66	2/29/96
TX0053325	17.95	40.66	2/29/96
TX0053325	44.48	76.88	3/31/96
TX0053325	44.48	76.88	3/31/96
TX0053325	36.29	65.29	4/30/96
TX0053325	36.29	65.29	4/30/96
TX0053325	31.89	43.69	5/31/96
TX0053325	31.89	43.69	5/31/96
TX0053325	20.18	27.68	6/30/96
TX0053325	20.18	27.68	6/30/96
TX0053325	21.53	75.61	7/31/96
TX0053325	21.53	75.61	7/31/96
TX0053325	15.51	19.05	8/31/96
TX0053325	15.51	19.05	8/31/96
TX0076651	10	10	8/31/96
TX0076651	10	10	8/31/96
TX0026352	< 1	< 1	9/30/96
TX0026875	1	2	9/30/96
TX0053325	31.47	55.57	9/30/96
TX0053325	31.47	55.57	9/30/96
TX0062235	1	1	9/30/96
TX0092908	< 10	< 10	9/30/96
TX0053325	20.52	28.97	10/31/96
TX0053325	20.52	28.97	10/31/96
TX0053325	20.4	203.9	11/30/96
TX0053325	20.4	203.9	11/30/96
TX0026352	1	1	12/31/96
TX0026697	< 1	< 1	12/31/96
TX0053325	16.9	20.9	12/31/96
TX0053325	16.9	20.9	12/31/96
TX0076651	< 10	< 10	12/31/96
TX0076651	< 10	< 10	12/31/96
TX0053325	16.3	27.7	1/31/97
TX0053325	16.3	27.7	1/31/97
TX0053325	14.6	21.5	2/28/97
TX0053325	14.6	21.5	2/28/97
TX0076651	< 10	< 10	2/28/97
TX0076651	< 10	< 10	2/28/97
TX0026247	30	30	3/31/97
TX0026352	< 2	< 2	3/31/97
TX0026697	< 1	< 1	3/31/97
TX0026875	0	0	3/31/97
TX0053325	20.9	29.8	3/31/97

APPENDIX B
SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0053325	20.9	29.8	3/31/97
TX0062235	< 1	< 1	3/31/97
TX0092908	2	2	3/31/97
TX0032300	0	0	4/30/97
TX0020247	12.8	31.6	4/30/97
TX0053325	12.8	31.6	4/30/97
TX0035323	0	0	5/31/97
TX0020247	32.5	100	5/31/97
TX0053325	32.5	100	5/31/97
TX0033323	2	2	6/30/97
TX0026332	< 1	<1	6/30/97
TX0020097	25	35.1	6/30/97
TX0053325	25 25	35.1 35.1	6/30/97
TX0053525		< 1	6/30/97
TX0062235 TX0093726	< 1		6/30/97 6/30/97
	< 2	< 2	
TX0093726	< 2	< 2	6/30/97
TX0053325	58.3	29.8	7/31/97
TX0053325	58.3	29.8	7/31/97
TX0053325	22.7	32.3	8/31/97
TX0053325	22.7	32.3	8/31/97
TX0026352	< 1	< 1	9/30/97
TX0026697	< 1	< 1	9/30/97
TX0053325	38.4	52.9	9/30/97
TX0053325	38.4	52.9	9/30/97
TX0062235	< 1	< 1	9/30/97
TX0092908	12	235	9/30/97
TX0093726	< 1	< 1	9/30/97
TX0093726	< 1	< 1	9/30/97
TX0053325	44.05	114.22	10/31/97
TX0053325	44.05	114.22	10/31/97
TX0026247	6	6	11/30/97
TX0053325	16.2	17.68	11/30/97
TX0053325	16.2	17.68	11/30/97
TX0026352	< 1	< 1	12/31/97
TX0026697	< 1	< 1	12/31/97
TX0053325	13.42	14.21	12/31/97
TX0053325	13.42	14.21	12/31/97
TX0062235	1	1	12/31/97
TX0076651	10	10	12/31/97
TX0076651	10	10	12/31/97
TX0092908	14	30	12/31/97
TX0093726	< 1	< 1	12/31/97
TX0093726	< 1	< 1	12/31/97
TX0053325	16.31	27.31	1/31/98
TX0053325	16.31	27.31	1/31/98
TX0053325	18.72	24.29	2/28/98
TX0053325	18.72	24.29	2/28/98

APPENDIX B
SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0026247	5	10	3/31/98
TX0026352	1	1	3/31/98
TX0026697	< 1	< 1	3/31/98
TX0026875	437	437	3/31/98
TX0053325	12.69	14.5	3/31/98
TX0053325	12.69	14.5	3/31/98
TX0062235	< 1	< 1	3/31/98
TX0092908	<13	20	3/31/98
TX0093726	4	4	3/31/98
TX0093726	4	4	3/31/98
TX0053325	10.61	12.19	4/30/98
TX0053325	10.61	12.19	4/30/98
TX0076651	10	10	4/30/98
TX0076651	10	10	4/30/98
TX0053325	16.6	39.06	5/31/98
TX0053325	16.6	39.06	5/31/98
TX0026247	9	25	6/30/98
TX0026352	< 1	< 1	6/30/98
TX0026697	2	2	6/30/98
TX0053325	20.95	28.49	6/30/98
TX0053325	20.95	28.49	6/30/98
TX0062235	< 1	< 1	6/30/98
TX0092908	< 10	< 10	6/30/98
TX0093726	< 1	< 1	6/30/98
TX0093726	< 1	< 1	6/30/98
TX0053325	23.42	40.81	7/31/98
TX0053325	23.42	40.81	7/31/98
TX0053325	17.45	24.86	8/31/98
TX0053325	17.45	24.86	8/31/98
TX0026247	1	1	9/30/98
TX0026352	< 1	< 1	9/30/98
TX0026697	< 1	< 1	9/30/98
TX0053325	35.42	61.85	9/30/98
TX0053325	35.42	61.85	9/30/98
TX0062235	< 1	< 1	9/30/98
TX0076651	10	10	9/30/98
TX0076651	10	10	9/30/98
TX0090115	1	1	9/30/98
TX0090735	< 2	< 2	9/30/98
TX0092908	< 10	< 10	9/30/98
TX0093726	< 1	< 1	9/30/98
TX0093726	< 1	< 1	9/30/98
TX0053325	18.59	56.58	10/31/98
TX0053325	18.59	56.58	10/31/98
TX0053325	16.4	25.21	11/30/98
TX0053325	16.4	25.21	11/30/98
TX0026247	3	10	12/31/98

APPENDIX B
SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0026352	1	1	12/31/98
TX0026697	, <1	· <1	12/31/98
TX0053325	15.9	21.55	12/31/98
TX0053325	15.9	21.55	12/31/98
TX0062235	3	3	12/31/98
TX0076651	10	10	12/31/98
TX0076651	10	10	12/31/98
TX0070031	3	6	12/31/98
TX0090735	< 2	< 2	12/31/98
TX0092908	< 10	< 10	12/31/98
TX0093726	3	3	12/31/98
TX0093726	3	3	12/31/98
TX0053720	20.52	27.28	1/31/99
TX0053325	20.52	27.28	1/31/99
TX0053325	16.28	18.34	2/28/99
TX0053325	16.28	18.34	2/28/99
TX0033323	10.20	10.54	3/31/99
TX0026247	1	1	3/31/99
TX0026332	< 1	< 1	3/31/99
TX0020097	18.34	26.47	3/31/99
TX0053325	18.34	26.47	3/31/99
TX0053325	23	23	3/31/99
TX0076651	10	10	3/31/99
TX0076651	10	10	3/31/99
TX0076651	4	11	3/31/99
TX0090115	4 < 2	< 2	3/31/99
TX0090735	< 10	< 10	3/31/99
TX0092908 TX0093726	< 10 4	< 10 4	
TX0093726	4	4	3/31/99 3/31/99
TX0093726 TX0053325	22	31.49	
TX0053325	22	31.49	4/30/99
	30.3		4/30/99
TX0053325 TX0053325	30.3 30.3	54.21 54.21	5/31/99 5/31/99
TX0053325	30.3 < 1	54.21 < 1	
	` .	, ,	6/30/99
TX0026697	< 1	< 1	6/30/99
TX0053325	41.74	83.91	6/30/99
TX0053325	41.74	83.91	6/30/99
TX0062235	1	1	6/30/99
TX0076651	< 10	< 10	6/30/99
TX0076651	< 10	< 10	6/30/99
TX0090115	1	1	6/30/99
TX0090735	< 2	< 2	6/30/99
TX0092908	< 10	< 10	6/30/99
TX0093726	2	2	6/30/99
TX0093726	2	2	6/30/99
TX0053325	40.13	53.45	7/31/99
TX0053325	40.13	53.45	7/31/99

APPENDIX B
SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0053325	60.54	124.7	8/31/99
TX0053325	60.54	124.7	8/31/99
TX0026247	24	24	9/30/99
TX0026352	<u>-</u> . < 1	<u>-</u> . <1	9/30/99
TX0053325	20.19	32.34	9/30/99
TX0053325	20.19	32.34	9/30/99
TX0062235	< 1	< 1	9/30/99
TX0076651	10	10	9/30/99
TX0076651	10	10	9/30/99
TX0090115	1	1	9/30/99
TX0090735	82	82	9/30/99
TX0092908	12.6	20	9/30/99
TX0093726	< 1	< 1	9/30/99
TX0093726	< 1	<1	9/30/99
TX0053725	15.4	21.67	10/31/99
TX0053325	15.4	21.67	10/31/99
TX0053325	26.44	27.12	11/30/99
TX0053325	26.44	27.12	11/30/99
TX0035325	4	4	12/31/99
TX0026247	2	2	12/31/99
TX0026875	1	1	12/31/99
TX0053325	47.96	154.286	12/31/99
TX0053325	47.96	154.286	12/31/99
TX0033323	< 10	< 10	12/31/99
TX0076651	< 10	< 10	12/31/99
TX0070031	1	1	12/31/99
TX0090715	96	96	12/31/99
TX0090733	22.2	110	12/31/99
TX0092908	< 1	< 1	12/31/99
TX0093726	<1	< 1	12/31/99
TX0053720	39.94	211.42	1/31/00
TX0053325	39.94	211.42	1/31/00
TX0053325	21.04	33.67	2/29/00
TX0053325	21.04	33.67	2/29/00
TX0035325	< 1	< 1	3/31/00
TX0053325	13.27	18.57	3/31/00
TX0053325	13.27	18.57	3/31/00
TX0090115	13.27	2	3/31/00
TX0090113	< 10	< 10	3/31/00
TX0053325	18.24	114.28	4/30/00
TX0053325	18.24	114.28	4/30/00
TX0053325	19.91	55	5/31/00
TX0053325	19.91	55 55	5/31/00
TX0053325 TX0026247	19.91	55 72	6/30/00
TX0026247 TX0053325	2 4 14.57		6/30/00
TX0053325 TX0053325	14.57	22.85	6/30/00
TX0053325 TX0090115	0	22.85	6/30/00
170090119	U	0	0/30/00

APPENDIX B SELF-REPORTED FC DATA FROM PCS

	DAILY AVERAGE	DAILY MAXIMUM	
NPDES No.	CONC (cfu/dL)	CONC (cfu/dL)	DATE
TX0053325	14.6	20	7/31/00
TX0053325	14.6	20	7/31/00
TX0053325	18.42	48.57	8/31/00
TX0053325	18.42	48.57	8/31/00

Data source: EPA Permit Compliance System (PCS). URL: www.epa.gov/enviro

APPENDIX C

OVERFLOW AND BYPASS DATABASES

- C.1 From City of Houston PW&E
- **C.2** From Individual Permit Files

Table C.1 Database from City of Houston PW&E

Problem	Location	Description	Receiving stream	Key map	Permit	Date Time	Volume	Un
	900W.FOREST @	MAIN SEWER LINE STOPPEDUP OVERFLOW INTO						
NORTHWEST QUADRANT	BRITOAK	SEWER.	BUFFALO BAYOU	489-B	TX0096172	02-Jan-95 07:00	7920	Gallo
		SEWER MAIN LINE STOPPED UP& OVFLW.INTO					.	
ORTHWEST QUADRANT	E.32 1/2-LINK	STORM SW LN	BUFFALO BAYOU	453-T	TX0096172	04-Jan-96 11:06	3065	
ASTEWATER OPERATION		#3 PUMP FAILED	BUFFALO BAYOU	488-G	TX0035017	13-Jan-96 00:01	110000	
ASTEWATER OPERATION	609 N.ELDRIDGE	#3 LP FAILED	BUFFALO BAYOU	488-G	TX0035017	13-Jan-96 16:00	10000	Galle
	l	SEWER MAIN BROKEN AT THE CONNECTION						L
OUTHEAST QUADRANT	1511 PRESTON	CAUSING SEWER	BUFFALO BAYOU	493-M	TX0096172	02-Feb-96 19:30	56	Gall
		ROUTINE SEWER MAIN STOPPAGE CAUSING						
ORTHWEST QUADRANT	8903 LANGFIELD	MANHOLE TO OVE	BUFFALO BAYOU	411-N	TX0057347	03-Feb-96 14:00	2340	
OUTHEAST QUADRANT	4801 CANAL	BROKEN SEWER LINE.	BUFFALO BAYOU	494-P	TX0096172	15-Feb-96 17:52	1073	_
OUTHEAST QUADRANT	4426 CANAL	4X8 SEWER LIN STOPPAGE	BUFFALO BAYOU	494-P	TX0096172	15-Feb-96 19:31	4170	
ORTHWEST QUADRANT	611W.MONTGOMERY	STOPPAGE IN SEWER LINE	BUFFALO BAYOU	412-V	TX0096172	27-Feb-96 14:58	15	GPI
		8'MAIN LINE STOPPED UP WHICH CAUSED						
ORTHWEST QUADRANT	1300 PERTHSHIRE	WASTEWATER TO	BUFFALO BAYOU	489-G	TX0063002	04-Mar-96 10:42	25	Gal
	6900 OLD CLINTON AT	CONTRACTORS BYPASS PUMP DISCHARGE HOSE					.	
ORTHEAST QUADRANT	LATHROP	DEVELOPED	BUFFALO BAYOU	494-H	TX0096172	05-Mar-96 22:00	600	Gal
		THERE WAS A LEAK FROM A CRACKED SEWER						
ASTEWATER OPERATION	2015 RUNNELS	FORCE MAIN.	BUFFALO BAYOU	493-M	TX0096172	06-Mar-96 15:00	2000	Gal
OUTHEAST QUADRANT	6230 PINEWAY	12X18 ROUTINE STOPPAGE IN MAIN.	BUFFALO BAYOU	534-G	TX0096172	07-Mar-96 12:00	20	Gal
		SEWER MAIN STOPPAGE DUE TO GREASE IN THE						
OUTHEAST QUADRANT	6230 PINEWAY	LINE.	BUFFALO BAYOU	534-G	TX0096172	12-Mar-96 09:49	20	GP
ASTEWATER OPERATION	2015 RUNNELS	POWER FAILURE	BUFFALO BAYOU	493-M	TX0096172	14-Mar-96 13:00	5000	Gal
		ROUTINE SEWR MAIN STOPPAGE CAUSING RAW						
ORTHWEST QUADRANT	1249 BLALOCK	SEWER TO	BUFFALO BAYOU	450-Y	TX0096172	21-Mar-96 10:36	315	Gal
· · · · · · · · · · · · · · · · · · ·		8" SEWER MAIN 8 FEET DEEP STOPPED UP		1			- 1	
OUTHWEST QUADRANT	4015 WILMER	CAUSING SEWER	BUFFALO BAYOU	494-S	TX0096172	03-Apr-96 09:34	4185	Gal
		CONTRACTORS REPAIRING SEWER MAIN PLUGGED	220 200	1.2.0		22.2.00000	.100	Jul
ORTHWEST QUADRANT	1615 WEST CLAY	LINE.	BUFFALO BAYOU	492-R	TX0096172	17-Apr-96 16:15	15525	Gal
OUTHEAST QUADRANT	5647 LAWSON	ROUTINE STOPPAGE	BUFFALO BAYOU	492-R 534-C	TX0096172	23-Apr-96 12:20	300	
OUTHEAST QUADRANT		ROUTINE STOPPAGE	BUFFALO BATOU	534-C	170090172	23-Apr-96 12.20	300	Gai
ODTUMEST OF VERNICAL	12507 WINDING BROOK	DOLITINE STORDAGE OREW ON OUT	DUEEN O DAYOU	400 N	TV0005017	07 May: 00 00 10		
ORTHWEST QUADRANT	LN.	ROUTINE STOPPAGE-CREW ON SITE	BUFFALO BAYOU	489-N	TX0035017	07-May-96 08:40	590	Ga
OUTUE 407 01115 - 117	400 AL TO::	ROUTINE STOPPAGE DUE TO A BROKEN SEWER	DUEEN O DATE:	40=	TV0000	45.4		
OUTHEAST QUADRANT	106 ALTON	MAIN	BUFFALO BAYOU	495-W	TX0096172	15-May-96 21:41	2940	
OUTHEAST QUADRANT	6500 AVE.F AT BRADY	ROUTINE SEWER STOPPAGE	BUFFALO BAYOU	494-U	TX0105058	15-May-96 13:00	12600	_
OUTHWEST QUADRANT	13123 HERMITAGE	SEWER BACKING UP DUE TO BREAK IN THE LINE	BUFFALO BAYOU	489-L	TX0035019	16-May-96 09:02	1080	Gal
ORTHWEST QUADRANT	1300 FOWLER	SEWER MAIN RELIEVING TO STORM SEWER	BUFFALO BAYOU	492-H	TX0096172	24-May-96 13:27	460	Gal
OUTHEAST QUADRANT	3226 N.MC GREGOR	ROUTINE STOPPAGE IN AN 8" SEWER MAIN	BUFFALO BAYOU	533-S	TX0105058	07-Jun-96 08:09	680	Gal
OUTHEAST QUADRANT	3938 FERNWOOD	ROUTINE STOPPAGE	BUFFALO BAYOU	533-H	TX0096172	10-Jun-96 11:25	118	Ga
		POWER FAILURE-HL&P, NO POWER TO THE						
ASTEWATER OPERATION	2015 RUNNELS	STATION	BUFFALO BAYOU	493-M	TX0096172	22-Jun-96 16:30	10000	Gal
		HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL IN		1.5				- 3
ASTEWATER OPERATION	4421 CRITES	THE AR	BUFFALO BAYOU	494-P	TX0096172	23-Jun-96 13:00	4000	Gal
	1600 SOUTH LOCKWOOD		220 200	1			.500	
VASTEWATER OPERATION		HEAVY RAIN /HYDRAULIC OVERLOAD	BUFFALO BAYOU	494-X	TX0062201	25-Jun-96 11:00	149000	Gal
VASTEWATER OF ERATION	DK.			434-7	170002201	25-5011-90 11.00	149000	Gai
ACTEMATED ODERATION	4404 CDITEC	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL IN		404 B	TV0000470	05 1 00 44.00	00000	0-1
VASTEWATER OPERATION	4421 CRITES	THE AR	BUFFALO BAYOU	494-P	TX0096172	25-Jun-96 14:00	60000	Gai
OUTUE A OT OU A DD A NE	7000 THE DOWN	ROUTINE STOPPAGE DUE TO A BROKEN SEWER	DUEEN O DAYOU	505 N	T)/0000470	00 1 100 1110		
OUTHEAST QUADRANT	7606 THUROW	MAIN	BUFFALO BAYOU	535-N	TX0096172	22-Jul-96 14:43	10	G.F
		MAIN BREAKER KICKED OFF WHICH CAUSED					.	
VASTEWATER OPERATION	204 ASBURY	WETWELL RISE	BUFFALO BAYOU	492-L	TX0096172	24-Jul-96 08:30	2000	Gal
		ROUTINE STOPPAGE-BROKEN SEWER MAIN					.	
OUTHEAST QUADRANT	212 NORWOOD	CAUSING O/FLOW.	BUFALLO BAYOU	494-U	TX0096172	05-Aug-96 11:13	1320	Gal
OUTHEAST QUADRANT	100 NAGLE	6" SEWER MAIN STOPPED-UP	BUFFALO BAYOU	494-N	TX0096172	13-Aug-96 11:51	625	Gal
		BROKEN SEWER MAIN CAUSED OVERFLOW INTO						
ORTHWEST QUADRANT	1600 SHEPHER AT EIGEL		BUFFALO BAYOU	492-H	TX0096172	27-Aug-96 13:19	825	Gal
OUTHEAST QUADRANT	1200 SIDNEY	ROUTINE STOPPSGE	BUFFALO BAYOU	494-S	TX0096172	28-Aug-96 13:52	1440	
		BROKEN SEWER MAIN CAUSING RAIN SEWER		1111				-
OUTHEAST QUADRANT	690 GLOBE	OVERFLOW	BUFFALO BAYOU	576-F	TX0096172	30-Aug-96 11:56	385	Gal
OUTHEAST QUADRANT	6309 BEEKMAN	ROUTINE STOPPAGE IN A SEWER MAIN.	BUFFALO BAYOU	576-F 534-N	TX0096172	01-Sep-96 11:45	960	
OUTTEAUT QUADRANT		NOUTINE STOFFAGE IN A SEWER MAIN.	DUFFALU DATUU	JJ4-IV	170090172	01-3eμ-90 11:45	900	Jal
ODTI WEST CLIADS AND	1712 KNOLL @ 8860	CII CONODETE CEMED LINE BROKE	DUEEN O DAYOU	450 !!	TV0000170	00.0 00 10.00		
ORTHWEST QUADRANT	SPRG. BRANCH	6" CONCRETE SEWER LINE BROKE.	BUFFALO BAYOU	450-U	TX0096172	03-Sep-96 13:08	573	
OUTHWEST QUADRANT	2047 W. GRAY	BROKEN SEWER MAIN IN THE PARKING LOT.	BUFALLO BAYOU	492-Q	TX0096172	16-Sep-96 10:59	42	Gal
	L	CITY MAIN STOPPED-UP AND OVERFLOWING INTO	L	1	<u> </u>		.	l.
OUTHWEST QUADRANT	2418 POTOMAC	S/S.	BUFFALO BAYOU	491-S	TX0062995	17-Sep-96 07:15	582	
OUTHEAST QUADRANT	2100 GULF CENTRAL	ROUTINE STOPPAGE IN AN 10'X10' SEWER MAIN	BUFFALO BAYOU	534-B	TX0096172	24-Sep-96 22:08	1928	Gal
		10'X10' SEWER MAIN BROKE CAUSING						
OUTHEAST QUADRANT	4924 GRIGGS	STOPPAGE,OVERFLOW	BUFFALO BAYOU	534-J	TX0096172	28-Sep-96 11:00	705	
OUTHWEST QUADRANT	1922 MORSE	SEWER MAIN STOPPED UP	BUFFALO BAYOU	492-R	TX0062995	01-Oct-96 08:15	285	Gal
		6"X 8' SEWER MAIN STOPPED UP CAUSING	Ì					
OUTHEAST QUADRANT	3030 HASBROOK	OVERFLOW	BUFFALO BAYOU	534-M	TX0096172	01-Oct-96 18:52	1720	Gal
OUTHEAST QUADRANT	6419 WESTSCOTT	ROUTINE STOPPAGE	BUFFALO BAYOU	492-F	TX0096172	01-Oct-96 21:40	9000	
		10" X 10' SEWER MAIN STOPPED UP CAUSING		1				
ORTHWEST QUADRANT	8849 LONG POINT	OVERFLOW.	BUFFALO BAYOU	450-V	TX0096172	14-Oct-96 10:20	1580	Ga
OUTHEAST QUADRANT	4704 PARK	ROUTINE STOPPAGE.	BUFFALO BAYOU	494-T	TX0096172	15-Oct-96 10:05	223	
OUTLIEROT QUADRAINT	TIVTIANN		DOLLATO DATOU	707-1	170030172	10-001-00 10.00	223	Jai
OLITHEAST OLIADDANT	406 HUTCHESON	ROUTINE STOPPAGE CAUSING RAW SEWER OVERFLOW.	BUFFALO BAYOU	494-N	TY0006170	22-00+ 06 12-02	200	G-
OUTHEAST QUADRANT	400 TO LOUESON		BOFFALO BATOU	494-IV	TX0096172	22-Oct-96 13:03	399	Ga
OUTHEAST OUASSANT	2000 PREMOND	SEWER MAIN 6" X 8' STOPPE UP, CAUSING	DUEEN O DAYOU	400.0	TV0000470	24 05+ 00 47 00		_
OUTHEAST QUADRANT	3000 BREMOND	OVERFLOW.	BUFFALO BAYOU	493-2	TX0096172	24-Oct-96 17:06		Ga
OUTHEAST QUADRANT	910 FAIR OAKS	STOPPAGE IN 10" X 8' MAIN	BUFFALO BAYOU	494-Y	TX0096172	28-Oct-96 14:29	2115	Ga
							. 1	
OUTHEAST QUADRANT		ROUTINE SEWER MAIN STOPPAGE.	BUFFALO BAYOU	494-Z	TX0096172	01-Nov-96 09:00	340	
ASTEWATER OPERATION	609 NORTH ELDRIDGE	POWER FAILURE DUE TO HL&P FUSE DROP	BUFFALO BAYOU	488-G	TX0035017	02-Dec-96 09:00	40000	Gal
ORTHWEST QUADRANT	600 SANDMAN	SEWER MAIN STOPPED UP CAUSING OVERFLOW	BUFFALO BAYOU	492-L	TX0096172	07-Dec-96 11:50	2725	
ORTHWEST QUADRANT	1502 GLEN OAKS	SEWER MAIN HAS STOPPAGE.	BUFFALO BAYOU	492-C	TX009672	07-Dec-96 23:42	1550	
OUTHEAST QUADRANT	6847 HARRISBURG	8" X 10' ROUTINE STOPPAGE	BUFFALO BAYOU	494-Z	TX0096172	09-Dec-96 17:29	132	
		8" X 8' SEWER MAIN STOPPAGE CAUSING		+			.02	- 3
	6200 PINEWAY	OVERFLOW.	BUFFALO BAYOU	534-G	TX0096172	13-Dec-96 10:03	2133	Gal
OUTHEAST QUADRANT	LYY/ ()		_ 3	10070	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	.5 550 00 10.00	2100	Jai
OUTHEAST QUADRANT		SEWER MAIN STORRAGE CALISING OVERELOW IN						
	1524 WHITE OAK	SEWER MAIN STOPPAGE CAUSING OVERFLOW IN	DI IEEAL O BAVOLI	402 C	TV0006470	12 Dog 06 10:45	245	Ga!
OUTHEAST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT	1524 WHITE OAK 1800 DALLAS	SEWER MAIN STOPPAGE CAUSING OVERFLOW IN STORM SR. STOPPED UP SEWER MAIN 8'X8".	BUFFALO BAYOU BUFFALO BAYOU	493-C 493-R	TX0096172 TX0096172	13-Dec-96 10:45 05-Jan-97 14:30	345	Gal

Problem	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
NORTHWEST QUADRANT	6203 BROWN BARK	SEWER MAIN STOPPED UP CAUSING RAW SEWER OVERFLOW.	BUEEN O BAYOU	451-F	TX0063011	06-Jan-97	12:20	005	Gallons
NORTHWEST QUADRANT	777 BATESWOOD	STOPPAGE IN SEWER LINE.	BUFFALO BAYOU BUFFALO BAYOU	489-E	TX0063011	08-Jan-97			Gallons
NORTHWEST QUADRANT	TIT BATESWOOD	OTOT FACE IN SEWER LINE.	DOITALO DATOO	403-L	170003002	00-Jan-37	22.54	700	Galloris
NORTHWEST QUADRANT	802 WALKWOOD COURT	ELECTRICAL OUTAGE AT THE LIFT STATION.	BUFFALO BAYOU	488-E	TX0063002	19-Jan-97	16:00	8100	Gallons
SOUTHEAST QUADRANT	2502 DELWIN	STOPPAGE FOUND IN AN 8X10 LINE.	BUFFALO BAYOU	576-F	TX0096172	29-Jan-97	20:01	670	Gallons
SOUTHEAST QUADRANT	7623 BROADVIEW	ROUTINE 10 X 10 MAIN STOPPAGE	BUFFALO BAYOU	535-W	TX0096172	02-Feb-97	13:43	3430	Gallons
		ROUTINE STOPPAGE IN SEWER LINE FLOWING INTO		1					
SOUTHEAST QUADRANT	805 DUMBLE AT WALKER		BUFFALO BAYOU	494-X	TX0096172	06-Feb-97	16:53	61	Gallons
WASTEWATER OPERATION	7909 1/2 MARKET	AIR RELIEVE VALVE BLEW OFF AND SPILLED RAW SEWER.	BUFFALO BAYOU	495-F	TX0096172	06-Feb-97	10.30	50	Gallons
WASTEWATER OPERATION		BROKEN FORCE MAIN SPILLED RAW SEWER	BUFFALO BAYOU	495-F	TX0096172	11-Feb-97			Gallons
	1500 TAFT @ ALLEN			1					
SOUTHWEST QUADRANT	PARKWAY	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	493-J	TX0034924	12-Mar-97	09:00	36000	Gallons
	1500 TAFT AT ALLEN								
SOUTHWEST QUADRANT	PARKWAY	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	493-J	TX0034924	12-Mar-97			Gallons
WASTEWATER OPERATION		HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	489-L	TX0063002	12-Mar-97	07:00	25000	Gallons
SOUTHWEST QUADRANT	1000 MONTROSE @ ALLEN PARKWAY	HYDRAULIC OVERFLOW DUE TO HEAVY RAINFALL	BUFFALO BYAOU	493-J	TX0034924	12-Mar-97	09:00	19500	Gallons
20011111201 Q0712111111	100 BLOCK TRAVIS AT	THE TOTAL COLOR OF EACH PORT OF THE PARTY OF	50117120 517100	100 0	17,000 102 1	12 11101 01	00.00	10000	Ganone
NORTHEAST QUADRANT	COMMERCE	HIGH RAINWATER AT 100 TRAVIS	BUFFALO BAYOU	493-L	TX0096172	18-Mar-97	20:51	30400	Gallons
SOUTH EAST QUADRANT	543 N. SUPER	6 x 8 ROUTINE STOPPAGES IN LINE	BUFFALO BAYOU	494-P	TX0096172	21-Mar-97	17:47	708	Gallons
		STOPPED-UP 6"X6' SEWER MAIN CAUSING							
SOUTHEAST QUADRANT	592 NORTH EASTWOOD	OVERFLOW.	BUFFALO BAYOU	494-P	TX0096172	26-Mar-97	18:58	141	Gallons
COUTUEACT OLIADDANT	FAO N. FACTIMOOD	6"x6' SEWER MAIN STOPPED-UP CAUSING SEWER	DUEEN O DAVOU	404 B	TY0000470	00 4 07	40.00	0750	0-11
SOUTHEAST QUADRANT	542 N. EASTWOOD	OVERFLOW	BUFFALO BAYOU	494-P	TX0096172	02-Apr-97	13:02	2/56	Gallons
SOUTHWEST QUADRANT	1500 TAFT AT ALLEN PARKWAY	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	493-J	TX0034924	04-Apr-97	07:00	30000	Gallons
			_ 5	1.55 0		5 / Api-3/	300	55000	Canona
WASTEWATER OPERATION	7700 WOODWAY	BREAKER BOX HAD BAD FUSES & HEAVY RAINFALL	BUFFALO BAYOU	490-R	TX0063002	04-Apr-97	14:30	32500	Gallons
WASTEWATER OPERATION	7700 WOODWAY	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	490-R	TX0063002	04-Apr-97	06:00	35000	Gallons
	100 SAN								
NODTHEACT CHARDANE	JACINTO/ALLEN&WOODS	LIVER ALL IC OVERLOAD BUT TO USAN SANCTON	DUEEN O DAYOU	400.0	TV0000170	04.4	07.00	7.05	0-11
NORTHEAST QUADRANT	ST 100 MILAM (N.OF	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	493-C	TX0096172	04-Apr-97	07:00	/4250	Gallons
NORTHEAST QUADRANT	BUFFALO BAYOU)	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	493-L	TX0096172	04-Apr-97	07:00	299250	Gallons
TOTAL CONTROL CONTROL	100 TRAVIS AT	THE WOLLD OVERLED AS DOE TO HEXWY TO WAY ALE	DOIT/ALO BATTOO	100 E	17,0000112	047tpi 07	07.00	200200	Calloris
NORTHWEST QUADRANT	COMMERCE	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	493-L	TX0096172	04-Apr-97	07:00	630000	Gallons
									ON
SOUTHWEST QUADRANT	1400 WEST LOOP SOUTH	18"x26" SEWER MAIN RUNNING OVER THE BAYOU	BUFFALO BAYOU	491-R	TX0063002	12-Apr-97	19:57	500	GOING
		DISCHARGE VALVES TO VARIOUS TANKS							
WASTEWATER OPERATION		ON,OVERFLOW ST.	BUFFALO BAYOU	488-F	TX0035017	24-Apr-97			Gallons
WASTEWATER OPERATION		HYSRAULIC OVERLOAD SUE TO HEAVY RAINFALL	BUFFALO BAYOU	494-P	TX0096172	25-Apr-97	21:00	65000	Gallons
SOUTHWEST QUADRANT	1500 TAFT @ ALLEN PARKWAY	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	493-J	TX0034924	26-Apr-97	19:00	24000	Gallons
WASTEWATER OPERATION		POWER FAILURE AND WE CALLED HL&P	BUFFALO BAYOU	488-B	TX0034324	06-May-97			Gallons
		HEAVY RAINFALL, LP#1 TRIPPED OUT & #2 LOST							
WASTEWATER OPERATION	4421 CRITES	HEAVY RAINFALL,LP#1 TRIPPED OUT & #2 LOST PRIME	BUFFALO BAYOU	494-P	TX0096172	09-May-97	17:30	35000	Gallons
		PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER				-			
WASTEWATER OPERATION WASTEWATER OPERATION		PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN	BUFFALO BAYOU	494-P 447-Y	TX0096172 TX0026395	09-May-97 21-May-97			Gallons Gallons
WASTEWATER OPERATION	16500 PARK ROW	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM	BUFFALO BAYOU	447-Y	TX0026395	21-May-97	13:00	5000	Gallons
	16500 PARK ROW 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING				-	13:00	5000	
WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY	BUFFALO BAYOU	447-Y 490-R	TX0026395 TX0063002	21-May-97	13:00	5000 3000	Gallons Gallons
WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	447-Y	TX0026395	21-May-97 21-May-97 22-May-97	13:00	5000 3000 38000	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	447-Y 490-R 493-L	TX0026395 TX0063002 TX0096172	21-May-97	13:00 22:00 19:50 15:00	3000 38000 95000	Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97	13:00 22:00 19:50 15:00 16:30	3000 38000 95000 10000	Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	447-Y 490-R 493-L 488-B	TX0026395 TX0063002 TX0096172 TX0035017	21-May-97 21-May-97 22-May-97 24-May-97	13:00 22:00 19:50 15:00 16:30	3000 38000 95000 10000	Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97	13:00 22:00 19:50 15:00 16:30	38000 38000 95000 10000 2307	Gallons Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL.	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97	13:00 22:00 19:50 15:00 16:30	38000 38000 95000 10000 2307	Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0063002 TX0090352	21-May-97 21-May-97 22-May-97 24-May-97 29-May-97 04-Jun-97	13:00 22:00 19:50 15:00 16:30	5000 3000 38000 95000 10000 2307	Gallons Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL.	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97	13:00 22:00 19:50 15:00 16:30	5000 3000 38000 95000 10000 2307	Gallons Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0063002 TX0090352	21-May-97 21-May-97 22-May-97 24-May-97 29-May-97 04-Jun-97	13:00 22:00 19:50 15:00 16:30 13:00	3000 38000 95000 10000 2307 50	Gallons Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19' SEWER MAIN STOPPED UP CAUSING	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0090352 TX0096172 TX0096172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50	5000 3000 38000 95000 10000 2307 50 96	Gallons Gallons Gallons Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19" SEWER MAIN STOPPED UP CAUSING OVERFLOW.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0063002 TX0090352 TX0090172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 04-Jun-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50	5000 3000 38000 95000 10000 2307 50 96	Gallons Gallons Gallons Gallons Gallons Gallons Gallons Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6' SEWER MAIN CAUSED OVERFLOW. 8' X 9' SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15' X 19' SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0090352 TX0090172 TX0096172 TX0096172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 26-Jun-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15	5000 3000 38000 95000 10000 2307 50 96	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 15" X 19' SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19' SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N 494-N 490-R	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096195	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 29-Jul-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55	5000 3000 38000 95000 10000 2307 50 96 1670 1950	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19' SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N 494-N 494-N 494-N	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 29-Jul-97 01-Aug-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19	5000 3000 38000 95000 10000 2307 50 96 1670 1950 3180 3400	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N 494-N 490-R	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096195	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 29-Jul-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19	5000 3000 38000 95000 10000 2307 50 96 1670 1950 3180 3400	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19' SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N 494-N 494-N 494-N	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 29-Jul-97 01-Aug-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15	5000 3000 38000 95000 10000 2307 50 96 1670 1950 3180 340	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT SOUTHWEST QUADRANT SOUTHWEST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6' SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N 494-N 490-R 454-A 492-U	TX0026395 TX0063002 TX0096172 TX0063002 TX0090352 TX0090172 TX0096172 TX0062995 TX0096172 TX0062995 TX0034924	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 01-Aug-97 18-Aug-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15	5000 3000 38000 95000 10000 2307 50 96 1670 1950 3180 3400 1900	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR.	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOYPED-UP SEWER MAIN CAUSED OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW. INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N 494-N 490-R 454-A 492-U 490-N	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 18-Jun-97 18-Jun-97 19-Aug-97 19-Aug-97 19-Aug-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00	5000 38000 38000 95000 10000 2307 50 96 1670 1950 3180 340 190	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR.	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX00963002 TX0096172 TX0096172 TX0096172 TX0096172 TX00360172 TX0034924 TX0096172 TX0096172 TX0036172 TX0036172 TX0036002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 29-Jul-97 01-Aug-97 19-Aug-97 02-Sep-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00	5000 3000 38000 38000 10000 2307 500 96 1670 1950 3180 340 190 844 500	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR.	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN STOPPAGE IN A 6"X 8" SEWER MAIN.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 488-E 494-X 494-N 494-N 490-R 454-A 492-U 490-N	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 18-Jun-97 18-Jun-97 19-Aug-97 19-Aug-97 19-Aug-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00	5000 3000 38000 38000 10000 2307 500 96 1670 1950 3180 340 190 844 500	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT SOUTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT SOUTHWEST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 15" X 19' SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19' SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN HLL&P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6" X 8" SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 490-R 494-X 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0096302 TX0096172 TX0034924 TX0096172 TX0096172 TX005058	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 01-Aug-97 19-Aug-97 02-Sep-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20	5000 3000 38000 95000 10000 2307 50 96 1670 1950 3180 340 190 844 500 50 390	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOYPED-UP SEWER MAIN CAUSED OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW. INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6" X 8" SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N	TX0026395 TX0063002 TX0096172 TX0035017 TX0063002 TX00963002 TX0096172 TX0096172 TX0096172 TX0096172 TX00360172 TX0034924 TX0096172 TX0096172 TX0036172 TX0036172 TX0036002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 29-Jul-97 01-Aug-97 19-Aug-97 02-Sep-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20	5000 3000 38000 95000 10000 2307 50 96 1670 1950 3180 340 190 844 500 50 390	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT SOUTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT SOUTHWEST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6°X 6° SEWER MAIN CAUSED OVERFLOW. 8°X 9° SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15°X 19° SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6°X 8° SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 490-R 494-X 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 24-May-97 12-Jun-97 18-Jun-97 18-Jun-97 18-Aug-97 19-Aug-97 10-Sep-97 23-Sep-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00	5000 30000 38000 38000 10000 2307 500 96 1670 1950 3180 3440 190 844 5000 500 3900	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOYPED-UP SEWER MAIN CAUSED OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW. INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6" X 8" SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 490-R 494-N 494-N 494-N 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0096302 TX0096172 TX0034924 TX0096172 TX0096172 TX005058	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 01-Aug-97 19-Aug-97 02-Sep-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00	5000 30000 38000 38000 10000 2307 500 96 1670 1950 3180 340 190 84 500 50 390	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6°X 6° SEWER MAIN CAUSED OVERFLOW. 8°X 9° SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15°X 19° SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6°X 8° SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 490-R 494-N 494-N 494-N 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 24-May-97 12-Jun-97 18-Jun-97 18-Jun-97 18-Aug-97 19-Aug-97 10-Sep-97 23-Sep-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00 13:00	5000 3000 38000 38000 95000 10000 2307 50 96 1670 1950 3180 340 190 84 500 50 390 30000	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6°X 6° SEWER MAIN CAUSED OVERFLOW. 8° X 9° SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15° X 19° SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6° X 8° SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE AREA. HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N 494-N 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J 489-L	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0063002 TX0063002 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 18-Aug-97 19-Aug-97 10-Sep-97 09-Oct-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00 13:00 15:00	5000 3000 38000 38000 10000 2307 50 96 1670 1950 3180 340 190 84 500 390 30000 459630	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 15" X 19" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN HLL & P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6" X 8" SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE AREA.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J 489-L	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0090352 TX0096172 TX0034924 TX0096172 TX0034924 TX0096172 TX0034924 TX0096172 TX0063002 TX0105058 TX0035017	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 04-Jun-97 12-Jun-97 18-Jun-97 18-Aug-97 19-Aug-97 10-Sep-97 10-Sep-97 09-Oct-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00 13:00 15:00	5000 3000 38000 38000 10000 2307 50 96 1670 1950 3180 340 190 84 500 390 30000 459630	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK 7700 WOODWAY 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW. INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6" X 8" SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE AREA. HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL. PUMPS FAILED DUE TO BLOWN FUSES.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J 489-L 490-R 490-R	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0034924 TX0096172 TX0034924 TX0063002 TX0105058 TX0035017 TX0063002 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 29-Jul-97 19-Aug-97 19-Aug-97 10-Sep-97 10-Sep-97 11-Oct-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00 13:00 12:00	5000 3000 38000 38000 95000 10000 2307 50 96 1670 1950 3180 340 190 50 390 30000 20000 459630	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK 7700 WOODWAY 7700 WOODWAY	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6°X 6° SEWER MAIN CAUSED OVERFLOW. 8° X 9° SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15° X 19° SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6° X 8° SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE AREA. HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N 494-N 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J 489-L	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0036172 TX0063002 TX0063002 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 18-Aug-97 19-Aug-97 10-Sep-97 10-Sep-97 10-Oct-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00 13:00 12:00	5000 3000 38000 38000 95000 10000 2307 50 96 1670 1950 3180 340 190 50 390 30000 20000 459630	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHWEST QUADRANT NORTHEAST QUADRANT NORTHEAST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK 7700 WOODWAY 698 LOCKWOOD	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6°X 6° SEWER MAIN CAUSED OVERFLOW. 8° X 9° SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15° X 19° SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6° X 8° SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE AREA. HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL. PUMPS FAILED DUE TO BLOWN FUSES.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N 494-N 494-N 494-N 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J 489-L 490-R 490-R 490-R 490-R	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX003092 TX0096172 TX0035017 TX0063002 TX0063002 TX0063002 TX0063002 TX0063002 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 18-Jun-97 18-Aug-97 19-Aug-97 10-Sep-97 10-Sep-97 11-Oct-97 12-Oct-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00 15:00 00:00	5000 30000 38000 38000 38000 10000 2307 50 96 1670 1950 3180 3440 1900 84 5000 30000 459630	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK 7700 WOODWAY 698 LOCKWOOD	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6'X 6" SEWER MAIN CAUSED OVERFLOW. 8" X 9" SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15" X 19" SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED-UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN H.L.& P. CO. DRILLED INTO A SEWER MAIN. MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6" X 8" SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE AREA. HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J 489-L 490-R 490-R	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0090352 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0034924 TX0096172 TX0034924 TX0063002 TX0105058 TX0035017 TX0063002 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 29-Jul-97 19-Aug-97 19-Aug-97 10-Sep-97 10-Sep-97 11-Oct-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 10:00 13:20 09:00 15:00 00:00	5000 30000 38000 38000 38000 10000 2307 50 96 1670 1950 3180 3440 1900 84 5000 30000 459630	Gallons
WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION WASTEWATER OPERATION SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHEAST QUADRANT NORTHWEST QUADRANT WASTEWATER OPERATION SOUTHWEST QUADRANT WASTEWATER OPERATION	16500 PARK ROW 7700 WOODWAY MILAM ST. @ BUFFALO BAYOU 15350 MEMORIAL DRIVE 7700 WOODWAY 950 HIGHWAY 6 SOUTH 4605 BELL @ LOCKWOOD 3500 PRESTON 2700 COMMERCE AT ENGELK 6600 WOODWAY AT VOSS 2635 TIM AT MONA 2500 KIPLING 114 STONEY CREEK DRIVE 1700 WHITE OAK DR. 120 GESSNER DR. 3700 TUAM 1235 KIRKWOOD DRIVE 10810 CRANBROOK 7700 WOODWAY 698 LOCKWOOD	PRIME CLARIFIER EFFLUENT OVERFLOWED THE FILTER BASIN OVERFLOW DUE TO POWER OUTAGE FROM LIGHTNING HYDRAULIC OVERLOAD DUE TO LOCALIZED HEAVY RAINFALL ELECTRICAL PROBLEMS; LIFT PUMPS TRIPPED OFF HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL HYDRAULIC OVERLOAD FROM RAIN & BAD FUSES ON 2 PUMP SURGING INFLUENT CAUSED MLSS IN AERATION TO SPILL. STOPPAGE IN A 6°X 6° SEWER MAIN CAUSED OVERFLOW. 8° X 9° SEWER MAIN STOPPED UP CAUSING OVERFLOW. 15° X 19° SEWER MAIN STOPPED UP CAUSING OVERFLOW. STOPPED UP SEWER MAIN CAUSED OVERFLOW INTO BAYOU. STOPPED UP SEWER MAIN MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE LINE. BREAK IN FORCE MAIN JIMMERSON CONTRACTORS DUMPING DIRT ON THE STREET STOPPAGE IN A 6° X 8° SEWER MAIN. H.L. & P. POWER FAILURE CAUSED POWER OUTAGE AT P.S HEAVY RAINFALL AND POWER FAILURE IN THE AREA. HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL. PUMPS FAILED DUE TO BLOWN FUSES.	BUFFALO BAYOU	447-Y 490-R 493-L 488-B 490-R 490-R 490-R 488-E 494-X 494-N 494-N 494-N 494-N 494-N 494-N 494-N 490-R 454-A 492-U 490-N 493-A 490-J 493-Z 489-J 489-L 490-R 490-R 490-R 490-R	TX0026395 TX0063002 TX0096172 TX0063002 TX0063002 TX0063002 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX003092 TX0096172 TX0035017 TX0063002 TX0063002 TX0063002 TX0063002 TX0063002 TX0063002 TX0063002	21-May-97 21-May-97 22-May-97 24-May-97 24-May-97 29-May-97 12-Jun-97 18-Jun-97 18-Jun-97 18-Aug-97 19-Aug-97 10-Sep-97 10-Sep-97 11-Oct-97 12-Oct-97	13:00 22:00 19:50 15:00 16:30 13:00 12:50 11:15 17:55 14:19 14:20 19:15 12:57 06:00 13:20 09:00 13:00 12:00 00:00 04:00	5000 3000 38000 38000 95000 10000 2307 50 96 1670 1950 3180 340 190 84 500 50 390 20000 459630 29000	Gallons

Problem SOUTHWEST QUADRANT	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Uni
	100 SUGARBERRY	PUMPS AT HUDSON COURT WERE OFF CAUSING OVERFLOW.	BUFFALO BAYOU	490-P	TX0088153	06-Nov-97			Gallor
SOUTHEAST QUADRANT	5646 NAVIGATION	STOPPAGE IN THE SEWER MAIN CAUSED OVERFLOW FROM.	BUFFALO BAYOU	494-Q	TX0096172	13-Nov-97	10:27	4050	Gallor
OUTHEAST QUADRANT	3800 LEELAND	15" X 20' SEWER MAIN STOPPED UP CAUSING OVERFLOW.	BUFFALO BAYOU	494-S	TX0096172	13-Nov-97	14:00	200	GPM
OUTHEAST QUADRANT	403 COWLING	STOPPAGE IN THE SEWER MAIN CAUSING OVERLOAD.	BUFFALO BAYOU	493-U	TX0096172	24-Nov-97	16:43	527	GAL.
IORTHEAST QUADRANT	4200 DALLAS AT SIDNEY STREET	SEWER MAIN STOPPED-UP CAUSING OVERLOAD.	BUFFALO BAYOU	494-S	TX0096172	24-Nov-97	12:00	38	GAL
OUTHEAST QUADRANT	4445 McKINNEY	ROUTINE STOPPAGE IN SEWER MAIN. SEWER LINE WAS SET UP FOR BY PASS PUMPING	BUFFALO BAYOU	494-T	TX0096172	26-Dec-97			Gallo
ORTHWEST QUADRANT	415 W. GRAY	DRIVER.	BUFFALO BAYOU	493-N	TX0096172	30-Dec-97		-	Gallo
OUTHEAST QUADRANT	5646 NAVIGATION	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-Q	TX0096172	09-Jan-98			Gallo
OUTHEAST QUADRANT	2400 NAVIGATION	SEWER MAIN STOPPED UP.	BUFFALO BAYOU	494-J	TX0096172	12-Jan-98		2790	
ORTHEAST QUADRANT	4800 COLLINGSWORTH	MAIN LINE NEED REPAIR.	BUFFALO BAYOU	454-Y	TX0096172	13-Jan-98	13:19	0	4 GF
OUTHEAST QUADRANT	2817 ENGELKE	ROUTINE STOPPAGE.	BUFFALO BAYOU	494-N	TX0096172	21-Jan-98	12:14	3460	Galle
ORTHWEST QUADRANT	1315 CROCKER	SEWER MAIN STOPPED UP.	BUFFALO BAYOU	493-N	TX0096172	25-Jan-98		3575	Gall
ORTHWEST QUADRANT	3300 BUTLER	TIRE AND TUBING STOPPED UP SEWER MAIN.	BUFFALO BAYOU	498-J	TX0096172	29-Jan-98	13:10	4830	Gall
ORTHWEST QUADRANT	3125 CRESTDALE 1500 SCHARPE /	NORMAL STOPPAGE	BUFFALO BAYOU	450-K	TX0063011	30-Jan-98	13:27	126	Gall
OUTHWEST QUADRANT	BROADMOORE	REPAIR PND IN REAR ON SEWER LINE AT 1534. MANHOLE OVERFLOWING DUE TO STOPPAGE IN	BUFFALO BAYOU	494-X	TX0096172	30-Jan-98	12:15	550	Gall
OUTHEAST QUADRANT	2406 NAVIGATION BLVD.	THE LINE. OVERFLOW FROM PRIVATE LEAK, GOING	BUFFALO BAYOU	494-J	TX0096172	04-Feb-98	09:31	2030	Gall
OUTHEAST QUADRANT	1543 LOMBARDY	INTO;STORM SEWER.	BUFFALO BAYOU	494-X	TX0096172	13-Feb-98	10:55	82	GAL
ODTHEAST OHASSANT	ECOO NIANZO ATION	STOPPAGE IN A SEWER MAIN CAUSING AN	BUEEN O BAYOU	404.0	TV0000170	10 5-1 6-	10:40	F.1==	
ORTHEAST QUADRANT	5600 NAVIGATION	OVERFLOW.	BUFFALO BAYOU	494-Q	TX0096172	19-Feb-98		5456	_
OUTHEAST QUADRANT	2410 STEVENS	SEWER LINE HAS STOPPAGE.	BUFFALO BAYOU	494-A	TX0096172	22-Feb-98	10:00	240	Galle
ASTEWATER PERATIONS	2525 S/SGT. MACARIO GARCIA	MANHOLE OVERFLOWED BY THE AUTOMATIC B/WASH FILTERS	BUFFALO BAYOU	494-R	TX0096172	22-Feb-98	02:45	5000	Gall
ORTHEAST QUADRANT	2900 CAVALCADE	A BLOCKAGE IN SEWER MAIN CAUSING OVERFLOW.	BUFFALO BAYOU	454-Y	TX0096172	26-Feb-98	13:48	6825	Gall
OUTHWEST QUADRANT	110 STONEY CREEK	SEWER MAIN STOPPED UP CAUSING OVERFLOW. CLEANOUT OVERFLOWING RAW SEWER INTO	BUFFALO BAYOU	490-J	TX0035017	27-Feb-98	10:48	2700	
ORTHEAST QUADRANT	5315 HARRISBURG BLVD.		BUFFALO BAYOU	494-T	TX0096172	27-Feb-98	13:21	45	Gall
OUTHEAST QUADRANT /ASTEWATER	5600 NAVIGATION	STOPPAGE. PUMPS 1&2 TRIPPED OFF SUBSEQUENTLY	BUFFALO BAYOU	494-Q	TX0096172	27-Feb-98	13:50	2000	Gall
PERATIONS	12903 IROQUOIS	SURCHARGE SYSTE	BUFFALLO BAYOU	413-Q	TX0096172	28-Feb-98	10:00	900	Galle
									_
ORTHEAST QUADRANT	3900 POLK STREET	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	BUFFALO BAYOU	494-S	TX0096172	04-Mar-98	12:18	170	Gall
OUTHWEST QUADRANT	3619 S.SHEPHERD DR.	SEWER MAIN STOPPED-UP RESULTING TO MANHOLE.	BUFFALO BAYOU	492-Y	TX0034924	05-Mar-98	11:00	72	Gall
OUTHWEST QUADRANT	1700 PORTSMOUTH	SEWER MAIN STOPPEDUP AND OVERFLOWING ONTO STREET.	BUFFALO BAYOU	492-Y	TX0034924	05-Mar-98	09:35	57	Gall
VASTEWATER DPERATIONS	2525 S/SGT. MACARIO GARCIA	MOTOR BYPASS FAILED TO OPEN RESULTING TO OVERFLOW.	BUFFALO BAYOU	494-R	TX0096172	16-Mar-98	18:00	0	Und
ORTHWEST QUADRANT	1833 SHARP LANE	STOPPED SEWER MAIN OVERFLOWING INTO STORM DRAIN.	BUFFALO BAYOU	492-Q	TX0096172	17-Mar-98	12:50	2550	
ORTHWEST QUADRANT	2001 FANNIN & GRAY	MAIN LINE STOPPED-UP.	BUFFALO BAYOU	493-Q	TX0096172	26-Mar-98			Galle
OUTHWEST QUADRANT	1747 PORTSMOUTH	LINE STOPPAGE. SEWER MAIN STOPPED UP & OVERFLOWED FROM	BUFFALO BAYOU	492-Z	TX0096172	31-Mar-98	19:00	93	Galle
OUTHWEST QUADRANT	2900 TRAVIS @ ANITA	MANHOLE.	BUFFALO BAYOU	493-T	TX0096172	17-Apr-98	14:44	80	Galle
ORTHEAST QUADRANT	4445 McKINNEY	LOTS OF GREASE IN MAIN LINE AT STOPPAGE.	BUFFALO BAYOU	494-T	TX0096172	02-May-98	10:35	666	Gall
ORTHWEST QUADRANT	1421 SOUTHWICK	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	BUFFALO BAYOU	450-W	TX0096172	04-May-98		744	Gall
OUTHWEST QUADRANT	9767 PAGEWOOD LANE	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	BUFFALO BAYOU	490-W	TX0098191	05-May-98			Gall
ORTHWEST QUADRANT	69 SADDLEBROOK	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	BUFFALO BAYOU	491-B	TX0096172	06-May-98			Gall
OUTHWEST QUADRANT	3717 WILLOWICK	AIRCELL FAILED & PUMPS FAILED TO COME ON IN AUTO	BUFFALO BAYOU	492-H	TX0034924	14-May-98			Gall
		SEWER MAIN STOPPED-UP CAUSING O/F AT 1306				-			
ORTHWEST QUADRANT	1306 PEDEN	PEDEN. SEWER MAIN STOPPED-UP, SURCHARGED & O/F	BUFFALO BAYOU	493-N	TX0096172	14-May-98			Gall
ORTHWEST QUADRANT	1909 SHARP PLACE	FROM M/H.	BUFFALO BAYOU	492-Q	TX0096172	26-May-98			Gall
ORTHEAST QUADRANT	2900 COMMERCE	BYPASS PUMP FAILED.	BUFFALO BAYOU	494-N	TX0096172	08-Jun-98		65500	
ORTHEAST QUADRANT	2900 COMMERCE	BLOCKAGE IN SEWER MAIN CAUSING OVERFLOW. ROUTINE STOPPAGE CAUSING OVERFLOW FROM A	BUFFALO BAYOU	494-P	TX0096172	15-Jun-98		1620	
OUTHWEST QUADRANT	2606 SOUTH SHEPHERD 10000 CEDAR CREEK	MANHOLE.	BUFFALO BAYOU	492-U	TX0096172	17-Jun-98	09:03	54	Gall
OUTHWEST QUADRANT	DRIVE	SEWER MAIN SURCHARGED DUE TO STOPPAGE. SEWER MAIN STOPPED-UP AND OVERFLOWED	BUFFALO BAYOU	490-N	TX0096172	17-Jun-98	09:51	665	Gall
ORTHEAST QUADRANT	4330 LEELAND 2400 NAVIGATION @ ST.	FROM MANHOLE. AN OLD 12" COMBINATION SEWER WAS NEVER	BUFFALO BAYOU	494-S	TX0096172	22-Jun-98	10:03	76	Gall
ORTHEAST QUADRANT	CHARLES	PLUGGED. BROKEN SEWER MAIN STOPPED-UP AND	BUFFALO BAYOU	494-N	TX0096172	02-Jul-98	09:10	2350	Gall
ORTHEAST QUADRANT	316 EASTWOOD	OVERFLOWED.	BUFFALO BAYOU	494-T	TX0096172	03-Jul-98	12:48	368	Gall
ORTHWEST QUADRANT		SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	BUFFALO BAYOU	488-G	TX0035017	04-Jul-98		1060	
	3400 HARRISBURG @			1					
DRTHEAST QUADRANT	YORK	BROKEN SEWER MAIN CAUSING LEAKAGE. SEWER STOPPED-UP DUE TO A BROKEN SEWER	BUFFALO BAYOU	494-N	TX0096172	08-Jul-98	12:30	2880	Gall
ORTHEAST QUADRANT	900 N. VELASCO	MAIN.	BUFFALO BAYOU	494-J	TX0096172	08-Jul-98	14:43	1620	Gall
ORTHEAST QUADRANT	5500 CAVALCADE	8" X 8' SEWER MAIN WAS STOPPED-UP WITH RAGS.	BUFFALO BAYOU	454-Y	TX0096172	15-Jul-98	11:52	2040	Gall
	1139 ZOE	SEWER MAIN STOPPED-UP & CAUSING OVERFLOW FROM M/H.	BUFFALO BAYOU	494-M	TX0096172	17-Jul-98			Gall
IORTHEAST QUADRANT	1203 CLINTON PARK	SEWER MAIN STOPPED-UP AND OVERFLOWED.	BUFFALO BAYOU	495-V	TX0096172	13-Aug-98	18:59	76	Gall
IORTHEAST QUADRANT		STOPPAGE IN SEWER MAIN DUE TO GREASE BUILD-						1	
	5304 JEFFERSON	STOPPAGE IN SEWER MAIN DUE TO GREASE BUILD- UP. BROKEN SEWER MAIN STOPPED-UP CAUSING	BUFFALO BAYOU	494-X	TX0096172	15-Aug-98	20:56	88	Gall

Problem	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
		SEWER MAIN STOPPAGE DUE TO GREASE IN THE							
NORTHEAST QUADRANT	7106 SHERMAN	BROKEN SEWER MAIN STOPPED-UP AND	BUFFALO BAYOU	494-Z	TX0096172	29-Aug-98			Gallons
NORTHEAST QUADRANT	500 JENKINS	OVERFLOWED.	BUFFALO BAYOU	494-P	TX0096172	09-Sep-98	10:49	603	Gallons
WASTEWATER OPERATIONS	16500 PARK ROW	HYDRAULIC OVERLOAD DUE TO HEAVY RAIN.	BUFFALO BAYOU	447-Y	TX0026395	11-Sep-98		2000	Gallons
WASTEWATER	2525 STAFF SGT.	THE INTERIOR OF THE PARTY IN THE INTERIOR I	BOIT THEO BITTOO	1447	170020000	11 Ocp 30		2000	Undete
OPERATIONS	MARCARIO GARCI 9139 BRIAR FOREST	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL.	BUFFALO BAYOU	494-R	TX0096172	11-Sep-98	05:30	0	mined
NORTHWEST QUADRANT	DRIVE	ROUTINE STOPPAGE	BUFFALO BAYOU	490-P	TX0063002	13-Sep-98	17:02	498	Gallons
NORTHWEST QUADRANT	5217 LINDSEY	SEWER MAIN STOPPED UP CAUSING OVERFLOW	BUFFALO BAYOU	494-X	TX0096172	14-Sep-98	13:41	108	Gallons
NORTHWEST QUADRANT	331 SAGE	LS PUMPS WERE TURNED OFF FOR REPAIRS IN THE SERVICELINE	BUFFALO BAYOU	491-G	TX0096172	15-Sep-98	09:47	760	Gallons
NORTHWEST QUADRANT	15759 FOXGATE	SEWER MAIN STOPPED-UP CAUSING OVERFLOW FROM MANHOLE.	BUFFALO BAYOU	488-B	TX0035017	15-Sep-98	08:39	1180	GALS.
NORTHEAST QUADRANT	7702 AVENUE J	SEWER MAIN STOPPED-UP AND OVERFLOWED FROM MANHOLE.	BUFFALO BAYOU	495-S	TX0096172	18-Sep-98	10:50	558	Gallons
NORTHEAST QUADRANT	920 ALTIC	BROKEN SEWER MAIN STOPPED-UP CAUSING OVERFLOW FROM M/H.	BUFFALO BAYOU	494-T	TX0096172	02-Nov-98			Gallons
NORTHEAST QUADRANT	5000 SHERMAN	STOPPAGE IN THE SEWER MAIN DUE TO GREASE.	BUFFALO BAYOU	494-T	TX0096172	13-Nov-98			Gallons
NORTHEAST QUADRANT		ROUTINE SEWER LINE STOPPAGE.	BUFFALO BAYOU	494-P	TX0096172	14-Nov-98			Gallons
	4300 W. ALABAMA @								
SOUTHWEST QUADRANT	WESTLANE	SEWER LINE STOPPED-UP. SEWER MAIN STOPPED-UP DUE TO GREASE IN THE	BUFFALLO BAYOU	491-V	TX0062995	03-Dec-98	12:39	2475	Gallons
NORTHEAST QUADRANT	4924 LEELAND	LINE.	BUFFALO BAYOU	494-X	TX0096172	07-Dec-98	13:27	612	Gallons 100
NORTHEAST QUADRANT			BUFFALO BAYOU	494-J	TX0096172	11-Dec-98			GMP
SOUTHWEST QUADRANT	6349 FAIRDALE	ROUTINE STOPPAGE.	BUFFALO BAYOU	491-W	TX0062995	17-Dec-98	09:30	120	Gallons
NORTHEAST QUADRANT	SE CORNER OF 500 LOCKWOOD.	ROUTINE STOPPAGE.	BUFFALO BAYOU	494-Q	TX0096172	31-Dec-98	14:00	1100	Gallons
WASTEWATER	EGGINAGOS.	LIFT PUMPS FAILED TO COME ON DUE TO AIRCELL	BOTTALO BATOO	101 Q	170000112	01 200 30	14.00	1100	Calloris
OPERATIONS WASTEWATER	15726 TANYA CIRCLE	FAILURE	BUFFALO BAYOU	488-E	TX0035017	05-Jan-99	11:00	6050	Gallons
OPERATIONS	1235 S.KIRKWOOD DR.	BAD AIR RELIEF VALVE ON THE FORSE MAIN	BUFFALO BAYOU	489-J	TX0035017	12-Jan-99	14:00	1500	GALS.
NORTHWEST QUADRANT	2248 SHADOWDALE	ROUTINE STOPPAGE.	BUFFALO BAYOU	449-R	TX0096172	15-Jan-99	15:50	2800	Gallons
NORTHEAST QUADRANT	5050 JEFFERSON	ROUTINE STOPPAGE	BUFFALO BAYOU	494-X	TX0096172	21-Jan-99	09:26	285	Gallons
SOUTHWEST QUADRANT	3000 TRAVIS AT 900 ANITA	RAW SEWAGE DISCHARGE FROM MAN HOLE DUE TO LINE STOPPAGE	BUFFALO BAYOU	493-T	TX0096172	27-Jan-99	14:30	2	Gallons
NORTHWEST QUADRANT	1370 AFTON	ROUTINE STOPPAGE - GREASE ON THE LINE.	BUFFALO BAYOU	451-Y	TX0096172	29-Jan-99			Gallons
NORTHWEST QUADRANT	5095 FIELDWOOD	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO STOPPAGE.	BUFFALO BAYOU	491-Q	TX0096172	01-Feb-99			Gallons
NORTHEAST QUADRANT	1900 EASTWOOD	UVAVOIDABLE RAW SEWAGE DISCHARGE DUE TO STOPPAGE IN LIN		494-W	TX0096172				
	STREET	PLUGGED SEWER MAIN TO ENABLE REPAIRS MAIN	BUFFALO BAYOU			18-Feb-99			Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT	2339 DREXEL 1312 W. PIERCE	OVERFLOW MAIN LINE STOPPED UP FROM MANHOLE	BUFFALO BAYOU BUFFALO BAYOU	492-S 493-N	TX0034924 TX0096172	19-Feb-99 22-Feb-99			Gallons Gallons
NORTHWEST QUADICANT	1312 W.TIEROL	ROUTINE STOPPAGE IN AN 8" X 8' MAIN CAUSING	DOITALO DATOO	433-14	170030172	22-1 60-33	03.30	100	Galloris
NORTHEAST QUADRANT	321 SOUTH 72 STREET 4445 McKINNEY	OVERFLOW.	BUFFALO BAYOU	494-Z	TX0096172	27-Feb-99			Gallons
NORTHEAST QUADRANT WASTEWATER	2525 S./SGT. MACARIO	STOPPAGE IN THE MAIN LINE. 2-F REACTOR INLUENT GATE VALVE FAILED &	BUFFALO BAYOU	494-T	TX0096172	13-Mar-99	17.44	13920	Gallons Undeter
OPERATIONS	GARCIA	CAUSED OVERFLOW	BUFFALO BAYOU	494-R	TX0096172	13-Mar-99	21:35	0	mined
WASTEWATER OPERATIONS	133 SAGE ROAD	CREW CHECKED AND DETERMINED THAT PUMPS FAILED IN AUTO	BUFFALO BAYOU	491-G	TX0034924	17-Mar-99	12:20	500	Gallons
SOUTHWEST QUADRANT	1500 BERRING DRIVE	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	BUFFALO BAYOU	491-G 491-T	TX0034924 TX0062995	17-Mar-99			Gallons
		UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO							
SOUTHWEST QUADRANT	2222 WEST LOOP SOUTH		BUFFALO BAYOU	491-R	TX0062995	23-Mar-99			Gallons
NORTHWEST QUADRANT NORTHWEST QUADRANT	2100 BANCROFT DRIVE 5801 VALLY FORGE	ROUTINE STOPPAGE.	BUFFALO BAYOU BUFFALO BAYOU	491-R 491-P	TX0096172 TX0096172	24-Mar-99			Gallons Gallons
SOUTHEAST QUADRANT	5000 PEASE	ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE	BUFFALO BAYOU	491-P 494-X	TX0105058	24-Mar-99 27-Mar-99			Gallons
		SEWER MAIN STOPPED-UP AND CAUSED		1					
NORTHWEST QUADRANT	4300 SCOTLAND	OVERFLOW.	BUFFALO BAYOU	492-M	TX0096172	07-Apr-99	08:45	710	Gallons
NORTHWEST QUADRANT	8900 CHATSWORTH DRIVE	RAW SEWAGE DISCHARGEFROM A M/H DUE TO STOPPAGE.	BUFFALO BAYOU	491-H	TX0096172	09-Apr-99	09:35	1950	Gallons
WASTEWATER		PUMPS FAILED TO COME ON DUE TO POWER		10111					
OPERATIONS	15634 MEMORIAL DRIVE	FAILURE TO STATION UNAVOIDABLE RAW SEWAGE DISCHARGE FROM A	BUFFALO BAYOU	488-B	TX0035017	12-Apr-99	08:30	7500	Gallons
NORTHWEST QUADRANT	410 EAST FAIR HARBOR	MAN HOLE DUE TO	BUFFALO BAYOU	488-B	TX0035017	12-Apr-99	08:30	6000	Gallons
NORTHEAST QUADRANT	909 WACO	ROUTINE STOPPAGE.	BUFFALO BAYOU	494-F	TX0096172	20-Apr-99			Gallons
NORTHEAST QUADRANT	500 NORTH JENKINS	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO STOPPAGE.	BUFFALO BAYOU	494-P	TX0096172	21-Apr-99	08:36	33	Gallons
NORTHWEST QUADRANT	1519 GLEN OAKS	ROUTINE STOPPAGE CAUSED BY GREASE IN THE LINE.	BUFFALO BAYOU	492-C	TX0096172	21-Apr-99	09:41	3540	Gallons
NORTHWEST QUADRANT	2222 WEST LOOP SOUTH	I .	BUFFALO BAYOU	491-R	TX0096172	21-Apr-99	10:34	1455	Gallons
NORTHWEST QUADRANT	6108 TYNE	UNAVOIDABLE RAW SEWAGE DIACHARGE DUE TO STOPPAGE.	BUFFALO BAYOU	492-G	TX0096172	22-Apr-99	11:48	680	Gallons
NORTHEAST QUADRANT	5119 NOBLE	ROUTINE LINE STOPPAGE.	BUFFALO BAYOU	494-C	TX0096172	22-Apr-99			Gallons
NORTHWEST QUADRANT	133 SAGE ROAD	DISCHARGING SEWER FROM MANHOLE DUE TO AIR CELL FAILURE	BUFFALO BAYOU	491-G	TX0034924	28-Apr-99	11:56	gen	Gallons
SOUTHWEST QUADRANT	14935 KIMBERLY	ROUTINE STOPPAGE.	BUFFALO BAYOU	488-G	TX0034324	30-Apr-99			Gallons
NORTHEAST QUADRANT	3827 LOCKWOOD	RAW SEWAGE DISCHARGE DUE TO MAIN LINE STOPPAGE	BUFFALO BAYOU	454-Y	TX0096172	04-May-99	08:58	45	Gallons
NORTHEAST QUADRANT		MAIN LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	05-May-99			Gallons
		UNAVOIDABLE SEWAGE DISCHARGE DUE TO							
NORTHEAST QUADRANT	9200 PECOS	STOPPAGE IN MAIN SEWAGE DISCHARGE DUE TO STOPPAGE CAUSED	BUFFALO BAYOU	450-Y	TX0096172	06-May-99	10:44	455	Gallons
NORTHEAST QUADRANT	6314 CINDY LANE	BY GREASE BUILD UNAVOIDABLE SEWAGE DISCHARGE DUE TO	BUFFALO BAYOU	452-X	TX0096172	07-May-99	11:06	710	Gallons
	000 ED 414/1 E1/	STOPPAGE IN MAIN	WHITE OAK BAYOU	453-V	TX0057347	11-May-99	09:32	1580	Gallons
NORTHWEST QUADRANT	900 FRAWLEY	SEWER MAIN WAS PLUGGED SUBSEQUENTLY	William Count Driving			.,			

Problem	1	B d. et	B	17	D	D. C.	T	1.14.1	
NORTHWEST QUADRANT	Location 903 OMAR	Description SEWER MAIN STOPPED UP CAUSING OVERFLOW	Receiving stream BUFFALO BAYOU	Key map 493-B	Permit TX0096172	Date 13-May-99	Time 07:50	Volume	Un Gallo
NORTHWEST QUADRANT		ROUTINE STOPPAGE, CLEARED CITY MAIN	BUFFALO BAYOU	450-Q	TX0063002	17-May-99			Gallo
SOUTHWEST QUADRANT.	1833 SHARP PLACE	ROUTINE STOPPAGE	BUFFALO BAYOU	492-Q	TX0003002	19-May-99			Gallo
SOUTHWEST QUADICITY.	14562 CHADBOURNE	RAW SEWER DISCHARGE DUE TO STOPPAGE IN	DOITINEO BITTOO	702 Q	1700000172	10 May 00	10.47	2700	Joano
NORTHWEST QUADRANT	DRIVE	MAIN LINE	BUFFALO BAYOU	489-E	TX0096172	20-May-99	11:20	1800	Gallo
WASTEWATER	7909 1/2 MARKET	BRAKE IN 24" FORCE MAIN FROM MARKET ST. PUMP							
OPERATIONS	STREET	STATION	BUFFALO BAYOU	495-F	TX0096172	21-May-99	11:00	10000	Gallo
		SEWER OVERFLOW FROM A MAIN DUE TO							
NORTHEAST QUADRANT	204 NORTH NAGLE	STOPPAGE BY GREASE	BUFFALO BAYOU	494-N	TX0096172	21-May-99	16:05	480	Gallo
NORTHWEST QUADRANT	1308 NORTHWOOD	SEWER MAIN STOPPED UP CAUSING OVERFLOW	BUFFALO BAYOU	453-T	TX0096172	21-May-99	08:31	1250	Gallo
		STOPPAGE IN 8' X 8" SEWER MAIN CAUSED RAW							
NORTHWEST QUADRANT	2300 CENTER	SEWER OVERFLO	BUFFALO BAYOU	483-F	TX0096172	24-May-99	09:02	2395	Gallo
SOUTHEAST QUADRANT	1224 N. POST OAK RD.	ROUTINE STOPPAGE	BUFFALO BAYOU	491-D	TX0096172	27-May-99	10:00	625	Gallo
		UNAVOIDABLE SEWER DISCHARGE DUE TO							
NORTHWEST QUADRANT	215 FARGO	STOPPAGE IN MAIN	BUFFALO BAYOU	493-P	TX0096172	01-Jun-99	07:25	172	2 Gallo
		CONTRACTOR BROKE AND STOPPED-UP SEWER							
NORTHWEST QUADRANT	10731 LONGMONT	CAUSING OVERFLOW.	BUFFALO BAYOU	489-Q	TX0088153	04-Jun-99	09:30	1356	Gallo
IODTHE ACT OHADDANT	4.400 LAWCON	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO	DUEEN O DAVOU	40.4 V	TV0000470	00 1 00	44.04	0.0	
NORTHEAST QUADRANT	1426 LAWSON	STOPPAGE.	BUFFALO BAYOU	494-X	TX0096172	08-Jun-99	11:31	83	Gallo
NORTHWEST QUADRANT	500 SAN JACINTO	UNAVOIDABLE RAW SEWER OVERFLOE DUE TO STOPPAGE.	BUFFALO BAYOU	493-L	TX0096172	10-Jun-99	00-10	7/	1 Gallo
NORTHWEST QUADRANT	500 SAN JACINTO		BUFFALO BATOU	493-L	170096172	10-3411-99	06.16	/4	+ Galic
NORTHWEST QUADRANT	1307 WELCH	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO STOPPAGE IN LIN	BUFFALO BAYOU	493-N	TX0096172	11-Jun-99	00.03	10/	1 Gallo
OUTHWEST QUADRANT	7900 WESTHEIMER	ROUTINE STOPPAGE.	BUFFALO BAYOU	490-V	TX0035172	13-Jun-99			Gallo
OUTHWEST QUADITAINT	7300 WESTTIENWER	UNAVOIDABLE RAWSEWAGE DISCHARGE CAUSED	DOITALO DATOO	430-V	170000017	13-3411-33	13.30	330	Jane
IORTHWEST QUADRANT	1307 WELCH	BY A BROKEN MAIN	BUFFALO BAYOU	493-N	TX0096172	18-Jun-99	09:11	458	Gallo
EST QUADITARI		UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO	_ 5	1.00 14		.5 5411-33	55.11	+30	Jan
IORTHWEST QUADRANT	777 BATESWOOD	MAIN STOPPAGE.	BUFFALO BAYOU	489-E	TX0096172	18-Jun-99	12:10	1416	Galle
OUTHEAST QUADRANT	4502 SHARON	ROUTINE STOPPAGE.	BUFFALO BAYOU	494-F	TX0096172	21-Jun-99			1 Gall
2. 42.200		BROKEN SEWER MAIN CAUSING UNAVOIDABLE		1		2330			
IORTHEAST QUADRANT	2417 WAYNE	SEWAGE DISCHARGE.	BUFFALO BAYOU	494-B	TX0096172	22-Jun-99	09:-5	9735	Gallo
J. 42. 200	··· -	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO		1				3.30	- 5(
IORTHWEST QUADRANT	14606 BROADGREEN	STOPPAGE IN MAI	BUFFALO BAYOU	489-E	TX0096172	24-Jun-99	11:10	800	Gallo
		UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO		1		50		1	1
NORTHWEST QUADRANT	3939 SAN FELIPE	STOPPAGE IN MAI	BUFFALO BAYOU	492-N	TX0034924	25-Jun-99	08:33	570	Gallo
		UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO							
ORTHWEST QUADRANT	915 WEST CAVALCADE	STOPPAGE.	BUFFALO BAYOU	453-T	TX0096172	29-Jun-99	11:58	4320	Gallo
		UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO							
OUTHWEST QUADRANT	12000 ASHFORD PARK	STOPPAGE IN MAI	BUFFALO BAYOU	489-S	TX0035017	30-Jun-99	13:50	207	Gallo
	2000 COLLIER AT	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO							
NORTHEAST QUADRANT	MULFORD	STOPPAGE.	BUFFALO BAYOU	494-X	TX0096172	01-Jul-99	10:58	54	4 Gallo
VASTEWATER									
OPERATIONS	2500 KIRBY DRIVE	BROKEN FORCE MAIN AT 2500 KIRBY @ SANSABA.	BUFFALO BAYOU	492-Q	TX0062995	08-Jul-99	15:00	6000	Galle
		UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO							
SOUTHWEST QUADRANT	7531 WESTHEIMER	STOPPAGE.	BUFFALO BAYOU	490-V	TX0035017	09-Jul-99	01:56	2532	Gall
ORTHWEST QUADRANT	10612 HEMPSTEAD	UNAVOIDABLE DISCHARGE DUE TO STOPPAGE.	BUFFALO BAYOU	457-U	TX0096172	09-Jul-99	10:36	1280	Galle
		SEWER MAIN STOPPED-UP CAUSING RAW SEWAGE							
IORTHEAST QUADRANT	4530 WALKER	DISCHARGE.	BUFFALO BAYOU	494-T	TX0096172	14-Jul-99	19:06	4770	Gall
		8" SEWER MAIN STOPPED-UP CAUSING RAW							
ORTHWEST QUADRANT	848 YALE	SEWAGE DISCHARGE.	BUFFALO BAYOU	492-D	TX0096172	16-Jul-99	06:30	420	Galle
	504 SAN JACINTO @								
NORTHWEST QUADRANT	TEXAS	STOPPAGE DUE TO BROKEN SEWER MAIN.	BUFFALO BAYOU	493-L	TX0096172	20-Jul-99			Gall
SOUTHWEST QUADRANT	600 WILCREST	STOPPAGE IN 8" X 11' SEWER MAIN.	BUFFALO BAYOU	489-K	TX0088153	22-Jul-99			Gall
IORTHWEST QUADRANT	700 JEWETT STREET	ROUTINE STOPPAGE.	BUFFALO BAYOU	453-X	TX0096172	26-Jul-99	12:57	1070	Gall
IORTHEAST QUADRANT	6018 CANAL	ROUTINE STOPPAGE.							
		ROOTHAL OTOLITAGE.	BUFFALO BAYOU	494-U	TX0096172	27-Jul-99	10:45		Gallo
	504 SAN JACINTO @ 1117					27-Jul-99		125	
	TEXAS	ROUTINE STOPPAGE IN SERVICE LINE.	BUFFALO BAYOU	493-L	TX0096172	27-Jul-99 04-Aug-99	16:49	125 4600	Galle
	TEXAS 3003 CHARTER OAKS					27-Jul-99	16:49	125 4600	Galle
NORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE.	BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S	TX0096172 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99	16:49 23:04	4600 5080) Gallo
	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY	ROUTINE STOPPAGE IN SERVICE LINE.	BUFFALO BAYOU	493-L	TX0096172	27-Jul-99 04-Aug-99	16:49 23:04	4600 5080) Gallo
NORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE.	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V	TX0096172 TX0096172 TX0062995	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99	16:49 23:04 10:57	125 4600 5080 4240	Galle Galle Galle
NORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE.	BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S	TX0096172 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99	16:49 23:04 10:57	125 4600 5080 4240	Galle Galle Galle
SOUTHWEST QUADRANT SOUTHWEST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V 493-N	TX0096172 TX0096172 TX0062995 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99	16:49 23:04 10:57	125 4600 5080 4240 1640) Gallo) Gallo) Gallo) Gallo
COUTHWEST QUADRANT COUTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW.	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V	TX0096172 TX0096172 TX0062995	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99	16:49 23:04 10:57	125 4600 5080 4240) Gallo) Gallo) Gallo) Gallo
COUTHWEST QUADRANT COUTHWEST QUADRANT CORTHWEST QUADRANT CORTHWEST QUADRANT CORTHWEST QUADRANT CORTHWEST QUADRANT CORTHWEST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q	TX0096172 TX0096172 TX0062995 TX0096172 TX0088153	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99	16:49 23:04 10:57 10:15 16:56	125 4600 5080 4240 1640) Gallo) Gallo) Gallo) Gallo) Gallo
COUTHWEST QUADRANT COUTHWEST QUA	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R	TX0096172 TX0096172 TX0062995 TX0096172 TX0088153 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99	16:49 23:04 10:57 10:15 16:56	125 4600 5080 4240 1640 12660	Gallo Gallo Gallo Gallo Gallo Gallo Gallo
COUTHWEST QUADRANT COUTHWEST QUA	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE.	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q	TX0096172 TX0096172 TX0062995 TX0096172 TX0088153	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99	16:49 23:04 10:57 10:15 16:56	125 4600 5080 4240 1640 12660	Gallo Gallo Gallo Gallo Gallo Gallo Gallo
CONTHEAST QUADRANT COUTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R	TX0096172 TX0096172 TX0062995 TX0096172 TX0088153 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24	125 4600 5080 4240 1640 12660 10000 940) Gall) Gall) Gall) Gall) Gall) Gall
CONTHEAST QUADRANT COUTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHEAST QUADRANT CONTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R	TX0096172 TX0096172 TX0062995 TX0096172 TX0088153 TX0096172 TX0035017	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 26-Aug-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24	125 4600 5080 4240 1640 12660 10000 940	Gall Gall Gall Gall Gall Gall Gall Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT VASTEWATER OPERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE.	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W	TX0096172 TX0096172 TX0062995 TX0096172 TX0088153 TX0096172 TX0035017	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 26-Aug-99 27-Aug-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25	125 4600 5080 4240 1640 12660 10000 940 145 900	Gall Gall Gall Gall Gall Gall Gall Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT VASTEWATER PERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 SYSGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S	TX0096172 TX0096172 TX0062995 TX0096172 TX0088153 TX0096172 TX0035017 TX0096172 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 26-Aug-99 27-Aug-99 27-Aug-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15	125 4600 5080 4240 1640 12660 10000 940 145 9900	(a) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT OUTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPED-UP.	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S	TX0096172 TX0096172 TX0096172 TX0088153 TX0096172 TX0035017 TX0096172 TX0096172 TX0096172 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 28-Aug-99 30-Aug-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51	125 4600 5080 4240 1640 12660 10000 940 145 900 411 2200	(a) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT IASTEWATER PERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT OUTHEAST QUADRANT OUTHEAST QUADRANT OUTHEAST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPED-UP. ROUTINE STOPPED-UP. ROUTINE STOPPED-UP.	BUFFALO BAYOU	493-L 411-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 494-S 493-Y	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 26-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 17:51 14:02	125 4600 5080 4240 1640 12660 10000 940 145 900 41 2200 755) Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT VASTEWATER PERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE.	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 493-Y 454-L	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 26-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 03-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55	125 4600 5080 4240 1640 12660 10000 940 145 900 41 2200 7555 1625) Gall 5 Gall) Gall 5 Gall 5 Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT //ASTEWATER PERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT OUTHEAST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPED-UP. ROUTINE STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 493-Y 493-Y 490-W	TX0096172 TX0096172 TX0096172 TX0096172 TX0088153 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 18-Aug-99 26-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 03-Sep-99 05-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55 17:36	125 4600 5080 4240 1640 12660 10000 940 145 9000 41 2200 755 16252 288	Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT OUTHEAST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPAGE. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE ROUTINE STOPPAGE.	BUFFALO BAYOU	493-L 491-V 493-N 499-Q 494-R 488-R 454-W 494-S 493-Y 454-L 490-W 490-W	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 17:51 14:02 09:55 17:36 09:33	125 4600 5080 4240 1640 12660 10000 940 145 2200 555 1625 288 848	Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT IASTEWATER IPPERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT OUTHEAST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW.	BUFFALO BAYOU	493-L 411-S 491-V 493-N 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 493-Y 454-L 490-W 494-S 494-H 494-S	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 05-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55 17:36 09:33 09:04	125 4600 5080 4240 1640 12660 10000 940 145 900 141 2200 755 1625 888 888	Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT VASTEWATER OPERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2022 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. BROKEN SEVER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPAGE.	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 494-S 493-Y 454-L 490-W 494-H 494-S 494-S 494-S 495-S	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 06-Sep-99 06-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55 17:36 09:33 09:04 10:30	125 4600 5080 4240 1640 12660 10000 940 145 2200 7555 1625 288 848 711 455) Gall
COUTHWEST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT CORTHWEST QUADRANT CORTHWEST QUADRANT CORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2022 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 493-Y 493-Y 493-Y 493-Y 493-H 494-H 494-S 495-S 495-S	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 06-Sep-99 07-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55 17:36 09:33 09:04 10:30 10:30 13:34	125 4600 5080 4240 1640 12660 10000 940 145 2200 755 16252 288 848 71 451	Gall
CONTHEAST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2022 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. BROKEN SEVER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPAGE.	BUFFALO BAYOU	493-L 491-V 493-N 493-N 499-Q 494-R 488-R 494-S 494-S 494-S 494-S 490-W 494-H 494-S 495-S 492-G	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 06-Sep-99 07-Sep-99 08-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 17:51 14:02 09:55 17:36 09:33 09:04 10:30 13:34 18:50	125 4600 5080 4240 1640 12660 10000 940 145 2200 411 258 848 848 71 45 1520 114	Gall (Gall (
CONTHEAST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT 714 NORTH EASTWOOD	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPED-UP. ROUTINE STOPPED-UP. ROUTINE STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPAGE. ROUTINE HAD STOPPAGE.	BUFFALO BAYOU	493-L 491-V 493-N 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 494-S 494-H 494-S 495-S 495-S 495-S 495-S 495-S 495-S 495-S 494-P	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 05-Sep-99 07-Sep-99 08-Sep-99 08-Sep-99 09-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 17:51 14:02 09:55 17:36 09:33 09:04 10:30 13:34 18:50 09:40	125 4600 5080 4240 1640 12660 10000 940 145 900 41 41 45 1520 1520 1144 82	Gall
ORTHEAST QUADRANT OUTHWEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT VASTEWATER OPERATIONS ORTHWEST QUADRANT ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT 7114 NORTH EASTWOOD 7128 AVENUE K	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. BOKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. MAIN LINE HAD STOPPAGE. MAIN LINE STOPPAGE. MAIN LINE STOPPAGE.	BUFFALO BAYOU	493-L 414-S 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 493-Y 454-L 490-W 494-H 494-S 495-S 495-S 495-S 495-S 495-P 494-P	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 05-Sep-99 07-Sep-99 08-Sep-99 09-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:09:05 17:36 09:33 09:04 10:30 13:34 18:50 09:40 11:35	125 4600 5080 4240 1640 12660 10000 940 145 900 41625 288 848 711 45 1520 1114 82	Gall
CONTHEAST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2022 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT 714 NORTH EASTWOOD 7128 AVENUE K 2100 BANCROFT 17700 VAN BUREN 2600 ALBANY @	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPED-UP. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. STOPPAGE IN THE MAIN LINE. SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	493-L 491-V 493-N 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 494-S 494-S 494-H 494-S 495-S	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 07-Sep-99 07-Sep-99 08-Sep-99 10-Sep-99 11-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 17:51 14:02 09:55 09:33 09:04 10:30 13:34 18:50 09:40 11:35 08:25	125 4600 5080 4240 1640 12660 10000 940 145 2200 755 288 848 71 45 1520 1114 82 6110 490	Gall (Gall (
CONTHEAST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHEAST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT CONTHWEST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT 714 NORTH EASTWOOD 7128 AVENUE K 2100 BANCROFT 1700 VAN BUREN 2600 ALBANY @ McGOWAN	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. BROKEN SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. MAIN LINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPAGE. ROUTINE STOPPAGE. MAIN LINE HAD STOPPAGE. MAIN LINE STOPPAGE. SEWER MAIN STOPPED-UP. STOPPAGE IN THE MAIN LINE. SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	493-L 491-V 493-N 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 493-Y 454-L 490-W 494-H 494-S 495-S 495-S 495-S 495-S 495-S 495-S 495-S 495-N 494-P 494-X 491-V 493-N	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 28-Aug-99 30-Aug-99 30-Sep-99 05-Sep-99 05-Sep-99 07-Sep-99 08-Sep-99 10-Sep-99 10-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 17:36 09:33 09:04 10:30 13:34 18:50 09:40 11:35 08:25	125 4600 5080 4240 1640 12660 10000 940 145 900 41 45 1625 288 848 71 45 1520 1144 822 6110 490) Galli (Galli) (Galli
COUTHWEST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT COUTHEAST QUADRANT COUTHWEST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT 714 NORTH EASTWOOD 7128 AVENUE K 2100 BANCROFT 1700 VAN BUREN 2600 ALBANY @ MCGOWAN 4516 CANAL	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8:X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPED-UP. MAIN LINE HAD STOPPAGE. ROUTINE STOPPAGE. BROKEN SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. STOPPAGE IN THE MAIN LINE. SEWER MAIN STOPPED-UP. STOPPAGE IN THE MAIN LINE. SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	493-L 491-V 493-N 491-V 493-N 489-Q 494-R 488-R 454-W 494-S 494-S 494-S 494-S 494-H 494-S 495-S	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 06-Sep-99 07-Sep-99 14-Sep-99 14-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55 17:36 09:33 09:04 10:30 13:34 18:50 09:40 11:35 08:25	125 4600 5080 4240 1640 12660 10000 940 145 900 411 2200 7555 1625 288 848 711 45 6110 490) Galli) Galli) Galli) Galli) Galli) Galli) Galli) Galli 1 Gall
COUTHWEST QUADRANT COUTHWEST QUADRANT COUTHWEST QUADRANT CORTHWEST QUADRANT CORTHWEST QUADRANT CORTHEST QUADRANT CORTHEST QUADRANT CORTHEAST QUADRANT CORTHWEST QUADRANT	TEXAS 3003 CHARTER OAKS 2022 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT 714 NORTH EASTWOOD 7128 AVENUE K 2100 BANCROFT 1700 VAN BUREN 2600 ALBANY @ McGOWAN 4516 CANAL 2117 EVERETT	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TO2BMOV ROUTINE STOPPAGE. 8'X8" SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. ROUTINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	493-L 491-V 493-N 493-N 499-Q 494-R 488-R 494-S 494-S 494-S 494-S 494-S 494-H 494-S 495-S 492-G 494-P 494-X 491-V 493-N 493-P 493-P 494-P 493-C	TX0096172	27-Jul-99 04-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 26-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 07-Sep-99 08-Sep-99 10-Sep-99 14-Sep-99 14-Sep-99 14-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55 17:36 09:33 09:04 10:30 13:34 18:50 09:40 11:13 09:25 09:40 11:13 09:25	125 4600 5080 4240 1640 12660 10000 940 145 9000 41 2200 755 16252 288 848 1520 1144 82 6110 490 2420 6755 355) Galli (Galli (
ORTHEAST QUADRANT	TEXAS 3003 CHARTER OAKS 2222 WEST LOOP FREEWAY 516 HYDE PARK @ HOSPKINS 10719 CANDLEWOOD @ WALNUT BEND 2525 S/SGT MACARIO GARCIA 12555 BRIAFOREST 3100 LEGION/BREWSTER 4330 LEELAND 1200 SYDNEY 2819 BERRY 4222 WEAVER 9800 PAGEWOOD LANE 934 HALO 4426 LEELAND 7505 NAVIGATION 4120 WALKER 6419 WESTCOTT 714 NORTH EASTWOOD 7128 AVENUE K 2100 BANCROFT 1700 VAN BUREN 2600 ALBANY @ MCGOWAN 4516 CANAL	ROUTINE STOPPAGE IN SERVICE LINE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE. ROUTINE STOPPAGE BROKEN SEWER MAIN STOPPED-UP AND CAUSING OVERFLOW. UNCHLORINATED EFFLUENT DISCHARGE INTO BAYOU DUE TOZBMOV ROUTINE STOPPAGE. 8:X8' SEWER MAIN STOPPED-UP DUE TO BREAKAGE. SEWER MAIN STOPPED-UP. MAIN LINE STOPPAGE. STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE. BROKEN SEWER MAIN CAUSING OVERFLOW. SEWER MAIN STOPPED-UP. MAIN LINE HAD STOPPED-UP. MAIN LINE HAD STOPPAGE. ROUTINE STOPPAGE. BROKEN SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED-UP. STOPPAGE IN THE MAIN LINE. SEWER MAIN STOPPED-UP. STOPPAGE IN THE MAIN LINE. SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	493-L 491-V 493-N 493-N 494-R 488-R 454-W 494-S 493-Y 454-L 490-W 494-H 494-S 495-S 495-S 495-S 492-G 494-P 494-V 493-N	TX0096172	27-Jul-99 04-Aug-99 06-Aug-99 10-Aug-99 16-Aug-99 18-Aug-99 27-Aug-99 27-Aug-99 30-Aug-99 30-Aug-99 05-Sep-99 05-Sep-99 06-Sep-99 07-Sep-99 14-Sep-99 14-Sep-99	16:49 23:04 10:57 10:15 16:56 15:45 08:24 11:01 16:25 11:15 17:51 14:02 09:55 10:30 10:30 13:34 18:50 09:40 11:35 08:25 09:26 09:00 16:40	125 4600 5080 4240 1640 12660 10000 940 145 2200 755 288 848 848 71 145 82 6110 4990 2420 6755 255	Gallo Gallo Gallo Gallo Gallo Gallo

Problem	Location	Description	Receiving stream	Key ma		Date	Time	Volume	Unit
NORTHEAST QUADRANT	3713 JENSEN	ROUTINE STOPPAGE.	BUFFALO BAYOU	454-W	TX0096172	17-Sep-99	14:18	680	Gallons
NORTHWEST QUADRANT	3000 HOUSTON	ROUTINE STOPPAGE.	BUFFALO BAYOU	493-C	TX0096172	18-Sep-99		1990	Gallons
NORTHWEST QUADRANT	810 10th W.	ROUTINE STOPPAGE.	BUFFALO BAYOU	492-D	TX0096172	18-Sep-99	12:00	1370	Gallons
		SEWER MAIN STOPPED-UP DUE TO GREASE BUILD-							
SOUTHWEST QUADRANT	2101 CITYWEST BLVD.	UP.	BUFFALO BAYOU	489-U	TX0035017	21-Sep-99			Gallons
NORTHWEST QUADRANT	15885 MEMORIAL	ROUTINE STOPPAGE.	BUFFALO BAYOU	488-E	TX0035017	21-Sep-99			Gallons
NORTHEAST QUADRANT	4604 EAST FREEWAY	SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	494-F	TX0096172	24-Sep-99			Gallons
NORTHEAST QUADRANT	710 SWITZER	MAIN LINE STOPPED-UP.	BUFFALO BAYOU	495-H	TX0096172	24-Sep-99			Gallons
NORTHWEST QUADRANT	812 SABINE	ROUTINE STOPPAGE IN LINE.	BUFFALLO BAYOU	493-K	TX0096172	26-Sep-99	10:51	135	Gallons
	5626 TERIWILLIGER	05.450 44.44 0500000 4.0							
NORTHWEST QUADRANT	DRIVE	SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	491-P	TX0062995	27-Sep-99			Gallons
NORTHEAST QUADRANT	1420 LAWSON	MAIN LINE STOPPED-UP.	BUFFALO BAYOU	494-X	TX0096172	29-Sep-99	11:20	70	Gallons
	1310 SOUTH POST OAK		L	<u>-</u>					L
SOUTHWEST QUADRANT	LANE	CONTRACTOR BROKE SEWER MAIN.	BUFFALO BAYOU	491-Q	TX0062995	02-Oct-99			Gallons
NORTHWEST QUADRANT	7947 KATY FREEWAY	STOPPAGE IN A LATERAL LINE.	BUFFALO BAYOU	491-B	TX0096172	06-Oct-99			Gallons
NORTHWEST QUADRANT NORTHWEST QUADRANT	2110 BROOKTREE DRIVE		BUFFALO BAYOU	452-S	TX0096172	08-Oct-99			Gallons
	2110 BROOKTREE DRIVE		BUFFALO BAYOU	452-J 415-Y	TX0096172 TX0096172	09-Oct-99			Gallons
NORTHEAST QUADRANT	3800 BRILEY	ROUTINE STOPPAGE.	BUFFALO BAYOU	415-1	170090172	10-Oct-99	09.30	200	Gallons
NORTHEAST OLIADBANT	4219 WOODLEIGH @ SIDNEY	SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	494-S	TX0096172	11 Oct 00	00.53	160	Gallons
NORTHEAST QUADRANT				494-3 494-T		11-Oct-99			
NORTHEAST QUADRANT	4445 McKINNEY	SEWER MAIN STOPPED-UP.	BUFFALO BAYOU	494-1	TX0096172	11-Oct-99	10:15	446	Gallons
NORTHWEST OUADBANT	14362 CHADBOURNE DRIVE	POLITINE STORBACE	BLIEFALO BAVOLI	488-H	TV0025017	15 Oct 00	00:40	1170	Callana
NORTHWEST QUADRANT NORTHWEST QUADRANT		ROUTINE STOPPAGE.	BUFFALO BAYOU BUFFALO BAYOU		TX0035017	15-Oct-99			Gallons
NORTHWEST QUADRANT	1950 SPENWICK DRIVE	MAIN LINE OVERFLOW DUE TO STOPPAGE.	BUFFALO BAYOU	451-S	TX0096172	16-Oct-99	18:55	600	Gallons
NORTHWEST QUADRANT	10027 WESTVIEW DRIVE	MAIN LINE STOPPED LID	BUFFALO BAYOU	450-W	TX0096172	16 0~+ 00	14:07	1000	Gallan-
NORTHWEST QUADRANT	10027 WESTVIEW DRIVE.		BUFFALO BAYOU			16-Oct-99			Gallons
SOUTHWEST QUADRANT	117 CAVALCADE 14222 CHADBOURNE	ROUTINE STOPPAGE IN THE MAIN LINE. ROUTINE STOPPAGE IN SEWER MAIN.	BUFFALO BAYOU	453-U 489-E	TX0096172 TX0035017	18-Oct-99			Gallons
NORTHEAST QUADRANT					TX0035017				Gallons
NORTHEAST QUADRANT	1500 MAIN AT BROOK 218 MOODY	MAIN LINE STOPPED UP ROUTINE STOPPAGE.	BUFFALO BAYOU	493-G 453-U	TX0096172	20-Oct-99			
NONTHEAST QUADRANT	600 NOTTINGHAM OAKS	NOUTINE STOFFAGE.	BUFFALO BAYOU	400-U	170090172	22-Oct-99	15.34	121	Gallons
SOUTHWEST QUADRANT	TRAIL	ROUTINE STOPPAGE FROM MAIN LINE	BUFFALO BAYOU	488-G	TX0035017	22-Oct-99	12:10	400	Gallons
SOUTHWEST QUADRANT	1143 KATY FREEWAY	ROUTINE STOPPAGE FROM MAIN LINE ROUTINE STOPPAGE	BUFFALO BAYOU	488-G 489-A	TX0035017 TX0096172	25-Oct-99			Gallons
SOUTHWEST QUADRANT	527 ELECTRA	ROUTINE STOPPAGE	BUFFALO BAYOU	489-A 489-G	TX0096172	26-Oct-99			Gallons
Northeast QUADRANT(713)	2906 Lavender	Routine Stoppage From Main Line.	Buffalo Bayou	494-C	TX0096172	27-Oct-99			Gallons
Northwest Quadrant	317 W. 6th Street	Routine Stoppage in Line.	Buffalo Bayou	494-C	TX0096172	27-Oct-99			Gallons
Southeast Quadrant	321 Baldinger	Routine Stoppage In Line.	Buffalo Bayou	494-z	TX0096172	27-Oct-99			Gallons
SOUTHWEST QUADRANT	1600 POST OAK	ROUTINE STOPPAGE	BUFFALO BAYOU	411-Q	TX0062995	01-Nov-99			Gallons
NORTHEAST QUADRANT	7320 DALLAS	MAIN LINE STOPED UP	BUFFALO BAYOU	494-Z	TX0096172				
SOUTHWEST QUADRANT	1010 ROSINE	MAIN LINE STOPED UP	BUFFALO BAYOU	494-Z 492-M	TX0096172	04-Nov-99			Gallons
SOUTHEAST QUADRANT NORTHWEST QUADRANT	611 SAMPSON	ROUTINE STOPPAGE	BUFFALO BAYOU BUFFALO BAYOU	494-N	TX0096172	05-Nov-99			Gallons
	5711 YALE	ROUTINE STOPPAGE		452-0	TX0096172	05-Nov-99			Gallons
NORTHEAST QUADRANT	13405 EAST FREEWAY	ROUTINE STOPPAGE	BUFFALO BAYOU	497-L	TX0096172	06-Nov-99			Gallons
NORTHEAST QUADRANT	2814 TEDDY	ROUTINE STOPPAGE	BUFFALO BAYOU	493-D	TX0096172	08-Nov-99			Gallons
NORTHWEST QUADRANT	1506 MAUX	ROUTINE STOPPAGE	BUFFALO BAYOU	450-W	TX0096172	09-Nov-99			Gallons
NORTHEAST QUADRANT	1742WOODVINE	BREAK IN MAIN LINE	BUFFALO BAYOU	451-T	TX0096172	09-Nov-99			Gallons
NORTHWEST QUADRANT	9601 KEMPWOOD	ROUTINE STOPPAGE	BUFFALO BAYOU	450-K	TX0063011	10-Nov-99			Gallons
NORTHEAST QUADRANT	1120 TEXAS	ROUTINE STOPPAGE	BUFFALO BAYOU	415-R	TX0096172	10-Nov-99			Gallons
NORTHEAST QUADRANT	317 72nd STREET	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-Z	TX0096172	11-Nov-99			Gallons
NORTHWEST QUADRANT	10023 LARSTON	ROUTINE STOPPAGE	BUFFALO BAYOU	450-W	TX0063002	14-Nov-99	09:55	245	Gallons
	W-34TH/NORTHWEST								
NORTHWEST QUADRANT	FREEWAY #2498	ROUTINE MAIN STOPPAGE	69TH STREET W.T.P	401-Q	TX0057327	16-Nov-99			Gallons
NORTHWEST QUADRANT	5506 RUSSETT	ROUTINE STOPPAGE	BUFFALO BAYOU	491-K	TX0063002	17-Nov-99			Gallons
NORTHEAST QUADRANT	505 BERING	ROUTINE STOPPAGE	BUFFALO BAYOU	491-K	TX0096172	17-Nov-99			Gallons
NORTHEAST QUADRANT	8001 FULTON	MAIN LINE STOPPED UP.	BUFFALO BAYOU	453-K	TX0096172	17-Nov-99	14:10	420	Gallons
N1/A	4500 DEDING DD	HYDRAULIC OVERLOAD DUE TO PELTIER	DUEEN O DAVOU	104 T	TV000000	40.11.00	00.00	500	
N/A	1500 BERING DR.	CONSTRUCTION	BUFFALO BAYOU	491-T	TX0062995	18-Nov-99			Gallons
NORTHEAST QUADRANT	100 GLENDON	MAIN LINE STOPPED UP.	BUFFALO BAYOU	495-W	TX0096172	18-Nov-99			Gallons
NORTHEAST QUADRANT	11817 FLEMING	ROUTINE STOPPAGE	BUFFALO BAYOU	496-F	TX0096172	20-Nov-99			Gallons
NORTHEAST QUADRANT	902 RIDONDO	ROUTINE STOPPAGE	BUFFALO BAYOU	496-H	TX0096172	20-Nov-99			Gallons
NORTHWEST QUADRANT	7209 DANE	ROUTINE STOPPAGE	BUFFALO BAYOU	454-J	TX0096172	21-Nov-99			Gallons
NORTHEAST QUADRANT	1900 YORKTOWN	ROUTINE STOPPAGE	BUFFALO BAYOU	491-Q	TX0096172	22-Nov-99			Gallons
NORTHEAST QUADRANT SOUTHWEST QUADRANT	5210 LIVE OAK	MAIN LINE STOPPED UP	BUFFALO BAYOU	533-B	TX0096172	27-Nov-99			Gallons
SOUTHWEST QUADRANT	13814 BRITOAK	ROUTINE STOPPAGE	BUFFALO BAYOU	489-A	TX0096172	28-Nov-99	10:04	2192	Gallons
NI/Δ	900 N. YORK	BROKEN 24" FORCE MAIN (BELONGS TO PROCESS OPERATIONS)	BUFFALO BAYOU	494-P	TY0006170	20 Nov 00	15:40	1200	Gallan
N/A NORTHEAST OLIADRANT		,	BUFFALO BAYOU	494-P 454-E	TX0096172 TX0096172	29-Nov-99			Gallons
NORTHEAST QUADRANT N/A	8811 MANUS 900 N. YORK	ROUTINE STOPPAGE FORCE MAIN TO LS BROKEN	BUFFALO BAYOU	454-E 494-P	TX0096172	29-Nov-99 30-Nov-99			Gallons
NORTH EAST QUADRANT	1554 ELLIOTT	ROUTNE STOPPAGE	BUFFALO BAYOU	494-P	TX0096172	01-Dec-99			Gallons
	4707 GULF FREEWAY	MAIN LINE STOPPED UP		494-X 494-W					
NORTHEAST QUADRANT WEST DISTRICT		I .	BUFFALO BAYOU BUFFALO BAYOU		TX0096172	01-Dec-99			Gallons
WEST DISTRICT	1144 KATY FRWY 855 GESSNER	ROUTINE STOPPAGE ROUTINE STOPPAGE	BUFFALO BAYOU	489-A 490-E	TX0063002 TX0063002	02-Dec-99			Gallons
		I .	BUFFALO BAYOU						Gallons
SOUTHWEST QUADRANT	971 KIRBY DR.	ROUTINE STOPPAGE		492-L	TX0096172	02-Dec-99			
NORTHEAST QUADRANT	1200 SIDNEY	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-S	TX0096172	03-Dec-99			Gallons
N/A	698 LOCKWOOD	AIR CELL FAILURE, WET WELL OVERFLOW	BUFFALO BAYOU	494-Q	TX0096172	03-Dec-99			Gallons
NORTHEAST QUADRANT	5112 LELIA ST.	MAIN LINE STOPPAGE	BUFFALO BAYOU	494-C	TX0096172	04-Dec-99			Gallons
NORTHWEST QUADRANT	4010 ROTMAN	ROUTINE LINE STOPPAGE	BUFFALO BAYOU	494-P	TX0096172	04-Dec-99			Gallons
NORTHWEST QUADRANT	730 ANTOINE	ROUTINE STOPPAGE	BUFFALO BAYOU	491-B	TX0063011	06-Dec-99			Gallons
SOUTHWEST QUADRANT	999 S. POST OAK LANE.	ROUTINE STOPPAGE	BUFFALO BAYOU	491-Z	TX0096172	06-Dec-99			Gallons
NORTHWEST QUADRANT.	5049 JEFFERSON	ROUTINE STOPPAGE	BUFFALO BAYOU	494-W	TX0096172	08-Dec-99			Gallons
SOUTHWEST QUADRANT	777 N. POST OAK RD.	ROUTINE STOPPAGE	BUFFALO BAYOU	489-L	TX0063002	09-Dec-99			Gallons
NORTHWEST QUADRANT	1 BRIAR TRAIL	ROUTINE LINE STOPPAGE	BUFFALO BAYOU	491-G	TX0063011	10-Dec-99			Gallons
NORTHEAST QUADRANT	9928 EDGEWORTH	MAIN LINE STOPPAGE	BUFFALO BAYOU	454-A	TX0063053	10-Dec-99			Gallon
SOUTHEAST QUADRANT	3335 WAYSIDE	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-Z	TX0096172	10-Dec-99			Gallon
NORTH EAST T.P.	3260 TRUXILLO	ROUTINE STOPPAGE	BUFFAL0 BAYOU	493-Y	TX0096172	13-Dec-99			Gallons
NORTHWEST QUADRANT	5095 FIELDWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-Q	TX0096172	13-Dec-99			Gallons
NORTHEAST QUADRANT	1200 CAMPBELL	MIAN LINE STOPPED UP	BUFFALO BAYOU	493-D	TX0096172	14-Dec-99			Gallons
NORTHEAST QUADRANT.	103 EASTGATE	ROUTINE STOPPAGE	BUFFALO BAYOU	495-W	TX0096172	14-Dec-99			Gallons
NORTHWEST QUADRANT	1833 JOHANNA	ROUTINE LINE STOPPAGE	BUFFALO BAYOU	451-T	TX0063061	15-Dec-99			Gallons
SOUTHEAST QUADRANT	7319 DALLAS	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-Z	TX0096172	15-Dec-99	11:00	118	Gallons
300 ITIEAST QUADRAINT	7010 DALLETTO	113 till 2 cil ci 2 ci 3 ci							

Dashlas	Itic-		DL Project-Contract#					
Problem	Location	Description MAIN LINE STORDAGE	Receiving stream	Key map		Date Time	Volume	Unit
NORTHWEST QUADRANT	10526 ROCK CREST	MAIN LINE STOPPAGE	BUFFALO BAYOU	450-E	TX0063002	17-Dec-99 10:39		Gallons
NORTHEAST QUADRANT	7401 KATY FREEWAY	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-C	TX0096172	17-Dec-99 08:27		Gallons
SOUTHEAST QUADRANT	4803 MCKINNY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	17-Dec-99 09:55		Gallons
NORTHEAST QUADRANT	6902 PALESTINE	SERVICE LINE STOPPAGE	BUFFALO BAYOU	495-E	TX0096172	17-Dec-99 09:41		Gallons Gallons
SOUTHEAST QUADRANT	100 TELEPHONE RD.	MAIN LINE STOPPED UP	BUFFALO BAYOU	495-S 494-U	TX0096172	17-Dec-99 11:45		
SOUTHEAST QUADRANT SOUTHEAST QUADRANT	6009 BRANDY 6013 BRANDY	ROUTINE STOPPAGE ROUTINE STOPPAGE	BUFFALO BAYOU BUFFALO BAYOU	494-U	TX0096172 TX0096172	17-Dec-99 16:47 17-Dec-99 16:49		Gallons Gallons
SOUTHEAST QUADRANT	103 BEDFORTH	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-0 495-W	TX0096172	17-Dec-99 10:49		Gallons
SOUTHWEST QUADRANT	1836 AUGUSTA DRIVE	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-P	TX0096172	18-Dec-99 10:00		Gallons
NORTHEAST QUADRANT	3907 RUSK	ROUTINE STOPPAGE	BUFFALO BAYOU	494-S	TX0096172	18-Dec-99 17:25		Gallons
SOUTHWEST QUADRANT	2100 YUPON	ROUTINE STOPPAGE	BUFFALO BAYOU	494-3 492-R	TX0096172	19-Dec-99 09:42		Gallons
SOUTHEAST QUADRANT	904 W. SCOTT	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-G	TX0096172	19-Dec-99 12:46		Gallons
300THEAST QUADRAINT	904 W. 3COTT	INIAIN LINE STOFFED OF	BOFFALO BATOO	492-0	170090172	19-Dec-99 12.40	310	Gallolis
NORTHWEST	11902 KEMPHOLLOW LN.	MAIN LINE STOPPED LIP	BUFFALO BAYOU	449-L	TX0035017	20-Dec-99 14:30	2700	Gallons
NORTHEAST QUADRANT.	2928 BRACKENRIDGE	ROUTINE STOPPAGE	BUFFALO BAYOU	494-A	TX0096172	21-Dec-99 15:43		Gallons
SOUTHWEST QUADRANT	5200 WOOD HEAD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0096172	21-Dec-99 17:08		Gallons
NORTHWEST QUADRANT	6014 INWOOD	ROUTINE STOPPAGE	BUFFALO BAYOU	491-N	TX00630172	22-Dec-99 08:24		Gallons
NORTHEAST QUADRANT	12601 ADELIA	ROUTINE STOPPAGE	BUFFALO BAYOU	494-A	TX0096172	22-Dec-99 15:23		Gallons
	1200171322171	LOSS OF INSTRUMENT AIR PRESSURE TO WASTING	20117120 271100	10171	1710000112	22 200 00 10:20	112.0	Ou.ioi.ic
N/A	2525 MACARIO GARCIA	STATION	BUFFALO BAYOU	494-R	TX0096172	22-Dec-99 21:30	350	Gallons
NORTHWEST QUADRANT	9628 HAMMERLY	MAIN LINE STOPPAGE	BUFFALO BAYOU	450-P	TX0063002	23-Dec-99 10:36		Gallons
SOUTHEAST QUADRANT	2900 WICHITA	ROUTINE STOPPAGE	BUFFALO BAYOU	533-C	TX0096172	23-Dec-99 17:33		Gallons
NORTHWEST QUADRANT	1000 VOSS	SERVICE LINE STOPPED UP	BUFFALO BAYOU	490-M	TX0096172	24-Dec-99 11:16		Gallons
SOUTHEAST QUADRANT	7133 RUSK ST.	HOUSE LINE STOPPED UP	BUFFALO BAYOU	494-W	TX0096172	24-Dec-99 11:10 24-Dec-99 15:04		Gallons
NORTHEAST QUADRANT	4805 LOCKWOOD	ROUTINE STOPPAGE	BUFFALO BAYOU	454-U	TX0096172	25-Dec-99 17:57		Gallons
NORTHEAST QUAD	2620 N. MAIN	STOPPED UP SEWER LINE	BUFFALO BAYOU	493-H	TX0096172	26-Dec-99 17:15		Gallons
NORTHEAST QUADRANT.	17 GREENWOOD	ROUTINE STOPPAGE	BUFFALO BAYOU	494-U	TX0096172	26-Dec-99 20:33		Gallons
NORTHWEST QUADRANT.	5050 YALE	ROUTINE STOPPAGE	BUFFALO BAYOU	452-H	TX0096172	28-Dec-99 15:55		Gallons
NORTHEAST QUADRANT.	3302 BRILL	ROUTINE STOPPAGE	BUFFALO BAYOU	454-W	TX0096172	28-Dec-99 14:00		Gallons
2. 22.0.0	5100 1/2 BAYOU TIMBER	EXCURSION CAUSED BY STOPPAGE IN COLLECTION					55	
SOUTHWEST QUADRANT	LANE	SYSTEM	BUFFALO BAYOU	491-G	TX0062995	29-Dec-99 09:00	5000	Gallons
SOUTHEAST QUADRANT	5022 LINDSAY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	29-Dec-99 10:34		Gallons
SOUTHWEST QUADRANT	13600 PERTHSHIRE	MAN HOLE OVERFLOWING	BUFFALO BAYOU	489-F	TX0096172	30-Dec-99 11:22		Gallons
NORTHWEST QUADRANT	10102 GREEN TREE	ROUTINE STOPPAGE	BUFFALO BAYOU	489-M	TX0063002	03-Jan-00 17:10		Gallons
NORTHWEST QUADRANT	11417 NORMEADOW	ROUTINE STOPPAGE	BUFFALO BAYOU	413-Y	TX0096172	03-Jan-00 12:58	60	Gallons
NORTHEAST QUADRANT	4206 WIPPRECHT	ROUTINE STOPPAGE	BUFFALO BAYOU	454-Y	TX0096172	03-Jan-00 12:06	153	Gallons
N.E.QUADRANT	1522 LAWSON	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	05-Jan-00 12:35		Gallons
NORTHEAST QUADRANT.	6013 BRADY	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-T	TX0096172	05-Jan-00 13:45		Gallons
SOUTHWEST QUADRANT	2800 DAIRY ASHFORD	SERVICE LINE STOPPED UP	BUFFALO BAYOU	488-V	TX0058068	06-Jan-00 20:00		Gallons
SOUTHEAST QUADRANT	4719 CAPITOL	ROUTINE STOPPAGE	BUFFALO BAYOU	494-T	TX0096172	07-Jan-00 11:49		Gallons
N.E.QUAD	302 75TH STREET	ROUTINE STOPPAGE	BUFFALO	495-W	TX0035106	08-Jan-00 17:33		Gallons
NORTHEAST QUADRANT	3909 LEE	ROUTINE STOPPAGE	BUFFALO BAYOU	494-B	TX0096172	10-Jan-00 15:59		Gallons
SOUTHWEST QUADRANT	1018 FAIRVIEW	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-N	TX0096172	10-Jan-00 12:30		Gallons
SOUTHWEST QUADRANT	1018 FAIRVIEW	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-N	TX0096172	10-Jan-00 12:30		Gallons
SOUTHWEST QUADRANT	900 RIVER VIEW WAY	ROUTINE STOPPAGE	BUFFALO BAYOU	491-J	TX0096172	11-Jan-00 09:40		Gallons
SOUTHWEST QUADRANT	2300 WILCREST	ROUTINE STOPPAGE	BUFFALO BAYOU	489-U	TX0065307	13-Jan-00 10:45		Gallons
NORTHEAST	5514 COLLINGSWORTH	ROUTINE STOPPAGE	BUFFALO BAYOU	455-Y	TX0096172	13-Jan-00 19:31		Gallons
SOUTHWEST Q	2306 HWY. 6 S.	MAIN LINE STOPPAGE	BUFFALO BAYOU	488-N	TX0035017	14-Jan-00 10:55		Gallons
SOUTHEAST QUADRANT.	616 N.MILBY	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-P	TX0096172	14-Jan-00 14:00		Gallons
NORTHWEST QUADRANT	509 WHITEWING LN.	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-J	TX0063002	17-Jan-00 11:55		Gallons
SOUTHEAST QUADRANT	227 EDGEWOOD	STOPPAGE IN MAIN LINE	BUFALLO BAYOU	494-T	TX0005002	18-Jan-00 07:36		Gallons
NORTHEAST QUADRANT	3603 LEE	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-B	TX0096172	18-Jan-00 11:15		Gallons
NORTHEAST QUADRANT	125 SIDNEY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494P	TX0096172	19-Jan-00 08:54		Gallons
NORTHEAST QUADRANT	701 SOLO	ROUTINE STOPPAGE	BUFFALO BAYOU	494-C	TX0096172	19-Jan-00 18:23		Gallons
SOUTHWEST QUADRANT	2010 FULHAM	ROUTINE STOPPAGE	BUFFALO BAYOU	494-C 490-V	TX0096172	20-Jan-00 15:20		Gallons
					TX0096172			
SOUTHEAST QUADRANT	4322 LEELAND 1800 WOODHEAD @	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-S	1X0096172	20-Jan-00 14:32	47	Gallons
NORTHEAST QUADRANT	RICHMOND	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0096172	23-Jan-00 09:40	201	Gallons
		SERVICE LINE STOPPED						
NORTH WEST QUADRANT SOUTH EAST QUADRANT	2928 MICHAUX 250 VICTORIA DR.	ROUTINE STOPPED	BUFFALO BAYOU BUFFALO BAYOU	493 B 453-E	TX0096172 TX0096172	24-Jan-00 9:53 24-Jan-00 9:58		Gallons Gallons
SOUTH EAST QUADRANT	7457 RUSK	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-E 495-W	TX0096172 TX0062201	24-Jan-00 9:58 26-Jan-00 10:05		Gallons Gallons
NORTHEAST QUADRANT	511 71ST STREET	ROUTINE STOPPED UP	BUFFALO BAYOU	495-W	TX0062201 TX0096172	26-Jan-00 10:05 26-Jan-00 17:35		Gallons
SOUTHEAST QUADRANT	615 N. MILBY	MAIN LINE STOPPED UP	BUFFALO BAYOU	495-S 494-P	TX0096172	26-Jan-00 17:35 29-Jan-00 08:18		Gallons
SOUTHWEST QUADRANT	1911 BERING DR.	MAIN LINE STOPPED OP	BUFFALO BAYOU	494-P 491-P	TX0096172	30-Jan-00 11:03		Gallons
COOTHWEST QUADRAINT	ISTI DENING DR.	INVESTIGATION OF AGE	DOLLATO DATOU	7017	170030172	30-3a11-00 11.03	1440	Janons
NORTH WEST QUADRANT	1500 COHN	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-C	TX00969172	31-Jan-00 11:03	1680	Gallons
SOUTHEAST QUADRAINT	1556 ELLIOT	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-C 494-X	TX105058	31-Jan-00 12:35		Gallons
NORTHEAST QUADRANT	6420 FRISCO	STOPPAGE IN MAIN LINE	BUFFALO BAYOU	453-R	TX0096172	01-Feb-00 14:14		Gallons
SOUTHWEST QUADRANT	2121 PELHAM	SEWAGE OVERFLOW DUE TO STOPPAGE IN LINE.	BUFFALO BAYOU	492-Q	TX0062995	03-Feb-00 09:25		Gallons
SOUTHWEST QUADRANT	1300 WILCREST	SEWER BACK-UP INTO STORM SEWER	BUFFALO BAYOU	492-Q 489-P	TX0082995	03-Feb-00 10:00		Gallons
NORTHWEST QUADRANT	20 NORTHWEST OAK	BROKEN MAIN LINE BY PUMP ON SITE	BUFFALO BAYOU	451-P	TX0096172	03-Feb-00 10.00 03-Feb-00 8:05		Gallons
NORTHWEST QUADRANT	757 N. ELDRIDGE	ROUTINE STOPPAGE	BUFFALO BAYOU	488-C	TX0096172	04-Feb-00 14:20		Gallons
NORTHWEST QUADRANT	811 W. GRAY	GEASE IN MAIN LINE	BUFFALO BAYOU	493-P	TX0063032	05-Feb-00 16:20		Gallons
NORTHEAST QUADRANT	909 WACO	MAIN LINE STOPPAGE	BUFFALO BAYOU	493-P 494-F	TX0096172	05-Feb-00 19:08		Gallons
SOUTHEAST QUADRANT	1454 MUNGER	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-L	TX0096172	06-Feb-00 9:13		Gallons
	11414 BRIAR ROSE	ROUTINE STOPPED OF	BUFFALO BAYOU	494-L 489-P	TX0096172	07-Feb-00 10;25		Gallons
	2135 SHADOWDALE	ROUTINE STOPPAGE, GREASE	BUFFALO BAYOU	449-R	TX0063002	07-Feb-00 10,23		Gallons
SOUTHWEST QUADRANT		· ·	BUFFALO BAYOU	489-P	TX0063002	08-Feb-00 9:20		Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT		MAIN LINE STOPPED UP	DOLL VIEW DATE	492-L		08-Feb-00 13:25		Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT	1300 WILCREST	MAIN LINE STOPPED UP	RUFFALO RAVOLI					
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT	1300 WILCREST 2187 TROON RD.	STOPPAGE CAUSED BY BROKEN SEWER LINE	BUFFALO BAYOU		TX0096172			
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT	1300 WILCREST	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP	BUFFALO BAYOU BUFFALP BAYOU	494-P	TX0096172	08-Feb-00 15:25 08-Feb-00 16:50		
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUAD	1300 WILCREST 2187 TROON RD. 615 N. MILBY	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING	BUFFALP BAYOU	494-P	TX0096172	08-Feb-00 16:50	53	Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUAD SOUTH WEST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION	BUFFALP BAYOU BUFFALO BAYOU	494-P 492-L	TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9;05	53 432	Gallons Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUAD SOUTH WEST QUADRANT NORTH EAST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY 1330AUGUSTA 6134 AIRLINE	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION HOUSE LANE STOPPED UP , CAUSED BY GREASE	BUFFALO BAYOU BUFFALO BAYOU	494-P 492-L 453-B	TX0096172 TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9;05 09-Feb-00 14:52	53 432 70	Gallons Gallons Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUAD SOUTH WEST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY 1330AUGUSTA 6134 AIRLINE 4401 LOVE JOY	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION HOUSE LANE STOPPED UP, CAUSED BY GREASE STOPPAGE IN A 8X8 MAIN LINE	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-P 492-L 453-B 494-P	TX0096172 TX0096172 TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9;05 09-Feb-00 14:52 09-Feb-00 21;00	432 70 45.5	Gallons Gallons Gallons Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUAD SOUTH WEST QUADRANT NORTH EAST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY 1330AUGUSTA 6134 AIRLINE 4401 LOVE JOY 5506 RUSSETT	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION HOUSE LANE STOPPED UP , CAUSED BY GREASE	BUFFALO BAYOU BUFFALO BAYOU	494-P 492-L 453-B	TX0096172 TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9;05 09-Feb-00 14:52	432 70 45.5	Gallons Gallons Gallons Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT SOUTH WEST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY 1330AUGUSTA 6134 AIRLINE 4401 LOVE JOY 5506 RUSSETT 612 MCINTOSH	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION HOUSE LANE STOPPED UP, CAUSED BY GREASE STOPPAGE IN A 8X8 MAIN LINE MAIN LINE OVERFLOWING	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-P 492-L 453-B 494-P 491-K	TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9:05 09-Feb-00 14:52 09-Feb-00 21:00 09-Feb-00 8:18	432 70 45.5 396	Gallons Gallons Gallons Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUAD SOUTH WEST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY 1330AUGUSTA 6134 AIRLINE 4401 LOVE JOY 5506 RUSSETT	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION HOUSE LANE STOPPED UP, CAUSED BY GREASE STOPPAGE IN A 8X8 MAIN LINE MAIN LINE OVERFLOWING ROUTINE STOPPAGE, GREASE IN LINE	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-P 492-L 453-B 494-P	TX0096172 TX0096172 TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9;05 09-Feb-00 14:52 09-Feb-00 21;00	432 70 45.5 396	Gallons Gallons Gallons Gallons Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUADRANT NORTHEAST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT SOUTH WEST QUADRANT SOUTH WEST QUADRANT NORTH EAST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY 1330AUGUSTA 6134 AIRLINE 4401 LOVE JOY 5506 RUSSETT 612 MCINTOSH WO#10078858	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION HOUSE LANE STOPPED UP, CAUSED BY GREASE STOPPAGE IN A 8X8 MAIN LINE MAIN LINE OVERFLOWING ROUTINE STOPPAGE, GREASE IN LINE MAIN LINE STOPED UP, CAUSEING CLEAN OUT TO	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-P 492-L 453-B 494-P 491-K 493-C	TX0096172 TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9;05 09-Feb-00 14:52 09-Feb-00 21;00 09-Feb-00 8:18 10-Feb-00 17;55	53 432 70 45.5 396 27.5	Gallons Gallons Gallons Gallons Gallons
SOUTHWEST QUADRANT NORTHWEST QUADRANT NORTH WEST QUADRANT SOUTH EAST QUADRANT NORTHEAST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT NORTH EAST QUADRANT SOUTH WEST QUADRANT	1300 WILCREST 2187 TROON RD. 615 N. MILBY 1330AUGUSTA 6134 AIRLINE 4401 LOVE JOY 5506 RUSSETT 612 MCINTOSH	STOPPAGE CAUSED BY BROKEN SEWER LINE STOPPAGE IN MAIN LINE DUE TO GREASE BILL- UP SEWER LEAKING (OVERFLOW), CAUSING EXCURSION HOUSE LANE STOPPED UP, CAUSED BY GREASE STOPPAGE IN A 8X8 MAIN LINE MAIN LINE OVERFLOWING ROUTINE STOPPAGE, GREASE IN LINE	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-P 492-L 453-B 494-P 491-K	TX0096172 TX0096172 TX0096172 TX0096172 TX0096172	08-Feb-00 16:50 09-Feb-00 9;05 09-Feb-00 14:52 09-Feb-00 21;00 09-Feb-00 8:18 10-Feb-00 17;55	53 432 70 45.5 396 27.5	Gallons Gallons Gallons Gallons Gallons

Problem	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
NORTHEAST QUAD	4111 VALOR	ROUTINE STOPPAGE	BUFFALO BAYOU	454-F	TX0096172	12-Feb-00			Gallons
NORTHEAST QUADRANT	1706 SILVERDALE	GREASE IN MAIN LINE	BUFFALO BAYOU	495-K	TX0096172	12-Feb-00			Gallons
NORTH EAST QUADRANT	7319 DALLAS AVE	MAIN LINE STOPPAGE	BUFFALO BAYOU	494-Z	TX00961723	14-Feb-00	18;10	123	Gallons
NORTH EAST QUADRANT	FULTON & HOGAN	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-H	TX0096172	16-Feb-00	14:10	80	Gallons
NORTHEAST QUADRANT	109 MARSDEN	GREASE AND SAND IN MAIN LINE	BUFFALO BAYOU	494-U	TX0096172	17-Feb-00	16:49	12.5	Gallons
		MAIN LINE HAD STOPPAGE DUE TO SAND AND							
NORTH EAST QUADRANT	109 MARSDEN	GREASE IN LINE	BUFFALO BAYOU	494-U	TX00961723	17-Feb-00	16:49	12.5	Gallons
NORTHEAST QUADRANT	3221 QUITMAN	COMMUNITY LINE STOPPED UP	BUFFLAO BAYOU	494-A	TX0096172	19-Feb-00	09:05	61	Gallons
NORTH WEST QUADRANT	2118 WASHINGTON	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-L	TX0096172	20-Feb-00	7:30	1340	Gallons
NORTHEAST QUADRANT	2500 CAMPBELL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-A	TX0096172	20-Feb-00	08:58	36.5	Gallons
NORTHEAST QUADRANT	909 WACO	6" CLEAN OUT STOPPED UP	BUFFALO BAYOU	494 F	TX0096172	20-Feb-00	10:06	151	Gallons
NORTHEAST QUADRANT	3310 NOBLES	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	494-A	TX0096172	20-Feb-00	9:10	1050	Gallons
SOUTH WEST QUADRANT	2633 WINROCK	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-S	TX0096172	21-Feb-00	18:25		Gallons
SOUTH WEST QUADRANT	902 WESTHIEMER	SERVICE LINE STOPPED UP CITY MAIN CLEAR	BUFFALO BAYOU	493-S	TX0096172	21-Feb-00	16:27	2118	Gallons
		MAIN LINE STOPPED UP REPAIR PENDING, CREW IN							
SOUTH EAST QUADRANT	5315 HARRISBURG	ROUTE	BUFFALO BAYOU	494-U	TX0096172	21-Feb-00			Gallon
NORTH WEST QUADRANT	5542 MARGARITA	MAIN LINE STOPPED UP ROUTINE	BUFFALO BAYOU	494-G	TX0096172	22-Feb-00			Gallons
NORTH EAST QUADRANT	111 SHOTWELL	MAIN LINE STOPPED UP/ROUTINE	BUFFALO BAYOU	494-C	TX0096172	22-Feb-00			Gallons
SOUTHWEST QUADRANT	3809 MAIN	ROUTINE STOPPAGE, GREASE AND SAND	BUFFALO BAYOU	493-T	TX0096172	22-Feb-00			Gallon
NORTHWEST QUADRANT	1514 WHITE OAK DRIVE	ROUTINE STOPPAGE	BUFFALO BAYOU	493-B	TX0096172	23-Feb-00			Gallon
NORTHEAST QUADRANT	200 DENNIS	ROUTINE STOPPAGE	BUFFALO BAYOU	493-T	TX0096172	23-Feb-00			Gallons
SOUTH WEST QUADRANT	2121 PELHAM	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-Q	TX0096172	24-Feb-00			Gallon
NORTHEAST QUADRANT	920 ALTIC	SEWER MAIN STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	24-Feb-00			Gallons
SOUTH EAST QUADRANT	222S.66th STREET	MAIN LINE STOPPED UP/ROUTINE	BUFFALO BAYOU	494-R	TX0096172	24-Feb-00			Gallons
NORTHEAST QUADRANT	11952 HEMPSTEAD	C-2 DYE TEST GOING TO BAYOU	BUFFALO BAYOU	451-I	TX0096172	26-Feb-00			Gallons
NORTHWEST QUADRANT	4702 LIDO	MAIN LINE STOPPAGE-LINE BROKEN	BUFFALO BAYOU	451-H	TX0096172	26-Feb-00			Gallon
NORTHWEST QUADRANT	7108 AVENUE J	ROUTINE STOPPAGE	BUFFALO BAYOU	494-V	TX0096172	27-Feb-00			Gallons
NORTH EAST QUADRANT	8433 DARLINGTON	MAIN LINE STOPPED UP	BUFFALO BAYOU	455-L	TX0096172	28-Feb-00	10:11	55	Gallon
	Lead Burgin	ROUTINE STOPPAGE CAUSED BY GREASE AND							
SOUTHEAST QUADRANT	4731 RUSK	SAND	BUFFALO BAYOU	494-T	TX0096172	28-Feb-00	11:27	104	Gallons
		SEWER MAIN STPOOAGE SERV LINE WILL NEED TO							
SOUTHEAST QUADRANT	927 NASHUA	BE CHLORINAT	BUFFALO BAYOU	492-C	TX0096172	28-Feb-00			Gallons
NORTHEAST QUADRANT	4401 LOVEJOY	STOPPAGE IN LINE	BUFFALO BAYOU	494-P	TX0096172	28-Feb-00			Gallon
NORTHEAST QUADS	913 TERMINAL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-V	TX0096172	29-Feb-00			Gallons
NORTHWEST QUADS	4020 MEADOW LAKE	SEWER MAIN STOPPED UP	BUFFALO BAYOU	492-N	TX0096172	29-Feb-00	09:30	840	Gallons
	714 MEMORIAL MEWS		L	l					L
SOUTHEAST QUADRANT	ST.	SEWER MAIN STOPPED UP	BUFFALO BAYOU	575-H	TX0035017	02-Mar-00			Gallons
NORTH EAST QUADRANT	909 WACO	CITY MAIN HAS STOPPAGE	BUFFALO BAYOU	494-H	TX0096172	03-Mar-00			Gallon
SOUTH WEST QUADRANT	2300 1/2 HUTTON	ROUTINE STOPPAGE	BUFFALO BAYOU	494-B	TX0096172	03-Mar-00			Gallons
SOUTHWEST QUADRANT.	2815 ROCK ARBOR	MAIN LINE STOPPED UP.	BUFFALO BAYOU	490-T	TX0063002	04-Mar-00			Gallons
SOUTHEAST QUADRANT	706 MORRIS	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	04-Mar-00	10:00		Gallons
SOUTHWEST QUADRANT	2826 WESTERLAND	MAIN LINE STOPPED UP	BUFFALO BAYOU	490-T	TX0063002	05-Mar-00			Gallons
NORTHEAST QUADRANT.	1405 COPELAND	STOPPAGE IN MAIN LINE.	BUFFALO BAYOU	494-F	TX0096172	06-Mar-00	15:51	69	Gallons
		MAIN LINE STOPPED UP DUE TO HEAVY GREASE IN							
NORTHWEST QUADRANT	3125 CRESTDALE	LINE	BUFFALO BAYOU	450-K	TX0063002	07-Mar-00			Gallons
NORTHWEST QUADRANT	9001 KEMPWOOD	MAIN LINE STOPPED UP DUE TO GREASE IN LINE	BUFFALO BAYOU	450-Q	TX0063002	07-Mar-00	10:02	1500	Gallons
SOUTH EAST QUADRANT	1100 CAROLINE/ LAMAR	SEWER MAIN STOPPAGE	BUFFALO BAYOU	493-Q	TX0096172	07-Mar-00	10:12	4125	Gallons
SOUTH EAST QUADRANT	400 PACIFIC	SEWEWR MAIN STOPPED UP	BUFFALO BAYOU	493-N	TX0096172	07-Mar-00	10;12	786	Gallon
NORTHWEST QUADRANT.	6024 SOUTHRIDGE	MAIN LINE STOPPED UP.	BUFFALO BAYOU	534-P	TX0096172	07-Mar-00	10:22	232	Gallons
NORTHWEST QUADRANT	202 TRAVIS	STOPPAGE IN LINE, FLOWING INTO STORM DRAIN	BUFFALO BAYOU	493-L	TX0096172	07-Mar-00	13:58	610	Gallons
SOUTHWEST QUADRANT	239 EMERSON	CITY MAIN STOPPED UP	BUFFALO BAYOU	493-S	TX0096172	07-Mar-00	16:15	5175	Gallons
NORTH WEST QUADRANT	2001 LOVERNE	MAIN LINE STOPPAGE CAUSED BY HEAVY GREASE	BUFFALO BAYOU	450-V	TX0063002	09-Mar-00	10:29	984	Gallons
SOUTH EAST QUADRANT	5107 STONEWALL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	09-Mar-00	20:00	290	Gallons
SOUTH EAST QUADRANT	4052 JEWEL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-B	TX0096172	09-Mar-00	22:03	468	Gallons
		ROUTINE STOPPAGE CAUSED BY GREASE AND							
SOUTH EAST QUADRANT	2810 BERRY	SAND	BUFFALO BAYOU	493-Y	TX0096172	09-Mar-00		1620	Gallons
SOUTHEAST QUADRANT	1902 AUGUSTA DR.	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-P	TX0096172	11-Mar-00	12:12	288	Gallons
NORTHWEST QUAD	8538-8539 ALCOTT	ROUTINE STOPPAGE, MAIN LINE	BUFFALO BAYOU	450-R	TX0096172	14-Mar-00	10:27	680	Gallons
SOUTHEAST	422 W. TRAY	SERVICE LINE STOPPED UP	BUFFALO BAYOU	452-D	TX0096172	14-Mar-00			Gallon
SOUTHEAST QUAD	904 BRISCO	CUSTOMER NOT TIED INTO SYSTEM.	BUFFALO BAYOU	453-R	TX0096172	15-Mar-00	08:18	381	Gallon
	L	CUSTOMER NOT TIED INTO SYSTEM WHEN THEY	L		L T				
NORTHEAST	904 FRISCO	FLUSH INTO DITC	BUFFALO BAYOU	453-R	TX0096172	15-Mar-00			Gallon
SOUTHWEST QUADS	2923 INWOOD	ROUTINE STOPPAGE	BUFFALO BAYOU	492-Q	TX0096172	15-Mar-00			Gallons
NORTHEAST QUAD	1201 NOBLE	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-D	TX0096172	15-Mar-00			Gallon
NORTHEAST QUAD	1201 NOBLE	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-D	TX0096172	15-Mar-00			Gallon
SOUTHEAST QUAD	905 OAKHURST	MAIN LINE STOP UP AT CONNECTION	BUFFALO BAYOU	494-S	TX0096172	16-Mar-00			Gallons
SOUTHEAST	9310 LONG POINT	SEWER MAIN STOPPED UP	BUFFALO BAYOU	450-Y	TX0096172	16-Mar-00			Gallon
SOUTHEAST QUADRANT.	205 SUPER	ROUTINE STOPPAGE	BUFFALO BAYOU	494-T	TX0096172	17-Mar-00			Gallon
SOUTHEAST QUADRANT	5513 NEWPORT	MAIN LINE STOPPED-UP	BUFFALO BAYOU	534-C	TX0096172	18-Mar-00			Gallon
SOUTHEAST QUAD	5107 STONEWALL	ROUTINE STOPPAGE	BUFFALO BAYOU	494-T	TX0096172	18-Mar-00	12;00	37	Gallons
		OVERFLOW FROM CLEANOUT CAUSING							
SOUTHEAST QUAD	1916 BALDWIN	EXCURSION IN FRONT	BUFFALO BAYOU	493-P	TX0096172	19-Mar-00			Gallon
NORTHWEST QUADRANT	5216 CHENEVERT	ROUTINE STOPPAGE	BUFFALO BAYOU	493-Q	TX0096172	20-Mar-00			Gallons
SOUTHWEST QUADRANT	11514 BRIAR ROSE	SERVICE LINE STOPPAGE	BUFFALO BAYOU	489-P	TX0063002	21-Mar-00			Gallon
SOUTHWEST QUADRANT	2509 DRISCOLL	MAIN LINE AND SERVICE LIN STOPPED UP	BUFFALO BAYOU	492-V	TX0096172	21-Mar-00			Gallons
SOUTHEAST QUAD	2519 LORRAINE	CONNUNITY LINE STOPPED UP	BUFFALO BAYOU	494-E	TX0096172	22-Mar-00	09:11	79	Gallon
NODELINESE SUIT	0047 FFFFFF	COMMUNITY LINE STOPPED UP CAUSING OVER	DUEEN C SANCE	400	TV00000:				
NORTHWEST QUAD	3317JEFFERSON	FLOW	BUFFALO BAYOU	493-V	TX0096172	22-Mar-00			Gallons
NORTHWEST QUAD	2907 JEWELL	COMMUNITY LINE STOPPED.	BUFFALO BAYOU	494-A	TX0096172	22-Mar-00			Gallons
NORTHWEST QUADRANT	2210 WENTWORTH	ROUTINE STOPPAGE	BUFFALO BAYOU	493-X	TX0096172	22-Mar-00			Gallon
SOUTHEAST QUAD	315 E.10TH STREET	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-A	TX0035009	23-Mar-00	08:00	4209	Gallons
		SEWER MAIN STOPPED UP CAUSING FLOOD IN							
SOUTHWEST QUADRANT	1714 HUDLY	BACK YARD OF SEW	BUFFALO BAYOU	442-Q	TX0096172	23-Mar-00			Gallon
SOUTHWEST	QUADRANT	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0096172	23-Mar-00	14:30	605	Gallon
NORTHWEST Q	9009 RICHMOND	ROUTINE STOPPAGE	BUFFALO BAYOU	490-X	TX0063002	24-Mar-00	11:00	97	Gallons
			DUEEN O DAYOU	490-E	TX0063002	04 14 00	l = = =	704	0-11
NORTHWEST	12219 COBBLESTONE	SERVICE LINE STOPPED UP, SPREAD 3LBS OF PO19	BUFFALO BAYOU	490-⊑	170003002	24-Mar-00	7:57	124	Gallons
NORTHWEST SOUTHEAST Q	12219 COBBLESTONE 1628 HARVARD	SERVICE LINE STOPPED UP, SPREAD 3LBS OF PO19 SEWER LINE STOPPED UP	BUFFALO BAYOU	490-E 493-A	TX0003002	24-Mar-00			Gallons

Problem	Location	Description	Receiving stream	Key map		Date	Time	Volume	Unit
SOUTHEAST QUAD	1900 EASTWOOD	MAIN LINE STOPPAGE.	BUFFALO BAYOU	494-W	TX0096177	24-Mar-00	13:43	105	Gallons
ORTHWEST QUAD	1119 LASHBROK	SEWER MAIN AND SERVICE LINE STOPPED UP	BUFFALO BAYOU	489-J	TX0063002	25-Mar-00	09:04	1110	Gallons
NORTHEAST	#3 CANAL	ROUTINE STOPPAGE	BUFFALO BAYOU	527-N	TX0096172	25-Mar-00			Gallons
NORTHEAST QUAD	101 EAST GATE	MAIN LINE STOPPED UP	BUFFALO BAYOU	495-W	TX0096172	25-Mar-00			Gallons
SOUTHEAST QUADRANT	#3 CANAL	ROUTINE STOPPAGE	BUFFALO BAYOU	494-P	TX0096172	25-Mar-00	-		Gallons
SOUTHEAST QUADRANT	110 LATHAM	ROUTINE STOPPAGE	BUFFALO BAYOU	494-P	TX0096172	25-Mar-00			Gallons
SOUTHEAST QUAD	5110 LATHAM	ROUTINE STOPPAGE	BUFFALO BYOU	494-V	TX0096172	25-Mar-00			Gallons
NORTHEAST QUAD	2801 CLINE	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-J	TX0096172	27-Mar-00	13:50	2740	Gallons
SOUTHEAST QUAD	2110 N. BRYAN	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-T	TX0096172	27-Mar-00	11:30	2100	Gallons
SOUTHWEST QUAD	1755 COLQUITT	SERVICE LINE STOPPED	BUFFALO BAYOU	492-Z	TX0096172	27-Mar-00			Gallons
COOTINEOT GOAD	1700 CCEQOTT	ROUTINE STOPPAGE CAUSED BY GREASE AND	DOITINEO DITTOO	402 Z	17(0000112	27 11101 00	10.14	100	Canonic
NODTHEAST SHAD	0007 WALKED		DUEEN ON DAYOU	454.0	T)/0000470	07.14	40.07	0774	
NORTHEAST QUAD	3807 WALKER	SAND	BUFFALON BAYOU	454-S	TX0096172	27-Mar-00			Gallons
SOUTHWEST QUAD	615 PEDEN	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-N	TX0096172	29-Mar-00			Gallons
NORTHWEST Q	915 W. CAVALCADE	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-T	TX0096172	29-Mar-00	12:40	396	Gallons
NORTHWEST QUAD	1610 BRINGHURST	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-K	TX0096172	29-Mar-00	13:10	72	Gallons
NORTHEAST QUAD	4207 OATS	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	494-E	TX0096172	29-Mar-00	13:13	81	Gallons
NORTHEAST Q	2115 GANO	COMMUNITY LINE STOPPED UIP	BUFFALO BAYOU	493-D	TX0096172	29-Mar-00			Gallons
SOUTHEAST QUAD	1702 WRIT	MAIN LINE STOPPED UP	BUFFALO BAYOU	451-X	TX0096172	29-Mar-00			Gallons
SOUTHEAST QUAD	3210 GARROW	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	494-N	TX0096172	31-Mar-00			Gallons
NORTHWEST QUADRANT	1110 STUDE	CITY MAIN STOPPED UP	BUFFALO BAYOU	493-A	TX0096172	01-Apr-00	10:38	810	Gallons
NORTHWEST QUADS	2222 WEST LOOP SOUTH	MAIN LINE STOPPAGE	BUFFALO BAYOU	491-V	TX0063002	02-Apr-00	09:21	255	Gallons
NORTHEAST QUAD	4400 COYLE	MAIN LINE STOPPAGE	BUFFALO BAYOU	494-W	TX0096172	02-Apr-00			Gallons
NORTHEADT QUAD	4400 COTEL		BOIT ALO BATOO	434-44	17/0030172	02-Api-00	3.40	1104	Callonia
		SEWER SERVECE STOPPED UP CAUSING							
SOUTHWEST QUAD	12714 WIDLEY CIR	EXCURSION	BUFFALO BAYOU	488-M	TX0035017	03-Apr-00			Gallons
SOUTHEAST QUAD	4925 MCKINNEY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	03-Apr-00		216	Gallons
NORTHEAST	543 N. SUPER	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	03-Apr-00	15:00	195	Gallons
SOUTHEAST QUAD	3201 ALABAMA	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-T	TX0096172	03-Apr-00			Gallons
NORTHEAST	2413 GENTRY	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	03-Apr-00			Gallons
	9310 LONG POINT	MAIN LINE STOPPED UP	BUFFALO BAYOU	450-U			-		
NORTHWEST QUAD					TX0096172	04-Apr-00			Gallons
NORTHEAST QUAD	4401 AVERILL	ROUTINE STOPPAGE	BUFFALO BAYOU	453-Y	TX0096172	04-Apr-00			Gallons
NORTHEAST QUAD	2115 DAVIS	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-A	TX0096172	05-Apr-00			Gallons
NORTHEAST QUAD	2120 MAURY	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-H	TX0096172	05-Apr-00	10:01	525	Gallons
SOUTHEAST QUAD	2606 HARRINGTON	SERVICE LINE STOPPED UP.	BUFFALO BAYOU	494-E	TX0096172	05-Apr-00		492	Gallons
SOUTHWEST QUAD	1627 MILFORD	MAIN LINE STOPPED UP.	BUFFALO BAYOU	492-Z	TX0096172	05-Apr-00			Gallons
	1627 MILFORD	MAIN LINE STOPPED UP ROUTINE STOPPAGE.		492-Z					
SOUTHWEST QUAD		I .	BUFFALO BAYOU		TX0096172	05-Apr-00			Gallons
SOUTHWEST QUAD	3422 TIMMONS	CITY MAIN STOPPED UP.	BUFFALO BAYOU	492-S	TX0096172	05-Apr-00	21:34	4275	Gallons
SOUTHWEST QUAD	13102 RICHMOND	SERVICE HOLD IN REAR.	BUFFALO BAYOU	488-Y	TX0035017	06-Apr-00	17:24	360	Gallons
SOUTHWEST QUAD	5200 WOODHEAD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0096172	06-Apr-00	10:25	145	Gallons
SOUTHWEST QUAD	3101 S. SHEPERD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-U	TX0096172	06-Apr-00			Gallons
		I .							
SOUTHEAST QUAD	2511 GANO	MAIN LINE STOPPED UP.	BUFFALO BAYOU	493-D	TX0096172	07-Apr-00			Gallons
SOUTHWEST QUAD	2113 BRUN	MAIN LINE STOPPED UP, ROUTINE STOPPAGE.	BUFFALO BAYOU	492-R	TX0096172	07-Apr-00			Gallons
SOUTHWEST QUAD	1736 INDIANA	MAIN LINE STOPPED UP, ROUTINE STOPPAGE	BUFFALO BAYOU	492-R	TX0096172	07-Apr-00	08:49	302	Gallons
NORTHWEST QUAD	10655 KATY FREEWAY	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-C	TX0035017	08-Apr-00	14:04	420	Gallons
NORTHEAST QUAD	920 ALTIC	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	08-Apr-00			Gallons
NORTHEAST QUAD	300 S. 75TH	MAIN LINE STOPPED UP	BUFFALO BAYOU	495-W		08-Apr-00			
		I .			TX0096172				Gallons
NORTHEAST QUAD	706 MORRIS	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	09-Apr-00			Gallons
NORTHEAST QUAD	5520 CAVALCADE	MAIN LINE STOPPED UP	BUFFALO BAYOU	454-Y	TX0096172	09-Apr-00	10:46	120	Gallons
NORTHEAST QUAD	4001 AVERILL	STOPPAGE IN MAIN LINE	BUFFALO BAYOU	453-Y	TX0096172	09-Apr-00	19:33	214	Gallons
SOUTHWEST QUAD	3619 S. SHEPHERD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Y	TX0096172	09-Apr-00	21.28	4710	Gallons
SOUTHEAST QUAD	14 GREENWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-U	TX0096172	10-Apr-00			Gallons
NORTHWEST QUAD	1300 WILCREST	MAIN LINE STOPPED UP.	BUFFALO BAYOU	489-K	TX0063002	12-Apr-00			Gallons
NORTHEAST QUAD	1612 SHERPHERD	MAIN LINE STOPPED UP.	BUFFALO BAYOU	492-H	TX0096172	12-Apr-00	13:42	592	Gallons
SOUTHWEST QUAD	2907 ALBANY	MAIN LINE STOPPED UP	BUFALO BAYOU	493-P	TX0096172	13-Apr-00	11:45	335	Gallons
NORTHWEST QUAD	2222WEST LOOP SOUTH	SEWER MAIN STOPPED UP.	BUFFALO BAYOU	491-R	TX0096172	13-Apr-00	13:10	420	Gallons
		MAIN LINE STOPPAGE, CAUSING MANHOLE TO							
NORTHWEST OF A DRANT	2502 SOLITH CESSNED	The state of the s	BUEEN O BAYOU	400 6	TV0062002	14 Apr 00	00.40	260	Callona
NORTHWEST QUADRANT	2503 SOUTH GESSNER	OVERFLOW	BUFFALO BAYOU	490-S	TX0063002	14-Apr-00			Gallons
NORTHEAST QUAD	1900 EASTWOOD	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-W	TX0096172	14-Apr-00			Gallons
SOUTHEAST QUADRANT	106 BURR	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	14-Apr-00			Gallons
SOUTHWEST QUADRANT	11427 BRIARFOREST	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-P	TX0063002	15-Apr-00	15:18	114	Gallons
NORTHWEST QUADRANT	1339 WINROCK	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-N	TX0096172	15-Apr-00			Gallons
	12639 ASHFORD			+			- · · ·	230	
SOUTHWEST QUADRANT	MEADOW	ROUTINE STOPPAGE	BUFFALO BAYOU	488-V	TX0035017	16-Apr-00	13.45	4-	Gallons
		I .							
SOUTHEAST QUADRANT	4434 CLAY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-S	TX0096172	16-Apr-00			Gallons
SOUTHWEST QUADRANT	5150 HILDAGO	MANHOLE OVERFLOWING CAUSING EXCURSION	BUFFALO BAYOU	491-U	TX0096172	16-Apr-00			Gallons
SOUTHWEST	2903 BERING	REPAIR PENDING ON MAIN LINE	BUFFALO BAYOU	491-T	TX0062995	17-Apr-00		780	Gallons
SOUTHEAST QUAD	2100 PEASE	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-V	TX0096172	17-Apr-00		500	Gallons
									ON
NORTHWEST QUAD	2903 BERING	REPAIR PENDING ON MAIN LINE	BUFFALO BAYOU	491-T	TX0062995	17-Apr-00	13:06		GOING
								1000	
SOUTHEAST QUAD	1711 GANO	COMMUNITY LINE STOPPED UP.	BUFFALO BAYOU	493-H	TX0096172	18-Apr-00			Gallons
SOUTHWEST QUAD	4321 HARZARD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0096172	18-Apr-00			Gallons
SOUTHWEST QUAD	2701 WESTLANE	MAIN STOPPED UP	BUFFALO BAYOU	491-V	TX0062995	19-Apr-00	18:04	2210	Gallons
SOUTHEAST QUAD	6110 FAIRDALE	MAIN LINE OVERFLOWING INTO STORM SEWER.	BUFFALO BAYOU	491-W	TX0096172	19-Apr-00	13:00	435	Gallons
NORTHWEST QUAD	7425 MARILYN	MAIN LINE STOPPED UP		415-W	TX0025291	21-Apr-00			Gallons
			DUEEN O BAYOU						
SOUTHEAST QUADRANT	3419 MCGOWEN	MAIN LINE STOPPED UP-REPAIRS PENDING ON MAIN		493-Z	TX0062201	21-Apr-00			Gallons
	605 BERRY RD.	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-G	TX0096172	21-Apr-00			Gallons
	3903 HARTSDALE	MANHOLE OVERFLOW IN STREET	BUFFALO BAYOU	490-Z	TX0096172	21-Apr-00	20:40	2143	Gallons
		MAIN STOPPED UP CAUSING MANHOLE TO							
			BUFFALO BAYOU	493-S	TX00096172	22-Apr-00	8:07	980	Gallons
SOUTHWEST QUAD	3300 GRAUSTARK ST	OVERFLOW ONTO STREET	220 200	1.50 5	55550172		2.5.	550	_ 30110
NORTHEAST QUAD SOUTHWEST QUAD SOUTHWEST QUAD	3300 GRAUSTARK ST	OVERFLOW ONTO STREET						0.0	0-11
SOUTHWEST QUAD		MAIN LINE STOPPED UP CAUSING MANHOLE TO	DUEEN O DAYCO	450.5	TVCCCCC		0.04		Gallons
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD	8807 EMNORA	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW	BUFFALO BAYOU	450-R	TX0063002	22-Apr-00			
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHWEST QUAD		MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION	BUFFALO BAYOU	450-R 489-P	TX0063002 TX0063002	23-Apr-00	13:50	1420	
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHWEST QUAD	8807 EMNORA	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW					13:50	1420	
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD	8807 EMNORA 11514 BRIAR ROSE DR	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION	BUFFALO BAYOU	489-P	TX0063002	23-Apr-00	13:50 17:35	1420 46	Gallons
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD NORTHEAST QUAD	8807 EMNORA 11514 BRIAR ROSE DR 2212 PANNELL 2819 FOX	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION MAIN LINE STOPPED UP MAIN LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	489-P 494-B 494-J	TX0063002 TX0096172 TX0096172	23-Apr-00 24-Apr-00 24-Apr-00	13:50 17:35 16:52	1420 46 500	Gallon:
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD NORTHEAST QUAD	8807 EMNORA 11514 BRIAR ROSE DR 2212 PANNELL	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE	BUFFALO BAYOU BUFFALO BAYOU	489-P 494-B	TX0063002 TX0096172	23-Apr-00 24-Apr-00	13:50 17:35 16:52	1420 46 500	Gallons
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD NORTHEAST QUAD SOUTHWEST QUADRANT	8807 EMNORA 11514 BRIAR ROSE DR 2212 PANNELL 2819 FOX 2701 WESTLANE	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION MAIN LINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPAGE HL&P CUT THE MAIN ELECTRICAL POWER TO LIFT	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	489-P 494-B 494-J 491-V	TX0063002 TX0096172 TX0096172 TX0096172	23-Apr-00 24-Apr-00 24-Apr-00 24-Apr-00	13:50 17:35 16:52 17:12	1420 46 500 414	Gallons Gallons Gallons
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD NORTHEAST QUAD SOUTHWEST QUADRANT	8807 EMNORA 11514 BRIAR ROSE DR 2212 PANNELL 2819 FOX 2701 WESTLANE	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE HL&P CUT THE MAIN ELECTRICAL POWER TO LIFT STATION	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	489-P 494-B 494-J 491-V 535-B	TX0063002 TX0096172 TX0096172 TX0096172 TX0105058	23-Apr-00 24-Apr-00 24-Apr-00 24-Apr-00 25-Apr-00	13:50 17:35 16:52 17:12	1420 46 500 414 95000	Gallons Gallons Gallons
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD NORTHEAST QUAD SOUTHWEST QUADRANT	8807 EMNORA 11514 BRIAR ROSE DR 2212 PANNELL 2819 FOX 2701 WESTLANE	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION MAIN LINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPAGE HL&P CUT THE MAIN ELECTRICAL POWER TO LIFT	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	489-P 494-B 494-J 491-V	TX0063002 TX0096172 TX0096172 TX0096172	23-Apr-00 24-Apr-00 24-Apr-00 24-Apr-00 25-Apr-00 26-Apr-00	13:50 17:35 16:52 17:12 15:00 13:30	1420 46 500 414 95000	Gallons Gallons Gallons
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD NORTHEAST QUAD SOUTHWEST QUADRANT	8807 EMNORA 11514 BRIAR ROSE DR 2212 PANNELL 2819 FOX 2701 WESTLANE	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE HL&P CUT THE MAIN ELECTRICAL POWER TO LIFT STATION	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	489-P 494-B 494-J 491-V 535-B	TX0063002 TX0096172 TX0096172 TX0096172 TX0105058	23-Apr-00 24-Apr-00 24-Apr-00 24-Apr-00 25-Apr-00 26-Apr-00	13:50 17:35 16:52 17:12 15:00 13:30	1420 46 500 414 95000 270	Gallons Gallons Gallons Gallons
SOUTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD NORTHEAST QUAD NORTHEAST QUAD SOUTHWEST QUADRANT N/A SOUTHWEST QUAD	8807 EMNORA 11514 BRIAR ROSE DR 2212 PANNELL 2819 FOX 2701 WESTLANE 8500 CYPRESS 933N WILCREST	MAIN LINE STOPPED UP CAUSING MANHOLE TO OVERFLOW OVER FLOW IN YARD CAUSING EXCURSION MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE HL&P CUT THE MAIN ELECTRICAL POWER TO LIFT STATION MAIN LINE STOPPED UP.	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	489-P 494-B 494-J 491-V 535-B 489-B	TX0063002 TX0096172 TX0096172 TX0096172 TX0105058 TX0063002	23-Apr-00 24-Apr-00 24-Apr-00 24-Apr-00 25-Apr-00	13:50 17:35 16:52 17:12 15:00 13:30 10:18	1420 46 500 414 95000 270 128	Gallons Gallons Gallons Gallons Gallons Gallons Gallons Gallons

Problem	Location	Description	Receiving stream	Key ma		Date	Time	Volume	Unit
NORTHEAST QUAD	711 MCINTOSH	SSERVICE LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	26-Apr-00	21:32	219	Gallons
NORTHEAST QUAD	401 GARGAN	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-D	TX0096172	26-Apr-00	17:40	116	Gallons
NORTHEAST QUAD	920 ALTIC	ROUTINE STOPPAGE	BUFFALO BAYOU	494-T	TX0096172	26-Apr-00	19:30	1730	Gallons
SOUTHWEST QUAD	4700 MONTROSE	ROUTINE STOPPAGE	BUFFALO BAYOU	493-W	TX0096172	27-Apr-00			Gallons
SOUTHEAST QUAD	920 ALTIC ST	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-U	TX0096172	27-Apr-00			Gallons
NORTHWEST QUAD	502 MAIN	SEWER LINE STOPPED UP	BUFFALO BAYOU	493-L	TX0096172	27-Apr-00			Gallons
SOUTHEAST QUAD	7006 TUCK	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-M	TX0096172	27-Apr-00			Gallons
			BULLATO BATOU						
NORTHEAST QUAD	8701 IRVINGTON	ROUTINE STOPPAGE	DUEEN O DAY(0)	454-P	TX0063029	28-Apr-00			Gallons
NORTHWEST QUAD	1911 COLQUITT	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-K	TX0063002	28-Apr-00			Gallons
SOUTHWEST QUADRANT	2317 MORSE	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Y	TX0096172	28-Apr-00			Gallons
NORTHEAST QUADS	6822 VICTORIA	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-D	TX0096172	28-Apr-00		1680	Gallons
SOUTHWEST QUAD	2701 WEST LANE	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-N	TX0096172	29-Apr-00	16:26	1045	Gallons
NORTHEAST QUAD	309 S. 72ND STREET	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-Z	TX0096172	29-Apr-00	16:35	210	Gallons
NORTHEAST QUAD	310 N. SAINT CHARLES	ROUTINE STOPPAGE	BUFFALO BAYOU	494-J	TX0096172	29-Apr-00	08:33	62	Gallons
NORTHEAST QUAD	#69 & #70 SADDLEBROOK	ROUTINE STOPPAGE	BUFFALO BAYOU	491-B	TX0096172	29-Apr-00	10:47	600	Gallons
NORTHWEST QUAD	5200 WOODHEAD	ROUTINE STOPPAGE	BUFFALO BAYOU	492-Z	TX0063002	30-Apr-00	13:55	620	Gallons
NORTHWEST QUAD	11514 BRIAR ROSE	STOPPAGE IN MAIN LINE CAUSED BY GREASE AND SAND	BUFFALO BAYOU	489-P	TX0063002	30-Apr-00	00:05	605	Gallons
NORTHWEST QUAD	4233 BETTIS	ROUTINE STOPPAGE	BUFFALO BAYOU	491-V	TX0096172	30-Apr-00			Gallons
NORTHWEST QUAD	614 FAIRVIEW	ROUTINE STOPPAGE	BUFFALO BAYOU	493-N	TX0096172	30-Apr-00			Gallons
		I .							
NORTHWEST QUAD	1613 SHEPHERD	ROUTINE STOPPAGE	BUFFALO BAYOU	492-H	TX0096172	30-Apr-00			Gallons
NORTHWEST QUAD	1612 SHEPHERD	ROUTINE STOPPAGE	BUFFALO BAYOU	492-H	TX0096172	30-Apr-00			Gallons
NORTHWEST QUAD	1801 DURHAM	ROUTINE STOPPAGE	BUFFALO BAYOU	452-G	TX0096172	30-Apr-00	12:12	304	Gallons
	900 STANFORD @ W.								
SOUTHWEST QUADRANT	DALLAS	MANHOLE STOPPED UP	BUFFALO BAYOU	493-N	TX0057347	01-May-00			Gallons
SOUTHEAST QUADRANT	1923 LOMBARDY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	01-May-00	10:05	711	Gallons
SOUTHEAST QUADRANT	615 FEAMSTER	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-E	TX0096172	02-May-00		162	Gallons
NORTHWEST QUADRANT	9855 PAGEWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU	490-W	TX0063002	03-May-00			Gallons
SOUTHWEST QUADRANT	2620 S. SHEPHERD	SERVICE LINE OVERFLOW INTO STORM DRAIN	BUFFALO BAYOU	492-U	TX0096172	03-May-00			Gallons
001111111111111111111111111111111111111	1000 EAIE: #5117 - 115	COMING UP ON TO STREET, GOING INTO STORM	DUEEN S SATISTIC	465.	TV6005:				
SOUTHWEST QUADS	1900 FAIRVIEW & MORSE		BUFFALO BAYOU	492-V	TX0096172	03-May-00			Gallons
NORTHEAST QUADRANT	5109 POLK	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	04-May-00			Gallons
SOUTHEAST QUADRANT	1400 WRIGHTWOOD	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	04-May-00		63	Gallons
SOUTHEAST QUADRANT	901 W. GRAY	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-N	TX0096172	04-May-00	14:39	199	Gallons
NORTHEAST QUADRANT	6636 EUREKA	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-B	TX0096172	04-May-00	8:24	3070	Gallons
SOUTHWEST QUADS	1655 HAWTHORNE	ROUTINE STOPPAGE	BUFFALO BAYOU	492-F	TX0034924	05-May-00			Gallons
SOUTHWEST QUADRANT	4049 WICKERSHAM	ROUTINE STOPPAGE DUE TO EXCESS GREASE	BUFFALO BAYOU	492-S	TX0062995	05-May-00			Gallons
SOUTHWEST QUADS	2308 SULFOLK	ROUTINE STOPPAGE	BUFFALO BAYOU	491-V	TX0063002	05-May-00			Gallons
NORTHEAST QUADS	4629 BELL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	05-May-00			Gallons
NORTHEAST QUADRANT	2004 N. WAYSIDE	SERVICE LINE STOPPED UP	BUFFALO BAYOU	495-A	TX0096172	05-May-00			Gallons
NORTHWEST QUADS	11514 BRAIR ROSE	ROUTINE STOPPAGE FROM GREASE	BUFFALO BAYOU	482-P	TX0063002	06-May-00			Gallons
NORTHEAST	902 GRACE LAND	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-V	TX0096172	06-May-00			Gallons
NORTHWEST QUADRANT	1609 BEACONSHIRE	ROUTINE STOPPAGE DUE TO EXCESS GREASE SERVICE LINE OVERFLOWING ONTO STREET AND	BUFFALO BAYOU	488-Q	TX0035017	07-May-00	10:45	735	Gallons
NORTHEAST QUADRANT	103 BEDFORD ST.	STORM DRAIN	BUFFALO BAYOU	495-W	TX0035106	08-May-00	10:40	960	Gallons
		I .							
NORTHEAST QUADRANT	4601 WALKER	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	08-May-00			Gallons
NORTHEAST QUADRANT	2509 GENTRY	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	08-May-00			Gallons
NORTHEAST QUADRANT	1400 WRIGHTWOOD	ROUTINE STOPPAGE	BUFFALO BAYOU	493-C	TX0096172	08-May-00		1128	Gallons
SOUTHEAST QUADRANT	8256 LENORE	SERVICE LINE STOPPED UP	BUFFALO BAYOU	535-V	TX0105058	08-May-00	12:41	132	Gallons
NORTHEAST QUADRANT	4120 WALKER	ROUTINE STOPPAGE	BUFFALO BAYOU	494-S	TX0096172	09-May-00	12:51	19	Gallons
SOUTHEAST QUADRANT	3071 LOCKE	ROUTINE STOPPAGE	BUFFALO BAYOU	492-U	TX0096172	09-May-00	15:00	404	Gallons
NORTHEAST	6 CLIFTON	RIGHT OF WAY MAINTANCE PULLED SERVICE LINE OUT	BUFFALO BAYOU	494-V	TX0096172	09-May-00	11:45	5/0	Gallons
NORTHLAGT	1900 EASTWOOD AT		BOTT ALO BATOO	434-V	17,0030172	03-May-00	11.43	343	Galloria
NORTHEAST QUADS	HARDY	ROUTINE STOPPAGE	BUFFALO BAYOU	494-W	TX0096172	10-May-00	08:19	1385	Gallons
NORTHEAST QUADS	3903 DREW ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-W	TX0096172	10-May-00	08:30	588	Gallons
NORTHEAST QUADRANT	6709 AVE O	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-R	TX0096172	10-May-00			Gallons
NORTHEAST QUADS	2211 PANNELL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-B	TX0096172	10-May-00			Gallons
NORTHEAST QUADRANT	1900 EASTWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	11-May-00			Gallons
NODTHE ACT CHARDANE	404 OLUTAAAN	MAINLINE OTOPPED LIP	BUFFALO BAYOU	400.0	TV0000170	40.1400	00.00	000	
NORTHEAST QUADRANT NORTHWEST QUADRANT	404 QUITMAN 1800 CONGRESS	MAIN LINE STOPPED UP. STOPPAGE IN CITY MAIN	BUFFALO BAYOU	493-C 493-M	TXOO96172 TX0096172	12-May-00 13-May-00			Gallons Gallons
MANUALOT QUADRAINT	1000 CONGRESS	BLEACH LINE CAME LOSE AT PUMP CREATING	DOLLARO DATOU	-30-IVI	170090172	10-ividy-00	17.11	1020	Janons
N/A	WEST DISTRICT WWTP	BLEACH SPILL	BUFFALO BAYOU	489-L	TX0063002	14-May-00	10:00	3200	Gallons
NORTHEAST QUADRANT	2212 PANNELL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-B	TX0003002	15-May-00			Gallons
NORTHEAST QUADRANT	2014 WEST ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-B 494-A	TX0096172	15-May-00			Gallons
SOUTHWEST QUADRANT	13023 WICKERSHAM					15-May-00			
		PUMP STATION WAS DOWN	BUFFALO BAYOU	488-U	TX0096172				Gallons
SOUTHWEST QUADRANT	5100 RICHMOND	ROUTINE STOPPAGE	BUFFALO BAYOU	491-Y	TX0096172	15-May-00			Gallons
NORTHWEST QUADRANT	202 KNOX	OVERFLOW CAUSING EXCURSION	BUFFALO BAYOU	492-L	TX0063002	16-May-00			Gallons
NORTHWEST QUADRANT	1719 OVID	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-F	TX0096172	16-May-00			Gallons
NORTHWEST	3311 BEAUCAMP	MAIN LINE OVER FLOWING	BUFFALO BAYOU	493-B	TX0096172	16-May-00	14:25	4860	Gallons
NORTHWEST	401 STUDEWOOD	MAIN LINE OVER FLOWING	BUFFALO BAYOU	493-H	TX0096172	16-May-00	01:50	277	Gallons
NORTHEAST QUADS	604 W. 11TH	SEWER LINE STOPPED UP	BUFFALO BAYOU	453-W	TX0096172	17-May-00			Gallons
NORTHEAST QUAD	4008 ROTMAN	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	17-May-00			Gallons
NORTHWEST	QUADRANT	ROUTINE STOPPED OF	BUFFALO BAYOU	450-M	TX0096172	18-May-00			Gallons
NORTHEAST QUAD	1406 JAMES	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-H	TX0096172	19-May-00			Gallons
NORTHWEST QUAD	3317 BEAUCHAMP	SEWER MAIN STOPPED UP	BUFFALO BAYOU	493-B	TX0096172	19-May-00			Gallons
NORTHWEST QUADRANT	83 LEGEND	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-M	TX0096172	19-May-00			Gallons
NORTHWEST QUADRANT	3917 SAN FELIPE	ROUTINE STOPPAGE.	BUFFALLO BAYOU	492-N	TX0096172	22-May-00			Gallons
NORTHEAST QUAD	311 N. YORK ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-N	TX0096172	22-May-00	09:31	151	Gallons
SOUTHWEST QUADRANT	1114 BRIAR BAYOU DR.	ROUTINE STOPPAGE	BUFFALO BAYOU	488-L	TX0096172	22-May-00			Gallons
NORTHWEST QUADRANT	4295 SAN FELIPE	SERVICE LINE STOPPED UP	BUFFALO BAYOU	491-R	TX0096172	22-May-00			Gallons
SOUTHEAST QUAD	2304 TRUXILLO	OVERFLOW STOPPAGE DUE TO NEEDED REPAIR	BUFFALO BAYOU	493-Y	TX0096172	22-May-00			Gallon
NORTHWEST QUAD		I .	BUFFALO BAYOU						
	800 N. DURHAM	PRIVATE LINE STOPPED UP		492-C	TX0096172	23-May-00			Gallons
NORTHEAST QUADRANT	1119 ALTIC	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	23-May-00			Gallons
NORTHWEST QUADRANT NORTHEAST QUAD	3923 SAN FELIPE	SEWER MAIN STOPPED UP	BUFFALO BAYOU	492-N	TX0096172	23-May-00			Gallons
	1101 YORK	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-S	TX0096172	23-May-00	10:36	1520	Gallons
NORTHEAST QUAD			i contract of the contract of	1	1				1
NORTHEAST QUAD	EASTWOOD AT HARBY	MAIN LINE STOPPED UP CAUSING MANHOLE OVERFLOWING	BUFFALO BAYOU	494-W	TX0096172	23-May-00			Gallons
NORTHEAST QUAD		MAIN LINE STOPPED UP CAUSING MANHOLE							

Problem	Location	Description	Receiving stream	Key ma		Date Time	Volume Unit
SOUTHWEST QUAD	4010 WOODHEAD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-V	TX0096172	24-May-00 08:17	412 Gallons
NORTHEAST QUAD	900 ALTIC	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-U	TX0096172	24-May-00 10:07	5940 Gallon
NORTHEAST QUADRANT	10818 BAUMAN	MAIN LINE STOPPED UP	BUFFALO BAYOU	413-Y	TX0096172	24-May-00 10:34	64 Gallon
NORTHEAST QUAD	1200 SIDNEY	CITY MAIN STOPPED UP	BUFFALO BAYOU	494-S	TX0096172	24-May-00 19:30	1096 Gallon
SOUTHEAST QUADRANT	3311 BEAUCHAMP	SEWER MAIN STOPPED UP	BUFFALO BAYOU	493-B	TX0096172	24-May-00 9:36	1412 Gallon
NORTHEAST QUAD	1317 TELEPHONE	MAIN LINE STOPPED UP.	BUFFALO BAYOU	494-X	TX0096172	25-May-00 09:50	462 Gallon
NORTHWEST QUADS	4418 ROEHLER	MAIN LINE STOPPED UP.	BUFFALO BAYOU	492-N	TX0096172	25-May-00 13:23	168 Gallon
NORTHEAST QUAD	7810 KATY FRWY	MAIN LINE STOPPED UP	BUFFALO BAYOU				
		I .		491-B	TX0096172	25-May-00 14:15	375 Gallon
NORTHEAST QUADRANT	2921 BRINGHURST	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-B	TX0096172	25-May-00 11:15	6000 Gallon
NORTHEAST QUADRANT	1612 CHESTNUT	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-H	TX0096172	26-May-00 10:24	312 Gallon
NORTHEAST QUAD	12 STILES ST	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	26-May-00 08:31	285 Gallon
NORTHEAST QUAD	6742 AVENUE O	OVERFLOW FROM PRIVATE LINE	BUFFALO BAYOU	494-R	TX0096172	26-May-00 15:47	13 Gallon
SOUTHEAST QUADS	3715 N. MACGREGOR	MAIN LINE STOPPED UP	BUFFALO BAYOU	533-H	TX0096172	26-May-00 22:58	694 Gallon
SOUTHWEST QUADRANT	1757 BRANARD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-V	TX0063002	28-May-00 07:37	932 Gallon
00011111201 Q07121111111		CITY MAIN STOPPED UP GOING INTO STORM	BOTT/IEG BATTOG	102 1	1710000002	20 may 00 07.01	OOZ Gallon
NODEL IMPORT OF A DECEMBER	0700 KATY EDEEMAY		DUEENLO DAVOLI	400 B	TVOOCOOO	20 May 200 47:05	500 0-11
NORTHWEST QUADRANT	8723 KATY FREEWAY	SEWER STORRED LIP	BUFFALO BAYOU	490-B	TX0063002	30-May-00 17:05	530 Gallon
SOUTHEAST QUADRANT	2400 NAVIGATION	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-J	TX0096172	30-May-00 12:11	362 Gallon
NORTHEAST QUADRANT	2514 SUMPTER	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-E	TX0096172	31-May-00 09:00	1096 Gallon
SOUTHEAST QUADRANT	5649 BARRYMORE	MAIN LINE STOPPED UP	BUFFALO BAYOU	534-C	TX0096172	31-May-00 10:02	440 Gallon
		FAILURE OF ON SITE TRANSFORMER CAUSED A					
N/A	TURKEY CREEK WWTP	POWER FAILURE	BUFFALO BAYOU	488-G	TX0035017	31-May-00 08:44	
NORTHWEST QUADS	803 SANDMAN	ROUTINE STOPPAGE	BUFFALO BAYOU	492-G	TX0096172	03-Jun-00 08:48	650 Gallon
NORTHEAST QUADRANT		MAIN LINE STOPPED UP		949-T			
NORTHEAST QUADRANT	4445 MCKINNEY ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	949-1	TX0096172	03-Jun-00 15:06	2318 Gallon
	l			1.			.
SOUTHWEST QUAD		ROUTINE STOPPAGE CAUSED BY GREASE	BUFFALO BAYOU	492-X	TX0096172	04-Jun-00 11:52	1330 Gallon
SOUTHWEST QUAD	1745 LEXINGTON	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0062995	05-Jun-00 15:10	140 Gallon
SOUTHWEST QUAD	5441 JUDALON	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-Y	TX0063002	05-Jun-00 10:40	170 Gallon
NORTHEAST QUAD	5000 JEFFERSON	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	05-Jun-00 10:14	1115 Gallon
NORTHEAST QUAD		MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	06-Jun-00 12:15	387 Gallon
NORTHEAST QUAD	7103 PALASTINE	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-M	TX0096172	06-Jun-00 17:53	2859 Gallon
NORTHEAST QUAD	7025 CANAL	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-V	TX0096172	06-Jun-00 19:00	2490 Gallon
NORTHEAST QUADS	103 BEDFORD	MAIN LINE STOPPAGE	BUFFALO BAYOU	495-U	TX0096172	08-Jun-00 16:59	231 Gallon
NORTHWEST QUADRANT	1344 ALEXANDER	MAIN LINE STOPPAGE	BUFFALO BAYOU	452-F	TX0096172	09-Jun-00 12:20	80 Gallon
SOUTHWEST QUADS	ALTIC & TEXAS ST	ROUTINE STOPPAGE	BUFFALO BAYOU	494-U	TX0096172	09-Jun-00 10:26	177 Gallon
NORTHEAST QUAD	7500 MARKET ST	ROUTINE STOPPAGE CAUSED BY GREASE	BUFFALO BAYOU	495-E	TX0096172	10-Jun-00 21:50	3900 Gallon
		MAIN LINE STOPPAGE CAUSED BY GREASE					
SOUTHEAST QUAD	1313 STANFORD	I .	BUFFALO BAYOU	493-N	TX0096172	12-Jun-00 10:19	188 Gallon
NORTHEAST QUADRANT	11 NORWOOD ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-U	TX0096172	12-Jun-00 12:05	162 Gallon
NORTHWEST QUAD	1600 POST OAK BLVD.	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-K	TX0096172	12-Jun-00 14:22	2386 Gallon
SOUTHWEST QUAD	1743 PORTMOUTH	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0096172	12-Jun-00 02:50	619 Gallon
SOUTHWEST QUAD	3050 POST OAK BLVD.	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-Y	TX0096172	14-Jun-00 11:16	582 Gallons
SOUTHEAST QUAD	4701 BELL	SEWER LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	15-Jun-00 12:46	240 Gallons
SOUTHEAST QUAD		SEVVER EINE STOLTED OI	BOITALO BATOO	434-X	17/0030172	15-5011-00 12.40	240 Galloris
	GRAUSTARK @	l		<u>-</u>			
SOUTHEAST QUAD	HAWTHORNE	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-S	TX0096172	15-Jun-00 14:45	500 Gallons
NORTHWEST QUAD	2108 AMBERLY CT.	MAIN LINE STOPPED UP	BUFFALO BAYOU	490-R	TX0096172	19-Jun-00 10:13	1200 Gallons
NORTHEAST QUAD	4309 HARBY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-W	TX0096172	19-Jun-00 11:49	60 Gallons
NORTHEAST QUAD	4707 BELL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	20-Jun-00 08:07	819 Gallons
				1.4			
NORTHWEST QUAD	113 MILAM ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-B	TX00961721	20-Jun-00 08:33	605 Gallons
NORTHEAST QUAD	5219 TREMPER	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-G	TX0096172	21-Jun-00 09:16	43 Gallon
SOUTHEAST QUAD	2608 STANFORD	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-N	TX0096172	21-Jun-00 11:16	144 Gallon
NORTHWEST QUAD	4000 W. 34TH STREET	MAIN LINE STOPPED UP	BUFFALO BAYOU	451-R	TX0096172	21-Jun-00 10:11	1030 Gallon
NORTHEAST QUAD	7118 EL PASO ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-H	TX0096172	21-Jun-00 11:02	185.5 Gallon
SOUTHEAST QUAD	1400 RUTHUEN	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-P	TX0096172	21-Jun-00 10:11	2376 Gallon
SOUTHEAST QUAD	3511 HILLCROFT	MAIN LINE STOPPED UP	BUFFALO BAYOU	490-Z	TX0096172	23-Jun-00 08:17	815 Gallon
	404 E. 43RD ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-J		23-Jun-00 11:15	
NORTHWEST QUAD					TX0096172		90 Gallons
NORTHWEST QUAD	2050 NORTH LOOP	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-Z	TX0096172	24-Jun-00 08:00	2250 Gallons
SOUTHWEST QUAD	1219 EDWARDS	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	493-G	TX0096172	24-Jun-00 14:24	180 Gallons
NORTHWEST QUAD	9801 MEADOWGLEN	MAIN LINE STOPPED UP	BUFFALO BAYOU	490-W	TX0063002	25-Jun-00 17:45	6280 Gallons
NORTHEAST QUAD	4123 LIBERTY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-B	TX0096172	26-Jun-00 12:36	152 Gallons
NORTHEAST QUAD	2803 RUSSELL	ROUTINE STOPPAGE	BUFFALO BAYOU	494-B	TX0096172	26-Jun-00 13:38	328 Gallons
NORTHEAST QUAD	211 KRESS ST.	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-D	TX0096172	27-Jun-00 17:28	104 Gallons
		I .					
NORTHEAST QUAD	600 YORK	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	27-Jun-00 14:25	600 Gallons
SOUTHWEST QUAD	7819 HIGHMEADOW DR.	MAIN LINE STOPPAGE	BUFFALO BAYOU	490-V	TX0063002	29-Jun-00 17:11	240 Gallons
NORTHEAST QUAD	4701 BELL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	29-Jun-00 13:14	265 Gallon
		REPAIR PENDING ON PARTS SEWER LEAKING INTO					
NORTHWEST QUAD	3407 LANG	BAYOU	BUFFALO BAYOU	451-J	TX0096172	29-Jun-00 09:46	Gallons
SOUTHEAST QUAD	3102 LIBERTY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-A	TX0096172	29-Jun-00 10:35	278 Gallons
NORTHWEST QUAD	11404 OLD KATY RD.	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-B	TX0096172	30-Jun-00 08:20	575 Gallons
NORTHEAST QUAD	909 WOODING	STOPPAGE IN MAIN LINE	BUFFALO BAYOU	494-V	TX0096172	01-Jul-00 10:59	188 Gallons
N/A	2525 MACARIO GARCIA	POWER FAILURE AT PLANT	BUFFALO BAYOU	494-R	TX0096172	03-Jul-00 09:25	Gallons
NORTHEAST QUAD	2509 EVERETT	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	03-Jul-00 13:05	345 Gallon
SOUTHWEST QUAD	790 BATEWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-E	TX0096172	03-Jul-00 11:26	3672 Gallon
NORTHWEST QUAD	1811 RUIZ	STOPPAGE IN MAIN LINE	BUFFALO BAYOU	493-M	TX0096172	05-Jul-00 16:15	795 Gallon
NORTHWEST QUAD	5854 SAN FELIPE	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-P	TX0096172	05-Jul-00 19:10	9650 Gallon
NORTHEAST QUAD	1143 HAHLO ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-M	TX0096172	06-Jul-00 08:21	50 Gallon
		MAIN LINE STOPPED UP		494-IVI 492-Z			
SOUTHWEST QUAD	1747 PORTSMOUTH		BUFFALO BAYOU		TX0096172	06-Jul-00 15:00	133 Gallon
COLITINATE OF COLUMN	112 1/2 TRAVIS	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-L	TX0096172	07-Jul-00 11:44	565 Gallon
SOUTHWEST QUAD	1430 MICTORIA	MAIN LINE STOPPED UP	BUFFALO BAYOU	452-H	TX0096172	07-Jul-00 16:17	4344 Gallon
NORTHWEST QUAD	138 VICTORIA	MAIN LINE CTORRED LID	BUFFALO BAYOU	493-L	TX0096177	07-Jul-00 16:29	728 Gallon
NORTHWEST QUAD	419 TRAVIS	MAIN LINE STOPPED UP		414-X	TX0096172	08-Jul-00 21:05	3325 Gallon
NORTHWEST QUAD SOUTHEAST QUAD		MAIN LINE STOPPED UP	BUFFALO BAYOU			1 11 1	
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD	419 TRAVIS 10401 JENSEN DR.	MAIN LINE STOPPED UP		492-€	TX0096172	08-Jul-00 06:40	1260 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST.	MAIN LINE STOPPED UP MAIN LINE STOPPED UP	BUFFALO BAYOU	492-C	TX0096172	08-Jul-00 06:40	
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHEAST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU	494-B	TX0096172	09-Jul-00 15:50	125 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHEAST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST.	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP	BUFFALO BAYOU				125 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHEAST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP HARRIS COUNTY PCT.3 PARKS DEPT. WAS	BUFFALO BAYOU BUFFALO BAYOU	494-B	TX0096172	09-Jul-00 15:50	125 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHEAST QUAD SOUTHWEST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU	494-B	TX0096172	09-Jul-00 15:50	125 Gallon 38100 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHEAST QUAD SOUTHWEST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST 14600 BRAMBLEWOOD	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP HARRIS COUNTY PCT.3 PARKS DEPT. WAS EXCAVATING AND HIT	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-B 488-M	TX0096172 TX0035017 TX0035017	09-Jul-00 15:50 10-Jul-00 19:48 10-Jul-00 20:00	125 Gallon 38100 Gallon 55000 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHEAST QUAD SOUTHWEST QUAD NORTHEAST QUAD SOUTHWEST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST 14600 BRAMBLEWOOD 14600 BRAMBLEWOOD 1811 RUIZ ST.	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP HARRIS COUNTY PCT.3 PARKS DEPT. WAS EXCAVATING AND HIT MAIN LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-B 488-M 488-M 493-M	TX0096172 TX0035017 TX0035017 TX0096172	09-Jul-00 15:50 10-Jul-00 19:48 10-Jul-00 20:00 11-Jul-00 7:50	125 Gallon 38100 Gallon 55000 Gallon 650 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD SOUTHWEST QUAD NORTHWEST QUAD SOUTHWEST QUAD N/A NORTHWEST QUAD SOUTHWEST QUAD SOUTHWEST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST 14600 BRAMBLEWOOD 14600 BRAMBLEWOOD 1811 RUIZ ST. 3003 WINDCHASE	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP HARRIS COUNTY PCT.3 PARKS DEPT. WAS EXCAVATING AND HIT MAIN LINE STOPPED UP MAIN LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-B 488-M 488-M 493-M 488-X	TX0096172 TX0035017 TX0035017 TX0096172 TX0063002	09-Jul-00 15:50 10-Jul-00 19:48 10-Jul-00 20:00 11-Jul-00 7:50 12-Jul-00 13:55	125 Gallon 38100 Gallon 55000 Gallon 650 Gallon 600 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHWEST QUAD SOUTHWEST QUAD N/A NORTHWEST QUAD SOUTHWEST QUAD SOUTHWEST QUAD SOUTHWEST QUAD SOUTHWEST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST 14600 BRAMBLEWOOD 14600 BRAMBLEWOOD 1811 RUIZ ST. 3003 WINDCHASE 1605 RUTH	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP HARRIS COUNTY PCT.3 PARKS DEPT. WAS EXCAVATING AND HIT MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-B 488-M 488-M 493-M 488-X 493-X	TX0096172 TX0035017 TX0035017 TX0096172 TX0063002 TX0096172	09-Jul-00 15:50 10-Jul-00 19:48 10-Jul-00 20:00 11-Jul-00 7:50 12-Jul-00 13:55 14-Jul-00 15:00	125 Gallon 38100 Gallon 55000 Gallon 650 Gallon 600 Gallon
NORTHWEST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHEAST QUAD SOUTHWEST QUAD N/A NORTHWEST QUAD	419 TRAVIS 10401 JENSEN DR. 15 GLEN OAK ST. 2915 BRINGHURST 14600 BRAMBLEWOOD 14600 BRAMBLEWOOD 1811 RUIZ ST. 3003 WINDCHASE	MAIN LINE STOPPED UP MAIN LINE STOPPED UP COMMUNITY LINE STOPPED UP MAIN LINE STOPPED UP HARRIS COUNTY PCT.3 PARKS DEPT. WAS EXCAVATING AND HIT MAIN LINE STOPPED UP MAIN LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-B 488-M 488-M 493-M 488-X	TX0096172 TX0035017 TX0035017 TX0096172 TX0063002	09-Jul-00 15:50 10-Jul-00 19:48 10-Jul-00 20:00 11-Jul-00 7:50 12-Jul-00 13:55	1260 Gallon 125 Gallon 38100 Gallon 55000 Gallon 650 Gallon 1087 Gallon 1488 Gallon

Problem	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
SOUTHWEST QUAD	3218 ROCK RILL	MAIN LINE STOPPED UP	recourting stream	572-F	TX0034924	19-Jul-00			Gallons
NORTHWEST QUAD	1300 WILCREST	8X8 ROUTINE STOPPAGE	BUFFALO BAYOU	489-P	TX0063002	19-Jul-00			Gallons
SOUTHEAST QUAD	1430 CAYWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU	451-X	TX0003002	19-Jul-00			Gallons
SOUTHEAST QUAD	4906 CHENEVERT	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-X	TX0096172	21-Jul-00	09:22	340	Gallons
	11113 KATY FRWY	l		1					
NORTHWEST QUAD	BEHIND LAQU	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-B	TX0096172	22-Jul-00			Gallons
NORTHEAST QUAD	610 S. WAYSIDE DR.	LINE SOPPED UP	BUFFALO BAYOU	494-V	TX0096172	26-Jul-00	09:24	243	Gallons
NORTHEAST QUAD	2003 MAFFITT	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	493-H	TX0096172	26-Jul-00	12:51	232.5	Gallons
SOUTHWEST QUADRANT	5647 WESTHEIMER	MAIN LIINE STOPPAGE	BUFFALO BAYOU	491-T	TX0096172	27-Jul-00	9:50	388	Gallons
SOUTHEAST QUADRANT	302 LENOX	MAIN LINE STOPPAGE	BUFFALO BAYOU	494-U	TX0096172	28-Jul-00	15:07	252	Gallons
NORTHWEST QUAD	2210 W. DALLAS	ROUTINE STOPPAGE	BUFFALO BAYOU	493-R	TX0096172	28-Jul-00			Gallons
SOUTHWEST QUAD	3409 LABRANCH	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-T	TX0096172	28-Jul-00			Gallons
NORTHEAST QUAD	1504 LUZON	STOPPAGE IN MAIN LINE	BUFFALO BAYOU	493-D	TX0096172	29-Jul-00			Gallons
NORTHEAST QUAD	246 MCCARTHY DR.	MAIN LINE AND SEWER LINE STOPPED UP	BUFFALO BAYOU	495-B	TX0096172	29-Jul-00			Gallons
	701 USENER	I .		493-B	TX0096172	30-Jul-00			
NORTHWEST QUAD		MAIN LINE STOPPED UP	BUFFALO BAYOU						Gallons
NORTHEAST QUAD	4322 LEELAND	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-S	TX0096172	30-Jul-00			Gallons
SOUTHWEST QUAD	2100 AMBERLY	MAIN LINE STOPPED UP DUE TO LIFT STATION	BUFFALO BAYOU	490-R	TX0096172	31-Jul-00	10:14	890	Gallons
SOUTHWEST QUAD	6227 SOUTHWEST FRWY	I .	BUFFALO BAYOU	491-X	TX0096172	01-Aug-00	01:20	710	Gallons
		BREAK IN FORCE MAIN SOME TYPE OF OIL COMING							
N/A	243 MCCARTY	INTO WET WE	BUFFALO BAYOU	495-B	TX0096172	01-Aug-00	11:30	2225	Gallons
NORTHEAST QUAD	2828 COLLINGSWORTH	MAIN LINE STOPPED UP	BUFFALO BAYOU	454-W	TX0035017	02-Aug-00	15:18	216	Gallons
NORTHEAST QUAD	8210 BAUMAN	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-G	TX0096172	02-Aug-00			Gallons
NORTHEAST QUAD	4409 BEGGS	SERVICE LINE STOPPED UP	BUFFALO BAYOU	453-Y	TX0096172	02-Aug-00			Gallons
SOUTHEAST QUAD	4423 CANAL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	03-Aug-00			Gallons
SOUTHEAST QUAD	5647 WESTHEIMER RD.	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-T	TX0096172	03-Aug-00			Gallons
SOUTHEAST QUAD	1206 EDDINGTON	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	05-Aug-00	12:44	297	Gallons
SOUTHWEST QUAD	2110 GLENKNOLL	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-P		08-Aug-00		2400	Gallons
NORTHWEST QUAD	8211 KINGSBROOK	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-B	TX0096172	08-Aug-00			Gallons
NORTHEAST QUAD	2311 NOBLE	SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-A	TX0096172	08-Aug-00			Gallons
SOUTHWEST QUAD	1401 CASTLE COURT	MAIN LINE STOPPED UP			TX0096172				
			BUFFALO BAYOU	493-W		08-Aug-00			Gallons
SOUTHWEST QUAD	3123 WESTWICK DR.	MAIN LINE STOPPED UP	BUFFALO BAYOU	488-Z	TX0035017	09-Aug-00	11:58	284	Gallons
SOUTHWEST QUAD	4126 SOUTHWEST FRWY	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-Z	TX0062995	09-Aug-00		1390	Gallons
SOUTHEAST QUAD	403 COWLING ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-U	TX0096172	09-Aug-00	18:00	190	Gallons
NORTHWEST QUAD	1010 W. WEBSTER AVE.	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-P	TX0096172	09-Aug-00			Gallons
SOUTHEAST QUAD	5440 SUGARHILL	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-L	TX0093172	12-Aug-00			Gallons
		I .							
NORTHWEST QUAD	1113 KATY FRWY.	SEWER MAIN LINE STOPPED UP	BUFFALO BAYOU	489-B	TX0096172	14-Aug-00			Gallons
NORTHWEST QUAD	5201 MEMORIAL	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-L	TX0096172	15-Aug-00			Gallons
NORTHEAST QUAD	7211 HARRISBURG	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-Z	TX0096172	16-Aug-00	12:25	625	Gallons
NORTHWEST QUAD	11757 KATY FRWY.	SEWER MAIN STOPPED UP	BUFFALO BAYOU	488-D	TX0063002	17-Aug-00	10:17	1065	Gallons
SOUTHEAST QUAD	3809 MAIN & TRUXILLO	MAIN LINE STOPPAGE	BUFFALO BAYOU	493-T	TX0096172	19-Aug-00			Gallons
SOUTHEAST QUAD	317 S. 72ND ST.	ROUTINE STOPPAGE	BUFFALO BAYOU	494-Z	TX0096172	19-Aug-00			Gallons
		I .							
SOUTHEAST QUAD	2001 JEFFERSON ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-U	TX0096172	20-Aug-00			Gallons
NORTHWEST QUAD	1811 RUIZ	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-M	TX0096172	21-Aug-00			Gallons
NORTHWEST QUAD	11113 KATY FRWY	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-A	TX0096172	21-Aug-00	18:59	705	Gallons
SOUTHEAST QUAD	1806 SUNNYLAND	MAIN LINE STOPPED UP	BUFFALO BAYOU	534-C	TX0096172	22-Aug-00	10:11	10000	Gallons
NORTHWEST QUAD	1500 ANDREW ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-P	TX0096172	25-Aug-00		42	Gallons
SOUTHEAST QUAD	600 COLUMBIA	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-A	TX0096172	25-Aug-00			Gallons
SOUTHEAST QUAD	4704 PEASE ST.	SERVICE & MAIN LINE STOPPED UP	BUFFALO BAYOU	494-Y	TX0096172	25-Aug-00			Gallons
SOUTHEAST QUAD	4609 MARKET	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-F	TX0096172	25-Aug-00			Gallons
NORTHEAST QUAD	4604 E. FRWY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-F	TX0096172	25-Aug-00			Gallons
SOUTHEAST QUAD	4701 BELL	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	26-Aug-00	08:33	34	Gallons
SOUTHEAST QUAD	13 S. WEST OAK DR.	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-L	TX0096172	28-Aug-00	11:55	375	Gallons
NORTHWEST QUAD	10027 WESTVIEW	CITY MAIN STOPPED UP	BUFFALO BAYOU	450-W	TX0096172	28-Aug-00	16:12	506	Gallons
SOUTHEAST QUAD	1420 GOLIAD	MAIN LINE AND SERVICE LINE HOLDING	BUFFALO BAYOU	493-G	TX0096172	28-Aug-00		150	Gallons
SOUTHEAST QUAD	3022 ROSALIE	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	493-Z	TX0096172	29-Aug-00			Gallons
NORTHWEST QUAD	2300 WILCREST	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-T	TX0063002	02-Sep-00			Gallons
NORTHWEST QUAD	547 KICKERILLO	SERVICE LINE OVERFLOWING	BUFFALO BAYOU	488-M	TX0035017	04-Sep-00			Gallons
SOUTHEAST QUAD	2810 BERRY	MAIN LINE STOPPED UP	BUFFALO BAYOU	454-E	TX0096172	07-Sep-00			Gallons
SOUTHWEST QUAD	12827 SKYKNOLL	MAIN LINE STOPPED UP	BUFFALO BAYOU	488-Y	TX0035017	08-Sep-00			Gallons
SOUTHWEST QUAD	2222 W. LOOP S	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-V	TX0063002	12-Sep-00	10:18	1920	Gallons
	5175 HACKLEBERRY								
NORTHWEST QUAD	CIRCLE	MAIN & SERVICE STOPPED UP	BUFFALO BAYOU	491-Q	TX0096172	12-Sep-00	11:25	216	Gallons
NORTHWEST QUADRANT	1510 COLQUITT	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-V	TX0063002	15-Sep-00			Gallons
NORTHWEST QUADRANT	11113 KATY FREEWAY	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-A	TX0063002	15-Sep-00			Gallons
SOUTHEAST QUADRANT	5175 HUCKLEBERRY	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-Q	TX0096172	15-Sep-00			Gallons
SOUTHEAST QUADRANT	600 WACO	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-K	TX0096172	16-Sep-00			Gallons
SOUTHEAST QUAD	7720 GREENWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-V	TX0096172	16-Sep-00			Gallons
NORTHWEST QUAD	1714 HULDY	SERVICE LINE HOLDING	BUFFALO BAYOU	492-R	TX0096172	18-Sep-00		113	Gallons
SOUTHWEST QUAD	2824 BRIARHURST	SERVICE LINE STOPPED UP	BUFFALO BAYOU	491-S	TX0096172	18-Sep-00		262	Gallons
NORTHWEST QUAD	1100 POST OAK BLVD.	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-K	TX0096172	19-Sep-00			Gallons
SOUTHEAST QUADRANT	1800 DISMUKE	MAIN LINE STOPPED UP	BUFFALO BAYOU	534-C	TX0096172	19-Sep-00			Gallons
			_ 5	357 5		. 5 Cop-00		1221	Canons
COLITINATEST CLAS	13858 BEECH HOLLOW	MAIN LINE CTOPPACE	DUEEN O BAYOU	400 1/	TV000504	00.0	00.45	100-	0-"
SOUTHWEST QUAD	LN.	MAIN LINE STOPPAGE	BUFFALO BAYOU	488-X	TX0035017	20-Sep-00			Gallons
NORTHEAST QUAD	4630 CLAY	MAIN LINE & SERVICE LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	20-Sep-00			Gallons
NORTHWEST QUAD	1300 WILCREST	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-P	TX0063002	21-Sep-00	11:50	174	Gallons
	COLDSTREAM @								
	SHAVELSON	SEWER MAIN STOPPED UP	BUFFALO BAYOU	491-C	TX0096172	21-Sep-00	11:15	387	Gallons
SOUTHEAST QUADRANT	211 N. BRYAN	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	23-Sep-00			Gallons
	WOODLEIGH @ SIDNEY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-S	TX0096172	25-Sep-00			Gallons
NORTHEAST QUADRANT									
NORTHEAST QUADRANT NORTHEAST QUAD			BUFFALO BAYOU	492-Z	TX0096172	25-Sep-00			Gallons
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD	1755 COLQUITT	MAIN LINE STOPPED UP		492-T	TX0096172	26-Sep-00	08:38	88	Gallons
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD	1755 COLQUITT 3271 SUL ROSS	MAIN STOPPED UP	BUFFALO BAYOU						
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD	1755 COLQUITT		BUFFALO BAYOU						
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD SOUTHWEST QUAD	1755 COLQUITT 3271 SUL ROSS		BUFFALO BAYOU BUFFALO BAYOU	494-N	TX0096172	26-Sep-00	08:30		Gallons
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD SOUTHWEST QUAD NORTHEAST QUAD	1755 COLQUITT 3271 SUL ROSS PRESTON @ HUTCHESON	MAIN STOPPED UP MAIN STOPPED UP	BUFFALO BAYOU	494-N				350	
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD SOUTHWEST QUAD NORTHEAST QUAD SOUTHEAST QUAD	1755 COLQUITT 3271 SUL ROSS PRESTON @ HUTCHESON 925 N. WILCREST	MAIN STOPPED UP MAIN STOPPED UP MAIN LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU	494-N 489-B	TX0096172	26-Sep-00	12:30	350 130	Gallons
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD SOUTHWEST QUAD NORTHEAST QUAD SOUTHEAST QUAD SOUTHEAST QUAD	1755 COLQUITT 3271 SUL ROSS PRESTON @ HUTCHESON 925 N. WILCREST 3201 DOWLING	MAIN STOPPED UP MAIN STOPPED UP MAIN LINE STOPPED UP SERVICE LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-N 489-B 493-Y	TX0096172 TX0096172	26-Sep-00 26-Sep-00	12:30 16:08	350 130 1536	Gallons
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD SOUTHWEST QUAD NORTHEAST QUAD SOUTHEAST QUAD SOUTHEAST QUAD NORTHWEST QUAD	1755 COLQUITT 3271 SUL ROSS PRESTON @ HUTCHESON 925 N. WILCREST 3201 DOWLING 1714 HULDY	MAIN STOPPED UP MAIN STOPPED UP MAIN LINE STOPPED UP SERVICE LINE STOPPED UP MAIN LINE STOPPAGE	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-N 489-B 493-Y 492-Q	TX0096172 TX0096172 TX0096172	26-Sep-00 26-Sep-00 27-Sep-00	12:30 16:08 13:25	350 130 1536 110	Gallons Gallons Gallons
NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD SOUTHWEST QUAD NORTHEAST QUAD SOUTHEAST QUAD NORTHEAST QUAD NORTHWEST QUAD NORTHWEST QUAD	1755 COLQUITT 3271 SUL ROSS PRESTON @ HUTCHESON 925 N. WILCREST 3201 DOWLING 1714 HULDY 1714 HULDY	MAIN STOPPED UP MAIN STOPPED UP MAIN LINE STOPPED UP SERVICE LINE STOPPED UP MAIN LINE STOPPAGE SEWER MAIN & SERVICE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-N 489-B 493-Y 492-Q 492-Q	TX0096172 TX0096172 TX0096172 TX0096172	26-Sep-00 26-Sep-00 27-Sep-00 27-Sep-00	12:30 16:08 13:25 14:57	350 130 1536 110 164	Gallons Gallons Gallons Gallons
SOUTHEAST QUADRANT NORTHEAST QUADRANT NORTHEAST QUAD SOUTHEAST QUAD SOUTHWEST QUAD NORTHEAST QUAD SOUTHEAST QUAD SOUTHEAST QUAD NORTHWEST QUAD NORTHWEST QUAD SOUTHEAST QUAD SOUTHEAST QUAD	1755 COLQUITT 3271 SUL ROSS PRESTON @ HUTCHESON 925 N. WILCREST 3201 DOWLING 1714 HULDY	MAIN STOPPED UP MAIN STOPPED UP MAIN LINE STOPPED UP SERVICE LINE STOPPED UP MAIN LINE STOPPAGE	BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU BUFFALO BAYOU	494-N 489-B 493-Y 492-Q	TX0096172 TX0096172 TX0096172	26-Sep-00 26-Sep-00 27-Sep-00	12:30 16:08 13:25 14:57	350 130 1536 110 164	Gallons Gallons Gallons Gallons Gallons

Problem NORTHWEST QUAD	Location 5085 FIELDWOOD	Description MAIN LINE STOPPED UP	Receiving stream BUFFALO BAYOU	Key map 491-Q	Permit TX0096172	Date 29-Sep-00	13:10	Volume 55	Unit Gallons
		OVER FLOW FROM SAMPLE WELL CAUSEING							
NORTHWEST QUADRANT NORTHEAST QUAD	500 LAMAR 4616 NICHOL	EXCURSION MAIN LINE STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU	493-L 494-B	TX0096172 TX0096172	29-Sep-00 02-Oct-00			Gallon
NORTHEAST QUAD	4402 WALKER	MAIN STOPPED UP	BUFFALO BAYOU	494-D 494-T	TX0096172	02-Oct-00			Gallon
NORTHEAST QUAD	118 NAGLE	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-N	TX0096172	02-Oct-00			Gallor
NORTHEAST QUAD	1413 ELLIOTT	MAIN STOPPED UP	BUFFALO BAYOU	494-X	TX0096172	03-Oct-00			Gallor
SOUTHWEST QUAD	2606 S. SHEPHERD	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-U	TX0096172	04-Oct-00			Gallor
NORTHEAST QUAD	5914 HARRISBURG	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-U	TX0096172	05-Oct-00	17:20	1290	Gallor
NORTHEAST QUAD	6626 SHERMAN	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-V	TX0096172	07-Oct-00	22:16	205	Gallor
NORTHEAST QUAD	215 MILBY	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	09-Oct-00	09:00	2874	Gallor
SOUTHEAST QUAD	6111 DEL RIO	MAIN LINE STOPPED UP	BUFFALO BAYOU	533-G	TX0096172	10-Oct-00			Gallor
SOUTHWEST QUAD	3412 CRAWFORD	LINE STOPPED UP WITH GREASE	BUFFALO BAYOU	493-T	TX0096172	11-Oct-00			Gallor
SOUTHEAST QUAD	5642 BRIAR DR.	MAIN STOPPED UP	BUFFALO BAYOU	491-F	TX0096172	11-Oct-00			Gallor
NORTHEAST QUAD	WACO @ SANDICK	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-F	TX0096172	11-Oct-00			Gallor
NORTHEAST QUAD NORTHEAST QUAD	5602 LYONS AV. 6600 NERDLING	SERVICE LINE HOLDING SEWER MAIN STOPPED UP	BUFFALO BAYOU BUFFALO BAYOU	494-G 413-W	TX0035106 TX0096172	12-Oct-00 12-Oct-00			Gallor
NORTHEAST QUAD	7000 NAVIGATION	ROUTINE STOPPAGE	BUFFALO BAYOU	494-V	TX0096172	12-Oct-00			Gallor
NORTHWEST QUAD	3540 W. DALLAS	MAIN LINE HAD STOPPAGE	BUFFALO BAYOU	492-M	TX0096172	12-Oct-00			Gallor
NORTHEAST QUAD	912 PRESS ST.	BROKEN MAIN LINE	BUFFALO BAYOU	494-F	TX0096172	14-Oct-00			Gallor
	4020 MEADOWLAKE			1.4.1					-
NORTHWEST QUAD	LANE	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-N	TX0096172	15-Oct-00	08:50	500	Gallor
SOUTHEAST QUAD	2812 WICHITA	SERVICE LINE STOPPED UP	BUFFALO BAYOU	533-C	TX0096172	15-Oct-00			Gallor
NORTHEAST QUAD	211 N. BRYAN	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-P	TX0096172	16-Oct-00			Gallor
SOUTHWEST QUAD	3262 BRANARD	SERVICE LINE STOPPED UP	BUFFALO BAYOU	492-T	TX0096172	16-Oct-00			Gallor
NORTHEAST QUAD	1719 BOUNDARY	COMMUNITY LINE STOPPED UP	BUFFALO BAYOU	493-C	TX0096172	16-Oct-00			Gallor
NORTHWEST QUAD	626 OMAR	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-B	TX0096172	17-Oct-00			Gallor
SOUTHEAST QUAD	4530 WALKER	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-T	TX0096172	18-Oct-00			Gallor
NORTHWEST QUAD	3371 CHEVY CHASE	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-P	TX0096172	18-Oct-00			Gallor
NORTHEAST QUAD	950 VILLA DE MATEL	MAIN LINE STOPPAGE	BUFFALO BAYOU	494-Y	TX0096172	19-Oct-00			Gallor
NORTHEAST QUAD		MAIN LINE HAS STOPPAGE	BUFFALO BAYOU	494-W	TX0096172	19-Oct-00			Gallor
NORTHEAST QUAD	4732 RUSK	MANHOLE OVERFLOWING	BUFFALO BAYOU	494-T	TX0096172	20-Oct-00			Gallor
SOUTHWEST QUAD	6000 RICHMOND AVE.	MAIN AND SERVICE LINE STOPPED UP	BUFFALO BAYOU	491-X	TX0096172	21-Oct-00			Gallor
NORTHWEST QUAD	916 SNOVER	COMMUNITY LINE	BUFFALO BAYOU	492-H	TX0096172	21-Oct-00			Gallor
SOUTHWEST QUAD	2606 SHEPHERD	STOPPAGE IN MAIN LINE	BUFFALO BAYOU BUFFALO BAYOU	492-U	TX0096172	21-Oct-00			Gallor
SOUTHEAST QUAD	1400 LUBBOCK	SERVICE LINE STOPPED UP ROUTINE STOPPAGE		493-K	TX0096172	24-Oct-00			Gallor
NORTHEAST QUAD NORTHEAST QUAD	4220 WOODLEIGH 7006 AVENUE C	STOPPAGE IN MAIN LINE	BUFFALO BAYOU BUFFALO BAYOU	494-S 494-V	TX0096172 TX0096172	24-Oct-00 24-Oct-00			Gallor
NORTHEAST QUAD	211 BRYAN	MAIN AND SERVICE LINE HOLDING	BUFFALO BAYOU	494-V 494-P	TX0096172	24-Oct-00			Gallor
NONTHEAST QUAD	ZII BRIAN	INAIN AND SERVICE LINE HOLDING	BOFFALO BATOO	494-1	170090172	24-001-00	09.45	203	Gallor
SOUTHEAST QUAD	2222 W. LOOP FREEWAY	MAIN LINE STOPPED LIP	BUFFALO BAYOU	491-V	TX0096172	25-Oct-00	14.25	2460	Gallon
NORTHEAST QUAD	7118 TUCK	MAIN LINE HAD STOPPAGE	BUFFALO BAYOU	494-N	TX0096172	25-Oct-00			Gallon
NORTHWEST QUAD	1516 ALAMO	MAIN LINE STOPPED UP	BUFFALO BAYOU	493-F	TX0096172	26-Oct-00			Gallon
NORTHEAST QUAD	7415 EL PASO	MAIN LINE STOPPED UP	BUFFALO BAYOU	495-E	TX0096172	26-Oct-00			Gallon
NORTHWEST QUAD	5238 CEDAR CREEK	MAIN LINE STOPPAGE	BUFFALO BAYOU	491-Q	TX0096172	26-Oct-00			Gallon
	COSTA RICA @ LA								
NORTHEAST QUAD	MONTE	ROUTINE STOPPAGE	BUFFALO BAYOU	451-L	TX0096172	26-Oct-00	15:25	78	Gallon
SOUTHEAST QUAD	1510 COLQUITT	MAIN LINE AND SERVICE LINE STOPPED UP	BUFFALO BAYOU	492-V	TX0096172	27-Oct-00	08:14	740	Gallon
NORTHEAST QUAD	5820 GANO	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-B	TX0063011	28-Oct-00	14:12	284	Gallor
NORTHEAST QUAD	900 ELEANOR	MAIN LINE STOPPED UP	BUFFALO BAYOU	453-V	TX0063011	28-Oct-00	14:03	242	Gallor
NORTHEAST QUAD	215 LENNOX	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-Q	TX0096172	28-Oct-00	08:46	92	Gallor
SOUTHEAST QUAD	4320 WATSON	MAIN OVERFLOWING INTO STORM SEWER	BUFFALO BAYOU	453-X	TX0096172	29-Oct-00			Gallor
NORTHWEST QUAD	835 HEIGHTS	MAIN LNE AND SERVICE LINE HOLDING	BUFFALO BAYOU	492-D	TX0096172	29-Oct-00			Gallor
SOUTHWEST QUAD	219 MARSHALL	SERVICE LINE STOPPED UP	BUFFALO BAYOU	493-T	TX0096172	29-Oct-00			Gallor
SOUTHWEST QUAD	7992 LOCKE LN.	SEWER MAIN STOPPED UP	BUFFALO BAYOU	490-V	TX0096172	29-Oct-00			Gallor
SOUTHWEST QUAD	4627 WARNING ST.	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-Z	TX0062995	30-Oct-00			Gallor
NORTHWEST QUAD	1802 BRUN	CITY MAIN STOPPED UP	BUFFALO BAYOU	492-Q	TX0096172	30-Oct-00			Gallor
NORTHEAST QUAD	211 N. BRYAN 7331 FARNSWORTH	MAIN LINE AND SERVICE LINE HOLDING	BUFFALO BAYOU BUFFALO BAYOU	494-P	TX0096172	30-Oct-00			Gallor
NORTHEAST QUAD NORTHWEST QUAD		MAIN LINE STOPPED UP MAIN STOPPED UP	BUFFALO BAYOU	453-L 491-C	TX0096172 TX0096172	30-Oct-00 30-Oct-00			Gallor
SOUTHEAST QUAD	1406 JAMES	MAIN LINE STOPPED UP	BUFFALO BAYOU	491-C 493-H	TX0096172	30-Oct-00			Gallor
COUTTLAUT QUAD	1-00 UNIVILO	IN ANY LINE OTOLI ED OI	BOITALO BATOU	700711	170030172	31-001-00	10.24	513	Janul
NORTHWEST QUAD	2520 PANAMA @ FULTON	MANHOLE OVERFLOWING INTO STORM SEWER	BUFFALO BAYOU	493-D	TX0096172	01-Nov-00	10:30	480	Gallon
NORTHEAST QUAD	6844 AVENUE O	MAIN LINE STOPPED UP	BUFFALO BAYOU	494-V	TX0096172	01-Nov-00			Gallor
NORTHEAST QUAD	782 FAWN DR.	MAIN LINE STOPPED UP	BUFFALO BAYOU	496-D	TX0096172	01-Nov-00			Gallor
NORTHWEST QUAD	8800 LONG POINT	CITY MAIN STOPPED UP AND OVERFLOWING	BUFFALO BAYOU	450-V	TX0096172	02-Nov-00			Gallor
NORTHEAST QUAD	7141 AVENUE C ST.	OVERFLOW INTO DITCH	BUFFALO BAYOU	494-Z	TX0096172	02-Nov-00			Gallor
NORTHWEST QUAD	2011 DREXEL	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-N	TX0096172	02-Nov-00	21:12	903	Gallor
NORTHWEST QUAD	12633 MEMORIAL	MAIN LINE STOPPED UP	BUFFALO BAYOU	489-G	TX0063002	03-Nov-00			Gallor
SOUTHWEST QUAD	322 WESTHEIMER	STOPPAGE IN MAIN LINE	BUFFALO BAYOU	493-S	TX0096172	05-Nov-00			Gallor
NORTHWEST QUAD	1037 GESSNER	MAIN STOPPED UP	BUFFALO BAYOU	490-J	TX0096172	05-Nov-00			Gallor
NORTHWEST QUAD	1037 GESSNER	MAIN STOPPED UP	BUFFALO BAYOU	490-J	TX0096172	05-Nov-00			Gallor
SOUTHWEST QUAD	2510 WILLOWICK	MAIN LINE STOPPED UP	BUFFALO BAYOU	492-S	TX0096172	06-Nov-00			Gallor
NORTHEAST QUAD	3713 JENSEN	MANHOLE OVERFLOWING CAUSING EXCURSION	BUFFALO BAYOU	454-W	TX0096172	07-Nov-00			Gallor
NORTHEAST QUAD	1121 TERMINAL	SERVICE LINE OVERFLOWING	BUFFALO BAYOU	494-V	TX0096172	07-Nov-00			Gallor
NORTHEAST QUAD	215 N. MILBY ST.	SERVICE LINE OVERFLOWING	BUFFALO BAYOU	494-P	TX0096172	07-Nov-00			Gallor
NORTHEAST QUAD		MAIN LINE STOPPED UP	BUFFALO BAYOU	494-S	TX0096172	08-Nov-00			Gallor
NORTHEAST QUAD	6815 ROSWELL	MAIN LINE OVERELOWING INTO STREET	BUFFALO BAYOU	453-Q	TX0096172	09-Nov-00			Gallor
NORTHWEST QUAD NORTHEAST QUAD	19 CRESTWOOD 1817 DUMBLE	MAIN LINE OVERFLOWING INTO STREET MAIN LINE STOPPAGE	BUFFALO BAYOU BUFFALO BAYOU	492-K	TX0096172 TX0096172	10-Nov-00 10-Nov-00			Gallor Gallor
NORTHEAST QUAD		MAIN LINE STOPPED UP	BUFFALO BAYOU	494-X 491-K	TX0096172 TX0063002	10-Nov-00 11-Nov-00			Gallor
NORTHEAST QUAD	10333 EAST FREEWAY	BROKEN CONNECTION OVER MAIN LINE	BUFFALO BAYOU	491-K	TX0063002	12-Nov-00			Gallor
WASTEWATER	10000 LAGT FREEWAT	STOTELY CONTRECTION OVER WAIN LINE	POLI ALO BATOU	490-E	170090172	12-140V-UU	12.30	3/68	Janor
OPERATIONS	1147 ENCLAVE PARKWAY	DRAIN WAS LEFT OPEN AND #3 LP TRIPPED.	BUFFALO BAYOU	488-G	TX0035017			2600	Gallor
SOUTHWEST QUAD	790 BATEWOOD	MAIN LINE STOPPED UP	BUFFALO BAYOU					2000	Janoi
			_ 5						
		MANHOLE STOPPED UP AND OVERFLOWING INTO							
NORTHWEST QUADRANT	8903 LANGFIELD	STORMSEWER	WHITE OAK BAYOU	410-V	TX0063011	22-Jan-96	07:00	2105	Gallon
	İ	SEWER MAIN STOPPAGE UP->OVERFLOW FROM							
			WHITE OAK BAYOU	1	TX0096172	29-Jan-96		13750	

			DL Project-Contract#						
Problem	Location	Description STOPPAGE IN WASTWATER MAIN, CAUSING	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
	611 W. LITTLE YORK	WASTEWATER TO	WHITE OAK BAYOU	411-V	TX0096172	15-Feb-96			Gallons
NORTHWEST QUADRANT	2000 THONING	8" MAIN STOPPED-UP.	WHITE OAK BAYOU	451-T	TX0057347	13-Mar-96	14:17	280	Gallons
NORTHWEST QUADRANT	10200 FIELD STONE	SEWER MAN STOPPED UP CAUSING SEWER OVERFLOW VIA A	WHITE OAK	450-E	TX0096172	18-Mar-96	18∙∩1	99.5	Gallons
HORTINEOT GONDRAIT	10200 TILLED GTONE	BROKEN SEWER MAIN 8' DISCHARGING RAN SEWER	Willie O/at	100 L	17.0000172	10 14101 50	10.01	55.5	Calloris
NORTHWEST QUADRANT	400 MERRILL	INTO	WHITE OAK BAYOU	493-B	TX0096172	18-Mar-96			Gallons
NORTHWEST QUADRANT	7300 KATY FRWY.	ROUTINE STOPPAGE ILLEGAL HOOK-UP ON PRIVATE	WHITE OAK BAYOU	492-B	TX0096172	22-Mar-96	13:24	3.5	Gallons
NORTHWEST QUADRANT	4843 GOLDEN FOREST	PROPERTY.CAUSING WW TO	WHITE OAK	451-G	TX0057347	23-Mar-96	10:15	1	GALLO
WASTEWATER OPERATION		FORCE LINE BROKEN	WHITE OAK BAYOU	492-H	TX0096172	02-Apr-96			Gallons
NODTH WEST OUT DO ANT	400 MEOT MUUTNEY	SEWER MAIN STOPPED UP CAUSING SEWER	MULTE CALL DAYOU	450 1	TV0057047	00.400	00.45		0.11
NORTHWEST QUADRANT NORTHWEST QUADRANT	100 WEST WHITNEY 5500 DESOTO	OVERFLOW MAIN LINE OVERFLOWING INTO S SEWER	WHITE OAK BAYOU WHITE OAK BAYOU	453-J 451-C	TX0057347 TX0096172	08-Apr-96 11-Apr-96			Gallons Gallons
	826 WOODLAND AT 800	6"SEWER LINE STOPPED UP CAUSING SEWER TO	WHITE OF ARE BY COO	4010	17.0000172	11740100	10.20	010	Calloris
NORTHWEST QUADRANT	EUCLID	OVERFLOW	WHITE OAK BAYOU	493-B	TX0057347	16-Apr-96	10:37	153	Gallons
NORTHWEST QUADRANT	2200 STUDEWOOD AT ADELL	BROKEN SEWER MAIN CAUSED RAW SEWER TO GET IN MAIN	WHITE OAK BAYOU	453-S	TX0057347	18-Apr-96	11:00	12200	GALL
NORTHWEST QUADRANT	ADELL	ROUTINE STOPPAGE-GOING INTO WHITE OAK	WITTE OAK BATOO	400-0	170037347	10-Ap1-90	11.00	12300	GALL
NORTHWEST QUADRANT	1806 STORY	BAYOU	WHITE OAK BAYOU	451-Y	TX0057347	03-May-96	13:31	1008	Gallons
NODTH WEST OUT DO ANT	404 E TIDINELI	STOPPAGE IN SEWER LINE WHICH CAUSED	MAILUTE OAK DAYOU	450.5	TV0000470	05.14	10.00	0050	0.11
NORTHWEST QUADRANT	101 E. TIDWELL	WASTEWATER TO STOPPED UP SEWER LINE RECEIVING INTO STORM	WHITE OAK BAYOU	453-E	TX0096172	05-May-96	13:03	3250	Gallons
NORTHWEST QUADRANT	1015 PEDDIE	SEWER	WHITE OAK BAYOU	453-X	TX0096172	06-May-96	13:07	413	Gallons
NORTHWEST QUADRANT	1600 STUDEWOOD	STOPPAGE IN SEWER LINE	WHITE OAK BAYOU	453-B	TX0096172	25-May-96	14:00	1580	Gallons
NORTHWEST OF A DRANT	9400 MAIN CT	MAIN SEWER LINE STOPGE;WW FLOW IN THE	WHITEOAK BAYOU	452 N	TV0006172	20 Jun 06	11.17	100	Gallons
NORTHWEST QUADRANT	8100 MAIN ST.	SYSTEM MAIN STOPPAGE OVERFLOWING RAW SEWER INTO	WHITEOAK BAYOU	453-N	TX0096172	20-Jun-96	11:47	180	Gallons
NORTHWEST QUADRANT	900 WINSTON	BAYOU	WHITE OAK BAYOU	453-X	TX0096172	26-Jun-96			Gallons
NORTHWEST QUADRANT	1000 W. 20TH STREET	SEWER MAIN HAS STOPPAGE.	WHITE OAK BAYOU	452-V	TX0096172	06-Jul-96			Gallons
	800 W.16 @ 1500 DIANE	MAIN STOPPED UP CAUSING SEWER OVERFLOW	WHITE OAK BAYOU	452-Y	TX0096172	09-Jul-96			Gallons
	800 W. 16 AT DIANE 4401 AIRLINE	SEWER MAIN STOPPED UP CAUSING OVERFLOW STOPPAGE IN SEWER LINE	WHITE OAK BAYOU WHITE OAK BAYOU	452-Y 453-K	TX0096172 TX0057347	18-Jul-96 24-Jul-96			Gallons Gallons
NORTHWEST QUADRAINT	4401 AIRLINE	BROKEN 6"X7' SEWER MAIN CAUSED STOPPAGE &	WITTE OAK BATOO	455-10	170037347	24-Jul-90	10.23	2040	Galloris
NORTHWEST QUADRANT	1500 W. 43	O/F.	WHITE OAK BAYOU	452-E	TX0096172	14-Aug-96	09:05	875	Gallons
NORTHWEST QUADRANT	3814 GARDENDALE	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-N	TX0096172	09-Sep-96		6000	Gallons
NORTHWEST QUADRANT	7822 MAPLE TREE	SEWER STOPPED - UP	WHITE OAK BAYOU	411-Q	TX0057347	15-Sep-96	21:10	1228	Gallons
NORTHEAST OLIADRANT	TRAVIS AND COMMERCE	DOSCODI E CAVE IN OR STORDAGE	WHITE OAK BAYOU	402	TV0006172	10 Con 06	10:20	200000	Callona
	MAIN AND WOOD	POSSOBLE CAVE-IN OR STOPPAGE	WHITE OAK BAYOU	493-L	TX0096172	19-Sep-96	10:20	288000	Gallons
	STREET	POSSIBLE CAVE-IN OR STOPPAGE.	WHITE OAK BAYOU	493-M	TX0096172	19-Sep-96	10:30	288000	Gallons.
	910 BYRON	STOPPED UP 6" SEWER MAIN CAUSING OVERFLOW.		493-B	TX0996172	19-Oct-96			Gallons
NORTHWEST QUADRANT	3635 ABINGER	8X10 MN. STOPPED UP SEWER LINE. OVERFLOW FROM MANHOLE ENTERING STORM	WHITE OAK BAYOU	411-R	TX0057347	26-Dec-96	21:15	3300	Gallons
NORTHWEST QUADRANT	4000 W. 34TH	DRAIN.	WHITE OAK BAYOU	451-R	TX0057347	18-Jan-97	13:12	7004	Gallons
		EXCESSIVE RAINFALL COLLECTION SYSTEM							
NORTHEAST QUADRANT	1200 WRIGHTWOOD	OVERFLOWING.	WHITE OAK BAYOU	493-C	TX0096172	27-Jan-97	20:00	640000	Gallons
NORTHWEST QUADRANT	1300 WRIGHTWOOD	TUNNEL SYSTEM HYDRAULIC OVERLOAD DUE TO HEAVY RAIN	WHITE OAK BAYOU	493-C	TX0096172	12-Feb-97	15:58	32600	Gallons
	1000 11111000	TUNNEL SYSTEM HYDRAULIC OVERLOAD DUE TO		100 0	17.0000112	12 1 00 01	10.00	02000	Camorio
NORTHWEST QUADRANT	1500 WHITE OAK DRIVE	HEAVY RAIN	WHITE OAK BAYOU	493-C	TX0096172	12-Feb-97	15:58	32600	Gallons
NODTHWEST OHADDANT	240 EMPDY	24" BROKEN SEWER MAIN CAUSED SEWAGE TO	MULTE OAK BAYOU	400.0	TV0000470	00 E-1 07	00.40	04.4	0-11
	319 EMBRY 9303 GUYWOOD	OVERFLOW 8x8 ROUTINE STOPPAGE	WHITE OAK BAYOU WHITE OAK BAYOU	493-C 410-V	TX0096172 TX0057347	20-Feb-97 22-Feb-97			Gallons Gallons
	10100 PINE MOSS	STOPPAGE IN AN 8"X12' CONCRETE SEWER MAIN.	WHITE OAK BAYOU	411-J	TX0057347	24-Feb-97			Gallons
NORTHWEST QUADRANT	4808 YALE	6"x6' STOPPED-UP MAIN CAUSED OVERFLOW	WHITE OAK BAYOU	452-H	TX0057347	31-Mar-97			Gallons
	1400 WHITE OAK AT								
NORTHWEST QUADRANT	HOUSTON AVE.	HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL	WHITE OAK BAYOU	493-C	TX0096172	04-Apr-97	07:00	60000	Gallons
NORTHWEST QUADRANT	10010 PINE MOSS DRIVE	BROKEN 8" X 6' SEWER MAIN STOPPED-UP CAUSING O/FL.	WHITE OAK BAYOU	411-N	TX0057347	15-Apr-97	11:37	2370	Gallons
		HYDRAULIC OVERLOAD DUE TO HEAVY RAINFALL. 2-							
WASTEWATER OPERATION		HR PK.	WHITE OAK BAYOU	450-A	TX0026875	22-May-97		60000	Gallons
WASTEWATER OPERATION		2 HOUR PEAK FLOW	WHITE OAK BAYOU	450-A	TX0026875	24-May-97		0	
WASTEWATER OPERATION	102/3 GERARD	2 HOUR PEAK FLOW RAS PUMP HAD STOPPAGE, SLUDGE SPILL OF	WHITE OAK BAYOU	450-A	TX0026875	25-May-97	11:00	0	
WASTEWATER OPERATION	10273 GENARD	MANHOLE	WHITE OAKS BAYOU	450-A	TX0026875	01-Jul-97	11:00	2000	Gallons
		PUMP SEWER MAIN OVERFLOW INTO STORM							
NORTHWEST QUADRANT	2322 PARANA	SEWER MAIN.	WHITE OAK BAYOU	450-P	TX0063002	03-Jul-97	12:30	5500	Gallons
NODTHWEST OF 14 DD 44 T	1002 CHAMBOARD @	MANHOLE OVERFLOWED DUE TO STOPPAGE IN THE		452.1	TV0000470	22 4	11.11	2004	Call
	ALBA 6006 NORTH FREEWAY	LINE.	WHITE OAK BAYOU	452-L 453-A	TX0096172	22-Aug-97			Gallons Gallons
NORTHWEST QUADRANT WASTEWATER OPERATION		8' X 12" ROUTINE STOPPAGE. 2 - HOUR PEAK	WHITE OAK BAYOU WHITE OAK BAYOU	450-A	TX0026875 TX0026875	13-Sep-97 22-Sep-97			MGD
		HEAVY RAINFALL SURCHARGED SYSTEM CAUSING							
NORTHWEST QUADRANT	1500 WHITE OAK DRIVE	OVERFLOW.	WHITE OAK BAYOU	493-B	TX0096172	23-Sep-97	13:45	36000	Gallons
NORTHEAST QUADRANT	1000 ALBER	SEWER MAIN STOPPED-UP CAUSING OVERFLOW INTO S/S.	WHITE OAK BAYOU	453-Z	TX0057347	25-Sep-97	10:43	150	Gallons
HOATILAGI QUADRANI	1000 ALDEN	8"* 9" SEWER MAIN BROKE , STOPPED-UP CAUSING	WHILL OAK BATOU	-100°L	170001341	20-0ep-97	10.43	403	Janons
NORTHEAST QUADRANT	64 WELFORD	O-L.	WHITE OAK	453-F	TX096172	23-Nov-97	10:15	11655	GAL
									Undeter
	3800 FULTON 3913 HAIN AT 3400	SURCHARGED SYSTEM.	WHITE OAK BAYOU	453-Y	TX0096172	07-Jan-98	06:30	0	mined
	FULTON.	MAIN LINE STOPPED UP.	WHITE OAK BAYOU	453-Y	TX0026875	09-Jan-98	16:36		40 GPM
		ROUTINE STOPPED UP.	WHITE OAK BAYOU	411-T	TX0026675	30-Jan-98		855	Gallons
	500 CROSSTIMBERS	GREASE IN LINE.	WHITE OAK BAYOU	452-M	TX0063011	30-Jan-98			Gallons
	500 WSET	SEWER LINE COLLAPSED BLOCKED MAIN AND							
NORTHWEST QUADRANT	CROSSTIMBERS	CAUSING O.F.	WHITE OAK BAYOU	452-M	TX0063011	03-Feb-98	14:30	415	Gallons
NORTHWEST QUADRANT	1700 SAWYER	STOPPAGE IN THE LINE CAUSING SEWER OVERFLOW.	WHITE OAK BAYOU	493-F	TX0096172	03-Feb-98	14.22	5.4	Gallons
THORTING QUADRANT	1700 OAWIER	BROKEN SEWER MAIN STOPPED-UP AND CAUSING	WHILE OAK BATOU	730-1	170030172	00-1-60-90	17.22	34	JailUIS
NORTHEAST QUADRANT	601 AVENUE OF OAKS	OVERFLOW.	WHITE OAK BAYOU	453-U	TX0096172	03-Feb-98	12:51	3	Gallons
							_	_	

Problem	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
NORTHWEST QUADRANT	600 WEST 6th	SEWER MAIN LINE STOPPAGE-UP CAUSING OVERFLOW.	WHITE OAK BAYOU	492-D	TX0096172	04-Feb-98	18:02	290	Gallons
NORTHWEST QUADRANT	1332 WEST 25	SEWER STOPPAGE	WHITE OAK BAYOU	452-U	TX0096172	04-Feb-98			Gallons
		SEWER MAIN HAD STOPPAGE WHICH CAUSED AN							
NORTHWEST QUADRANT	701 USENER	EXCURSION.	WHITE OAK BAYOU	439-B	TX0063011	08-Feb-98	18:18	23.5	Gallons
NORTHWEST QUADRANT	515 HIGHLAND	STOPPED UP SEWER MAIN, FLOWING INTO STORM SEWER.	WHITE OAK BAYOU	493-B	TX0057347	11-Feb-98	09:25	54	Gallons
		SEWER MAIN STOPED UP AND OVERFLOWING INTO							
NORTHWEST QUADRANT	1828 LYNNVIEW	SEWER.	WHITE OAK BAYOU	451-S	TX0063011	12-Feb-98	08:18	205	Gallon
ORTHEAST QUADRANT	3200 NORTH MAIN	ROUTINE STOPPAGE.	WHITE OAK BAYOU	493-C	TX0096172	14-Feb-98	14:18	156	Gallon
NORTHWEST QUADRANT	1839 SALFORD	SEWER MAIN STOPPED-UP CAUSING OVER FLOW.	WHITE OAK BAYOU	452-S	TX0057347	18-Feb-98	10:39	690	Gallon
NORTHWEST QUADRANT	7028 ANTOINE	MAIN LINE STOPPED-UP CAUSING OVERFLOW.	WHITE OAK BAYOU	411-Y	TX0057347	18-Feb-98	10:01	24	Gallon
		STOPPAGE IN SEWER MAIN CAUSING AN							
NORTHWEST QUADRANT	5411 LONG CREEK	OVERFLOW.	WHITE OAK BAYOU	411-U	TX0057347	19-Feb-98	11:35	60	GALS
NORTHWEST QUADRANT	522 HEIDRIDGE	MAIN LINE STOPPED UP.	WHITE OAK BAYOU	452-M	TX0057347	23-Feb-98	11:12	500	Gallon
NORTHWEST QUADRANT	249 NORVIEW	MAIN LINE STOPPED STOPPED UP.	WHITE OAK BAYOU	452-H	TX0057347	23-Feb-98	08:58	1270	Gallon
	510 TABOR & 506								
NORTHWEST QUADRANT	WALTRIP	8 X 15 SEWER MAIN STOPPED-UP. SEWER MAIN STOPPED UP & OVERFLOWING INTO	WHITE OAK BAYOU	453-X	TX0096172	23-Feb-98	12:00	380	Gallon
NORTHWEST QUADRANT	4000 GOLF DRIVE	S/SEWER.	WHITE OAK BAYOU	452-L	TX0057347	27-Feb-98	11:10	110	Gallon
		SEWER MAIN STOPPED-UP AND OVERFLOWING							
NORTHWEST QUADRANT	1200 CHANTILLY	INTO STORM/D	WHITE OAK BAYOU.	452-K	TX0057347	18-Mar-98	08:48	282	Gallon
NORTHWEST QUADRANT	431 RED RIPPLE ROAD	SEWER MAIN STOPPED-UP.	WHITE OAK BAYOU	452-D	TX0057347	19-Mar-98	11:59	420	Gallon
		SEWER MAIN STOPPED-UP DUE TO A DAMAGED							
NORTHWEST QUADRANT	3300 FULTON	MAIN.	WHITE OAK BAYOU.	453-Y	TX0026875	03-Apr-98			Gallons
NORTHWEST QUADRANT	768 WORTHSHIRE	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	WHITE OAK BAYOU	492-C	TX0026875	05-Apr-98			Gallon
NORTHWEST QUADRANT	1920 W. 18th	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	WHITE OAK BAYOU	452-T	TX0026875	08-Apr-98			Gallon
NORTHWEST QUADRANT	2721 NORTH SHEPHERD	SEWER MAIN STOPPED UP.	WHITE OAK BAYOU	452-V	TX0057347	10-Apr-98	10:28	40	Gallon
		PUMP STATION FAILED CAUSING MANHOLE TO	l	1	L				
NORTHWEST QUADRANT	1522 GLEN OAKS	OVERFLOW.	WHITE OAK BAYOU	492-C	TX0096172	23-Apr-98			Gallon
NORTHWEST QUADRANT	3000 CRESDALE	SEWER MAIN STOPPED-UP AND OVERFLOWING .	WHITE OAK BAYOU	450-K	TX0057347	28-Apr-98	08:26	1600	Gallon
	4400 NORTH SHEPHERD								
NORTHWEST QUADRANT	@ QUALEY	SEWER MAIN STOPPED-UP CAUSING OVERFLOW. STOPPAGE IN THE LINE CAUSING OVERFLOW INTO	WHITE OAK BAYOU	452-M	TX0057347	07-May-98	14:04	660	Gallons
NORTHWEST QUADRANT	1002 WEST CAVACADE	S/SEWER	WHITE OAK BAYOU	453-T	TX0057347	11-May-98	11:27	106	Gallons
		SEWER MAIN STOPPED-UP CAUSING OVERFLOW							
NORTHWEST QUADRANT	5710 YALE	FROM M/HOLE PRIVATE SEPTIC TANK TAPPED INTO STORM SEWER	WHITE OAK BAYOU	452-D	TX0057347	18-May-98	12:10	435	Gallons
NORTHWEST QUADRANT	4512 PINEMONT STREET	MAIN.	WHITE OAK BAYOU	451-H	TX0063011	22-May-98	10:35	155	Gallons
		SEWER MAIN SURCHARGED DUE TO STOPPAGE &							
NORTHWEST QUADRANT	8700 VARNER	OVERFLOWED	WHITE OAK BAYOU	450-V	TX0057347	02-Jun-98	12:58	330	Gallons
NORTHWEST QUADRANT	3135 CRESTDALE	SEWER MAIN SURCHARGED DUE TO STOPPAGE.	WHITE OAK BAYOU	450-K	TX0057347	17-Jun-98	13:28	60	Gallons
		SEWER MAIN STOPPED-UP AND CAUSING							
NORTHEAST QUADRANT	8700 MADIE DRIVE	OVERFLOW.	WHITE OAK BAYOU	453-F	TX0096172	17-Jun-98	09:04	725	Gallons
	8012 RAVENWOOD								
NORTHEAST QUADRANT	CIRCLE	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	WHITE OAK BAYOU	451-S	TX0057347	05-Aug-98	10:07	60	Gallons
		SEWER MAIN STOPPED-UP CAUSING UNAVOIDABLE							
NORTHWEST QUADRANT	1518 GLEN OAKS	VOERFLOW	WHITE OAK BAYOU	492-C	TX0057347	23-Aug-98	15:11	2220	Gallons
		LATERAL LINE STOPPED-UP CAUSING OVERFLOW							
NORTHWEST QUADRANT	800 NORTH DURHAM	FROM C/OT	WHITE OAK BAYOU	432-Y	TX0057347	26-Aug-98			Gallons
NORTHWEST QUADRANT	100 W. TIDWELL	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-D	TX0096172	31-Aug-98			Gallons
NORTHWEST QUADRANT	9235 PECOS	SEWER LINE STOPPED-UP	WHITE OAK BAYOU	450-Y	TX0096172	30-Oct-98	13:10	480	Gallons
		48" SEWER LINE SURCHARGED AND OVERFLOWING							Undete
NORTHWEST QUADRANT	WATSON AND RIDGE	INTO 6 MANHOL	WHITE OAK BAYOU	493-B	TX0096172	13-Nov-98			mined
NORTHWEST QUADRANT	309 THORNTON	SEWER MAIN STOPPED-UP AND VERFLOWED.	WHITE OAK BAYOU	452-M	TX0057347	19-Nov-98	08:10	3200	Gallon
	3125 CRESTDALE			.=					
NORTHWEST QUADRANT	STREET	STOPPAGE IN SEWER MAIN CAUSED OVERFLOW.	WHITE OAK BAYOU	450-K	TX0057347	03-Dec-98	11:57	7800	Gallons
NORTHEAST OLIADBANT	4404 EDISON	UNAVOIDABLE RAW SEWER DISCHARGE DUE	WHITE OAK BAYOU	453-Y	TX0096172	20 Dec 00	10.20	174	Callons
NORTHEAST QUADRANT NORTHWEST QUADRANT	4401 EDISON 7032 ANTOINE	STOPPAGE IN THE LIN ROUTINE STOPPAGE.	WHITE OAK BAYOU	453-Y 411-Y	TX0096172	29-Dec-98			Gallons
NORTHWEST QUADRANT	1001 USENER AT	UNAVOIDABLE RAW SEWAGE DICHARGE DUE TO	WHITE OAK BATOU	411-1	170057347	21-Jan-99	11.22	1090	Gallons
NORTHWEST QUADRANT	MICHAUX	LINE STOPPAGE	WHITE OAK BAYOU	493-B	TX0096172	26-Jan-99	12:55	924	Gallons
	5353 DEEP FOREST	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO	III JAK BATOU	755-0	17,0000112	20-0an-99	12.00	324	Janoris
NORTHWEST QUADRANT	DRIVE	STOPPAGE.	WHITE OAK BAYOU	451-F	TX0057347	04-Feb-99	12:30	1515	Gallons
		UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO							
NORTHWEST QUADRANT	9702 JAY WOOD	STOPPAGE.	WHITE OAK BAYOU	410-P	TX0057347	04-Feb-99	13:20	410	Gallons
NORTHEAST QUADRANT	10410 BAUMAN	MAIN LINE STOPPAGE	WHITE OAK BAYOU	453-C	TX0026875	19-Feb-99			Gallons
		SEWER MAIN STOPPAGE DUE TO GREASE IN THE							
NORTHWEST QUADRANT	5300 DEEP FOREST	LINE.	WHITE OAK BAYOU	451-F	TX0057347	22-Feb-99	16:01	213	Gallons
NORTHWEST QUADRANT	2003 HARLAND	STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	451-T	TX0096172	22-Feb-99	10:35	1230	Gallons
NORTHEAST QUADRANT	7618 APPLETON	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-L	TX0096172	22-Feb-99	13:35	60	Gallons
NORTHWEST QUADRANT	7030 ANTOINE	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-Y	TX0057347	03-Mar-99			Gallons
NORTHWEST QUADRANT		ROUTINE SEWER MAIN STOPPAGE	WHITE OAK BAYOU	450-Q	TX0063002	05-Mar-99			Gallons
TORTHWEST QUADRAINT	SO TO INCIVIT WOODD DIVINE	UNAVOIDABLE SEWER DISCHARGE DUE TO	THE CAN BATOU	75070	170003002	00-Wai-99	10.17	090	Janufi
NORTHWEST QUADRANT	9426 SPRING VIEW	STOPPAGE IN THE LINE	WHITE OAK BAYOU	450-K	TX0063011	10-Mar-99	13:35	2700	Gallons
EOT QUADIANT	2 .20 3	SEWER MAIN STOPPED-UP DUE TO GREASE IN THE	2 3/11 BATOU	.50 10	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	. 5 IVIGIT-33	. 5.55		Canonia
NORTHWEST QUADRANT	700 WEST - 27 STREET	LINE.	WHITE OAK BAYOU	452-V	TX0096172	10-Mar-99	12:05	410	Gallons
201 40/10/10/11	2118 WASHINGTON		= 3/11/3/11/00					-10	23011
NORTHWEST QUADRANT	AVENUE	CONTRACTOR FAILED TO TAP-IN WHILE SLIP LINING.	WHITE OAK RAYOU	493-K	TX0096172	22-Mar-99	14:00	15875	Gallons
NORTHWEST QUADRANT	5555 HOLLY VIEW DR.	ROUTINE LINE STOPPAGE	WHITE OAK BAYOU	411-Y	TX0050172	29-Mar-99			Gallons
NORTHWEST QUADRANT	434 FENN	ROUTINE LINE STOPPAGE	WHITE OAK BAYOU	452-M					_
VORTHWEST QUADRANT	TON FEININ		WITH LOAK BATOU	4-0Z-IVI	TX0063011	29-Mar-99	10.10	900	Gallons
NODTHWEST OF INDUNIT	2025 CETTI	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO	WHITE OAK BAYOU	403 D	TV0057047	02 4== 00	14:40	400	Gall-
NORTHWEST QUADRANT	2835 CETTI	STOPPAGE. SEWER MAIN STOPPED-UP CAUSING OVERFLOW	WHITE OAK BAYOU	493-D	TX0057347	03-Apr-99	14.48	122	Gallon
NORTHWEST QUADRANT	7703 STREAMSIDE	FROM A MANHOLE.	WHITE OAK BAYOU	411-U	TX0057347	09-Apr-99	13:55	2750	Gallons
TONTINVEST QUADRAINT	7,00 OTREAMODE	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO	WITE OAK BATOU	71170	170001341	03-Api-99	10.00	Z130	Janun
	202 1/1070014	STOPPAGE.	WHITE OAK BAYOU	453-E	TX0096172	10-Apr-99	11:46	160	Gallons
NORTHWEST QUADRANT	ZUZ VICTURIA					. 5 , 101-33		100	Canoria
NORTHWEST QUADRANT	202 VICTORIA 835 HEIGHTS								
NORTHWEST QUADRANT	835 HEIGHTS BOULEVARD	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO STOPPAGE.	WHITE OAK BAYOU	493-A	TX0096172	15-Apr-99	09:06	330	Gallon
	835 HEIGHTS	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO		493-A	TX0096172	15-Apr-99	09:06	330	Gallon

Problem	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
		SEWER MAIN STOPPED-UP SURCHAREGED MAIN							
ORTHWEST QUADRANT	901 HEIGHTS BLVD.	AND OVERFLOWED.	WHITE OAK BAYOU.	493-A	TX0057347	22-Apr-99			Gallons
NORTHWEST QUADRANT	915 MILWAUKEE	SEWER MAIN STOPPED-UP CAUSING OVERFLOW.	WHITE OAK BAYOU	453-U	TX0057347	13-May-99			Gallons
NORTHWEST QUADRANT	322 EAST JANISCH	ROUTINE STOPPAGE.	WHITE OAK BAYOU	453-D	TX0096172	14-May-99	11:22	1055	Gallons
IODTI IMECT OLIADDANT	4544 KNOV	ROUTINE STOPPAGE CAUSED RAW SEWAGE	MULTE OAK BAYOU	400.0	TV0000470	40 M 00	00.07	4740	0-11
NORTHWEST QUADRANT NORTHWEST QUADRANT	1514 KNOX	OVERFLOW	WHITE OAK BAYOU WHITE OAK BAYOU	492-G 492-C	TX0096172 TX0096172	19-May-99			Gallons Gallons
NORTHWEST QUADRANT	2411 REINERMAN	UNAVOIDABLE RAW SEWAGE DISCHARGE UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO	WHITE OAK BAYOU	492-C	170096172	01-Jun-99	09:35	250	Gallons
NORTHEAST QUADRANT	313 MOODY	STOPPAGE IN MAI	WHITE OAK BAYOU	453-U	TX0057347	04-Jun-99	09.55	76	Gallons
TORTILAGI QUADRANI	6900 LOG HOLLOW	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO	WITTE OAK BATOO	455-0	17,0037347	0 4 -3u11-33	03.33	70	Galloris
NORTHWEST QUADRANT	DRIVE	STOPPAGE.	WHITE OAK BAYOU	411-J	TX0057347	29-Jun-99	08:09	695	Gallons
	52	UNAVOIDABLE RAW SEWAGE DISCHARGE DUE TO			17.0007011	20 0011 00	00.00	000	Gamorio
NORTHWEST QUADRANT	1002 GARDENIA	STOPPAGE.	WHITE OAK BAYOU	452-K	TX0057347	16-Jul-99	11:51	450	Gallons
NORTHEAST QUADRANT	3627 LEMON TREE LANE		WHITE OAK BAYOU	411-V	TX0057347	29-Jul-99			Gallons
NORTHWEST QUADRANT	430 TRUMAN	ROUTINE STOPPAGE.	WHITE OAK BAYOU	452-M	TX0057347	01-Aug-99	15:30	250	Gallons
NORTHWEST QUADRANT	10271 NORTH FREEWAY	SEWER MAIN STOPPED-UP.	WHITE OAK BAYOU	412-M	TX0057347	05-Aug-99		45300	Gallons
NORTHWEST QUADRANT	4513 OXFORD	ROUTINE STOPPAGE.	WHITE OAK BAYOU	453-J	TX0096172	05-Aug-99		335	Gallons
NORTHWEST QUADRANT	6335 FRENCH CHATEAU	ROUTINE STOPPAGE.	WHITE OAK BAYOU	411-T	TX0057347	06-Aug-99		1780	Gallons
NORTHWEST QUADRANT	1103 CLOVIS	ROUTINE MAIN STOPPAGE.	WHITE OAK BAYOU	452-X	TX0063011	13-Aug-99			Gallons
NORTHWEST QUADRANT	101 EAST TIDWELL	ROUTINE STOPPAGE.	WHITE OAK BAYOU	453-B	TX0096172	27-Aug-99	09:45	240	Gallons
	3000 HOUSTON AVENUE								
NORTHWEST QUADRANT	@ NORTH ST	ROUTINE STOPPAGE.	WHITE OAK BAYOU	493-C	TX0096172	27-Aug-99			Gallons
NORTHEAST QUADRANT	2326 OTTO	SEWER MAIN STOPPED-UP.	WHITE OAK BAYOU	454-A	TX0096172	31-Aug-99	08:00	435	Gallons
				l					UNDTE
NORTHEAST QUADRANT	808 ELEANOR	MAIN LINE STOPPED-UP	WHITE OAK BAYOU	453-R	TX0063029	05-Sep-99			RMINE
SOUTHEAST QUADRANT	5820 GANO	SEWER MAIN STOPPER LIB	WHITE OAK BAYOU	452-V	TX0096172	13-Sep-99			Gallons
SOUTHEAST QUADRANT	4516 IRVINGTON	SEWER MAIN STOPPED-UP.	WHITE OAK BAYOU	453-Y	TX0096172	13-Sep-99	15:50	355	Gallons
NORTHWEST OUR DRAFT	6147 OHEENNAGOOD I ATTE	SEWIED MAIN STORDED UP	WHITE OAK BAYOU	400 B	TV0000170	01.0- 0-	16:40		Call
NORTHWEST QUADRANT NORTHWEST QUADRANT		SEWER MAIN STOPPED-UP. ROUTIN STOPPAGE IN LINE.	WHITE OAK BAYOU	492-B	TX0096172	21-Sep-99			Gallons
NORTHWEST QUADRANT	2611 BAYLOR	NOUTIN STOFFAGE IN LINE.	WHITE OAK BAYOU	453-T	TX0057347	26-Sep-99	UO:23	560	Gallons
NORTHWEST QUADRANT	509 BARKLEY @ HAYGOOD	SEWER MAIN STOPPED	WHITE OAK BAYOU	453-J	TX0096172	27-Sep-99	10:54	712	Gallons
TONTINVEST QUADRANT	4000 AIRLINE @	OLIVEIX WAIN STOLFED	WHILL OAK BATOU	700-0	170090172	21-3ep-98	10.04	/ 12	Janons
NORTHEAST QUADRANT	CROSSTIMBERS	SEWER MAIN STOPPED-UP.	WHITE OAK BAYOU	453-K	TX0096172	27-Sep-99	11:56	1/17	Gallons
NORTHWEST QUADRANT	818 PINEMONT	ROUTINE STOPPAGE.	WHITE OAK BAYOU	452-G	TX0096172	28-Sep-99		1417	15 GPN
NORTHWEST QUADICANT	5350 GULF BANK @	NOOTINE STOLL AGE.	WITTE OAK BATOO	432-0	17/0030172	20-06p-33	03.30		13 01 10
NORTHWEST QUADRANT	STREAMSIDE	LIFT STATION DOWN.	WHITE OAK BAYOU	411-Q	TX0063011	02-Oct-99	10:57	12900	Gallons
NORTHWEST QUADRANT	9831 KNOBOAK DRIVE	ROUTINE STOPPAGE.	WHITE OAK BAYOU	450-S	TX0096172	04-Oct-99			Gallons
NORTHWEST QUADRANT	5100 SAN FELIPE	ROUTINE STOPPAGE.	WHITE OAK BAYOU	491-Q	TX0096172	04-Oct-99			Gallons
NORTHWEST QUADRANT	4400 DONNA BELL	ROUTINE LINE STOPPAGE.	WHITE OAK BAYOU	452-E	TX0063011	11-Oct-99			Gallons
NORTHWEST QUADRANT	6438 CINDY	BROKEN SEWER MAIN STOPPED-UP.	WHITE OAK BAYOU	452-X	TX0096172	11-Oct-99			Gallons
NORTHEAST QUADRANT	1107 CLOVIS	SEWER MAIN STOPPED-UP.	WHITE OAK BAYOU	452-X	TX0096172	12-Oct-99			Gallons
NORTHWEST QUADRANT	1742 WOODVINE	ROUTINE STOPPAGE.	WHITE OAK BAYOU	451-T	TX0063011	13-Oct-99			Gallons
NORTHWEST QUADRANT	6506 RUSSETT	STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	411-R	TX0057347	20-Oct-99	08:47	370	Gallons
Northwest Quadrant	5300 DeSoto	Main Line Stopped Up.	White Oak Bayou	451-C	TX0057347	26-Oct-99	10:06	1410	Gallons
NORTHWEST QUADRANT	1200 SHIRKMERE RD.	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-X	TX0057347	29-Oct-99	10:02	520	Gallons
NORTHWEST QUADRANT	432 TRUMAN	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-M	TX0026875	03-Nov-99	11:40	880	Gallons
NORTHWEST QUADRANT	116 W.CROSSTIMBERS	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-M	TX0096172	03-Nov-99	11:50	1860	Gallons
NORTHWEST QUADRANT	1500 W.43RD STREET	MAIN LINE STOPED UP	WHITE OAK BAYOU	453-J	TX0026875	04-Nov-99	13:50	205	Gallons
NORTHWEST QUADRANT	3615 CHERRY FOREST	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-V	TX0096172	05-Nov-99	16:30		Gallons
NORTHWEST QUADRANT	116 W.CROSSTIMBERS	MAIN LINE STOPED UP DUE TO REPAIR	WHITE OAK BAYOU	452-M	TX0057347	06-Nov-99	11:13	340	Gallons
NORTHWEST QUADRANT	5555 W.GULFBANK	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P	TX0057347	06-Nov-99			Gallons
NORTHWEST QUADRANT	7062 W.GULFBANK	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-N	TX0057347	06-Nov-99	13:33	195	Gallons
	9800 NORTHWEST								
NORTHWEST QUADRANT	FREEWAY	ROUTINE STOPPAGE	WHITE OAK BAYOU	451-V	TX0096172	06-Nov-99			Gallons
NORTHEAST QUADRANT	1703 STONECREST	MAIN LINE HAD STOPPAGE	WHITE OAK BAYOU	452-P	TX0096172	09-Nov-99	08:20	855	Gallons
	432 & 412 TRUMAN								
NORTHWEST QUADRANT	STREET	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-M	TX0096172	10-Nov-99			Gallons
NORTHWEST QUADRANT	7030 ANTOINE 4000 W. 43rd	ROUTINE STOPPAGE ROUTINE STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	411-U	TX0057347	11-Nov-99			Gallons
NORTHWEST QUADRANTS NORTHEAST QUADRANT	2222 WHITE OAK	ROUTINE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE	WHITE OAK BAYOU WHITE OAK BAYOU	451-R 493-O	TX0096172 TX0035009	12-Nov-99			Gallons Gallons
NORTHEAST QUADRANT	6002 CHRYSTELL	ROUTINE STOPPAGE	WHITE OAK BAYOU	493-O 451-F	TX0035009	17-Nov-99			Gallons
NORTHEAST QUADRANT	121 E. TIDWELL RD.	ROUTINE STOPPAGE	WHITE OAK BAYOU	451-F 452-D	TX0035009	17-Nov-99			Gallons
NORTHWEST QUADRANT	6042 CRAB ORCHARD	ROUTINE STOPPAGE	WHITE OAK BAYOU	491-J	TX0033009	18-Nov-99			Gallons
NORTHEAST QUADRANT	1002 CAVALCADE	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-T	TX0096172	18-Nov-99			Gallons
NORTHWEST QUADRANT	7058 W.GULF BANK	MAIN STOPPED UP	WHITE OAK BAYOU	410-R	TX0057347	24-Nov-99			Gallons
	OLD YALE/ 222 E.					50		1 230	1 20
NORTHEAST QUADRANT	CROSSTIMBERS	SEWAGE BACK UP	WHITE OAK BAYOU	453-S	TX0057347	24-Nov-99	13:08	4920	Gallons
NORTHWEST QUADRANT		CITY MAIN STOPPED UP	WHITE OAK BAYOU	451-D	TX0063011	24-Nov-99			Gallons
NORTHWEST QUADRANT	1518 GLEN OAK	ROUTINE STOPPAGE	WHITE OAK BAYOU	492-C	TX0096172	27-Nov-99			Gallons
NORTHWEST QUADRANT	7426 SAWMILL TRAIL	ROUTINE STOPPAGE	WHITE OAK BAYOU	410-M	TX0057347	29-Nov-99	12:26	320	Gallons
NORTHEAST QUADRANT	101 E. TIDWELL	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-A	TX0096172	29-Nov-99	16:05	170	Gallons
NORTHEAST QUADRANT	2222 WHITE OAK	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-A	TX0096172	29-Nov-99			Gallons
NORTHWEST QUADRANT	1119 WISTERWOOD	ROUTINE STOPPAGE	WHITEOAK BAYOU	449-Z	TX0057347	29-Nov-99			Gallons
NORTHWEST QUADRANT		MAIN LINE STOPPAGE	WHITE OAK BAYOU	411-S	TX0096172	01-Dec-99			Gallons
NORTHEAST QUADRANT	621 WENDELL	ROUTINE LINE STOPPAGE	WHITE OAK BAYOU	493-B	TX0096172	02-Dec-99			Gallons
WESTWAY MUD	526 EAGLE GLEN	ROUTINE STOPPAGE	WHITE OAKS BAYOU	449-H	TX0026875	02-Dec-99			Gallons
NORTHWEST	1926 WOODVINE926	ROUTINE STOPPAGE	WHITE OAKS BAYOU	451-T	TX0063011	02-Dec-99			Gallons
NORTHEAST QUADRANT	902 E. 33 RD	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-N	TX0096172	05-Dec-99			Gallons
NORTHWEST QUADRANT.	621 WENDEL	ROUTINE STOPPAGE	WHITE OAK BAYOU	493-B	TX0096172	07-Dec-99			Gallons
NORTHWEST QUADRANT	116 W. CROSSTIMBERS	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-M	TX0057347	08-Dec-99			Gallons
NORTHWEST QUADRANT	7202 ANTOINE	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-Y	TX0057347	09-Dec-99			Gallons
NORTHEAST QUADRANT	116 E. CROSSTIMBERS	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-J	TX0096172	10-Dec-99			Gallons
SOUTHWEST QUADRANT	918 PEDEN	MAIN-LINE STOPPED LID	WHITE OAK BAYOU	493-D	TX0096172	10-Dec-99			Gallons
NORTHWEST QUADRANT	7202 ATHLONE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Y	TX0057347	13-Dec-99			Gallons
NORTHWEST QUADRANT	WEST 34TH AT 290	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-R	TX0096172	13-Dec-99			Gallons
NORTHWEST QUADRANT	7202 RIDGE OAK	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-T	TX0057347	15-Dec-99			Gallons
IODTUNECT OUT SEC.	5800 SHAVELSON	ROUTINE STOPPAGE	WHITE OAK BAYOU	491-E	TX0063011	17-Dec-99	19:24	2525	Gallons
		I .	MULTE OALL DAVICE	444 31	T)/00F=0 :-		44 10		
NORTHWEST QUADRANT NORTHWEST QUADRANT NORTHWEST QUADRANT	7202 ATHLONE 6505 ANTOINE	MAIN LINE STOPPED UP ROUTINE STOPPAGE	WHITE OAK BAYOU WHITE OAK BAYOU	411-Y 411-Y	TX0057347 TX0063011	18-Dec-99			Gallons

Problem	Location	Description POLITIME CTORPAGE	Receiving stream	Key map		Date Time	Volume Un
NORTHWEST QUADRANT.	8701 HAMMERLY	ROUTINE STOPPAGE	WHITE OAK BAYOU	450-Q	TX0026875	19-Dec-99 13:15	1280 Gallo
NORTHWEST QUADRANT	7028 ANTOINE	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-U	TX0057347	22-Dec-99 11:44	610 Gallo
ORTHWEST QUADRANT.	310 FENN	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-N	TX0057347	22-Dec-99 20:43	3000 Gallo
ORTHWEST QUADRANT.	206 FAUST	ROUTINE STOPPAGE	WHITE OAK BAYOU	489-M	TX0063011	22-Dec-99 11:37	2980 Gallo
IORTHWEST QUADRANT	8807 EMNORA	MAIN LINE STOPPED UP	WHITE OAK BAYOU	450-R	TX0057347	24-Dec-99 10:00	204 Gallo
IORTHWEST QUADRANT	5700 W. GULF BANK	SEWER LINE STOPPED UP	WHITE OAK BAYOU	411-P	TX0063011	25-Dec-99 17:27	130 Gallo
IORTHEAST QUADRANT	1613 CHESTNUT	ROUTINE STOPPAGE	WHITE OAK BAYOU	493-H	TX0096172	25-Dec-99 11:48	19 Gallo
I.W. QUADRANT	5300 W. GULFBANK	SEWER MAIN STOPPED UP	WHITEOAK BAYOU	412-M	TX0057347	25-Dec-99 16:45	180 Gallo
IORTHWEST QUAD	1235WEST 25TH	SEWER MAIN STOPPED UP	WHITE OAK BAYOU	452-W	TX0057347	26-Dec-99 14:21	310 Gallo
IORTHWEST QUADRANT.		I .	WHITE OAK BAYOU				
	5222 LIDO	ROUTINE STOPPAGE		451-G	TX0063011	28-Dec-99 11:59	665 Gallo
IORTHWEST QUADRANT	4920 MARABLE	ROUTINE LINE STOPPAGE	WHITE OAK BAYOU	453-E	TX0063011	29-Dec-99 08:39	700 Gallo
IORTHWEST QUADRANT	5673 YALE	ROUTINE LINE STOPPAGE	WHITE OAK BAYOU	452-D	TX0063011	29-Dec-99 11:43	545 Gallo
	5819 VILLAGE FOREST						
IORTHWEST QUADRANT	CT	STOPPAGE IN MAIN	WHITE OAKS BAYOU	451-C	TX0063011	30-Dec-99 13:26	635 Gallo
	4010 CYPRESSGROVE	MAIN LINE STOPPED UP, OVERFLOWING INT STORM					
ORTHWEST QUADRANT.	LN.	SEWER.	WHITE OAK BAYOU	411-U	TX0057347	02-Jan-00 20:50	3825 Gallo
ORTHWEST QUADRANT.	7200 ANTHLONE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Y	TX0057347	02-Jan-00 20:02	5026 Gallo
ORTHWEST	4300 ROSSLYN RD.	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-J	TX0096172	02-Jan-00 14:01	1545 Gallo
ORTHWEST QUADRANT.	1332 W. 25TH. STREET	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-T	TX0096172	02-Jan-00 18:50	9600 Gallo
ORTHWEST QUADRANT	1100 STUDEWOOD	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-W	TX0026875	03-Jan-00 13:49	955 Gallo
ORTHWEST QUADRANT	500 THORNTON	ROUTINE LINE STOPPAGE	WHITE OAK BAYOU	452-M	TX0096172	03-Jan-00 11:40	1730 Gall
		I .					
.W.T.P. QUAD	5349 LYNBROOK	ROUTINE STOPPAGE	WHITE OAK BAYOU	491-L	TX0026875	04-Jan-00 11:32	104 Gallo
.W. QUADRANT	8019 W.RAY CT.	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P	TX0057347	05-Jan-00 10:09	415 Galle
OUTHWEST QUADRANT	4909 SAXON	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-L	TX0057347	06-Jan-00 09:26	1305 Galle
ORTHWEST QUADRANT	7207 ATHLONE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Y	TX0057347	07-Jan-00 08:39	320 Gallo
ORTHWEST QUADRANT	4630 DACOMA	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-Y	TX0096172	09-Jan-00 09:15	444 Gallo
OUTHWEST QUADRANT	5427 GESSNER	ROUTINE STOPPAGE	WHITE OAK BAYOU	450-A	TX0062995	11-Jan-00 08:15	222 Gallo
ORTHWEST QUADRANT	1855 WIRT	ROUTINE STOPPAGE	WHITE OAK BAYOU	451-T	TX0096172	11-Jan-00 11:35	2345 Gall
ORTHWEST QUADRANT	430 DEL NORTE	ROUTINE STOPPAGE	WHITE OAK BAYOU	451-1 452-H		12-Jan-00 10:46	
					TX0057347		875 Galle
ORTHEAST QUADRANT	735 W. CALVALCADE	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-T	TX0096172	12-Jan-00 13:48	1860 Galle
IORTH CENTRAL	826 W. 30TH	PRIVATE STOPPAGE	WHITE OAKS BAYOU	452-Q	TX0096172	13-Jan-00 11:04	6120 Galle
IORTHWEST QUADRANT.	7200 ATHLONE	MAIN LINE STOPPED UP.	WHITE OAK BAYOU	411-U	TX0057347	14-Jan-00 10:45	1200 Galle
IORTHWEST QUADRANT	6335 FRENCH CHATON	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-T	TX0057347	16-Jan-00 13:!5	1515 Galle
IORTHWEST QUADRANT	8311 MELROSE	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-C	TX0057347	17-Jan-00 17:18	145 Galle
IORTHEAST QUADRANT	417 THORNTON	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-M	TX0096172	17-Jan-00 10:21	510 Galle
IORTHWEST QUADRANT	1400 SPRING ROCK	ROUTINE STOPPAGE	WHITE OAK BAYOU	450-X	TX0057347	18-Jan-00 13:06	290 Gallo
OKTIWEST QUADRANT	1400 SI KING KOCK		WITTE OAK BATOO	430-X	170007347	10-3411-00 13.00	230 Gain
IODTI IMEGT OLIA DO ANT	0.405 01/504050	SEWER LINE APARTMENTFLOWING INTO WHITE	MAILUTE CALCEANOLING	450.4	T)/0057047	40 1 00 40 50	4700 0 11
IORTHWEST QUADRANT	3405 SHEPARED	OAK BAYOU	WHITE OAK BAYOUY	452-A	TX0057347	18-Jan-00 18:58	1706 Gallo
ORTHEAST QUADRANT	4808 MICHAUX	ROUTINE STOPPAGE	WHITE OAK BAOYU	453-X	TX0096172	19-Jan-00 09:56	855 Gallo
ORTHWEST QUADRANT	800 WILKES	MAIN LINE STOPPED UP	WHITE OAK BAYOU	493-C	TX0057347	19-Jan-00 10:40	450 Galle
ORTHWEST QUADRANT	418 BISHOP	STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	493-G	TX0057347	19-Jan-00 09:10	641 Gallo
IORTHWEST QUADRANT	10984 NORTH FREEWAY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	412-M	TX0057347	19-Jan-00 13:50	1888 Galle
IORTHWEST QUADRANT	2627 GARWOOD	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Z	TX0057347	19-Jan-00 08:05	8450 Gallo
ORTHEAST QUADRANT	2816 CALLIE	ROUTINE STOPPAGE	WHITE OAK BAYOU	494-W	TX0096172	19-Jan-00 18:16	230 Gallo
NORTHWEST QUADS	735 CAVALCADE	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-T	TX0096172	22-Jan-00 08:01	644 Gallo
NORTHWEST QUADRANT	207 LINDALE	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-Q	TX0026875	23-Jan-00 16:43	120 Gallo
NORTHWEST QUADRANT	5550 HOLLY VIEW	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Y	TX0057347	26-Jan-00 13:15	225 Gallo
ORTHEAST QUADRANT	735CALVACADE	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-V	TX0096172	26-Jan-00 7:51	3090 Gallo
	10333 NORTHWEST						
ORTHWEST QUADRANT	FREEWAY	ROUTINE STOPPAGE	WHITE OAK BAYOU	451-C	TX0096172	27-Jan-00 12:26	1070 Gallo
ORTHWEST QUAD	809 MILWAUKEE	ROUTINE STOPPAGE	WHITE OADK BAYOU	453-W	TX0057347	30-Jan-00 08:25	175 Gallo
ORTHWEST QUAD	3300 JULIAN	MAIN LINE STOPPED UP	WHITE OAK BAYOU	493-B			
		1			TX0096172	31-Jan-00 10:15	2232 Gallo
IORTH WEST QUADRANT	5403 LONG CREEK	BROKEN SEWER PIPE	WHITE OAK BAYOU	411-U	TX0063011	01-Feb-00 10:21	5780 Gallo
		MAIN LINE STOPPED UP,FLOWING INTO					
IORTHEAST QUADRANT	1107 HERKIMER ST.	STREET,&SEWER	WHITE OAKS BAYOU	452-Z	TX0096172	02-Feb-00 14:41	150 Gallo
IORTHWEST QUADRANT	206 W. 44TH ST.	SEWER STOPPAGE	WHITE OAK BAYOU	452-M	TX0096172	03-Feb-00 09:35	575 Gallo
IORTHWEST QUADRANT	W.34TH STREET @ 290	GREASE IN LINE CAUSING SEWAGETO GO IN BAYOU	WHITE OAK BAYOU	451-R	TX0096172	03-Feb-00 11:07	504 Gallo
		APARTMENT STOPPAGE CAUSED SEWER					
IORTHWEST QUADRANT	4200 W 34th ST	EXCURSION	WHITE OAK BAYOU	451-R	TX0096172	03-Feb-00 10:25	1140 00
ION I TIMES I QUADRANT	4200 W. 34th ST.		WITH E OAK BATOU	451-K	170090172	U3-FBD-UU 10:25	1140 Gall
		DAMAGED FORCE (REPAIR PENDING)CALLED		1	1		
	LONG LEAF @ BAYOU		l	1		04 5-4 00 0.05	
IORTH WEST QUADRANT	FOREST	PROCESS OPER. ON G	WHITE OAK BAYOU	411-P	TX0057347	04-Feb-00 8:05	420 Gallo
NORTH WEST QUADRANT			WHITE OAK BAYOU	411-P	TX0057347	04-Feb-00 8:05	420 Gallo
	FOREST	PROCESS OPER. ON G	WHITE OAK BAYOU WHITE OAK BAYOU	411-P	TX0057347 TX0057347	04-Feb-00 8:05 04-Feb-00 12;27	420 Gallo
IORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU	PROCESS OPER. ON G DAMAGED FORCE (REPAIR					
IORTH WEST QUADRANT IORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE	WHITE OAK BAYOU WHITE OAK BAYOU	411-P 411Y	TX0057347 TX0063002	04-Feb-00 12;27 09-Feb-00 10:19	420 Gallo 540 Gallo
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP	WHITE OAK BAYOU WHITE OAK BAYOU WHITE OAK BAYOU	411-P 411Y 411-P	TX0057347 TX0063002 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00	420 Gallo 540 Gallo 665 Gallo
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP	WHITE OAK BAYOU WHITE OAK BAYOU WHITE OAK BAYOU WHITE OAK BAYOU	411-P 411Y 411-P 493-B	TX0057347 TX0063002 TX0057347 TX0096172	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14	420 Gallo 540 Gallo 665 Gallo 717 Gallo
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD.	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE	WHITE OAK BAYOU WHITE OAK BAYOU WHITE OAK BAYOU WHITE OAK BAYOU WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40	420 Gallo 540 Gallo 665 Gallo 717 Gallo 162 Gallo
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED/GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE	WHITE OAK BAYOU WHITE OAK	411-P 411Y 411-P 493-B 450-V 453-W	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37	420 Gallo 540 Gallo 665 Gallo 717 Gallo 162 Gallo 158 Gallo
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR.	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11;06	420 Galli 540 Galli 665 Galli 717 Galli 162 Galli 158 Galli 84 Galli
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR.	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED (GEORGE) OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:06 15-Feb-00 11:01	420 Galli 540 Galli 665 Galli 717 Galli 162 Galli 158 Galli 84 Galli 480 Galli
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR.	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11;06	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 84 Gall 480 Gall
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR.	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED (GEORGE) OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:06 15-Feb-00 11:01	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 84 Gall 480 Gall 573 Gall
ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED/GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP OVER LAP ROUTINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 411-S 451-X	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:06 15-Feb-00 10:22 18-Feb-00 13;20	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 84 Gall 480 Gall 573 Gall
ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 411-S 451-X 410-V	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12:27 09-Feb-00 10:19 10-Feb-00 13:00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19:37 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13:20 18-Feb-00 9:47	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 84 Gall 480 Gall 160 Gall
ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 411-S 451-X 410-V 452 H	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX00057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:06 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 9:47 20-Feb-00 10:00	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 480 Gall 573 Gall 4340 Gall 4340 Gall
ORTH WEST QUADRANT ORTHEAST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED (GEORGE) OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 451-X 411-S 451-X 410-V 452-H 411-T	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 11;06 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 9:47 20-Feb-00 10:05	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 480 Gall 480 Gall 573 Gall 4340 Gall 590 Gall
ORTH WEST QUADRANT ORTHEAST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 411-S 451-X 410-V 452 H	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX00057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:06 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 9:47 20-Feb-00 10:00	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 480 Gall 573 Gall 4340 Gall 590 Gall 363 Gall
ORTH WEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPED UP	WHITE OAK BAYOU	411-P 411Y 493-B 450-V 453-W 451-T 451-T 451-X 410-V 452-H 411-S 410-V	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 10:00 21-Feb-00 10:00 22-Feb-00 09:58	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 84 Gall 573 Gall 160 Gall 4340 Gall 590 Gall 5720 Gall
ORTH WEST QUADRANT ORTHEAST QUADRANT ORTHEAST QUADRANT ORTH WEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED (GEORGE) OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 451-X 411-S 451-X 410-V 452-H 411-T	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 11;06 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 9:47 20-Feb-00 10:05	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 84 Gall 573 Gall 160 Gall 4340 Gall 590 Gall 5720 Gall
ORTH WEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPED UP	WHITE OAK BAYOU	411-P 411Y 493-B 450-V 453-W 451-T 451-T 451-X 410-V 452-H 411-S 410-V	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 10:00 21-Feb-00 10:00 22-Feb-00 09:58	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 184 Gall 573 Gall 160 Gall 4340 Gall 590 Gall 5720 Gall
ORTH WEST QUADRANT ORTHWEST QUADRANT ORTH WEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPED UP ROUTINE STOPPED UP ROUTINE STOPPAGE: SEWER MAIN STOPPED UP ROUTINE STOPPAGE: SEWER MAIN STOPPED UP	WHITE OAK BAYOU	411-P 4111Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452 H 411-T 410-Y 451-K	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11;40 15-Feb-00 11;06 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 09:58 22-Feb-00 9:03 23-Feb-00 13:11	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 84 Gall 573 Gall 160 Gall 4340 Gall 590 Gall 5720 Gall 1300 Gall
ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN A058 BOLIN 1600 N.DURHAM	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP OVER LAP ROUTINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE: SEWER MAIN STOPPED UP ROUTINE STOPPAGE STOPPAGE	WHITE OAK BAYOU	411-P 4111-P 493-B 450-V 453-W 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 411-J 451-K 452-Y	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0063011 TX0057347 TX0063011 TX0063011 TX0063011	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13:00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 11:06 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13:20 18-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 09:58 22-Feb-00 9:03 23-Feb-00 13:11 23-Feb-00 17:06	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 480 Gall 573 Gall 4340 Gall 4340 Gall 4340 Gall 4350 Gall 363 Gall 5720 Gall 375 Gall
ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MOUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE STOPPAGE STOPPAGE STOPPAGE MAIN LINE STOPPED UP ROUTINE STOPPAGE STOPPAGE MAIN LINE STOPPAGE STOPPAGE MAIN LINE STOPPAGE	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 451-K 452-K 453-Y 453-J	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 13;00 11-Feb-00 11:40 11-Feb-00 11:40 15-Feb-00 11:01 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 10:00 21-Feb-00 10:00 22-Feb-00 10:05 22-Feb-00 99:58 22-Feb-00 99:03 23-Feb-00 13:11 23-Feb-00 13:11 23-Feb-00 17:06 24-Feb-00 14:37	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 573 Gall 573 Gall 4340 Gall 590 Gall 363 Gall 375 Gall 375 Gall
ORTH WEST QUADRANT ORTHWEST QUADRANT ORTHWEST QUADRANT ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER 3627 LEMON TREE	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE ROUTINE STOPPAGE STOPPAGE MAIN LINE STOPPAGE STOPPAGE MAIN LINE STOPPED UP ROUTINE STOPPAGE STOPPAGE MAIN LINE STOPPED UP STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	411-P 4111Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 451-K 452-Y 453-J 411-N	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:06 15-Feb-00 11:06 15-Feb-00 13:20 18-Feb-00 13:20 18-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 09:58 22-Feb-00 9:03 23-Feb-00 17:06 24-Feb-00 17:06 24-Feb-00 17:06 24-Feb-00 18:35	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 573 Gall 160 Gall 590 Gall 363 Gall 375 Gall 375 Gall 375 Gall 375 Gall
ORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MOUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE STOPPAGE STOPPAGE STOPPAGE MAIN LINE STOPPED UP ROUTINE STOPPAGE STOPPAGE MAIN LINE STOPPAGE STOPPAGE MAIN LINE STOPPAGE	WHITE OAK BAYOU	411-P 411Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 451-K 452-K 453-Y 453-J	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 13;00 11-Feb-00 11:40 11-Feb-00 11:40 15-Feb-00 11:01 15-Feb-00 11:01 18-Feb-00 10:22 18-Feb-00 13;20 18-Feb-00 10:00 21-Feb-00 10:00 22-Feb-00 10:05 22-Feb-00 99:58 22-Feb-00 99:03 23-Feb-00 13:11 23-Feb-00 13:11 23-Feb-00 17:06 24-Feb-00 14:37	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 188 Gall 573 Gall 160 Gall 570 Gall 375 Gall 375 Gall 375 Gall 375 Gall 376 Gall
IORTH WEST QUADRANT IORTHWEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER 3627 LEMON TREE	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE ROUTINE STOPPAGE STOPPAGE MAIN LINE STOPPAGE STOPPAGE MAIN LINE STOPPED UP ROUTINE STOPPAGE STOPPAGE MAIN LINE STOPPED UP STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	411-P 4111Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 451-K 452-Y 453-J 411-N	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 19;37 15-Feb-00 11:06 15-Feb-00 11:06 15-Feb-00 13:20 18-Feb-00 13:20 18-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 09:58 22-Feb-00 9:03 23-Feb-00 17:06 24-Feb-00 17:06 24-Feb-00 17:06 24-Feb-00 18:35	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 188 Gall 480 Gall 160 Gall 573 Gall 160 Gall 579 Gall 3720 Gall 3720 Gall 3740 Gall 740 Gall 46 Gall
IORTH WEST QUADRANT IORTHEAST QUADRANT IORTHEAST QUADRANT IORTHWEST QUADRANT IORTHWEST QUADRANT IORTHWEST QUADRANT IORTHEAST QUADRANT IORTHWEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER 3627 LEMON TREE 4001 AVERILL 509 E. WELLINGTON	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE ROUTINE STOPPAGE STOPPAGE STOPPAGE MAIN LINE STOPPED UP STOPPAGE MAIN LINE STOPPED UP STOPPAGE MAIN LINE STOPPED UP STOPPAGE IN MAIN LINE MAIN LINE STOPPED UP STOPPAGE IN MAIN LINE MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 4111Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 451-K 452-Y 453-J 411-N 453-Y	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13:00 10-Feb-00 8:14 11-Feb-00 11:40 15-Feb-00 11:06 15-Feb-00 11:06 15-Feb-00 11:01 18-Feb-00 13:20 18-Feb-00 13:20 18-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 10:05	420 Gall 540 Gall 665 Gall 717 Gall 162 Gall 158 Gall 480 Gall 573 Gall 160 Gall 4340 Gall 363 Gall 3720 Gall 3720 Gall 366 Gall 740 Gall 46 Gall 900 Gall
IORTH WEST QUADRANT IORTH EAST QUADRANT IORTH EAST QUADRANT IORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER 3627 LEMON TREE 4001 AVERILL 509 E. WELLINGTON 724W . 21st street	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE MAIN LINE STOPPED UP STOPPAGE MAIN LINE STOPPED UP STOPPAGE MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 411-P 493-B 450-V 453-W 451-T 451-T 451-T 451-X 410-V 452-H 411-T 451-K 452-Y 453-J 411-N 453-Y 453-Y 453-Y 452-V 452-V	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13:00 10-Feb-00 13:00 10-Feb-00 19:37 15-Feb-00 19:37 15-Feb-00 11:06 15-Feb-00 10:22 18-Feb-00 13:20 18-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 10:05 22-Feb-00 10:05 23-Feb-00 13:11 23-Feb-00 13:11 23-Feb-00 13:31 123-Feb-00 13:35 28-Feb-00 18:35 28-Feb-00 11:00 01-Mar-00 10:05	420 Galli 540 Galli 665 Galli 717 Galli 162 Galli 158 Galli 158 Galli 573 Galli 573 Galli 590 Galli 363 Galli 570 Galli 3720 Galli 3720 Galli 3740 Galli 486 Galli 490 Galli 490 Galli 170 Galli
IORTH WEST QUADRANT IORTHWEST QUADRANT IORTH WEST QUADRANT IORTH WEST QUADRANT IORTH WEST QUADRANT IORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7601 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER 3627 LEMON TREE 4001 AVERILL 509 E. WELLINGTON 724W. 21st street 4803 YALE	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP, OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE STOPPAGE MAIN LINE STOPPED UP STOPPAGE MAIN LINE STOPPED UP STOPPAGE IN MAIN LINE MAIN LINE STOPPED UP ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P 4111Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 452-Y 453-Y 411-N 453-Y 413-Y 452-H	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 11:40 11-Feb-00 11:40 15-Feb-00 11:06 15-Feb-00 11:01 18-Feb-00 13;20 18-Feb-00 13;20 12-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 10:05 22-Feb-00 10:06 23-Feb-00 17:06 24-Feb-00 17:06 24-Feb-00 18:35 28-Feb-00 11:00 01-Mar-00 10:05 02-Mar-00 13:25	420 Gall 540 Gall 540 Gall 665 Gall 717 Gall 162 Gall 184 Gall 573 Gall 160 Gall 573 Gall 1300 Gall 375 Gall 375 Gall 376 Gall 376 Gall 46 Gall 900 Gall 170 Gall
IORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7611 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER 3627 LEMON TREE 4001 AVERILL 509 E. WELLINGTON 724W. 21st street 4803 YALE 2807 BEAUCHAMP	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIEDIGEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP OVER LAP ROUTINE STOPPED UP. OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPAGE ROUTINE STOPPED UP MAIN LINE STOPPED UP MAIN LINE STOPPED UP STOPPAGE ROUTINE STOPPAGE STOPPAGE STOPPAGE MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P 4111-P 493-B 450-V 453-W 451-T 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 453-Y 453-Y 413-Y 453-Y 413-Y 452-U 452-U 493-B	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0006172 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 11:40 11-Feb-00 11:40 15-Feb-00 11:06 15-Feb-00 11:06 15-Feb-00 10:22 18-Feb-00 13:20 18-Feb-00 10:05 22-Feb-00 10:05 22-Feb-00 10:05 22-Feb-00 10:05 24-Feb-00 13:11 23-Feb-00 13:11 23-Feb-00 14:37 27-Feb-00 14:22 29-Feb-00 11:00 11-Feb-00 11:00 01-Feb-00 10:05 02-Mar-00 10:25 03-Mar-00 09:24	420 Galil 540 Galil 540 Galil 665 Gali 717 Galil 162 Galil 184 Galil 480 Galil 160 Galil 180 Galil 573 Galil 190 Galil 3720 Galil 3720 Galil 3720 Galil 3740 Galil 46 Galil 1740 Galil 1740 Galil 1740 Galil 1740 Galil 1740 Galil
IORTH WEST QUADRANT IORTHWEST QUADRANT IORTH WEST QUADRANT IORTH WEST QUADRANT IORTH WEST QUADRANT IORTH WEST QUADRANT	FOREST LONG LEAF @ BAYOU FOREST 7028 ANTOINE 5714 GULF BANK 915 OMAR 8900 LONGPOINT RD. 604 W.11th 2076 ANTOINE DR. 2010 JOHANNA DR. 6906 LOGHOLLOW 7601 WESTVIEW 7602 MOSEWOOD 250 VICTORIA 7206 BAYOUWOOD 7502 BREEZEWAY 9200 N. HOUSTON ROSSLYN 4058 BOLIN 1600 N.DURHAM 4503 WERNER 3627 LEMON TREE 4001 AVERILL 509 E. WELLINGTON 724W. 21st street 4803 YALE	PROCESS OPER. ON G DAMAGED FORCE (REPAIR PENDING)NOTIFIED(GEORGE)OF PROCES MAIN LINE STOPPED UP, ROUTINE STOPPAGE MAIN LINE STOPPED UP, OVER LAP ROUTINE STOPPAGE STOPPAGE IN MAIN LINE ROUTINE STOPPAGE RAPAIR PENDING/CAUSING OVER FLOW MAIN LINE STOPPED UP MAIN LINE STOPPED UP ROUTINE STOPPAGE ROUTINE STOPPAGE STOPPAGE STOPPAGE MAIN LINE STOPPED UP STOPPAGE MAIN LINE STOPPED UP STOPPAGE IN MAIN LINE MAIN LINE STOPPED UP ROUTINE STOPPAGE	WHITE OAK BAYOU	411-P 4111Y 411-P 493-B 450-V 453-W 451-T 451-T 451-T 411-S 451-X 410-V 452-H 411-T 410-Y 452-Y 453-Y 411-N 453-Y 413-Y 452-H	TX0057347 TX0063002 TX0057347 TX0096172 TX0026875 TX0096172 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347 TX0057347	04-Feb-00 12;27 09-Feb-00 10:19 10-Feb-00 13;00 10-Feb-00 11:40 11-Feb-00 11:40 15-Feb-00 11:06 15-Feb-00 11:01 18-Feb-00 13;20 18-Feb-00 13;20 12-Feb-00 10:00 21-Feb-00 10:05 22-Feb-00 10:05 22-Feb-00 10:06 23-Feb-00 17:06 24-Feb-00 17:06 24-Feb-00 18:35 28-Feb-00 11:00 01-Mar-00 10:05 02-Mar-00 13:25	420 Galil 540 Galil 540 Galil 665 Gali 717 Galil 162 Galil 184 Galil 480 Galil 160 Galil 160 Galil 170 Galil 170 Galil 170 Galil 170 Galil 1300 Galil

NORTHEAST QUADRANT. 5: NORTHEAST QUADRANT 4: NORTHWEST QUAD 8: SOUTHEAST QUADRANT. 4:	5 SUNNYSIDE 001 AVERILL	MAIN LINE STOPPED UP/ ROUTINE MAIN LINE STOPPED UP.	WHITE OAK BAYOU WHITE OAK BAYOU	452-D 413-X	TX0057347 TX0057347	06-Mar-00			Gallons
NORTHEAST QUADRANT 4 NORTHWEST QUAD 8 SOUTHEAST QUADRANT. 4	001 AVERILL		WHITE OAK BAYOU	413-X	TX0057347	06-Mar-00	09:26	147	
NORTHWEST QUAD 8 SOUTHEAST QUADRANT. 4							00.20		Gallons
SOUTHEAST QUADRANT. 4		ROUTINE STOPPAGE	WHITE OAK BAYOU	453-Y	TX0096172	07-Mar-00			Gallons
	718 ROAING POINT	MAIN LINE STOPPED UP/ ROUTINE	WHITE OAK BAYOU	411-R	TX0057347	15-Mar-00			Gallons
VIODTHIMEST OF INDOMIT 12	120 KOLB	ROUTINE STOPPAGE	WHITE OAK BAYOU	494-H	TX0096172	17-Mar-00			Gallons
	201 GARDENIA LN.	MANHOLE OVERFLOWING CAUSEING EXCURSION	WHITEOAK BAYOU	451-M	TX0057347	18-Mar-00			Gallons
	810LONGPOINT	ROUTINE STOPPAGE CAUSING OVERFLOW	WHITE OAKS BAYOU	450-V	TX0026875	19-Mar-00			Gallons
		MANHOLE OVERFLOW CAUSING EXCURSION	WHITE OAKS BAYOU	410-M	TX0057347	19-Mar-00			Gallons
		MAIN LINE STOP UP SEWER IN DITCH	WHITE OAD BAYOU	453-J	TX0057347	20-Mar-00			Gallons
NORTHWEST QUAD 8	601 NORTH MAIN	NAIN LINE STOP-UP FLOWING INTO STORM DRAIN	WHITE OAK BAYOU	453-J	TX0057347	20-Mar-00	13:16	84	Gallons
SOUTHWEST QUADRANT 3	400 BLALOCK	MAINLINE STOPPED UP	WHITE OAK	450-L	TX0057347	23-Mar-00	10:07	2051	Gallons
NORTHEAST QUADRANT 7	05 BERRY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-G	TX0063053	23-Mar-00	18:23	150	Gallons
NORTHEAST QUADRANT 4	001 AVERILL	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-U	TX0096172	23-Mar-00	17:35	275	Gallons
NORTHWEST QUAD 2	536 NORHT GRWY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-A	TX0057347	24-Mar-00	20:22	474	Gallons
NORTHWEST Q 5	13 BARKLEY	SEWER MAIN STOPPAGE	WHITE OAK	453-J	TX0057347	25-Mar-00	7:30	192.5	Gallons
NORTHWEST Q 9:	22 NASHUA	SEWER STOPPED UP	WHITE OAK	492-C	TX0057347	25-Mar-00	7:47	390	Gallons
	70 PARKER RD	SEWER MAIN STOPPED UP	WHITE OAK BAYOU	412-Z	TX0051427	25-Mar-00		1215	Gallons
NORTHWEST QUAD 6	02 EMELWOOD	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-S	TX0057347	25-Mar-00	15;21	204	Gallons
				.== \					
		MAIN LINE SPPED UP BROKEN COMMUNITY LINE	WHITE OAK BAYOU	453-X	TX0026875	27-Mar-00			Gallons
		MAIN LINE STOPPED UP.	WHITE OAK BAYOU	452-P	TX0096172	27-Mar-00			Gallons
SOUTHWEST QUAD 1	700 SEA SPRAY CT.	MAIN LINE STOOPPED UP	WHITE OAK BAYOU	452-X	TX0057347	30-Mar-00	13:30	215	Gallons
NORTHWEST QUADS 9	606 PANOLA WAY	MAIN LINE STOPPAGE	WHITE OAK BAYOU	450-X	TX0026875	02-Apr-00	11:26	1482	Gallons
NORTHWEST QUAD 9	638 PANOLA WAY	MAINLINE STOPPAGE	WHITE OAK BAYOU	450-X	TX0026875	02-Apr-00	11:20	1518	Gallons
									UNKNO
	614 MCKINLEY	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-V	TX0057347	02-Apr-00			WN
		SEWER MAIN STOPPED UP	WHITE OAK BAYOU	411-T	TX0057347	03-Apr-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-L	TX0057347	03-Apr-00		154	Gallons
		MAIN LINE STOPPED UP.	WHITE OAK BAYOU	450-Y	TX0026875	04-Apr-00	13:20	1005	Gallons
NORTHEAST QUADS 4	001 AVERILL	SERVICE LINE STOPPED UP	WHITE OAK BAYOU	453-Y	TX0096172	04-Apr-00	19:33	1390	Gallons
	709 BENBOW	MAIN LINE STOPPED UP, ROUTINE STOPPAGE	WHITE OAK BAYOU	450-Y	TX0026875	05-Apr-00			Gallons
	322 RUTLAND	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-Z	TX0057347	05-Apr-00			Gallons
		MAIN LINE STOPPAGE	WHITE OAK BAYOU.	494-T	TX0026875	06-Apr-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-Y	TX0026875	07-Apr-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	412-V	TX0057347	07-Apr-00			Gallons
		MAIN LINE STOPPAGE	WHITE OAK BAYOU	452-Z	TX0057347	07-Apr-00			Gallons
	731 KNOBBY KNOLL	MAIN LINE STOOPPED UP	WHITE OAK BAYOU	451-B	TX0057347	10-Apr-00			Gallons
NORTHWEST QUAD 5	731 KNODDT KNOLL	MAIN LINE STOOPPED OP	WHITE OAK BATOU	431-D	170057347	TU-Apt-00	0.30	360	Gallons
NORTHWEST QUAD 1	1099 NORTHWEST FWY	MAIN LINE STOPPED LIP	WHITE OAK BAYOU	451-E	TX0057347	12-Apr-00	0.35	3000	Gallons
	607 AIRLINE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-T	TX0057347	13-Apr-00			Gallons
		MAIN LINE STOPPED UP.	WHITE OAK BAYOU	453-X	TX0057397	13-Apr-00			Gallons
	406 JAMES	ROUTINE STOPPED UP.	WHITE OAK BAYOU	493-A	TX0057397	15-Apr-00			Gallons
	500 PINEMONT	ROUTINE STOPPAGE	WHITE OAK BAYOU	450-H	TX0057347	15-Apr-00			Gallons
		MAIN LINE STOPPED UP.	WHITE OAK BAYOU	411-Q	TX0003011				
						18-Apr-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	413-Q	TX0057347	21-Apr-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-W	TX0057347	22-Apr-00			Gallons
	108 PASCHALL	COMMUNITY LINE STOPPED UP.	WHITE OAK BAYOU	493-D	TX0026875	25-Apr-00			Gallons
	306 FIRNAT	SERVICE LINE STOPPED UP	WHITE OAK BAYOU	454-E	TX0026875	26-Apr-00			Gallons
	877 LANGFIELD RD	MAINLINE STOPPED UP	WHITE OAK BAYOU	450-H	TX0057347	26-Apr-00			Gallons
	350 W. GULF BANK	SEWER MAIN STOPPED UP	WHITE OAK	411-Q	TX0057347	27-Apr-00	8:53	1500	Gallons
NORTHWEST QUADRANT 5	316 ANTOINE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-G	TX0057347	03-May-00	14:00	600	Gallons
NORTHWEST QUADRANT 5	943 DON WHITE LANE	ROUTINE STOPPAGE	WHITE OAK BAYOU	411-S	TX0057347	03-May-00	12:48	720	Gallons
NORTHWEST QUADRANT 2	071 ANTOINE	SEWER SERVICE LINE STOPPED UP	WHITE OAK BAYOU	451-I	TX0057347	03-May-00	10:03	90	Gallons
NORTHWEST QUADRANT 3	11 E. DELY	SEWER MAIN STOPPED UP	WHITE OAK BAYOU	453-E	TX0057347	05-May-00	11:08	192	Gallons
		STOPPAGE IN MAIN LINE OVERFLOWING INTO							
	114 BAYOU FOREST	STORM DRAIN	WHITE OAK BAYOU	411-T	TX0057347	06-May-00			Gallons
	410 GESSNER	SERVICE LINE STOPPED UP	WHITE OAK BAYOU	450-W	TX0057347	09-May-00			Gallons
NORTHWEST QUADS 1	707 BENLOW	OPEN JOINT IN SEWER LINE	WHITE OAK BAYOU	450-Y	TX0057347	10-May-00		3244	Gallons
NORTHWEST QUADRANT 6	600 CHATEAU FOREST	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-S	TX0057347	13-May-00			Gallons
NORTHWEST 6	35 E. 11 1/2	CITY MAIN AND SERVICE LINE STOPPED UP	WHITE OAK BAYOU	453-W	TX0026875	14-May-00		1356	Gallons
NORTHWEST QUAD 9	546 HAMMERLY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	450-T	TX0096172	18-May-00	8:37	363	Gallons
NORTHWEST QUAD 4:	35 FENN	CITY MAIN STOPPED UP	WHITE OAK BAYOU	452-M	TX0057347	19-May-00	8:47	848	Gallons
NORTHEAST QUAD 6	618 INWOOD WEST	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P	TX0096172	19-May-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	490-A	TX0096172	19-May-00			Gallons
	17 GRACELAND	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-V	TX0057347	20-May-00			Gallons
	06 1/2 GRACELAND	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-U	TX0096172	20-May-00			Gallons
	811 SOWAY	ROUTINE STOPPAGE (GREASE)	WHITE OAK BAYOU	450-M	TX0026875	21-May-00			Gallons
	414 ACORN FOREST DR.		WHITE OAK	411-S	TX0057347	22-May-00	12:59	3016	Gallons
NORTHEAST QUADRANT 4	06 GRACELAND	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-W	TX0057347	22-May-00	12:10	620	Gallons
	17 GRACE LAND	MAIN LINE STOPPED UP	WHITE OAK	453-V	TX0057347	23-May-00			Gallons
1	0999 NORTHWEST								
		MAIN LINE STOPPED UP, SERVICE LINE STOPPED UP	WHITE OAK BAYOU	451-E	TX0057347	23-May-00	12:03	924	Gallons
	35 E. 11TH1/2	ROUTINE STOPPAGE	WHITE OAK BAYOU	453-W	TX0096172	24-May-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-M	TX0057347	25-May-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	450-Q	TX0057347	26-May-00			Gallons
		SERVICE LINE STOPPED UP	WHITE OAK BAYOU	413-Y	TX0057347	26-May-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Q	TX0057347	29-May-00			Gallons
		MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-G	TX0057347	01-Jun-00			Gallons
		MAIN LINE STOPPED OP	WHITE OAK BAYOU	453-G 452-G	TX0057347	09-Jun-00			Gallons
	835 GROW LANE	CITY MAIN AND SERVICE LINE STOPPED UP	WHITE OAK BAYOU	452-G 450-D	TX0037347	11-Jun-00			Gallons
	DJEMAN & ALCOH	ROUTINE STOPPAGE	WHITE OAK BAYOU	450-R	TX0026875	12-Jun-00			Gallons
NORTHEAST QUAD 5	904 RUBERTSON	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-R	TX0057347	12-Jun-00			Gallons
LODELINATECT COME		MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-Q	TX0096172	14-Jun-00			Gallons
	500 N. MAIN	MAIN LINE STOPPAGE	WHITE OAK BAYOU	453-Y	TX0057347	16-Jun-00			Gallons
NORTHWEST QUAD 4			MALUTE OAK DAYOU	451-H	TX0096172	19-Jun-00	11.54	200	Gallons
NORTHWEST QUAD 4: NORTHWEST QUAD 4:	518 OAK SHADOWS	MAIN LINE STOPPED UP	WHITE OAK BAYOU					390	
NORTHWEST QUAD 4: NORTHWEST QUAD 4: NORTHEAST QUAD 2:	518 OAK SHADOWS 900 HARDY	MAIN LINE STOPPED UP OVER FLOW INTO STORM SEWER	WHITE OAK BAYOU	493-D	TX0057347	20-Jun-00			
NORTHWEST QUAD 4: NORTHWEST QUAD 4: NORTHEAST QUAD 2: 1 1:	518 OAK SHADOWS 900 HARDY 108 PASCHALL-C/S	OVER FLOW INTO STORM SEWER	WHITE OAK BAYOU	493-D	TX0057347	20-Jun-00	8:35		Gallons
NORTHWEST QUAD 4: NORTHWEST QUAD 4: NORTHEAST QUAD 2: 1 1:	518 OAK SHADOWS 900 HARDY						8:35		Gallons

			DL Project-Contract#						
Problem NORTHEAST QUAD	Location 57 PARKER RD.	Description	Receiving stream	Key map	Permit	Date 00	Time	Volume	Unit
NORTHWEST QUAD	7107 DEEP FOREST	MAIN LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU WHITE OAK BAYOU	413-X 411-X	TX0057347 TX0057347	26-Jun-00 28-Jun-00			Gallons Gallons
NORTHWEST QUAD	9318 EBLEN	MAIN LINE STOPPED UP	WHITE OAKS BAYOU	410-R	TX0057347	30-Jun-00			Gallons
	CHATEAU FOREST &								
NORTHWEST QUAD	DEIDRE ANNE D	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-S	TX0057347	03-Jul-00			Gallons
NORTHWEST QUAD	4701 DE MILO	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-H	TX0063011	03-Jul-00			Gallons
NORTHWEST QUAD NORTHWEST QUAD	8531 WILD BASIN 9227 GUYWOOD	SERVICE LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU WHITE OAK BAYOU	411-R 410-V	TX0057347	05-Jul-00 05-Jul-00			Gallons Gallons
NORTHWEST QUAD	1343 YALE ST.	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-Z	TX0057347	11-Jul-00			Gallons
NORTHWEST QUAD	1019 MARCELLA	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-C	TX0057347	12-Jul-00			Gallons
NORTHWEST QUAD	3219 TILSON	STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	450-L	TX0057347	13-Jul-00			Gallons
	3926 ARLINGTON								
SOUTHEAST QUAD	SQUARE DR.	OVERFLOW CAUSING EXCURSION	WHITE OAK BAYOU	453-J	TX0057347	14-Jul-00			Gallons
NORTHWEST QUAD	3000 N. LOOP FRWY	STOPPAGE CASUING OVERFLOW	WHITE OAK BAYOU	452-S	TX0057347	14-Jul-00	17:42	560	Gallons
NORTHWEST OHAD	3125 CRESTDOLE &	POLITINE STORDAGE	WHITE OAK BAYOU	450 K	TX0026875	45 Jul 00	00.50	420	Callona
NORTHWEST QUAD NORTHWEST QUADRANT	KEMPWOOD 810 W. 21ST	ROUTINE STOPPAGE ROUTINE STOPPAGE	WHITE OAK BAYOU WHITE OAK BAYOU	450-K 452-U	TX0026875	15-Jul-00 17-Jul-00			Gallons Gallons
NORTHWEST QUAD	307 E. DELZ	MAIN LINE STOPPED UP	WHITE OAK BATOO	453-E	TX0096172	19-Jul-00			Gallons
NORTHWEST QUAD	3000 N. LOOP FRWY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-S	TX0096172	21-Jul-00			Gallons
NORTHWEST QUAD	3606 ECHO GROVE LN.	MAIN LINE STOPPED UP	WHITE OAK BAYOU	449-B	TX0026875	24-Jul-00	13:41	1430	Gallons
NORTHWEST QUAD	10655 KATY FREEWAY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	489-C	TX0026875	25-Jul-00			Gallons
NORTHWEST QUAD	4026 BOLIN	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-K	TX0096172	25-Jul-00			Gallons
NORTHWEST QUADRANT	5005 GEORGI	ROUTINE STOPPAGE	WHITE OAK BAYOU	451-L	TX0057347	27-Jul-00			Gallons
NORTHWEST QUAD	2102 DELERY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-P	TX0057347	03-Aug-00			Gallons
NORTHWEST QUAD NORTHWEST QUAD	2050 N. LOOP FRWY 2600 N. SHEPHERD	MAIN LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU WHITE OAK	452-S 452-V	TX0057347 TX0096172	07-Aug-00 09-Aug-00			Gallons Gallons
NORTHWEST QUAD	9001 KEMPWOOD	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-V 450-Q	TX0096172	12-Aug-00			Gallons
NORTHWEST QUAD	1003 WAKEFIELD	MAIN STOPPED UP	WHITE OAK BAYOU	450-Q 452-P	TX0026675	15-Aug-00			Gallons
SOUTHEAST QUAD	2812 WICHITA ST.	SEWER LINE STOPPED UP	WHITE OAK BAYOU	533-C	TX0057347	16-Aug-00			Gallons
NORTHWEST QUAD	8800 GLENHOUSE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	412-K	TX0057347	20-Aug-00			Gallons
SOUTHWEST QUAD	2015 KIPLING	CITY MAIN STOPPED UP	WHITE OAK BAYOU	492-V	TX0057347	21-Aug-00	17:10		Gallons
NORTHWEST QUAD	3125 CRESTDALE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	450-P	TX0096172	21-Aug-00			Gallons
NORTHWEST QUAD	3502 CAMPBELL RD.	SERVICE LINE STOPPED UP	WHITE OAK BAYOU	450-K	TX0026875	22-Aug-00			Gallons
NORTHWEST QUAD	7224 BROOKSTONE	MAIN LINE STOPPED UP	WHITE OAK BAYOU WHITE OAK BAYOU	411-S	TX0057347	23-Aug-00			Gallons
NORTHWEST QUAD NORTHWEST QUAD	3125 CRESTDALE 911 W. LITTLE YORK	MAIN LINE STOPPED UP MAIN LINE STOPPED UP	WHITE OAK BAYOU	450-K 413-U	TX0026875 TX0057347	26-Aug-00 27-Aug-00			Gallons Gallons
NORTHWEST QUAD	2728 W. T.C. JESTER	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-S	TX0057347	31-Aug-00			Gallons
NORTHEAST QUAD	802 E. BURRESS	SERVICE LINE STOPPED UP	WHITE OAK BAYOU	453-E	TX0057347	06-Sep-00			Gallons
NORTHWEST QUAD	7835 GROW LN.	MAIN STOPPED UP	WHITE OAK	450-D	TX0057347	11-Sep-00			Gallons
NORTHWEST QUAD	7350 TC JESTER BLVD.	MAIN LINE STOPPED UP	WHITE OAK	411-V	TX0096172	18-Sep-00			Gallons
NORTHWEST QUAD	1934 GLOSRIDGE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	451-S	TX0057347	19-Sep-00		246	Gallons
NORTHWEST QUADRANT	1137 KEY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-W	TX0063011	19-Sep-00			Gallons
NORTHWEST QUAD	10110 BAMBOO RD.	CITY MAIN STOPPED UP GOING INTO STORM DRAIN		450-A	TX0026875	20-Sep-00			Gallons
SOUTHEAST QUAD	7800 N. MAIN	MAIN STOPPED UP	WHITE OAK BAYOU	453-N	TX0096172	21-Sep-00			Gallons
NORTHWEST QUAD	9001 KEMPWOOD CHATEAU FOREST@	MAIN LINE STOPPED UP	WHITE OAK BAYOU	450-L	TX0026875	22-Sep-00	08:37	52	Gallons
NORTHWEST QUADRANT	DEIRDRE ANNE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-S	TX0054347	23-Sep-00	11:41	291	Gallons
NORTHWEST QUAD	10110 BAMBOO RD	MAIN LINE STOPPAGE	WHITE OAK	450-Q	TX0026875	26-Sep-00			Gallons
	515 LITTLE YORK/NORTH								
NORTHWEST QUAD	FREEWAY	MAIN LINE STOPPED UP	WHITE OAK BAYOU	412-V	TX0057347	26-Sep-00	14:10	567	Gallons
NORTHWEST QUAD	209 W. 44TH	MAIN LINE STOPPAGE	WHITE OAK BAYOU	452-M	TX0057347	26-Sep-00	18:48	1015	Gallons
NORTHWEST QUAD	5555 HOLLINVIEW	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Y	TX0057347	29-Sep-00			Gallons
NORTHWEST QUAD	5714 W. GULF BANK RD.	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P	TX0063011	02-Oct-00			Gallons
NORTHEAST QUAD	328 VAN MOLAN	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-L	TX0057347	04-Oct-00			Gallons
NORTHWEST QUAD	5311 IRVINGTON 1300 W. 43RD	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-V	TX0057347 TX0096172	06-Oct-00 10-Oct-00			Gallons
NORTHWEST QUAD NORTHWEST QUAD	7930 PINEMONT	MAIN LINE STOPPED UP SEWER MAIN STOPPED UP	WHITE OAK BAYOU WHITE OAK BAYOU	452-K 450-H	TX0096172	12-Oct-00			Gallons Gallons
NORTHWEST QUAD	73301 INLINION1	CITY MAIN STOPPED UP ALSO SEWER COMING	WITTE OAK BATOO	430-11	17.0020073	12-001-00	12.40	244	Galloris
NORTHWEST QUAD	1410 GESSNER	FROM SAMPLE WELL	WHITE OAK BAYOU	450-W	TX0026875	12-Oct-00	20:23	498.5	Gallons
NORTHWEST QUAD	512 THORNTON	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-M	TX0057347	12-Oct-00			Gallons
NORTHWEST QUAD	9403 KEMPWOOD	MAIN LINE STOPPAGE	WHITE OAK BAYOU	450-L	TX0026875	13-Oct-00	19:23	834	Gallons
NORTHWEST QUAD	411 W. 23RD ST.	COMMUNITY LINE STOPPED UP	WHITE OAK BAYOU	452-T	TX0057347	16-Oct-00			Gallons
NORTHWEST QUAD	406 BARKLEY	SERVICE LINE STOPPED UP	WHITE OAK BAYOU	453-J	TX0057347	16-Oct-00	08:44	82.5	Gallons
NORTHWEST OURS	7150 BUSINESS PARK	CITY MAIN OVERFLOWING FROM WASTEWATER	WHITE OAK BAYOU	400 !!	TV0057047	17.0	15:40		Call- 1
NORTHWEST QUAD NORTHWEST QUAD	DR. 7840 BATEMAN	VALVE MAIN LINE STOPPED UP	WHITE OAK BAYOU WHITE OAK BAYOU	409-U 411-P	TX0057347 TX0057347	17-Oct-00			Gallons Gallons
NORTHWEST QUAD	400 REDAN	ROUTINE STOPPED UP	WHITE OAK BAYOU	411-P 493-B	TX0057347	17-Oct-00			Gallons
NORTHWEST QUAD	5815 W.LITTLE YORK	MAIN LINE STOPPAGE	WHITE OAK BAYOU	493-B 411-X	TX0057347	19-Oct-00			Gallons
NORTHWEST QUAD	307 E. DELZ	STOPPAGE IN CITY MAIN	WHITE OAK BAYOU	453-E	TX0096172	19-Oct-00			Gallons
NORTHWEST QUAD	1118 WORTSHIRE	ROUTINE STOPPAGE	WHITE OAK BAYOU	452-Y	TX0057347	20-Oct-00			Gallons
NORTHWEST QUAD	4118 CHERRY OAK	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-U	TX0057347	21-Oct-00	14:34		Gallons
NORTHWEST QUAD	11600 KILBURN	SEWER MAIN STOPPED UP	WHITE OAK BAYOU	451-P	TX0057347	21-Oct-00			Gallons
NORTHWEST QUAD	1400 SPRINGROCK	MAIN LINE STOPPED UP	WHITE OAK BAYOU	450-X	TX0057347	24-Oct-00			Gallons
NORTHWEST QUAD	5639 YALE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	452-D	TX0057347	25-Oct-00			Gallons
NORTHEAST QUAD	517 CATHER	ROUTINE STOPPAGE	WHITE OAK BAYOU	535-U	TX0057347	26-Oct-00	09:00	1446	Gallons
NORTHWEST QUAD	5555 W. GULFBANK	CITY MAIN STOPPED UP OVERFLOWING INTO MANHOLE	WHITE OAK BAYOU	411-Q	TX0057347	30-Oct-00	08:55	240	Gallons
NORTHEAST QUAD	8521 SCHNEIDER	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-H	TX0057347	30-Oct-00			Gallons
NORTHWEST QUAD	5698 W. LITTLE YORK	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-Y	TX0057347	31-Oct-00			Gallons
NORTHWEST QUAD	3007 SOWY	MAIN STOPPED UP	WHITE OAK BAYOU	450-R	TX0026875	01-Nov-00			Gallons
NORTHWEST QUAD	1608 SHEPARD DR.	MAIN STOPPED UP	WHITE OAK BAYOU	492-H	TX0057347	01-Nov-00			Gallons
	7635 AMELIA @								
NORTHWEST QUAD	COUNTER POINT	MAIN STOPPED UP	WHITE OAK BAYOU	451-T	TX0057347	02-Nov-00	11:00	1545	Gallons
NODTHWEST OF A	222 MEATHERI EV MAN	OVERFLOW FLOWING INTO DITCH CAUSING	WHITE OAK BAYOU	452 F	TV0057047	04 No 00	14:22		Calla
NORTHWEST QUAD NORTHWEST QUAD	223 WEATHERLEY WAY 8800 LONG POINT	EXCURSION MAIN STOPPED UP	WHITE OAK BAYOU WHITE OAK BAYOU	453-E 450-V	TX0057347 TX0026875	04-Nov-00 05-Nov-00			Gallons Gallons
HORTHWEST QUAD	SOUD LOING FOINT	IVII III TOTOLI LO OL	WHILL OAK BATOU	750°V	170020013	00-1407-00	. 00.10	13/60	Januis
NORTHWEST QUAD	9915 INWOOD SHADOWS	STOPPAGE IN MAIN LINE	WHITE OAK BAYOU	411-P	TX0057347	05-Nov-00	10:44	910	Gallons
NORTHWEST QUAD	13806 HEMPSTEAD HWY.	I .	WHITE OAK BAYOU	450-B	TX0026875	07-Nov-00			Gallons
NORTHWEST QUAD	1607 AIRLINE	MAIN LINE STOPPED UP	WHITE OAK BAYOU	453-X	TX0057347	07-Nov-00	07:44	1530	Gallons

Problem	Location	Description	Receiving stream	Key map	Permit	Date	Time	Volume	Unit
NORTHWEST QUAD	7800 GREEEN LAWN	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P	TX0057347	11-Nov-00	11:48	1864	Gallons
NORTHWEST QUAD	6507 VENA JEAN	MAIN LINE STOPPED UP	WHITE OAK BAYOU	411-P	TX0057347	12-Nov-00	12:35	711	Gallons
	1.1/4		1.1/4						
N/A	N/A	BAYOU BACKED UP CAUSING RESTRICTED FLOW	N/A	373-N	N/A	19-May-00	9:30		
NI/A	40500 DADK DOW	EFFLUENT FILTER BACKWASH SYSTEM	N/A	447-Y	TYOOOCOOL	00 0 00	LINUZNIO		0-11
N/A	16500 PARK ROW	FAILED, CAUSING FILTER T	N/A	447-1	TX0026395	29-Sep-00	UNKNO		Gallons
WASTEWATER OPERATION	6301 #1 FLIOUA W	DIGESTER OVERFILLED&SPILLED SLUDGE ON PLANT GROUND	N/A	571-X	TX0026433	20-Mar-97		2000	Gallons
WASTEWATER OF ERATION	0301#110Q0A, W.	SLUDGE HAULERS SPILLED SLUDGE WHILE	IV/A	371-7	170020433	20-IVIAI-37		2000	Galloris
WASTEWATER OPERATION	10273 GENARD	DISCONNECTING	N/A	450-A	TX0026875	30-Jan-96	14:30	50	Gallons
WASTEWATER OPERATION		SLUDGE TANK TRUCK HOSE LEAK.	N/A	450-A	TX0026875	05-Feb-96			Gallons
	10270 02111110	DIGESTER UNATTENDED;WASTING OVERFILLING	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10071	1710020010	00 1 00 00	02.00		Gallorio
WASTEWATER OPERATION	9610 KINGSPOINT	DIGESTER	N/A	576-W	TX0035009	08-Feb-96	11:10	1000	Gallons
WASTEWATER OPERATION		DIGESTER SPILL DUE TO THE PLANT OPERATOR.	N/A	576-W	TX0035009	04-Dec-97			Gallons
		DIGESTER OVERFLOW DUE TO HEAVY RAINFALL IN							
WASTEWATER OPERATION	13702 TRAILVILLE	AREA.	N/A	488-G	TX0058068	28-Jan-97	03:00	5000	Gallons
		SYNAGRO WHO'S CLEANING SLUDGE/GRIT FROM		100 0					
N/A	255 ISOLDE	AERATION BASINS	N/A	489-L	TX0063002	26-Sep-00	10:00	20	YDS.
		10"DISCHARGE HOSE NOT HOOKEDUP AERATION-		1.44					
WASTEWATER OPERATION	655 MAXEY ROAD	SEWAGESPIL	N/A	496-G	TX0063037	09-May-97	17:30	300000	Gallons
	7410 OLD GALVESTON								
N/A	RD	4" (TEMP) SLUDGE LINE BROKE	N/A	576-F	TX0063045	06-Feb-00	16:00	68000	Gallons
Wastewater Operation	8219 Kellett	Sludge spill, Clarifier # 1, Air Lift Too High	N/A	455-G	Tx0063053	29-Nov-97	un:kn	2000	Gallons
		MECH. JOINT CAME LOOSE ON THE FLUGDE WATER							
N/A	11700 SAGEARBOR	PUMP DISC.	N/A	576-Z	TX0063070	21-Jan-00	07:20	5000	Gallons
		CONTRACTOR DROVE OVER & DAMAGED A TEMP.4"							
WASTEWATER OPERATION	10518 BELLAIRE	SLUDGE	N/A	529-G	TX0065307	04-Feb-97	13:30	500	Gallons
	22 DEER RIDGE ESTATES	LIFT STATION OVERFLOWED DUE TO BREAKERS							
N/A	BLVD.	TRIPPING ON LP	N/A	336-G	TX0066583	29-Nov-99	06:00	200	Gallons
N/A	3928 KINGWOOD DR.	LEAK ON SCUM PUMP DISCHARGE LINE, LEAKAGE	N/A	337-V	TX0066583	29-Dec-99	05:00	500	Gallons
		LEAK DEVELOPED IN SCUM PUMP, NEAR REPAIRED							
N/A	3928 KINGWOOD DR	CLAMP	N/A	337-F	TX0066583	06-Jan-00	12:00	1000	Gallons
KINGWOOD CENTRAL		RAW SEWER BACKED UP FROM MANHOLE WHEN							
WWTP	4545 KINGWOOD DR.	POWER WENT OUT	N/A	337-B	TX0066583	20-May-00	2:00	2000	Gallons
		LIFT PUMP OVERLOADS;TRIPPED AND MILTRONICS							
N/A	2910 ROYAL CIRCLE	FAILED AND M	N/A	336-D	TX0066583	12-Aug-00	20:00	1000	Gallons
		FORCE MAIN FROM TRAIL RIVER LIFT STATION							
	4500 KINGWOOD DRIVE	DEVELOPED A LE	N/A	337-C	TX0066583	19-Sep-00	10:00	2000	Gallons
N/A	4722 ALDINE BENDER	BAR SCREEN CLOGGED	N/A	374-Y	TX0090166	10-Jan-00	UNK	600	Gallons
		A 24" FORCE MAIN WAS LEAKING AT 3700 HIRSCH							
WASTEWATER OPERATION	3700 HIRSCH ROAD	ROAD.	N/A	494-J	TX0096172	05-Nov-96	13:00	50	Gallons
	2200 HUFFMAN								
N/A	EASTGATE	FORCE MAIN LEAK	N/A	339-G	TX0103667	02-Jan-00	11:45		
		BARSCREEN CLOGGEDUP, SUBSEQUENTLY							Undeter
WASTEWATER OPERATION	3005 GALVESTON ROAD	OVERFLOW ONGROUND	N/A	535-L	TX0105058	12-May-97		0	mined
		CONTRACTOR TURNED PUMPS OFF TO REPLACE							
N/A	8209 GULF FREEWAY	CHECK VALVES.	N/A	535-T	TX0105058	22-Feb-00	13:55	200	Gallons
		HYDRAULIC OVERLOAD CAUSED DIGESTER TO							
WASTEWATER OPERATION		OVERFLOW.	NONE	488-F	TX0058068	29-Aug-96	03:00	2000	Gallons
	1/2 W. OF 11000 BLK	AIR RELIEF MALFUNCTION ON THE EXCESS SLUDGE							MILLION
WASTEWATER OPERATION	WOODFOREST	LINE	NONE	496-B	TX0063037			1.01	GAL.
WASTEWATER		THICKNER WAS FULL OF SCUM PLUGGED UP							
OPERATIONS	10518 BELLAIRE	DISCHARGE.	NONE	529-G	TX0065307	10-Jan-98	15:00	400	Gallons

Table C-2 Individual Permit Database

Database	TAG	END DATE	STORET GT	VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH		CALC. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	16056	06-Aug-96	31613	1400		11345	00-Jan-00	0.3			0)			WC	FO	RT
tnrccweb	20125	14-Oct-97	31613	27000		11345					0				WC		RT
tnrccweb	22801	25-Feb-98		1800		11345					0	-			WC		RT
tnrccweb	23084	18-May-98		1100		11345					0	-					RT
tnrccweb	U097989	03-Aug-98	31625	310		11345	00-Jan-00				0					GS	
tnrccweb	23684	06-Aug-98	31613 >	60000			00-Jan-00				0	-					RT
tnrccweb	U097990	22-Aug-98		11000			00-Jan-00				0					GS	
tnrccweb	24955	05-Nov-98	31613	1700		11345					0				WC		RT
tnrccweb	24957	10-Feb-99	31613	760		11345					0				WC		RT
tnrccweb	25972	05-May-99	31613	4000			00-Jan-00				0				WC		RT
tnrccweb	27701	03-Aug-99		330		11345					0				WC		RT
tnrccweb	U097972	03-Aug-98		500		11351	00-Jan-00				0	-				GS	
tnrccweb	U097973	22-Aug-98	31625	190		11351	00-Jan-00				0					GS	D.T.
tnrccweb	16061	06-Aug-96		700		11358	00-Jan-00				0						RT
tnrccweb	U097968	03-Aug-98		2200		11360					0	-				GS	
tnrccweb	U097970	22-Aug-98		3300		11360	00-Jan-00				0					GS	n.m.
tnrccweb	16055	06-Aug-96		2700		11362					0						RT
tnrccweb	20126	14-Oct-97	31613	5500			00-Jan-00				0	-			WC		RT
tnrccweb	22802	25-Feb-98	31613	1200		11362					0						RT
tnrccweb	23685	06-Aug-98		250			00-Jan-00				0)					RT
tnrccweb	24845	05-Nov-98		340		11362					0				WC		RT
tnrccweb	25989	10-Feb-99	31613	2650		11362					0)			WC		RT
tnrccweb	26952	05-May-99	31613	900		11362					0)			WC		RT
tnrccweb	U097974	15-Feb-94	31625	4200		11387	00-Jan-00				0)				GS	
tnrccweb	U097975	03-May-94	31625	6000		11387	00-Jan-00				0					GS	
tnrccweb	U097976	02-Aug-94	31625	680		11387	00-Jan-00				0	-				GS	
tnrccweb	U097977	13-Mar-95	31625	19000		11387	00-Jan-00				0					GS	
tnrccweb	U097978	22-May-95		520		11387	00-Jan-00				0	-				GS	
tnrccweb	U097979	03-Aug-95	31625	1900		11387	00-Jan-00				0					GS	
tnrccweb	U097980	27-Feb-96	31625	2500		11387	00-Jan-00				0					GS	
tnrccweb	U097981	29-May-96		4100		11387	00-Jan-00				0					GS	
tnrccweb	16062	06-Aug-96		60000		11387	00-Jan-00				0						RT
tnrccweb	U097982	26-Aug-96	31625	6700		11387	00-Jan-00				0					GS	
tnrccweb	U097983	26-Feb-97	31625	2800		11387	00-Jan-00				0					GS	
tnrccweb	U097984	14-May-97	31625	2800		11387	00-Jan-00				0					GS	
tnrccweb	U097985	18-Aug-97	31625	750		11387	00-Jan-00				0					GS	n.m.
tnrccweb	20130	14-Oct-97	31613	23000		11387	00-Jan-00				0	-					RT
tnrccweb	U097986	02-Feb-98	31625	7700		11387	00-Jan-00				0	1				GS	n.m.
tnrccweb	22806	25-Feb-98	31613	18000		11387	00-Jan-00				0						RT
tnrccweb	U097987	18-May-98		7000		11387	00-Jan-00				0	-				GS	D.T.
tnrccweb	23596	06-Aug-98		53000		11387	00-Jan-00				0	1			WC		RT
tnrccweb	U097988	11-Aug-98		2300		11387	00-Jan-00				0					GS	D.T.
tnrccweb	24956	05-Nov-98	31613	4800		11387	00-Jan-00					-					RT
tnrccweb	25992	10-Feb-99	31613	5000		11387	00-Jan-00				0						RT
tnrccweb	26957	05-May-99		1000		11387 11387	00-Jan-00				0	1			WC WC		RT RT
tnrccweb	27706	03-Aug-99	31613	1700			00-Jan-00				0	1					
rwqmdata	1000461	21-Jan-98		600			00-Jan-00								HG HG		RT RT
rwqmdata	I000462	09-Feb-98		380			00-Jan-00										
rwqmdata	1000809	13-Jul-98		3700			00-Jan-00								HG		RT
rwqmdata	I000810	17-Aug-98		3500			00-Jan-00										RT
rwqmdata	1000811	21-Sep-98		280			00-Jan-00										RT
rwqmdata	I000812	12-Oct-98		700			00-Jan-00										RT
rwqmdata	I000813	02-Nov-98		7200			00-Jan-00								HG		RT
rwqmdata	I000814	16-Dec-98		170			00-Jan-00								HG		RT
rwqmdata	1000815	04-Feb-98		1200			00-Jan-00								HG		RT
rwqmdata	I000816	23-Mar-98		4800			00-Jan-00										RT
rwqmdata	I000817	13-Apr-98		2100			00-Jan-00										RT
rwqmdata	1000818	11-May-98	31616	140		11354	00-Jan-00	0.3	1						HG	HP	RT

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
rwqmdata	I000819	03-Jun-98	31616	440		11354	00-Jan-00	0.3								HG		RT
rwqmdata	1000820	13-Jul-98	31616	2000			00-Jan-00	0.3								HG		RT
rwqmdata	1000821	17-Aug-98	31616	9200			00-Jan-00									HG		RT
rwqmdata	I000822 I000823	21-Sep-98 12-Oct-98	31616 31616	400 580			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata rwqmdata	I000823	02-Nov-98	31616	40000			00-Jan-00 00-Jan-00	0.3								HG		RT
rwqmdata	1000825	16-Dec-98	31616	2600			00-Jan-00									HG		RT
rwqmdata	1001005	13-Feb-98	31616	570			00-Jan-00	0.3								HG		RT
rwqmdata	I001006	18-May-98	31616	7400			00-Jan-00									HG		RT
rwqmdata	I001007	17-Jul-98	31616	2900		11390	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000463	02-Mar-98	31616	250		11351	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000464	01-Apr-98	31616	4500		11351	00-Jan-00	0.3								HG		RT
rwqmdata	I000465	04-May-98	31616	230		11351	00-Jan-00	0.3								HG		RT
rwqmdata	I000466	08-Jun-98	31616	20000			00-Jan-00	0.3								HG		RT
rwqmdata	I000467	22-Jul-98	31616	450			00-Jan-00	0.3								HG		RT
rwqmdata	I000468	05-Aug-98	31616	2100			00-Jan-00	0.3								HG		RT
rwqmdata	I000469	16-Oct-98	31616	3300			00-Jan-00	0.3								HG		RT
rwqmdata	I000470	04-Nov-98	31616	480			00-Jan-00	0.3								HG		RT
rwqmdata	I000471	08-Jun-98	31616	8900 23000			00-Jan-00	0.3								HG HG		RT RT
rwqmdata rwqmdata	I000472 I000473	22-Jul-98 05-Aug-98	31616 31616	1700			00-Jan-00 00-Jan-00	0.3								HG		RT
rwqmdata	I000473	08-Sep-98	31616	29000			00-Jan-00									HG		RT
rwqmdata	1000474	16-Oct-98	31616	7100			00-Jan-00	0.3								HG		RT
rwqmdata	I000476	04-Nov-98	31616	400			00-Jan-00									HG		RT
rwqmdata	1000477	09-Dec-98	31616	860		15826	00-Jan-00	0.3								HG		RT
rwqmdata	I000551	04-Feb-98	31616	350			00-Jan-00	0.3								HG		RT
rwqmdata	1000552	23-Mar-98	31616	25000		11353	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000553	13-Apr-98	31616	2200		11353	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000554	11-May-98	31616	99		11353	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000555	03-Jun-98	31616	470		11353	00-Jan-00	0.3								HG		RT
rwqmdata	I000556	13-Jul-98	31616	1900			00-Jan-00	0.3								HG		RT
rwqmdata	1000557	17-Aug-98	31616	3700			00-Jan-00									HG		RT
rwqmdata	1000558	21-Sep-98	31616	430			00-Jan-00									HG		RT
rwqmdata	I000559	12-Oct-98	31616	590			00-Jan-00									HG		RT
rwqmdata	I000560	02-Nov-98	31616	8600			00-Jan-00	0.3								HG		RT
rwqmdata	I000561	16-Dec-98	31616	1000 780			00-Jan-00	0.3								HG HG		RT RT
rwqmdata	I000562 I000563	12-Oct-98 02-Nov-98	31616 31616	33000			00-Jan-00 00-Jan-00	0.3								HG		RT
rwqmdata rwqmdata	I000563	16-Dec-98	31616	1200			00-Jan-00	0.3								HG		RT
rwqmdata	1000566	04-Feb-98	31616	700			00-Jan-00	0.3								HG		RT
rwqmdata	1000567	23-Mar-98	31616	33000		15844	00-Jan-00	0.3								HG		RT
rwqmdata	1000568	13-Apr-98	31616	30000		15844	00-Jan-00	0.3								HG		RT
rwqmdata	I000569	11-May-98	31616	140		15844	00-Jan-00	0.3								HG		RT
rwqmdata	1000570	03-Jun-98	31616	2700		15844	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000571	13-Jul-98	31616	2000		15844	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000572	17-Aug-98	31616	5800		15844	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000573	04-Feb-98	31616	1200		11351	00-Jan-00									HG		RT
rwqmdata	I000574	23-Mar-98	31616	30000			00-Jan-00									HG		RT
rwqmdata	1000575	13-Apr-98	31616	37000			00-Jan-00									HG		RT
rwqmdata	I000576	11-May-98	31616	210			00-Jan-00									HG		RT
-	1000577	03-Jun-98	31616	2400			00-Jan-00									HG		RT
rwqmdata	1000578	13-Jul-98	31616	3000			00-Jan-00									HG		RT
rwqmdata	1000579	17-Aug-98	31616	3900			00-Jan-00									HG		RT RT
rwqmdata	I000580 I000581	21-Sep-98 12-Oct-98	31616 31616	660 570			00-Jan-00 00-Jan-00									HG HG		RT
rwqmdata rwqmdata	I000581 I000582	02-Nov-98	31616	16000			00-Jan-00 00-Jan-00									HG HG		RT
	1000582	16-Dec-98	31616	910			00-Jan-00									HG		RT
rwqmdata	1000584	04-Feb-98	31616	980			00-Jan-00									HG		RT

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
rwqmdata	I000585	23-Mar-98	31616	380		15846	00-Jan-00									HG		RT
	I000586	13-Apr-98	31616	410			00-Jan-00	0.3								HG		RT
-	1000587	11-May-98	31616	390	-		00-Jan-00									HG		RT
-	I000588 I000589	03-Jun-98 13-Jul-98	31616 31616	540 1600			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
	1000589	13-Jul-98 17-Aug-98	31616	8200			00-Jan-00 00-Jan-00	0.3								HG		RT
-	1000591	21-Sep-98	31616	490			00-Jan-00									HG		RT
rwqmdata	1000592	12-Oct-98	31616	840			00-Jan-00									HG		RT
	1000593	02-Nov-98	31616	4800		-	00-Jan-00									HG		RT
rwqmdata	I000594	16-Dec-98	31616	27			00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000595	04-Feb-98	31616	380		15845	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000596	23-Mar-98	31616	7000		15845	00-Jan-00	0.3								HG		RT
	I000597	13-Apr-98	31616	480			00-Jan-00	0.3								HG		RT
	I000598	11-May-98	31616	160		-	00-Jan-00	0.3								HG		RT
-	I000599	03-Jun-98	31616	470			00-Jan-00	0.3								HG		RT
1	I000600	13-Jul-98	31616	1600			00-Jan-00	0.3								HG		RT
-	I000601	17-Aug-98	31616	5800		-	00-Jan-00	0.3								HG		RT
-	I000602 I000603	21-Sep-98 12-Oct-98	31616	460 850			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata rwqmdata	I000603	02-Nov-98	31616 31616	24000			00-Jan-00 00-Jan-00									HG		RT
rwqmdata	I000604	16-Dec-98	31616	750			00-Jan-00 00-Jan-00	0.3								HG		RT
rwqmdata	I000606	04-Feb-98	31616	170			00-Jan-00	0.3								HG		RT
rwqmdata	1000607	23-Mar-98	31616	6700			00-Jan-00	0.3								HG		RT
rwqmdata	1000608	13-Apr-98	31616	340			00-Jan-00	0.3								HG		RT
rwqmdata	1000609	11-May-98	31616	580			00-Jan-00	0.3								HG		RT
	I000610	03-Jun-98	31616	260	-	11362	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000611	13-Jul-98	31616	3000		11362	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000612	17-Aug-98	31616	4400		11362	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000613	21-Sep-98	31616	850		11362	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000614	12-Oct-98	31616	680		11362	00-Jan-00	0.3								HG		RT
-	I000615	02-Nov-98	31616	30000			00-Jan-00	0.3								HG		RT
rwqmdata	I000616	16-Dec-98	31616	36			00-Jan-00									HG		RT
rwqmdata	I000617	04-Feb-98	31616	300			00-Jan-00									HG		RT
rwqmdata	I000618	23-Mar-98	31616	180			00-Jan-00	0.3								HG		RT
_	I000619	13-Apr-98	31616	260			00-Jan-00	0.3								HG		RT
1	I000620 I000621	11-May-98 03-Jun-98	31616 31616	760 260			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata rwqmdata	I000621	13-Jul-98	31616	770			00-Jan-00 00-Jan-00	0.3								HG		RT
	I000623	17-Aug-98	31616	2200			00-Jan-00	0.3								HG		RT
-	1000624	21-Sep-98	31616	170			00-Jan-00	0.3								HG		RT
	1000625	12-Oct-98	31616	300	-		00-Jan-00	0.3								HG		RT
	I000626	02-Nov-98	31616	5600			00-Jan-00	0.3								HG		RT
	I000627	16-Dec-98	31616	18	-	11363	00-Jan-00	0.3								HG		RT
rwqmdata	1000628	04-Feb-98	31616	400		11359	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000629	23-Mar-98	31616	670		11359	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000630	13-Apr-98	31616	410		11359	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000631	11-May-98	31616	790	-	11359	00-Jan-00	0.3								HG		RT
	I000632	03-Jun-98	31616	480		11359	00-Jan-00									HG		RT
-	I000633	13-Jul-98	31616	3300			00-Jan-00									HG		RT
-	I000634	17-Aug-98	31616	7600			00-Jan-00									HG		RT
-	I000635	21-Sep-98	31616	390	-	-	00-Jan-00				-					HG		RT
	I000636	12-Oct-98	31616	830			00-Jan-00				-					HG		RT
-	I000637	02-Nov-98	31616	21000	-		00-Jan-00				-					HG		RT RT
-	I000638 I000649	16-Dec-98 04-Feb-98	31616 31616	63 380			00-Jan-00 00-Jan-00									HG HG		RT
•	I000649 I000650	04-Feb-98 23-Mar-98	31616	27			00-Jan-00 00-Jan-00									HG HG		RT
•	I000650	23-Mar-98 13-Apr-98	31616	155			00-Jan-00 00-Jan-00									HG		RT
-	1000652	13-Apr-98	31616	720		-	00-Jan-00									HG		RT

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
rwqmdata	1000653	03-Jun-98	31616	235		11364	00-Jan-00	0.3								HG		RT
rwqmdata	1000654	13-Jul-98	31616	375			00-Jan-00	0.3								HG		RT
rwqmdata	1000655	17-Aug-98	31616	3100			00-Jan-00									HG		RT
rwqmdata	1000656	21-Sep-98	31616	220			00-Jan-00	0.3								HG		RT
rwqmdata	I000657 I000658	12-Oct-98 02-Nov-98	31616 31616	730 4800			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata rwqmdata	1000638	23-Mar-98	31616	42000			00-Jan-00									HG		RT
rwqmdata	1000683	13-Apr-98	31616	49000			00-Jan-00	0.3								HG		RT
rwqmdata	1000684	11-May-98	31616	1700			00-Jan-00									HG		RT
rwqmdata	1000685	13-Jul-98	31616	29000			00-Jan-00	0.3								HG		RT
rwqmdata	1000696	17-Aug-98	31616	3900		11345	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000697	21-Sep-98	31616	810		11345	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000698	12-Oct-98	31616	390		11345	00-Jan-00	0.3								HG		RT
rwqmdata	1000699	02-Nov-98	31616	40000			00-Jan-00	0.3								HG		RT
rwqmdata	1000700	16-Dec-98	31616	650			00-Jan-00	0.3								HG		RT
rwqmdata	1000701	03-Jun-98	31616	2700			00-Jan-00	0.3								HG		RT
rwqmdata	1000749	04-Feb-98	31616	2900			00-Jan-00	0.3								HG		RT
rwqmdata	1000750	23-Mar-98	31616	21000			00-Jan-00	0.3										RT
rwqmdata	1000751	13-Apr-98	31616	41000			00-Jan-00	0.3								HG		RT
rwqmdata	I000752 I000753	11-May-98 03-Jun-98	31616 31616	1400 1600			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata	1000753	13-Jul-98	31616	36000			00-Jan-00									HG		RT
rwqmdata rwqmdata	1000754	13-Jul-98 17-Aug-98	31616	6000			00-Jan-00	0.3								HG		RT
rwqmdata	1000755	21-Sep-98	31616	680			00-Jan-00	0.3								HG		RT
rwqmdata	1000757	12-Oct-98	31616	580		15843	00-Jan-00	0.3								HG		RT
rwqmdata	1000758	02-Nov-98	31616	43000			00-Jan-00	0.3								HG		RT
rwqmdata	1000759	16-Dec-98	31616	980		15843	00-Jan-00	0.3								HG		RT
rwqmdata	1000760	04-Feb-98	31616	910			00-Jan-00	0.3								HG		RT
rwqmdata	I000761	23-Mar-98	31616	4100		11357	00-Jan-00	0.3								HG		RT
rwqmdata	1000762	13-Apr-98	31616	450		11357	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000763	11-May-98	31616	160		11357	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000764	03-Jun-98	31616	440		11357	00-Jan-00											RT
rwqmdata	1000765	13-Jul-98	31616	3800			00-Jan-00									HG		RT
rwqmdata	I000766	17-Aug-98	31616	3800			00-Jan-00									HG		RT
rwqmdata	1000767	21-Sep-98	31616	500			00-Jan-00	0.3								HG		RT
rwqmdata	1000768	12-Oct-98	31616	600			00-Jan-00	0.3								HG		RT
rwqmdata	1000769	02-Nov-98	31616	23000			00-Jan-00	0.3								HG		RT RT
rwqmdata	I000770 I000793	16-Dec-98 04-Feb-98	31616 31616	160 800			00-Jan-00 00-Jan-00	0.3								HG HG		RT
rwqmdata rwqmdata	1000793	23-Mar-98	31616	600		11360	00-Jan-00	0.3								HG		RT
rwqmdata	1000795	13-Apr-98	31616	390			00-Jan-00	0.3								HG		RT
rwqmdata	1000796	11-May-98	31616	820		11360	00-Jan-00	0.3								HG		RT
rwqmdata	1000797	03-Jun-98	31616	1200			00-Jan-00	0.3										RT
rwqmdata	1000798	13-Jul-98	31616	2500		11360	00-Jan-00									HG		RT
rwqmdata	1000799	17-Aug-98	31616	4100		11360	00-Jan-00	0.3								HG		RT
rwqmdata	1000800	21-Sep-98	31616	350		11360	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000801	12-Oct-98	31616	2300		11360	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000802	02-Nov-98	31616	44000		11360	00-Jan-00	0.3								HG		RT
rwqmdata	1000803	16-Dec-98	31616	130			00-Jan-00									HG		RT
rwqmdata	1000804	04-Feb-98	31616	760			00-Jan-00	-								HG		RT
rwqmdata	1000805	23-Mar-98	31616	920			00-Jan-00	-								HG		RT
rwqmdata	1000806	13-Apr-98	31616	370			00-Jan-00									HG		RT
rwqmdata	1000807	11-May-98	31616	760			00-Jan-00	-										RT
rwqmdata	1000808	03-Jun-98	31616	340			00-Jan-00									HG		RT
rwqmdata	1001008	02-Sep-98	31616	3400			00-Jan-00									HG		RT
rwqmdata	1001009	13-Feb-98	31616	520 960			00-Jan-00 00-Jan-00	-								HG HG		RT RT
rwqmdata	1001010	18-May-98 17-Jul-98	31616	5600			00-Jan-00 00-Jan-00									HG HG		RT
rwqmdata	1001011	1 /-Jui-98	31616	2000	L	15829	oo-jan-00	0.3		l .		l .				пυ	пР	N.I

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
rwqmdata	1001012	02-Sep-98	31616	2200		15829	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1001013	17-Jul-98	31616	4700		-	00-Jan-00	0.3								HG		RT
rwqmdata	1001014	02-Sep-98	31616	5200		-	00-Jan-00									HG		RT
rwqmdata	1001017	13-Feb-98	31616	2200			00-Jan-00	0.3								HG		RT
rwqmdata	1001018	18-May-98	31616	8600			00-Jan-00	0.3								HG		RT
rwqmdata	1001019	17-Jul-98	31616	5700			00-Jan-00	0.3								HG		RT
rwqmdata	1001020	02-Sep-98	31616	4900			00-Jan-00									HG		RT
rwqmdata	1001021	13-Feb-98	31616	590			00-Jan-00	0.3								HG		RT
rwqmdata	1001022	18-May-98	31616	11000			00-Jan-00									HG		RT
rwqmdata	1001023	17-Jul-98	31616 31616	3300 11000			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata	I001024 I001040	02-Sep-98 13-Feb-98	31616	680			00-Jan-00	0.3								HG		RT
rwqmdata rwqmdata	1001040	18-May-98	31616	11000			00-Jan-00	0.3								HG		RT
rwqmdata	1001041	13-Feb-98	31616	500			00-Jan-00	0.3								HG		RT
rwqmdata	1001047	18-May-98	31616	580			00-Jan-00	0.3								HG		RT
rwqmdata	1001048	17-Jul-98	31616	830			00-Jan-00	0.3								HG		RT
rwqmdata	1001049	02-Sep-98	31616	790			00-Jan-00	0.3								HG		RT
rwqmdata	I001050	13-Feb-98	31616	600			00-Jan-00	0.3										RT
rwqmdata	I001051	18-May-98	31616	600		15830	00-Jan-00	0.3								HG		RT
rwqmdata	1001052	17-Jul-98	31616	4000		15830	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1001053	02-Sep-98	31616	2100		15830	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1003288	08-Feb-99	31616	12000		15843	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1003544	09-Dec-98	31616	8900		11351	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1003546	16-Dec-98	31616	18		11364	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I001015	13-Feb-98	31616	2900		16636	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I001016	18-May-98	31616	22000		16636	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1001025	13-Feb-98	31616	780		16646	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I001026	18-May-98	31616	4000		16646	00-Jan-00	0.3								HG		RT
rwqmdata	I001028	02-Sep-98	31616	5500		16646	00-Jan-00	0.3								HG		RT
rwqmdata	1001042	13-Feb-98	31616	770			00-Jan-00	0.3								HG		RT
rwqmdata	1001043	18-May-98	31616	35000			00-Jan-00	0.3								HG		RT
rwqmdata	I001044	17-Jul-98	31616	4100			00-Jan-00											RT
rwqmdata	1001045	02-Sep-98	31616	3500			00-Jan-00									HG		RT
rwqmdata	1001054	17-Jul-98	31616	7600			00-Jan-00	0.3								HG		RT
rwqmdata	1001055	02-Sep-98	31616	6000			00-Jan-00									HG		RT
rwqmdata	1000478	21-Jan-98	31616	6800 5400			00-Jan-00	0.3								HG HG		RT RT
rwqmdata	I000479 I000480	09-Feb-98 02-Mar-98	31616 31616	200			00-Jan-00	0.3								HG		RT
rwqmdata rwqmdata	1000480	02-Mar-98 01-Apr-98	31616	25000		-	00-Jan-00 00-Jan-00									HG		RT
rwqmdata	1000481	04-May-98	31616	6700		-	00-Jan-00	0.3								HG		RT
rwqmdata	1000482	23-Mar-98	31616	26000			00-Jan-00	0.3								HG		RT
rwqmdata	1000639	13-Apr-98	31616	47000			00-Jan-00	0.3								HG		RT
rwqmdata	1000641	11-May-98	31616	1900			00-Jan-00	0.3										RT
rwqmdata	1000642	13-Jul-98	31616	20000			00-Jan-00									HG		RT
rwqmdata	1000643	17-Aug-98	31616	4900		-	00-Jan-00									HG		RT
rwqmdata	1000644	21-Sep-98	31616	2100			00-Jan-00									HG		RT
rwqmdata	1000645	12-Oct-98	31616	8500		-	00-Jan-00									HG		RT
rwqmdata	I000646	02-Nov-98	31616	28000			00-Jan-00									HG		RT
rwqmdata	1000647	16-Dec-98	31616	4300		16647	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000648	03-Jun-98	31616	2100		16647	00-Jan-00	0.3							Green color observed.	HG		RT
	1000670	04-Feb-98	31616	590		11163	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1000671	23-Mar-98	31616	230		11163	00-Jan-00	0.3								HG		RT
rwqmdata	1000672	13-Apr-98	31616	210			00-Jan-00											RT
rwqmdata	1000673	11-May-98	31616	2900		-	00-Jan-00									HG		RT
rwqmdata	1000674	03-Jun-98	31616	200			00-Jan-00									HG		RT
rwqmdata	1000675	17-Aug-98	31616	3400			00-Jan-00						1			HG		RT
rwqmdata	1000676	21-Sep-98	31616	240			00-Jan-00											RT
rwqmdata	I000677	12-Oct-98	31616	150		11163	00-Jan-00	0.3								HG	HP	RT

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
rwqmdata	I000678	02-Nov-98	31616	430		11163	00-Jan-00	0.3								HG	HP	RT
rwqmdata	I000679	16-Dec-98	31616	45			00-Jan-00	0.3								HG		RT
rwqmdata	I000771	04-Feb-98	31616	240			00-Jan-00	0.3								HG		RT
rwqmdata	I000772	23-Mar-98	31616	130			00-Jan-00	0.3								HG		RT
rwqmdata	I000773	13-Apr-98	31616	300			00-Jan-00	0.3								HG		RT
rwqmdata	I000774	11-May-98	31616	290			00-Jan-00	0.3								HG		RT
rwqmdata	I000775	03-Jun-98	31616	950			00-Jan-00	0.3								HG		RT
rwqmdata	I000776	13-Jul-98	31616	2400			00-Jan-00	0.3								HG		RT
rwqmdata	I000777	17-Aug-98	31616	2700			00-Jan-00									HG		RT
rwqmdata	I000778 I000779	21-Sep-98 12-Oct-98	31616 31616	210 5000			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata	1000779	02-Nov-98	31616	36000			00-Jan-00	0.3								HG		RT
rwqmdata rwqmdata	1000780	16-Dec-98	31616	910			00-Jan-00	0.3								HG		RT
rwqmdata	1003270	08-Feb-99	31616	220			00-Jan-00	0.3								HG		RT
rwqmdata	1003270	08-Feb-99	31616	90			00-Jan-00	0.3								HG		RT
rwqmdata	I003545	04-Feb-98	31616	2800			00-Jan-00	0.3								HG		RT
rwqmdata	1003577	15-Jan-99	31616	7200			00-Jan-00	0.3								HG		RT
rwqmdata	1003578	29-Jan-99	31616	2100			00-Jan-00	0.3								HG		RT
rwqmdata	1003579	15-Jan-99	31616	3500			00-Jan-00	0.3								HG		RT
rwqmdata	1003580	19-Jan-99	31616	1500			00-Jan-00	0.3								HG		RT
rwqmdata	I003581	19-Jan-99	31616	4400			00-Jan-00	0.3								HG		RT
rwqmdata	I003634	15-Jan-99	31616	> 200000		16648	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I003635	29-Jan-99	31616	13000		16648	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I003643	15-Jan-99	31616	510		11387	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I003644	29-Jan-99	31616	9700		11387	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I003815	08-Jan-99	31616	> 200000		16595	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I003816	22-Jan-99	31616	11000		16595	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I003817	08-Jan-99	31616	43000		16594	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I003818	22-Jan-99	31616	47000		16594	00-Jan-00	0.3								HG		RT
rwqmdata	I003819	08-Jan-99	31616	31000		16593	00-Jan-00	0.3								HG		RT
rwqmdata	I003820	25-Jan-99	31616	540			00-Jan-00	0.3								HG		RT
rwqmdata	I003823	15-Jan-99	31616	14000			00-Jan-00									HG		RT
rwqmdata	I003825	29-Jan-99	31616	> 200000			00-Jan-00	0.3								HG		RT
rwqmdata	I003826	08-Jan-99	31616	1100			00-Jan-00	0.3								HG		RT
rwqmdata	I003827	25-Jan-99	31616	120			00-Jan-00	0.3								HG		RT
rwqmdata	I003828	19-Jan-99	31616	2800			00-Jan-00	0.3								HG		RT
rwqmdata	I003829	19-Jan-99	31616	72			00-Jan-00	0.3								HG		RT
rwqmdata	I003830	19-Jan-99	31616	150			00-Jan-00	0.3								HG		RT
rwqmdata	I003833	25-Jan-99	31616	130			00-Jan-00	0.3								HG		RT
rwqmdata	I003834	25-Jan-99	31616	130			00-Jan-00	0.3								HG		RT RT
rwqmdata	I003931 I003932	10-Feb-99 15-Feb-99	31616 31616	5300 3000			00-Jan-00 00-Jan-00	0.3								HG HG		RT
rwqmdata	I003932 I003933	22-Feb-99	31616	2000			00-Jan-00 00-Jan-00	0.3								HG		RT
rwqmdata	I003935	05-Feb-99	31616	1200			00-Jan-00	0.3								HG		RT
rwqmdata rwqmdata	I003930	22-Feb-99	31616	120000			00-Jan-00	0.3								HG		RT
rwqmdata	I005496	22-Feb-99	31616	690			00-Jan-00	0.3								HG		RT
rwqmdata	1003938	05-Feb-99	31616	1500			00-Jan-00	0.3								HG		RT
rwqmdata	I003939	22-Feb-99	31616	72000			00-Jan-00									HG		RT
rwqmdata	1003940	11-Feb-99	31616	31000			00-Jan-00	0.3								HG		RT
rwqmdata	I003941	15-Feb-99	31616	5600			00-Jan-00									HG		RT
	I003942	22-Feb-99	31616	2300			00-Jan-00									HG		RT
rwqmdata	I004011	15-Feb-99	31616	2500			00-Jan-00									HG		RT
rwqmdata	I004012	22-Feb-99	31616	2300			00-Jan-00									HG		RT
rwqmdata	I004013	10-Feb-99	31616	92000			00-Jan-00									HG		RT
rwqmdata	I004014	15-Feb-99	31616	4200			00-Jan-00									HG		RT
rwqmdata	I004015	22-Feb-99	31616	3700			00-Jan-00									HG		RT
	I004017	03-Feb-99	31616	2000		16591	00-Jan-00											RT
rwqmdata	I004019	22-Feb-99	31616	2200		16591	00-Jan-00	0.3								HG	НН	RT

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
rwqmdata	1004020	01-Feb-99	31616	500		11188	00-Jan-00	0.3								HG		RT
rwqmdata	1004021	08-Feb-99	31616	1800			00-Jan-00	0.3								HG		RT
rwqmdata	1004022	17-Feb-99	31616	54000			00-Jan-00	0.3								HG		RT
rwqmdata	1004023	24-Feb-99	31616	9400			00-Jan-00	0.3								HG		RT
rwqmdata	1004025	01-Feb-99	31616	440			00-Jan-00	0.3								HG		RT
rwqmdata	1004026	08-Feb-99	31616	15000			00-Jan-00	0.3								HG HG		RT RT
rwqmdata	I004027 I004028	17-Feb-99 24-Feb-99	31616 31616	15000 180			00-Jan-00 00-Jan-00	0.3								HG		RT
rwqmdata rwqmdata	1004028	01-Feb-99	31616	370			00-Jan-00 00-Jan-00									HG		RT
rwqmdata	1004030	08-Feb-99	31616	< 10			00-Jan-00	0.3								HG		RT
rwqmdata	1004030	17-Feb-99	31616	1300			00-Jan-00	0.3								HG		RT
rwqmdata	1004032	24-Feb-99	31616	220			00-Jan-00	0.3								HG		RT
rwqmdata	1004035	03-Feb-99	31616	260		+	00-Jan-00	0.3								HG		RT
rwqmdata	1004036	10-Feb-99	31616	850			00-Jan-00	0.3								HG		RT
rwqmdata	1004037	17-Feb-99	31616	58000			00-Jan-00	0.3								HG		RT
rwqmdata	1004038	24-Feb-99	31616	120000		16592	00-Jan-00	0.3								HG	НН	RT
rwqmdata	1004039	03-Feb-99	31616	710		16597	00-Jan-00	0.3								HG	НН	RT
rwqmdata	1004040	10-Feb-99	31616	380		16597	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I004041	24-Feb-99	31616	950		16597	00-Jan-00	0.3								HG	НН	RT
rwqmdata	1005497	10-Feb-99	31616	12000		11351	00-Jan-00	0.3								HG		RT
rwqmdata	1004043	15-Feb-99	31616	4300		11351	00-Jan-00	0.3								HG		RT
rwqmdata	I004044	22-Feb-99	31616	3600			00-Jan-00	0.3								HG		RT
rwqmdata	1004045	01-Feb-99	31616	1500			00-Jan-00	0.3								HG		RT
rwqmdata	1004046	03-Feb-99	31616	860			00-Jan-00	0.3								HG		RT
rwqmdata	1004047	17-Feb-99	31616	100000			00-Jan-00	0.3								HG		RT
rwqmdata	1004048	24-Feb-99	31616	450			00-Jan-00	0.3								HG		RT
rwqmdata	1004049	01-Feb-99	31616	4800			00-Jan-00	0.3								HG		RT
rwqmdata	1004050	08-Feb-99	31616	7500			00-Jan-00	0.3								HG		RT
rwqmdata	1004051	17-Feb-99	31616	16000			00-Jan-00	0.3								HG		RT
rwqmdata	I004052 I004053	24-Feb-99 01-Feb-99	31616 31616	860 300			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata rwqmdata	1004053	08-Feb-99	31616	370			00-Jan-00 00-Jan-00									HG		RT
rwqmdata	1004054	17-Feb-99	31616	750			00-Jan-00									HG		RT
rwqmdata	1004056	24-Feb-99	31616	230			00-Jan-00	0.3								HG		RT
rwqmdata	1005832	12-Apr-99	31616	3500			00-Jan-00	0.3								HG		RT
rwqmdata	1005857	17-May-99	31616	100			00-Jan-00	0.3								HG		RT
rwqmdata	1005881	07-Jun-99	31616	4300			00-Jan-00	0.3								HG		RT
rwqmdata	1005883	07-Jun-99	31616	830		15843	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1005907	23-Aug-99	31616	1800		11351	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1005909	23-Aug-99	31616	1400		15843	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1005503	23-Jul-99	31616	3500		11351	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1005577	14-Jun-99	31616	2800		11351	00-Jan-00	0.3								HG	HP	RT
rwqmdata	1005578	14-Jun-99	31616	9000		11351	00-Jan-00	0.3								HG		RT
rwqmdata	1005594	21-Sep-99	31616	21000			00-Jan-00									HG		RT
rwqmdata	1005607	25-Aug-99	31616	7100			00-Jan-00									HG		RT
rwqmdata	1005608	25-Aug-99	31616	6000			00-Jan-00	0.3								HG		RT
rwqmdata	1005727	12-Jul-99	31616	2200			00-Jan-00									HG		RT
rwqmdata	1005729	12-Jul-99	31616	2000			00-Jan-00									HG		RT
rwqmdata	1005807	08-Mar-99	31616	12000			00-Jan-00									HG		RT
rwqmdata	1005934	27-Sep-99	31616	3300			00-Jan-00									HG		RT
rwqmdata	1005936	27-Sep-99		2200			00-Jan-00									HG		RT
rwqmdata	1006340	16-Jul-99		7400			00-Jan-00									HG		RT
rwqmdata	1006341	16-Jul-99		4800			00-Jan-00									HG		RT
rwqmdata	1006354	09-Apr-99		22000			00-Jan-00									HG		RT
rwqmdata	1006355	09-Apr-99	31616	9800			00-Jan-00									HG		RT
rwqmdata	1006368	26-May-99		860 700			00-Jan-00 00-Jan-00									HG HG		RT RT
rwqmdata	1006369	26-May-99		9000			00-Jan-00 00-Jan-00											RT
rwqmdata	1006381	21-Jun-99	31616	9000	1	15825	00-jan-00	0.3								HG	пP	K1

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
rwqmdata	1006382	21-Jun-99	31616	15000		16647	00-Jan-00									HG		RT
rwqmdata	I006395	05-Aug-99	31616	290			00-Jan-00	0.3								HG		RT
rwqmdata	1006396	05-Aug-99	31616	590			00-Jan-00									HG		RT
rwqmdata	1006409	15-Sep-99	31616 31616	5200 2400			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata rwqmdata	I006410 I009099	15-Sep-99 01-Mar-99	31616	69000			00-Jan-00 00-Jan-00	0.3								HG HG		RT
rwqmdata	1009099	08-Mar-99	31616	21000			00-Jan-00									HG		RT
rwqmdata	1009101	15-Mar-99	31616	3400			00-Jan-00									HG		RT
rwqmdata	I009103	07-Apr-99	31616	> 200000			00-Jan-00									HG		RT
rwqmdata	1009104	29-Apr-99	31616	120000		16675	00-Jan-00	0.3								HG	НН	RT
rwqmdata	I009105	05-May-99	31616	21000		16675	00-Jan-00	0.3								HG	HH	RT
rwqmdata	I009106	11-May-99	31616	21000		16675	00-Jan-00	0.3								HG		RT
rwqmdata	I009107	19-May-99	31616	31000			00-Jan-00	0.3								HG		RT
rwqmdata	1009108	26-May-99	31616	41000			00-Jan-00	0.3								HG		RT
rwqmdata	I009109	14-Jun-99	31616	2300			00-Jan-00	0.3								HG		RT
rwqmdata	I009110	29-Jun-99	31616	7000			00-Jan-00	0.3								HG		RT
rwqmdata	1009236	08-Jun-99	31616	15000			00-Jan-00	0.3								HG		RT
rwqmdata	1009237	14-Jun-99	31616	4700			00-Jan-00	0.3										RT
rwqmdata	1009238	17-Jun-99	31616	6500 5300			00-Jan-00 00-Jan-00	0.3								HG HG		RT RT
rwqmdata	I009239 I009240	23-Jun-99 29-Jun-99	31616 31616	800			00-Jan-00 00-Jan-00									HG HG		RT
rwqmdata swqm10	1311	03-Aug-92	31616	92000			00-Jan-00									WC		RT
swqm10	1312	03-Aug-92	31616	> 60000			00-Jan-00	0.3								WC		RT
swqm10	1313	03-Aug-92	31616	107000			00-Jan-00	0.3								WC		RT
swqm10	1314	03-Aug-92	31616	74000			00-Jan-00	0.3								WC		RT
swqm10	1315	03-Aug-92	31616	60000			00-Jan-00	0.15								WC		RT
swqm10	1441	19-Nov-92	31616	37000			00-Jan-00	0.3								WC		RT
swqm10	1442	19-Nov-92	31616	1500			00-Jan-00	0.15								WC		RT
swqm10	1447	19-Nov-92	31616	2300		11354	00-Jan-00	0.3								WC	FO	RT
swqm10	1448	19-Nov-92	31616	8000		11387	00-Jan-00	0.15								WC	FO	RT
swqm10	1449	17-Nov-92	31616	115		11398	00-Jan-00	0.15								WC	FO	RT
swqm10	U010851	26-Feb-92	31625	2700		11387	00-Jan-00	0.3								GS	GS	
swqm10	U010852	11-May-92	31625	820			00-Jan-00									GS	GS	1
swqm10	U010853	04-Aug-92	31625	2600			00-Jan-00	0.3								GS	GS	
swqm10	X010019	06-Feb-92	31616	220			00-Jan-00	0.3			0				WATER YELLOW-GREENISH E			RT
swqm10	X010020	06-Feb-92	31616	590			00-Jan-00	0.15			0				WATER YELLOWISH-GREEN V			RT
swqm10	X010023	24-Feb-92	31616	4000			00-Jan-00	0.3			0				WATER BROWN WITH SOME T			RT
swqm10	X010024	24-Feb-92	31616	105000			00-Jan-00	0.3			0				WATER BROWN WITH DEBRIS			RT
swqm10	X010025 X011037	24-Feb-92 26-May-92	31616 31616	56000 13000			00-Jan-00 00-Jan-00	0.3			0				WATER BROWN WITH MUCH WATER BROWN, OVERCAST S			RT RT
swqm10 swqm10	X011037 X011038	26-May-92	31616	6000			00-Jan-00	0.3			0				WATER GREEN, OVERCAST SI			RT
swqm10	X011038 X011039	26-May-92	31616	60			00-Jan-00	0.3			0				WATER GREEN, SKY OVERCA			RT
swqm10	X011040	26-May-92	31616	450			00-Jan-00	0.3			0				WATER BROWN, OVERCAST S			RT
tnrccweb	2759	04-Feb-93	31616	110			00-Jan-00				0				WITTER BROWN, O'ERCHET	WC		RT
tnrccweb	2764	11-Feb-93	31616	9000			00-Jan-00	0.3			0					WC		RT
tnrccweb	2765	11-Feb-93	31616	10000		11362	00-Jan-00	0.3			0					WC		RT
tnrccweb	2774	11-Feb-93	31616	13000		11354	00-Jan-00	0.3			0					WC	FO	RT
tnrccweb	2775	11-Feb-93	31616	10000		11387	00-Jan-00	0.3			0					WC	FO	RT
tnrccweb	2919	13-May-93	31616	305		11398	00-Jan-00	0.15			0					WC	FO	RT
tnrccweb	2924	20-May-93	31616	6800			00-Jan-00				0					WC	FO	RT
tnrccweb	2925	20-May-93	31616	630			00-Jan-00				0					WC		RT
tnrccweb	2931	20-May-93	31616	4700			00-Jan-00				0		1			WC		RT
tnrccweb	2932	20-May-93	31616	3400			00-Jan-00				0		1			WC		RT
tnrccweb	3809	25-Aug-93	31616	620			00-Jan-00				0					WC		RT
tnrccweb	3814	16-Aug-93	31616	20000			00-Jan-00				0		1			WC		RT
tnrccweb	3816	16-Aug-93	31616	5800			00-Jan-00				0		-			WC		RT
tnrccweb	3821	16-Aug-93	31616	2300			00-Jan-00				0		-			WC		RT
tnrccweb	3822	16-Aug-93	31616	2450		11387	00-Jan-00	0.3			0					WC	FO	RT

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END S	START DATE	START TIME	START DEPTH	CATEGORY CALC	. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	4791	09-Nov-93	31616	> 60000		11345	00-Jan-00				0						RT
tnrccweb	7159	08-Feb-94	31616	60000			00-Jan-00	0.3			0						RT
tnrccweb	7160	08-Feb-94	31616	1050			00-Jan-00				0						RT
tnrccweb	1005872	07-Jun-99 07-Jun-99	31616	1300			00-Jan-00	0.3			0						RT RT
tnrccweb tnrccweb	I005873 I005874	07-Jun-99 07-Jun-99	31616 31616	860 7100			00-Jan-00 00-Jan-00	0.3			0						RT
tnrccweb	1005875	07-Jun-99	31616	590			00-Jan-00				0						RT
tnrccweb	1005876	07-Jun-99	31616	1500			00-Jan-00				0						RT
tnrccweb	1005877	07-Jun-99	31616	860			00-Jan-00				0						RT
tnrccweb	1005885	07-Jun-99	31616	610		11345	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005890	23-Aug-99	31616	730		11364	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005892	23-Aug-99	31616	270		11363	00-Jan-00	0.3			0				HG		RT
tnrccweb	1005894	23-Aug-99	31616	2300		11362	00-Jan-00	0.3			0	ı			HG	HP	RT
tnrccweb	1005895	23-Aug-99	31616	2700			00-Jan-00	0.3			0						RT
tnrccweb	1005897	23-Aug-99	31616	1500			00-Jan-00	0.3			0						RT
tnrccweb	1005898	23-Aug-99	31616	2300			00-Jan-00	0.3			0						RT
tnrccweb	1005899	23-Aug-99	31616	1200			00-Jan-00	0.3			0						RT
tnrccweb	1005900	23-Aug-99	31616	1200			00-Jan-00	0.3			0						RT
tnrccweb	1005901	23-Aug-99	31616	230			00-Jan-00				0						RT
tnrccweb	1005902	23-Aug-99	31616	220			00-Jan-00				0						RT
tnrccweb	1005903	23-Aug-99	31616	250			00-Jan-00	0.3			0						RT RT
tnrccweb	I005911 I005917	23-Aug-99 27-Sep-99	31616 31616	670 120			00-Jan-00 00-Jan-00	0.3			0						RT
tnrccweb	1005917	27-Sep-99 27-Sep-99	31616	99			00-Jan-00 00-Jan-00	0.3			0						RT
tnrccweb tnrccweb	1005919	27-Sep-99	31616	180			00-Jan-00	0.3			0						RT
tnrccweb	1005922	27-Sep-99	31616	2100			00-Jan-00	0.3			0						RT
tnrccweb	1005924	27-Sep-99	31616	2200			00-Jan-00	0.3			0						RT
tnrccweb	1005925	27-Sep-99	31616	840			00-Jan-00	0.3			0						RT
tnrccweb	1005926	27-Sep-99	31616	100			00-Jan-00	0.3			0						RT
tnrccweb	1005927	27-Sep-99	31616	180		11357	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005928	27-Sep-99	31616	170		15845	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005929	27-Sep-99	31616	150		11354	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005930	27-Sep-99	31616	160		11353	00-Jan-00	0.3			0	ı			HG	HP	RT
tnrccweb	1005938	27-Sep-99	31616	14000		11345	00-Jan-00	0.3			0						RT
tnrccweb	1006330	16-Jul-99	31616	2500			00-Jan-00	0.3			0						RT
tnrccweb	I006331	16-Jul-99	31616	880			00-Jan-00	0.3			0						RT
tnrccweb	1006332	16-Jul-99	31616	970			00-Jan-00	0.3			0						RT
tnrccweb	1006333	16-Jul-99	31616	1200			00-Jan-00	0.3			0						RT
tnrccweb	1006334	16-Jul-99	31616	2100			00-Jan-00	0.3			0						RT
tnrccweb	I006335 I006337	16-Jul-99 16-Jul-99	31616 31616	3100 2200			00-Jan-00	0.3			0						RT RT
tnrccweb tnrccweb	1006337	09-Apr-99	31616	820			00-Jan-00 00-Jan-00	0.3			0						RT
tnrccweb	1006345	09-Apr-99	31616	1200			00-Jan-00	0.3			0						RT
tnrccweb	1006346	09-Apr-99	31616	973			00-Jan-00				0						RT
tnrccweb	1006347	09-Apr-99	31616	4000			00-Jan-00				0						RT
tnrccweb	1006348	09-Apr-99	31616	3200			00-Jan-00	0.3			0				HG		RT
tnrccweb	1006349	09-Apr-99	31616	32000			00-Jan-00				0						RT
tnrccweb	I006351	09-Apr-99	31616	34000			00-Jan-00				0						RT
tnrccweb	1006358	26-May-99	31616	750		15831	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1006359	26-May-99	31616	720		15830	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1006360	26-May-99	31616	1100		11390	00-Jan-00	0.3			0						RT
tnrccweb	1006361	26-May-99	31616	1200			00-Jan-00				0						RT
tnrccweb	1006362	26-May-99	31616	3600			00-Jan-00				0						RT
tnrccweb	1006363	26-May-99	31616	2000			00-Jan-00				0						RT
tnrccweb	1006365	26-May-99	31616	8900			00-Jan-00				0						RT
tnrccweb	1006367	26-May-99	31616	460			00-Jan-00				0						RT
tnrccweb	1006371	21-Jun-99	31616	16000			00-Jan-00				0						RT
tnrccweb	1006372	21-Jun-99	31616	8000		15830	00-Jan-00	0.3			0				HG	HP	RT

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY CALC	. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	1006373	21-Jun-99	31616	11000		11390	00-Jan-00				0				HG		RT
tnrccweb	I006374	21-Jun-99	31616	9000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1006375	21-Jun-99	31616	11000			00-Jan-00				0				HG		RT
tnrccweb	1006376	21-Jun-99 21-Jun-99	31616	19000 15000			00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb tnrccweb	I006378 I006385	05-Aug-99	31616 31616	880			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT
tnrccweb	1006386	05-Aug-99	31616	620		 	00-Jan-00				0				HG		RT
tnrccweb	1006387	05-Aug-99	31616	740		 	00-Jan-00				0				HG		RT
tnrccweb	1006388	05-Aug-99	31616	500			00-Jan-00				0				HG		RT
tnrccweb	1006389	05-Aug-99	31616	520		11391	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1006390	05-Aug-99	31616	2200		16637	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1006392	05-Aug-99	31616	710		15826	00-Jan-00	0.3			0				HG		RT
tnrccweb	1006399	15-Sep-99	31616	1400		15831	00-Jan-00	0.3			0				HG		RT
tnrccweb	1006400	15-Sep-99	31616	1000		 	00-Jan-00	0.3			0				HG		RT
tnrccweb	1006401	15-Sep-99	31616	1400			00-Jan-00	0.3			0				HG		RT
tnrccweb	1006402	15-Sep-99	31616	1500			00-Jan-00	0.3			0				HG		RT
tnrccweb	1006403	15-Sep-99	31616	1700			00-Jan-00	0.3			0				HG		RT
tnrccweb	1006404	15-Sep-99	31616	1400		1	00-Jan-00				0						RT
tnrccweb	1006406	15-Sep-99	31616	2500			00-Jan-00	0.3			0				HG		RT
tnrccweb	I008632 I008633	01-Mar-99	31616	3400 3900		 	00-Jan-00	0.3			0				HG		RT RT
tnrccweb		08-Mar-99 15-Mar-99	31616	4500		1	00-Jan-00 00-Jan-00				0				HG HG		RT
tnrccweb	I008634 I008635	22-Mar-99	31616 31616	2500			00-Jan-00	0.3			0				HG HG		RT
tnrccweb	1008635	14-Apr-99	31616	53000			00-Jan-00	0.3			0				HG		RT
tnrccweb tnrccweb	1008637	20-Apr-99	31616	21000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1008638	26-Apr-99	31616	540		 	00-Jan-00	0.3			0				HG		RT
tnrccweb	1008639	29-Apr-99	31616	2500		 	00-Jan-00	0.3			0				HG		RT
tnrccweb	1008640	05-May-99	31616	1100			00-Jan-00	0.3			0				HG		RT
tnrccweb	1008641	08-Jun-99	31616	47000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1008642	17-Jun-99	31616	3900		11387	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1008643	23-Jun-99	31616	12000		11387	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	I008644	29-Jun-99	31616	6100		11387	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1008645	15-Mar-99	31616	1600		16596	00-Jan-00	0.3			0				HG		RT
tnrccweb	1008647	07-Apr-99	31616	3000		16596	00-Jan-00				0				HG		RT
tnrccweb	1008649	21-Apr-99	31616	1000			00-Jan-00				0				HG		RT
tnrccweb	1008650	29-Apr-99	31616	65000			00-Jan-00	0.3			0				HG		RT
tnrccweb	I008651	05-May-99	31616	15000		1	00-Jan-00	0.3			0				HG		RT
tnrccweb	1008652	19-May-99	31616	7300			00-Jan-00	0.3			0				HG		RT
tnrccweb	I008653 I008654	26-May-99 01-Jun-99	31616 31616	> 200000			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb	1008654	09-Jun-99	31616	> 200000			00-Jan-00	0.3			0				HG		RT
tnrccweb tnrccweb	1008655	14-Jun-99	31616	3900			00-Jan-00	0.3			0				HG		RT
tnrccweb	1008657	21-Jun-99	31616	44000			00-Jan-00	0.3			0						RT
tnrccweb	1008658	01-Jul-99	31616	5000		1	00-Jan-00				0				HG		RT
tnrccweb	1008659	15-Mar-99	31616	1000			00-Jan-00				0				HG		RT
tnrccweb	1008661	07-Apr-99	31616	44000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1008663	21-Apr-99	31616	42000		16595	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1008664	29-Apr-99	31616	5700		16595	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1008665	05-May-99	31616	> 200000		16595	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1008666	19-May-99	31616	> 200000		16595	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	1008667	26-May-99					00-Jan-00				0				HG		RT
tnrccweb	1008668	01-Jun-99	31616	67000			00-Jan-00				0				HG		RT
tnrccweb	1008669	09-Jun-99		> 200000			00-Jan-00				0						RT
tnrccweb	1008670	14-Jun-99	31616	26000			00-Jan-00				0				HG		RT
tnrccweb	1008671	21-Jun-99	31616				00-Jan-00				0		1		HG		RT
tnrccweb	1008672	01-Jul-99	31616	12000			00-Jan-00	-			0				HG		RT
tnrccweb	1008673	15-Mar-99		2600			00-Jan-00				0		+				RT
tnrccweb	1008675	07-Apr-99	31616	31000		16594	00-Jan-00	0.3			0				HG	HH	RT

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END STAF	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	I008677	21-Apr-99	31616	5700		16594	00-Jan-00		0)			HG		RT
tnrccweb	I008678	29-Apr-99	31616	11000			00-Jan-00		0				HG		RT
tnrccweb	I008679	05-May-99	31616	760			00-Jan-00		0				HG		RT
tnrccweb	1008680	19-May-99	31616	10000			00-Jan-00		0				HG		RT
tnrccweb	1008681	26-May-99	31616	33000 8100			00-Jan-00	0.3	0				HG		RT RT
tnrccweb tnrccweb	I008682 I008683	01-Jun-99 09-Jun-99	31616 31616	52000			00-Jan-00 00-Jan-00	0.3	0				HG HG		RT
tnrccweb	1008684	14-Jun-99	31616	73000		1	00-Jan-00	0.3	0				HG		RT
tnrccweb	1008685	21-Jun-99	31616	47000			00-Jan-00	0.3	0				HG		RT
tnrccweb	I008686	01-Jul-99	31616	6400		1	00-Jan-00	0.3	0				HG		RT
tnrccweb	I008687	15-Mar-99	31616	1800		16593	00-Jan-00	0.3	0				HG	НН	RT
tnrccweb	I008689	07-Apr-99	31616	2000		16593	00-Jan-00	0.3	0				HG	HH	RT
tnrccweb	I008691	21-Apr-99	31616	14000		16593	00-Jan-00	0.3	0)			HG	HH	RT
tnrccweb	I008692	29-Apr-99	31616	1300		16593	00-Jan-00		0				HG		RT
tnrccweb	I008693	05-May-99	31616	850			00-Jan-00		0				HG		RT
tnrccweb	I008694	19-May-99	31616	1600			00-Jan-00		0				HG		RT
tnrccweb	1008695	26-May-99	31616	6400			00-Jan-00		0				HG HG		RT RT
tnrccweb	I008696 I008697	01-Jun-99 09-Jun-99	31616 31616	9500 8000		1	00-Jan-00 00-Jan-00	0.3	0				HG		RT
tnrccweb	1008697	14-Jun-99	31616	31000			00-Jan-00	0.3	0				HG		RT
tnrccweb	1008699	21-Jun-99	31616	140000			00-Jan-00	0.3	0				HG		RT
tnrccweb	1008700	01-Jul-99	31616	510		1	00-Jan-00		0				HG		RT
tnrccweb	I008701	01-Mar-99	31616	1900		16648	00-Jan-00	0.3	0				HG		RT
tnrccweb	1008702	08-Mar-99	31616	1700		16648	00-Jan-00	0.3	0				HG	НН	RT
tnrccweb	1008703	15-Mar-99	31616	77000		16648	00-Jan-00	0.3	0)			HG	HH	RT
tnrccweb	I008704	22-Mar-99	31616	5600		16648	00-Jan-00	0.3	0				HG		RT
tnrccweb	I008705	14-Apr-99	31616	86000			00-Jan-00		0				HG		RT
tnrccweb	7165	08-Feb-94	31616	870			00-Jan-00		0				WC		RT
tnrccweb	7166	08-Feb-94	31616	8600			00-Jan-00		0				WC		RT
tnrccweb tnrccweb	7167 7466	02-Feb-94 04-May-94	31616 31616	210 12000			00-Jan-00 00-Jan-00	0.3	0				WC WC		RT RT
tnrccweb	7467	04-May-94	31616	550			00-Jan-00	0.3	0				WC		RT
tnrccweb	7472	04-May-94	31616	1500		1	00-Jan-00		0				WC		RT
tnrccweb	7473	04-May-94	31616	22000			00-Jan-00	0.3	0				WC		RT
tnrccweb	7474	25-May-94	31616	1000		11398	00-Jan-00	0.3	0				WC	FO	RT
tnrccweb	8576	10-Aug-94	31616	13000		11398	00-Jan-00	0.3	0				WC	FO	RT
tnrccweb	8589	18-Aug-94	31616	> 60000		11358	00-Jan-00	0.3	0				WC		RT
tnrccweb	9445	13-Feb-95	31613	455			00-Jan-00	0.3	0				WC		RT
tnrccweb	9453	08-Feb-95	31613	10000			00-Jan-00	0.3	0			LIM 70300 1 TRDE H	WC		RT
tnrccweb	9455	08-Feb-95	31613	3850			00-Jan-00		0				WC		RT
tnrccweb	9460	08-Feb-95	31613	21000			00-Jan-00		0				WC		RT
tnrccweb tnrccweb	9461 9754	08-Feb-95 08-Nov-94	31613 31613	21000 1200			00-Jan-00 00-Jan-00	0.3	0	\			WC WC		RT RT
tnrccweb	9756	08-Nov-94	31613	60			00-Jan-00		0				WC		RT
tnrccweb	9761	08-Nov-94	31613	110			00-Jan-00	0.3	0				WC		RT
tnrccweb	9762	08-Nov-94	31613	6000			00-Jan-00	0.3	0				WC		RT
tnrccweb	12560	01-Aug-95	31613	3000			00-Jan-00	0.3	0				WC	FO	RT
tnrccweb	12568	03-Aug-95	31613	17000		11345	00-Jan-00	0.3	0			LIM 01220 1 TRDE Totals did 1	WC .	FO	RT
tnrccweb	12569	03-Aug-95		9000			00-Jan-00		0				WC		RT
tnrccweb	12574	03-Aug-95	31613	12000			00-Jan-00		0				WC		RT
tnrccweb	12575	03-Aug-95	31613	21500			00-Jan-00		0				WC		RT
tnrccweb	13917	06-Nov-95	31613	14000			00-Jan-00		0				WC		RT
tnrccweb	13918	06-Nov-95	31613	470 4800			00-Jan-00		0				WC		RT
tnrccweb	13923 13924	06-Nov-95 06-Nov-95	31613 31613	60000			00-Jan-00 00-Jan-00		0				WC WC		RT RT
tnrccweb	13924	16-Nov-95	31613	200			00-Jan-00		0				WC		RT
tnrccweb	14044	31-Jan-96	31613	45			00-Jan-00		0				WC		RT
tnrccweb	14052	29-Jan-96	31613	4000			00-Jan-00		0				WC		RT
	17002	27-Jan-70	31013	7000	L	11,543	50 Jan-00	0.5	 	1	1	I .	.,.		14.4

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	14053	29-Jan-96	31613	180		11362	00-Jan-00	0.3			0					WC	FO	RT
tnrccweb	14058	29-Jan-96	31613	300			00-Jan-00	0.3			0							RT
	14059	29-Jan-96	31613	10000			00-Jan-00				0							RT
	14950	06-May-96	31613	380			00-Jan-00	0.3			0							RT
	14958 14959	08-May-96 08-May-96	31613 31613	1600 380			00-Jan-00 00-Jan-00	0.3			0							RT RT
	14964	08-May-96	31613	1800			00-Jan-00				0							RT
tnrccweb	14965	08-May-96	31613	2100			00-Jan-00				0							RT
tnrccweb	16079	07-Aug-96	31613	2800			00-Jan-00				0							RT
tnrccweb	16740	08-Oct-96	31613	30000			00-Jan-00	0.3			0				LIM 00593 1 TRDE Above Cal.	WC		RT
tnrccweb	16741	08-Oct-96	31613	24000		11362	00-Jan-00				0							RT
	16748	08-Oct-96	31613	3000		11387	00-Jan-00	0.3			0					WC	FO	RT
tnrccweb	17596	10-Feb-97	31613	7000		11345	00-Jan-00	0.3			0					WC	FO	RT
tnrccweb	17597	10-Feb-97	31613	240		11362	00-Jan-00	0.3			0					WC	FO	RT
tnrccweb	17601	10-Feb-97	31613	90		11387	00-Jan-00	0.3			0					WC	FO	RT
tnrccweb	18258	08-May-97	31613	440			00-Jan-00	0.3			0							RT
tnrccweb	18262	08-May-97	31613	3500			00-Jan-00	0.3			0							RT
	19525	05-Aug-97	31613	100		1	00-Jan-00				0							RT
	19526	05-Aug-97	31613	5200			00-Jan-00				0							RT
	19530	05-Aug-97	31613	4600			00-Jan-00	-			0							RT
tnrccweb	22968	26-May-98	31613	1500			00-Jan-00	0.3			0							RT
	22969	26-May-98	31613	510			00-Jan-00				0							RT
	22970	26-May-98	31613	470			00-Jan-00	0.3			0							RT
	23083	18-May-98	31613	550			00-Jan-00	0.3			0							RT
	23085	18-May-98	31613	> 6000			00-Jan-00	0.3			0							RT
	23087	01-Jun-98	31613	1500 38000			00-Jan-00	0.3			0							RT RT
	23088 23089	01-Jun-98 01-Jun-98	31613 31613	310			00-Jan-00 00-Jan-00	0.3			0							RT
	23108	07-May-98	31613	800			00-Jan-00	0.3			0							RT
	23112	07-May-98	31613	700		1	00-Jan-00	0.3			0							RT
	23112	07-May-98	31613	900			00-Jan-00				0							RT
	23446	13-May-98	31613	160		 	00-Jan-00				0							RT
	23447	13-May-98	31613	21500			00-Jan-00				0							RT
	23448	13-May-98	31613	1000			00-Jan-00				0							RT
	I005501	23-Jul-99	31616	3500		15826	00-Jan-00	0.3			0					HG	HP	RT
tnrccweb	I005512	28-Jan-99	31616	2500		11351	00-Jan-00	0.3			0					HG	HP	RT
tnrccweb	I005513	28-Jan-99	31616	2100		11351	00-Jan-00	0.3			0					HG	HP	RT
tnrccweb	I005516	28-Jan-99	31616	2700		15826	00-Jan-00	0.3			0					HG	HP	RT
tnrccweb	I005525	15-Feb-99	31616	2500		11351	00-Jan-00	0.3			0					HG	HP	RT
tnrccweb	I005526	15-Feb-99	31616	7400		11351	00-Jan-00	0.3			0					HG	HP	RT
	I005529	15-Feb-99	31616	4100			00-Jan-00	0.3			0							RT
	I005538	23-Mar-99	31616	4200			00-Jan-00	0.3			0							RT
	I005542	23-Mar-99	31616	3800		 	00-Jan-00	0.3			0							RT
	I005551	26-Apr-99	31616	72			00-Jan-00				0							RT
	I005552	26-Apr-99	31616	510			00-Jan-00				0							RT
tnrccweb	1005555	26-Apr-99	31616	910			00-Jan-00	0.3			0							RT
tnrccweb	I005564	20-May-99	31616	63			00-Jan-00				0							RT
	1005565	20-May-99	31616				00-Jan-00				Ü							RT
	I005568 I005581	20-May-99 14-Jun-99	31616 31616	510 1400			00-Jan-00 00-Jan-00				0							RT RT
	1005581	21-Sep-99	31616	500			00-Jan-00				0							RT
	1005592	21-Sep-99 25-Aug-99	31616	860			00-Jan-00				0							RT
	1005000	23-Aug-99 12-Jul-99	31616	730			00-Jan-00				0							RT
	1005710	12-Jul-99	31616	5000			00-Jan-00				0							RT
	1005712	12-Jul-99	31616	2200			00-Jan-00				0							RT
	1005714	12-Jul-99	31616	2300			00-Jan-00				0							RT
	1005717	12-Jul-99	31616	2200			00-Jan-00				0							RT
	1005717	12-Jul-99	31616	2900			00-Jan-00				0							RT

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	I005719	12-Jul-99	31616	3200		15846	00-Jan-00				0				HG		RT
	1005720	12-Jul-99	31616	6000			00-Jan-00	0.3			0				HG		RT
	I005721	12-Jul-99	31616	3000			00-Jan-00				0				HG		RT
	1005722	12-Jul-99 12-Jul-99	31616 31616	7300 9500		1	00-Jan-00	0.3			0				HG HG		RT RT
	I005723 I005731	12-Jul-99 12-Jul-99	31616	35000			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT
	1005762	08-Feb-99	31616	270		 	00-Jan-00				0				HG		RT
	1005764	08-Feb-99	31616	220			00-Jan-00				0				HG		RT
	1005766	08-Feb-99	31616	500			00-Jan-00				0				HG		RT
	1005767	08-Feb-99	31616	810			00-Jan-00	0.3			0				HG		RT
	1005769	08-Feb-99	31616	690		11360	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005770	08-Feb-99	31616	500		11359	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	I005771	08-Feb-99	31616	930		15846	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005772	08-Feb-99	31616	1300		11357	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005773	08-Feb-99	31616	210		15845	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005774	08-Feb-99	31616	220			00-Jan-00	0.3			0				HG		RT
	1005775	08-Feb-99	31616	1100			00-Jan-00	0.3			0				HG		RT
	1005779	08-Feb-99	31616	1000		1	00-Jan-00	0.3			0				HG		RT
	1005783	08-Feb-99	31616	660			00-Jan-00				0				HG		RT
	1005788	08-Mar-99	31616	200			00-Jan-00	-			0				HG		RT
	I005790	08-Mar-99	31616	180			00-Jan-00	0.3			0				HG		RT
tnrccweb	1005792	08-Mar-99	31616	3000			00-Jan-00				0				HG		RT
	I005793	08-Mar-99	31616	810		 	00-Jan-00	0.3			0				HG		RT
	1005795	08-Mar-99	31616	690			00-Jan-00	0.3			0				HG		RT
	I005796	08-Mar-99	31616	390			00-Jan-00	0.3			0				HG		RT
	1005797	08-Mar-99 08-Mar-99	31616	930 170		 	00-Jan-00	0.3			0				HG HG		RT RT
	I005798 I005799	08-Mar-99	31616 31616	220			00-Jan-00 00-Jan-00	0.3			0				HG		RT
	1005799	08-Mar-99	31616	1000		 	00-Jan-00	0.3			0				HG		RT
	I005800	08-Mar-99	31616	1100		1	00-Jan-00	0.3			0				HG		RT
	1005805	08-Mar-99	31616	1000			00-Jan-00				0				HG		RT
	1005809	08-Mar-99	31616	660		 	00-Jan-00				0				HG		RT
	1005813	12-Apr-99	31616	230			00-Jan-00				0				HG		RT
	1005815	12-Apr-99	31616	14000			00-Jan-00	0.3			0				HG		RT
	1005817	12-Apr-99	31616	38000		11362	00-Jan-00	0.3			0				HG	HP	RT
	1005818	12-Apr-99	31616	23000		11361	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005820	12-Apr-99	31616	6000		11360	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005821	12-Apr-99	31616	3000		11359	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	1005822	12-Apr-99	31616	1200		15846	00-Jan-00	0.3			0				HG	HP	RT
tnrccweb	I005823	12-Apr-99	31616	790		11357	00-Jan-00	0.3			0				HG	HP	RT
	I005824	12-Apr-99	31616	780		15845	00-Jan-00	0.3			0				HG		RT
	1005825	12-Apr-99	31616	8100			00-Jan-00	0.3			0				HG		RT
tnrccweb	1005826	12-Apr-99	31616	1400		11353	00-Jan-00	0.3			0				HG		RT
	1005830	12-Apr-99	31616	8400			00-Jan-00				0				HG		RT
	1005834	12-Apr-99	31616	1200			00-Jan-00				0				HG		RT
tnrccweb	I005838	17-May-99	31616	3300			00-Jan-00	0.3			0				HG		RT
tnrccweb	1005840	17-May-99	31616	1900			00-Jan-00				0				HG		RT
	I005842	17-May-99	31616	870			00-Jan-00				0				HG		RT
	I005843	17-May-99	31616	2100			00-Jan-00				0				HG		RT
	I005845 I005846	17-May-99 17-May-99	31616 31616	700 2700			00-Jan-00 00-Jan-00				0		+-		HG HG		RT RT
	I005846 I005847	17-May-99 17-May-99	31616	480			00-Jan-00 00-Jan-00				0		+		HG HG		RT
	I005847 I005848	17-May-99 17-May-99	31616	590			00-Jan-00 00-Jan-00				0				HG HG		RT
	I005848 I005849	17-May-99 17-May-99	31616	670			00-Jan-00	-			0				HG		RT
	1005850	17-May-99 17-May-99	31616	2800			00-Jan-00				0				HG		RT
	I005850 I005851	17-May-99	31616	1900			00-Jan-00				0				HG		RT
	1005855	17-May-99	31616	590			00-Jan-00	-			0				HG		RT
	-300000	17-May-99	31616	660			00-Jan-00				0		1		HG		RT

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	1005864	07-Jun-99	31616	130		11364	00-Jan-00	0.3		0				HG	HP	RT
tnrccweb	1005866	07-Jun-99	31616	270			00-Jan-00			0				HG		RT
tnrccweb	1005868	07-Jun-99	31616	690			00-Jan-00			0				HG		RT
tnrccweb	1005869	07-Jun-99	31616	1200			00-Jan-00			0				HG		RT
tnrccweb	I005871 I008706	07-Jun-99 20-Apr-99	31616 31616	2100 1200			00-Jan-00 00-Jan-00	0.3		0				HG HG		RT RT
tnrccweb	1008700	26-Apr-99	31616	3200			00-Jan-00 00-Jan-00	0.3		0				HG		RT
tnrccweb	1008708	29-Apr-99	31616	2200			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008709	11-May-99	31616	130000			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008710	17-May-99	31616	560			00-Jan-00	0.3		0				HG		RT
tnrccweb	I008711	08-Jun-99	31616	> 200000		16648	00-Jan-00	0.3		0				HG	НН	RT
tnrccweb	1008712	17-Jun-99	31616	15000		16648	00-Jan-00	0.3		0				HG	НН	RT
tnrccweb	1008713	29-Jun-99	31616	1600		16648	00-Jan-00	0.3		0				HG		RT
tnrccweb	I008714	08-Mar-99	31616	31000			00-Jan-00			0				HG		RT
tnrccweb	1008715	15-Mar-99	31616	130000			00-Jan-00			0				HG		RT
tnrccweb	1008716	18-Mar-99	31616	100000			00-Jan-00			0				HG		RT
tnrccweb	1008718	07-Apr-99	31616	23000			00-Jan-00	0.3		0				HG HG		RT RT
tnrccweb	I008719 I008721	07-Apr-99	31616 31616	13000 7600			00-Jan-00 00-Jan-00	0.3		0				HG		RT
tnrccweb	1008721	21-Apr-99 21-Apr-99	31616	7400			00-Jan-00 00-Jan-00	0.3		0				HG		RT
tnrccweb	1008722	29-Apr-99	31616	17000			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008724	29-Apr-99	31616	16000			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008725	05-May-99	31616	6500			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008726	05-May-99	31616	8700			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008727	19-May-99	31616	7400		11148	00-Jan-00	0.3		0				HG	НН	RT
tnrccweb	1008728	19-May-99	31616	6400		11148	00-Jan-00	0.3		0				HG	НН	RT
tnrccweb	1008729	26-May-99	31616	8400		11148	00-Jan-00	0.3		0				HG		RT
tnrccweb	1008730	26-May-99	31616	8100			00-Jan-00			0				HG		RT
tnrccweb	1008731	01-Jun-99	31616	2200			00-Jan-00			0				HG		RT
tnrccweb	1008732	01-Jun-99	31616	2800			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008733	09-Jun-99	31616	> 200000 22000			00-Jan-00	0.3		0				HG HG		RT RT
tnrccweb	I008735 I008736	14-Jun-99 14-Jun-99	31616 31616	23000			00-Jan-00 00-Jan-00			0				HG		RT
tnrccweb	1008737	21-Jun-99	31616	180000			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008739	01-Jul-99	31616	29000			00-Jan-00	0.3		0				HG		RT
tnrccweb	1008740	01-Jul-99	31616	27000			00-Jan-00	0.3		0				HG		RT
tnrccweb	1009083	01-Mar-99	31616	1100			00-Jan-00	0.3		0				HG		RT
tnrccweb	1009084	08-Mar-99	31616	1200		11347	00-Jan-00	0.3		0				HG	НН	RT
tnrccweb	1009085	15-Mar-99	31616	13000		11347	00-Jan-00	0.3		0				HG	НН	RT
tnrccweb	1009086	22-Mar-99	31616	2200		11347	00-Jan-00	0.3		0	ı			HG	HH	RT
tnrccweb	1009087	29-Mar-99	31616	28000			00-Jan-00			0				HG		RT
tnrccweb	1009088	14-Apr-99	31616	13000			00-Jan-00			0				HG		RT
tnrccweb	1009089	20-Apr-99	31616	2000			00-Jan-00	0.3		0				HG		RT
tnrccweb	1009090	26-Apr-99	31616	1100			00-Jan-00			0				HG		RT
tnrccweb	1009091	29-Apr-99	31616	700 2000			00-Jan-00	0.3		0				HG HG		RT RT
tnrccweb	I009092 I009093	05-May-99 05-May-99	31616 31616	2800			00-Jan-00 00-Jan-00	0.3		0				HG		RT
tnrccweb	1009093	17-May-99	31616	1400			00-Jan-00 00-Jan-00			0				HG		RT
tnrccweb	1009095	01-Jun-99	31616	2800			00-Jan-00			0				HG	+	RT
tnrccweb	1009096	17-Jun-99	31616	15000			00-Jan-00			0				HG		RT
tnrccweb	1009097	23-Jun-99	31616	6200			00-Jan-00			0				HG		RT
tnrccweb	1009098	29-Jun-99	31616	1700			00-Jan-00			0				HG		RT
tnrccweb	1009111	15-Mar-99	31616	680			00-Jan-00			0				HG		RT
tnrccweb	1009112	31-Mar-99	31616	450		16591	00-Jan-00	0.3		0				HG		RT
tnrccweb	1009113	31-Mar-99	31616	360			00-Jan-00			0				HG		RT
tnrccweb	1009114	07-Apr-99	31616	420			00-Jan-00			0				HG		RT
tnrccweb	1009115	07-Apr-99	31616	480			00-Jan-00			0				HG		RT
tnrccweb	I009116	15-Apr-99	31616	900		16591	00-Jan-00	0.3	1	0				HG	HH	RT

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY CALC	. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	1009117	21-Apr-99	31616	3900		16591	00-Jan-00				0				HG		RT
tnrccweb	I009119	29-Apr-99	31616	2600			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009120	05-May-99	31616	400			00-Jan-00				0				HG		RT
tnrccweb	1009121	11-May-99	31616	8000 3800			00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb tnrccweb	I009122 I009123	11-May-99 19-May-99	31616 31616	400			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT
tnrccweb	1009124	26-May-99	31616	150000			00-Jan-00				0				HG		RT
tnrccweb	1009125	14-Jun-99	31616	1700			00-Jan-00				0				HG		RT
tnrccweb	I009126	29-Jun-99	31616	1100			00-Jan-00				0				HG		RT
tnrccweb	1009127	03-Mar-99	31616	180		11188	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	I009128	10-Mar-99	31616	1500		11188	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	I009129	17-Mar-99	31616	310		11188	00-Jan-00	0.3			0	l .			HG		RT
tnrccweb	I009130	24-Mar-99	31616	7700			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009131	31-Mar-99	31616	1900			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009132	07-Apr-99	31616	21000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009133	15-Apr-99	31616	1300			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009134	21-Apr-99	31616	920			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009135 I009136	29-Apr-99	31616 31616	1500 59000			00-Jan-00				0				HG HG		RT RT
tnrccweb tnrccweb	1009136	29-Apr-99 05-May-99	31616	2300			00-Jan-00 00-Jan-00				0				HG		RT
tnrccweb	1009137	11-May-99	31616	24000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009139	19-May-99	31616	1000			00-Jan-00				0				HG		RT
tnrccweb	1009140	26-May-99	31616	12000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009141	14-Jun-99	31616	1200			00-Jan-00				0				HG		RT
tnrccweb	1009142	14-Jun-99	31616	1100			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009143	29-Jun-99	31616	4000		11188	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	I009144	03-Mar-99	31616	72		15847	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	I009145	10-Mar-99	31616	99		15847	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	I009146	17-Mar-99	31616	590		15847	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	I009147	24-Mar-99	31616	2900		15847	00-Jan-00	0.3			0	ı			HG		RT
tnrccweb	I009148	31-Mar-99	31616	2300			00-Jan-00				0				HG		RT
tnrccweb	I009149	07-Apr-99	31616	1100			00-Jan-00				0						RT
tnrccweb	I009150	15-Apr-99	31616	1800			00-Jan-00				0				HG		RT
tnrccweb	1009151	21-Apr-99	31616	110			00-Jan-00				0				HG		RT
tnrccweb	1009152	29-Apr-99	31616	56000			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009153 I009154	05-May-99 05-May-99	31616 31616	1200 700			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb	1009154	11-May-99	31616	18000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009155	19-May-99	31616	1000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009157	19-May-99	31616	1400			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009158	26-May-99	31616	4000			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009159	26-May-99	31616	300			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009160	14-Jun-99	31616	4000		15847	00-Jan-00	0.3			0				HG		RT
tnrccweb	I009161	29-Jun-99	31616	1000		15847	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	I009162	29-Jun-99	31616	400		15847	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1009163	03-Mar-99	31616	220		11163	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	I009164	10-Mar-99	31616	120			00-Jan-00				0				HG		RT
tnrccweb	I009165	17-Mar-99	31616	1100		11163	00-Jan-00	0.3			0	l .			HG	HH	RT
tnrccweb	I009166	24-Mar-99	31616	180			00-Jan-00				0				HG		RT
tnrccweb	I009167	31-Mar-99	31616	960			00-Jan-00				0				HG		RT
	1009168	07-Apr-99	31616	860			00-Jan-00				0						RT
tnrccweb	1009169	15-Apr-99	31616	200			00-Jan-00				0				HG		RT
tnrccweb	1009171	21-Apr-99	31616	140			00-Jan-00				0						RT
tnrccweb	1009172	29-Apr-99	31616	45000			00-Jan-00				0				HG		RT
tnrccweb	1009173	05-May-99	31616	500			00-Jan-00				0				HG		RT
tnrccweb	1009174	11-May-99	31616	1600 800			00-Jan-00 00-Jan-00				0				HG HG		RT RT
tnrccweb	1009175	19-May-99	31616	200			00-Jan-00 00-Jan-00				0				HG HG		RT
tnrccweb	I009176	26-May-99	31616	200	L	11103	oo-jan-00	0.3			0	<u> </u>			пО	пп	I I

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY CALC	. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	1009177	14-Jun-99	31616	3800		11163	00-Jan-00				0				HG		RT
tnrccweb	1009195	03-Mar-99	31616	530			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009196	10-Mar-99	31616	530			00-Jan-00				0				HG		RT
tnrccweb	1009197	17-Mar-99	31616	540			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009198 I009199	24-Mar-99 31-Mar-99	31616 31616	890 3000			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb	1009199	07-Apr-99	31616	580			00-Jan-00 00-Jan-00				0				HG		RT
tnrccweb	1009201	21-Apr-99	31616	1100			00-Jan-00				0				HG		RT
tnrccweb	1009202	29-Apr-99	31616	4900			00-Jan-00				0				HG		RT
tnrccweb	1009203	05-May-99	31616	36000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009204	11-May-99	31616	58000		16592	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1009205	19-May-99	31616	3200		16592	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	1009206	26-May-99	31616	3700		16592	00-Jan-00	0.3			0				HG		RT
tnrccweb	1009207	14-Jun-99	31616	2800			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009208	29-Jun-99	31616	1000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009209	03-Mar-99	31616	850			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009210	10-Mar-99	31616	3200			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009211 I009212	17-Mar-99 24-Mar-99	31616 31616	5400 1600			00-Jan-00 00-Jan-00				0				HG HG		RT RT
tnrccweb	1009212	31-Mar-99	31616	30000			00-Jan-00 00-Jan-00				0				HG		RT
tnrccweb	1009214	07-Apr-99	31616	2200			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009215	15-Apr-99	31616	290000			00-Jan-00				0				HG		RT
tnrccweb	1009216	21-Apr-99	31616	56000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009217	29-Apr-99	31616	90000		16597	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1009218	05-May-99	31616	3800		16597	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	1009219	11-May-99	31616	140000			00-Jan-00				0				HG		RT
tnrccweb	1009220	19-May-99	31616	41000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009221	26-May-99	31616	3400			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009222	14-Jun-99	31616	4200 400			00-Jan-00	0.3			0				HG		RT RT
tnrccweb	I009223 I009224	29-Jun-99 01-Mar-99	31616 31616	4300			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT
tnrccweb	1009224	08-Mar-99	31616	18000			00-Jan-00				0						RT
tnrccweb	1009226	15-Mar-99	31616	9000			00-Jan-00				0				HG		RT
tnrccweb	1009227	22-Mar-99	31616	1400			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009228	29-Mar-99	31616	36000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009229	14-Apr-99	31616	14000		11351	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1009230	20-Apr-99	31616	17000		11351	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	1009231	26-Apr-99	31616	3300			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009232	29-Apr-99	31616	5400			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009233	05-May-99	31616	1200			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009234 I009235	17-May-99	31616	510 2900			00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb tnrccweb	1009233	01-Jun-99 03-Mar-99	31616 31616	2900			00-Jan-00 00-Jan-00	0.3			0						RT
tnrccweb	1009241	10-Mar-99	31616	200			00-Jan-00				0				HG		RT
tnrccweb	1009243	29-Mar-99	31616	11000			00-Jan-00				0				HG		RT
tnrccweb	1009244	14-Apr-99	31616	30000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009245	20-Apr-99	31616	980			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009246	26-Apr-99	31616	290		11356	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1009248	29-Apr-99	31616	1400		11356	00-Jan-00	0.3			0				HG		RT
tnrccweb	1009249	05-May-99	31616	680			00-Jan-00				0				HG		RT
tnrccweb	1009250	11-May-99	31616	33000			00-Jan-00				0				HG		RT
tnrccweb	1009251	11-May-99	31616	26000			00-Jan-00				0				HG		RT
tnrccweb	1009252	17-May-99	31616	1700			00-Jan-00				0						RT
tnrccweb	1009253	01-Jun-99	31616	4200			00-Jan-00				0				HG		RT
tnrccweb	1009254	08-Jun-99	31616	5900			00-Jan-00 00-Jan-00				0				HG		RT RT
tnrccweb	I009255 I009256	14-Jun-99 17-Jun-99	31616 31616	3600			00-Jan-00 00-Jan-00				0				HG HG		RT
	1009256	23-Jun-99	31616	4700			00-Jan-00 00-Jan-00				0				HG HG		RT
tnrccweb	1009237	∠3-Jun-99	31010	4/00	L	11336	oo-jan-00	0.3			1 0	1			UU	шП	IN I

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY CALC	. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	1009258	29-Jun-99	31616	690		11356	00-Jan-00				0				HG		RT
tnrccweb	I009259	03-Mar-99	31616	540			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009260	10-Mar-99	31616	210			00-Jan-00				0				HG		RT
tnrccweb	1009261	17-Mar-99	31616	1300			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009262 I009263	24-Mar-99 29-Mar-99	31616 31616	340 6200			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb	I009264	29-Mar-99	31616	7400			00-Jan-00				0				HG		RT
tnrccweb	1009265	14-Apr-99	31616	4200			00-Jan-00				0				HG		RT
tnrccweb	I009266	14-Apr-99	31616	2300			00-Jan-00				0				HG		RT
tnrccweb	1009267	20-Apr-99	31616	700			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009268	20-Apr-99	31616	680		11360	00-Jan-00				0				HG		RT
tnrccweb	I009269	26-Apr-99	31616	700		11360	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	I009270	29-Apr-99	31616	1700		11360	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	I009271	29-Apr-99	31616	1500		11360	00-Jan-00	0.3			0				HG		RT
tnrccweb	I009272	05-May-99	31616	760		11360	00-Jan-00	0.3			0				HG		RT
tnrccweb	I009273	11-May-99	31616	40000			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009274	17-May-99	31616	2000			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009275	01-Jun-99	31616	15000			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009276	08-Jun-99	31616	10000			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009277	14-Jun-99	31616	15000			00-Jan-00				0				HG		RT
tnrccweb	1009278	17-Jun-99	31616	3200			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009279 I009280	23-Jun-99 29-Jun-99	31616 31616	33000 320			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb	1009280	03-Mar-99	31616	170			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT
tnrccweb	1009281	03-Mar-99	31616	140			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009283	10-Mar-99	31616	140			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009284	17-Mar-99	31616	1300			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009285	24-Mar-99	31616	200			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009286	29-Mar-99	31616	850			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009287	14-Apr-99	31616	3400		11364	00-Jan-00	0.3			0				HG		RT
tnrccweb	1009288	20-Apr-99	31616	18		11364	00-Jan-00	0.3			0				HG		RT
tnrccweb	1009289	26-Apr-99	31616	110		11364	00-Jan-00	0.3			0				HG	НН	RT
tnrccweb	1009290	29-Apr-99	31616	220		11364	00-Jan-00	0.3			0				HG	HH	RT
tnrccweb	I009291	05-May-99	31616	670		11364	00-Jan-00	0.3			0				HG		RT
tnrccweb	I009292	11-May-99	31616	4900			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009293	17-May-99	31616	2300			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009294	17-May-99	31616	3100			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009295	01-Jun-99	31616	2700			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009296	01-Jun-99	31616	1400			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009297	08-Jun-99	31616	480			00-Jan-00	0.3			0				HG		RT
tnrccweb	I009298 I009299	08-Jun-99 14-Jun-99	31616 31616	1100 3000			00-Jan-00 00-Jan-00	0.3			0				HG HG		RT RT
tnrccweb	1009299	14-Jun-99	31616	2900			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009301	17-Jun-99	31616	2500			00-Jan-00				0				HG		RT
tnrccweb	1009302	17-Jun-99	31616	1700			00-Jan-00				0				HG		RT
tnrccweb	1009303	23-Jun-99	31616	1300			00-Jan-00	0.3			0				HG		RT
tnrccweb	1009304	23-Jun-99	31616	3000			00-Jan-00				0				HG		RT
tnrccweb	1009305	29-Jun-99	31616	81			00-Jan-00				0				HG		RT
tnrccweb	I009306	29-Jun-99	31616	90			00-Jan-00				0				HG	НН	RT
tnrccweb	R161838	18-Aug-94	31616	> 60000		11362	00-Jan-00	0.3			0			WATER CHOCOLATE BROWN,	WC	FO	RT
tnrccweb	R161839	18-Aug-94	31616	> 60000		11345	00-Jan-00	0.3			0			WATER CHOCOLATE BROWN,	WC	FO	RT
tnrccweb	R161840	18-Aug-94	31616	> 60000		11387	00-Jan-00	0.3			0			WATER CHOCOLATE BROWN,	WC	FO	RT
tnrccweb	R163665	24-May-95	31616	1100		11345	00-Jan-00	0.3			0			WATER GREEN. MOSTLY CLO	WC	FO	RT
	R163672	25-May-95	31616	5000			00-Jan-00				0			WATER CLEAR. HEAVY TRAF			RT
	R163678	24-May-95	31616	450			00-Jan-00				0			WATER TURBID BROWN. LOT			RT
	R163691	24-May-95	31616	6000			00-Jan-00				0			WATER GREENISH-BROWN. M			RT
	R163692	24-May-95		750			00-Jan-00				0			WATER GREEN. MODERATE T			RT
tnrccweb	U059775	05-May-93	31625	6700		11351	00-Jan-00	0.3			0				GS	GS	

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
tnrccweb	U059776	05-May-93	31625	8700		11351	00-Jan-00			0)			GS	GS	
tnrccweb	U059777	05-May-93	31625	9300			00-Jan-00			0)			GS	GS	
tnrccweb	U059778	06-May-93	31625	23000			00-Jan-00			0				GS	GS	
tnrccweb	U059779	06-May-93	31625	20000			00-Jan-00	0.3		0)			GS	GS	
tnrccweb	U059780 U059781	06-May-93 23-May-93	31625 31625	9300 2900			00-Jan-00 00-Jan-00	0.3		0				GS GS	GS GS	
tnrccweb	U059781	23-May-93	31625	3300			00-Jan-00	0.3		0				GS	GS	
tnrccweb	U059783	23-May-93	31625	10000		1	00-Jan-00	0.3		0	´			GS	GS	
tnrccweb	U059784	24-May-93	31625	25000			00-Jan-00	0.3		0)			GS	GS	
tnrccweb	U059785	24-May-93	31625	34000			00-Jan-00	0.3		0)			GS	GS	
tnrccweb	U059786	24-May-93	31625	12000		11351	00-Jan-00	0.3		0)			GS	GS	
tnrccweb	U059787	19-Jun-93	31625	7000		11351	00-Jan-00	0.3		0)			GS	GS	
tnrccweb	U059788	20-Jun-93	31625	16000		11351	00-Jan-00	0.3		0)			GS	GS	
tnrccweb	U059789	20-Jun-93	31625	29000			00-Jan-00			0				GS	GS	
tnrccweb	U059790	21-Jun-93	31625	1000			00-Jan-00			0				GS	GS	
tnrccweb	U059791	21-Jun-93	31625	8000			00-Jan-00			0)			GS	GS	
tnrccweb	U059792 U059793	21-Jun-93 08-Feb-93	31625 31625	11000 2700			00-Jan-00 00-Jan-00	0.3		0)			GS GS	GS GS	
tnrccweb	U059794	02-Jun-93	31625	3700		1	00-Jan-00	0.3		0)			GS	GS	
tnrccweb	U059795	23-Aug-93	31625	4100			00-Jan-00	0.3		0)			GS	GS	
bayouwq	WOL8801	07-Jul-88	31616	58000			00-Jan-00	0.5						pother1		9901
bayouwq	WOL8802	01-Aug-88	31616	13600			00-Jan-00							pother1	HP	9925
bayouwq	WOL8803	01-Sep-88	31616	48000		15824	00-Jan-00							pother1	HP	9950
bayouwq	WOL8804	10-Oct-88	31616	100000		15824	00-Jan-00							pother1	HP	9974
bayouwq	WOC9011	11-Dec-90	31616	18			00-Jan-00							pother1	HP	7473
bayouwq	WOB9011	11-Dec-90	31616	99			00-Jan-00							pother1	HP	7471
bayouwq	WOL9101	14-Jan-91	31616	1700			00-Jan-00							pother1	HP	1453
bayouwq	WOE0101	22-Jan-91	31616	38000			00-Jan-00							pother l		6969
bayouwq	WOE9101 WOF9101	22-Jan-91 22-Jan-91	31616 31616	9			00-Jan-00 00-Jan-00							pother1	HP HP	6959 6961
bayouwq bayouwq	WOL9101	22-Jan-91	31616	3100			00-Jan-00							pother1 pother1	HP	6973
bayouwq	WOK9101	22-Jan-91	31616	17000			00-Jan-00							pother1	HP	6971
bayouwq	WOJ9101	22-Jan-91	31616	130		1	00-Jan-00							pother1	HP	6967
bayouwq	WOA9101	22-Jan-91	31616	9		15827	00-Jan-00							pother1	HP	6965
bayouwq	WOG9101	22-Jan-91	31616	27		15828	00-Jan-00							pother1	HP	6963
bayouwq	WOD9101	22-Jan-91	31616	27			00-Jan-00							pother1	HP	6957
bayouwq	WOC9101	22-Jan-91	31616	9			00-Jan-00							pother1	HP	6955
bayouwq	WOB9101	22-Jan-91	31616	9			00-Jan-00							pother1	HP	6953
bayouwq	WOL9103	18-Feb-91	31616	6600			00-Jan-00							pbayou	HP	658
bayouwq	WOM9102 WOE9102	20-Feb-91 20-Feb-91	31616 31616	39000 45			00-Jan-00 00-Jan-00							pbayou	HP HP	1000 990
bayouwq bayouwq	WOF9102	20-Feb-91 20-Feb-91	31616	72			00-Jan-00							pbayou pbayou	HP	990
bayouwq	WOL9104	20-Feb-91	31616	15000			00-Jan-00							pbayou	HP	1004
bayouwq	WOK9102	20-Feb-91	31616	12000		1	00-Jan-00							pbayou	HP	1002
bayouwq	WOJ9102	20-Feb-91	31616	540		15826	00-Jan-00							pbayou	HP	998
bayouwq	WOA9102	20-Feb-91	31616	310		15827	00-Jan-00							pbayou	HP	996
bayouwq	WOG9102	20-Feb-91	31616	110		15828	00-Jan-00							pbayou	HP	994
bayouwq	WOD9102	20-Feb-91	31616	18			00-Jan-00							pbayou	HP	988
	WOC9102	20-Feb-91	31616	140			00-Jan-00							pbayou		986
	WOB9102	20-Feb-91	31616	4000			00-Jan-00							pbayou		984
	WOL9105	25-Feb-91	31616	6100			00-Jan-00							pbayou		731
bayouwq bayouwq	WOL9106 WOM9103	04-Mar-91 05-Mar-91	31616 31616	6100 5200			00-Jan-00 00-Jan-00							pbayou pbayou		1164 1579
bayouwq	WOE9103	05-Mar-91	31616	45			00-Jan-00 00-Jan-00							pbayou	HP	1569
bayouwq	WOF9103	05-Mar-91	31616	63			00-Jan-00							pbayou	HP	1571
	WOL9107	05-Mar-91	31616	7100			00-Jan-00							pbayou	HP	1583
-	WOJ9103	05-Mar-91	31616	240			00-Jan-00							pbayou	HP	1577
	WOA9103	05-Mar-91	31616	99		15827	00-Jan-00							pbayou	HP	1575

Database	TAG	END DATE	CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq W	WOG9103	05-Mar-91	31616	180		15828	00-Jan-00							pbayou	HP	1573
	WOD9103	05-Mar-91	31616	9			00-Jan-00							pbayou	HP	1567
	WOC9103	05-Mar-91	31616	9			00-Jan-00							pbayou	HP	1565
	WOB9103	05-Mar-91	31616	640			00-Jan-00							pbayou	HP	1563
1	WOL9108 WOL9109	20-Mar-91 25-Mar-91	31616 31616	23000 5800			00-Jan-00 00-Jan-00							pbayou	HP HP	1237 1310
	WOL9109 WOL9110	02-Apr-91	31616	96000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	1743
	WOL9111	09-Apr-91	31616	22000			00-Jan-00							pbayou	HP	1816
	WOM9104	10-Apr-91	31616	3900			00-Jan-00							pbayou	HP	2158
	WOE9104	10-Apr-91	31616	230			00-Jan-00							pbayou	HP	2148
	WOF9104	10-Apr-91	31616	180		11391	00-Jan-00							pbayou	HP	2150
bayouwq W	WOL9112	10-Apr-91	31616	40000		15824	00-Jan-00							pbayou	HP	2162
bayouwq W	WOJ9104	10-Apr-91	31616	380		15826	00-Jan-00							pbayou	HP	2156
	WOA9104	10-Apr-91	31616	110			00-Jan-00							pbayou	HP	2154
	WOG9104	10-Apr-91	31616	120			00-Jan-00							pbayou	HP	2152
	WOD9104	10-Apr-91	31616	9			00-Jan-00							pbayou	HP	2146
	WOC9104 WOB9104	10-Apr-91 10-Apr-91	31616 31616	140 5500			00-Jan-00 00-Jan-00							pbayou	HP HP	2144 2142
	WOL9113	30-Apr-91	31616	20000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	1889
	WOL9114	06-May-91	31616	6000			00-Jan-00							pbayou	HP	3236
	WOE9105	07-May-91	31616	370			00-Jan-00							pbayou	HP	3641
	WOF9105	07-May-91	31616	450			00-Jan-00							pbayou	HP	3643
	WOJ9105	07-May-91	31616	1100		15826	00-Jan-00							pbayou	HP	3649
bayouwq W	WOA9105	07-May-91	31616	1100		15827	00-Jan-00							pbayou	HP	3647
	WOG9105	07-May-91	31616	580			00-Jan-00							pbayou	HP	3645
	WOD9105	07-May-91	31616	27			00-Jan-00							pbayou	HP	3639
	WOC9105	07-May-91	31616	54			00-Jan-00							pbayou	HP	3637
	WOB9105	07-May-91	31616	320			00-Jan-00							pbayou	HP	3635
	WOL9115 WOL9116	13-Jun-91 17-Jun-91	31616 31616	6100 33000			00-Jan-00 00-Jan-00							pbayou	HP HP	4791 4864
	WOL9116 WOM9105	17-Jun-91 18-Jun-91	31616	11000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	5133
	WOE9106	18-Jun-91	31616	8500			00-Jan-00							pbayou	HP	5123
	WOF9106	18-Jun-91	31616	14000			00-Jan-00							pbayou	HP	5125
	WOJ9106	18-Jun-91	31616	1500			00-Jan-00							pbayou	HP	5131
bayouwq W	WOA9106	18-Jun-91	31616	10000		15827	00-Jan-00							pbayou	HP	5129
bayouwq W	WOG9106	18-Jun-91	31616	5500		15828	00-Jan-00							pbayou	HP	5127
	WOD9106	18-Jun-91	31616	460			00-Jan-00							pbayou	HP	5121
	WOC9106	18-Jun-91	31616	1700			00-Jan-00							pbayou	HP	5119
	WOB9106	18-Jun-91	31616	5500			00-Jan-00							pbayou	HP	5117
	WOL9117	01-Jul-91	31616	10000			00-Jan-00							pbayou	HP	6464
	WOM9106 WOE9107	02-Jul-91 02-Jul-91	31616 31616	60000 2400			00-Jan-00 00-Jan-00							pbayou	HP HP	7143 7133
	WOF9107	02-Jul-91	31616	5100			00-Jan-00 00-Jan-00							pbayou pbayou	HP	7135
	WOL9118	02-Jul-91	31616	22000			00-Jan-00							pbayou	HP	7147
	WOK9103	02-Jul-91	31616	35000			00-Jan-00							pbayou	HP	7145
	WOJ9107	02-Jul-91	31616	11000			00-Jan-00							pbayou	HP	7141
	WOA9107	02-Jul-91	31616	11000			00-Jan-00							pbayou	HP	7139
bayouwq W	WOG9107	02-Jul-91	31616	9200		15828	00-Jan-00							pbayou	HP	7137
	WOD9107	02-Jul-91	31616	980			00-Jan-00							pbayou	HP	7131
	WOC9107	02-Jul-91	31616	1000			00-Jan-00							pbayou	HP	7129
	WOB9107	02-Jul-91	31616	10000			00-Jan-00							pbayou	HP	7127
	WOL9119	09-Jul-91	31616	140000			00-Jan-00							pbayou	HP	6539
	WOL9120 WOL9121	16-Jul-91 23-Jul-91	31616 31616	15000 160000			00-Jan-00 00-Jan-00					1		pbayou	HP HP	6614 6688
	WOL9121 WOL9122	23-Jul-91 29-Jul-91	31616	35000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	6766
	WOL9122 WOL9123	29-Jul-91 05-Aug-91	31616	8700			00-Jan-00 00-Jan-00							pbayou	HP	8385
	WOE9123 WOE9108	06-Aug-91	31616	1500			00-Jan-00							pbayou	HP	8870
	WOF9108	06-Aug-91	31616	1300			00-Jan-00							pbayou	HP	8872

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOL9124	06-Aug-91	31616	7500		15824	00-Jan-00							pbayou	HP	8884
bayouwq	WOK9104	06-Aug-91	31616	5900			00-Jan-00							pbayou	HP	8882
bayouwq	WOJ9108	06-Aug-91	31616	950			00-Jan-00							pbayou	HP	8878
bayouwq	WOA9108	06-Aug-91	31616	600			00-Jan-00							pbayou	HP	8876
bayouwq	WOD0108	06-Aug-91	31616	860 160			00-Jan-00							pbayou	HP	8874 8868
bayouwq bayouwq	WOD9108 WOC9108	06-Aug-91 06-Aug-91	31616 31616	99		t	00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	8866
bayouwq	WOB9108	06-Aug-91	31616	1500			00-Jan-00							pbayou	HP	8864
bayouwq	WOL8805	03-Nov-88	31616	8378			00-Jan-00							pother1	HP	9998
bayouwq	WOL8806	12-Dec-88	31616	928		t	00-Jan-00							pother1	HP	10022
bayouwq	WOL8902	02-Feb-89	31616	8900		15824	00-Jan-00							pother1	HP	10071
bayouwq	WOL8903	06-Mar-89	31616	3900		15824	00-Jan-00							pother1	HP	10096
bayouwq	WOL8904	04-Apr-89	31616	7600		15824	00-Jan-00							pother1	HP	10123
bayouwq	WOL8905	01-May-89	31616	17000			00-Jan-00							pother1	HP	10149
bayouwq	WOL8906	13-Jun-89	31616	3700			00-Jan-00							pother1	HP	10174
bayouwq	WOL8907	13-Jul-89	31616	6000			00-Jan-00							pother1	HP	10199
bayouwq	WOL8908	04-Dec-89	31616	12000			00-Jan-00							pother l	HP	10262
bayouwq	WOE8901 WOF8901	20-Dec-89 20-Dec-89	31616 31616	63 110			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	7530 7532
bayouwq bayouwq	WOL8909	20-Dec-89	31616	640			00-Jan-00 00-Jan-00							pother1	HP	7542
bayouwq	WOK8901	20-Dec-89	31616	820		t	00-Jan-00							pother1	HP	7540
bayouwq	WOJ8901	20-Dec-89	31616	81			00-Jan-00							pother1	HP	7538
bayouwq	WOA8901	20-Dec-89	31616	300			00-Jan-00							pother1	HP	7536
bayouwq	WOG8901	20-Dec-89	31616	220		15828	00-Jan-00							pother1	HP	7534
bayouwq	WOD8901	20-Dec-89	31616	9		15829	00-Jan-00							pother1	HP	7528
bayouwq	WOC8901	20-Dec-89	31616	9			00-Jan-00							pother1	HP	7526
bayouwq	WOB8901	20-Dec-89	31616	9			00-Jan-00							pother1	HP	7524
bayouwq	WOL8910	21-Dec-89	31616	1600			00-Jan-00							pother1	HP	10329
bayouwq	WOL8911	28-Dec-89	31616	2000			00-Jan-00							pother1	HP	10398
bayouwq bayouwq	WOL9001 WOL9002	05-Jan-90 12-Jan-90	31616 31616	9700			00-Jan-00 00-Jan-00							pother1	HP HP	10467 10538
bayouwq	WOE9001	18-Jan-90	31616	1500		t	00-Jan-00							pother1	HP	6908
bayouwq	WOF9001	18-Jan-90	31616	1100			00-Jan-00							pother1	HP	6910
bayouwq	WOL9003	18-Jan-90	31616	24000			00-Jan-00							pother1	HP	6920
bayouwq	WOK9001	18-Jan-90	31616	26000		15825	00-Jan-00							pother1	HP	6918
bayouwq	WOJ9001	18-Jan-90	31616	29000		15826	00-Jan-00							pother1	HP	6916
bayouwq	WOA9001	18-Jan-90	31616	2200		15827	00-Jan-00							pother1	HP	6914
bayouwq	WOG9001	18-Jan-90	31616	1300			00-Jan-00							pother1	HP	6912
bayouwq	WOD9001	18-Jan-90	31616	54			00-Jan-00							pother1	HP	6906
bayouwq	WOC9001	18-Jan-90	31616	36			00-Jan-00							pother1	HP	6904
bayouwq	WOB9001	18-Jan-90	31616	260			00-Jan-00							pother1	HP	6902
bayouwq bayouwq	WOL9004 WOL9005	22-Jan-90 29-Jan-90	31616 31616	13000 17000			00-Jan-00 00-Jan-00							pother1	HP HP	10609 10680
bayouwq	WOL9006	06-Feb-90	31616	18000			00-Jan-00							pother1	HP	10751
bayouwq	WOE9002	12-Feb-90	31616	27			00-Jan-00							pother1	HP	7012
bayouwq	WOF9002	12-Feb-90	31616	87000		t	00-Jan-00							pother1	HP	7014
bayouwq	WOL9007	12-Feb-90	31616	4500		15824	00-Jan-00							pother1	HP	7024
bayouwq	WOK9002	12-Feb-90	31616	11000		15825	00-Jan-00							pother1	HP	7022
bayouwq	WOJ9002	12-Feb-90	31616	640			00-Jan-00							pother1	HP	7020
bayouwq	WOA9002	12-Feb-90	31616	150			00-Jan-00							pother1	HP	7018
bayouwq	WOG9002	12-Feb-90	31616	3300			00-Jan-00							pother1	HP	7016
bayouwq	WOD9002	12-Feb-90	31616	9			00-Jan-00					\vdash		pother1	HP	7010
bayouwq	WOC9002	12-Feb-90	31616	9			00-Jan-00							pother1	HP	7008
bayouwq	WOI 9008	12-Feb-90	31616	78000			00-Jan-00 00-Jan-00							pother1	HP	7006 10822
bayouwq bayouwq	WOL9008 WOL9009	15-Feb-90 23-Feb-90	31616 31616	3600			00-Jan-00 00-Jan-00							pother1	HP HP	10822
bayouwq	WOL9009 WOL9010	28-Feb-90	31616	40000			00-Jan-00							pother1	HP	10964
bayouwq	WOL9011	08-Mar-90	31616	48000		t	00-Jan-00							pother1	HP	11035
oayouwq	11 OL9011	00-Mai-90	31010	40000	l	13024	oo-san-00	1 1		1	1			Pomer r	111	11000

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	COMMENT		SOURCE 2	
bayouwq	WOE9003	19-Mar-90	31616	1000			00-Jan-00						pother1	HP	7063
bayouwq	WOF9003	19-Mar-90	31616	480			00-Jan-00						pother1	HP	7065
bayouwq	WOL9012	19-Mar-90	31616	340000			00-Jan-00						pother1	HP	7075
bayouwq	WOJ9003	19-Mar-90	31616 31616	850 620		15826 15827	00-Jan-00						pother1	HP HP	7071 7069
bayouwq bayouwq	WOA9003 WOG9003	19-Mar-90 19-Mar-90	31616	800		15827	00-Jan-00 00-Jan-00						pother l	HP	7069
bayouwq	WOD9003	19-Mar-90	31616	4700		15829	00-Jan-00						pother1	HP	7061
bayouwq	WOC9003	19-Mar-90	31616	7700		15830	00-Jan-00						pother1	HP	7059
bayouwq	WOB9003	19-Mar-90	31616	19000		15831	00-Jan-00						pother1	HP	7057
bayouwq	WOL9013	20-Mar-90	31616	2000		15824	00-Jan-00						pother1	HP	11106
bayouwq	WOL9014	27-Mar-90	31616	200000		15824	00-Jan-00						pother1	HP	11177
bayouwq	WOL9015	12-Apr-90	31616	5300		15824	00-Jan-00						pother1	HP	11248
bayouwq	WOE9004	25-Apr-90	31616	1500			00-Jan-00						pother1		7114
bayouwq	WOF9004	25-Apr-90	31616	980			00-Jan-00						pother1		7116
bayouwq	WOL9016	25-Apr-90	31616	8000			00-Jan-00						pother1		7126
bayouwq	WOJ9004 WOA9004	25-Apr-90	31616 31616	2600 2100		15826 15827	00-Jan-00 00-Jan-00						pother1	HP HP	7122 7120
bayouwq bayouwq	WOG9004	25-Apr-90 25-Apr-90	31616	1800			00-Jan-00						pother l		7118
bayouwq	WOD9004	25-Apr-90	31616	18			00-Jan-00						pother1		7112
bayouwq	WOC9004	25-Apr-90	31616	36		15830	00-Jan-00						pother1		7110
bayouwq	WOB9004	25-Apr-90	31616	45			00-Jan-00						pother1	HP	7108
bayouwq	WOL9017	10-May-90	31616	16000		15824	00-Jan-00						pother1	HP	11390
bayouwq	WOE9005	15-May-90	31616	1000		11390	00-Jan-00						pother1	HP	7165
bayouwq	WOF9005	15-May-90	31616	1700		11391	00-Jan-00						pother1	HP	7167
bayouwq	WOL9018	15-May-90	31616	1200			00-Jan-00						pother1		7177
bayouwq	WOK9003	15-May-90	31616	2400			00-Jan-00						pother1		7175
bayouwq	WOJ9005	15-May-90	31616	820			00-Jan-00						pother1	HP	7173
bayouwq	WOA9005	15-May-90	31616	1800		15827	00-Jan-00						pother1	HP	7171
bayouwq	WOG9005 WOD9005	15-May-90 15-May-90	31616 31616	1100 150		15828 15829	00-Jan-00						pother1	HP HP	7169 7163
bayouwq bayouwq	WOC9005	15-May-90 15-May-90	31616	130		15830	00-Jan-00 00-Jan-00						pother l		7161
bayouwq	WOB9005	15-May-90	31616	140			00-Jan-00						pother1	HP	7159
bayouwq	WOL9019	21-May-90	31616	6500		15824	00-Jan-00						pother1	HP	11461
bayouwq	WOL9020	30-May-90	31616	4600		15824	00-Jan-00						pother1	HP	11532
bayouwq	WOL9021	04-Jun-90	31616	62000		15824	00-Jan-00						pother1	HP	11603
bayouwq	WOL9023	20-Jun-90	31616	45000		15824	00-Jan-00						pother1	HP	11745
bayouwq	WOE9006	25-Jun-90	31616	2500		11390	00-Jan-00						pother1		7216
bayouwq	WOF9006	25-Jun-90	31616	3000			00-Jan-00						pother1		7218
bayouwq	WOL9024	25-Jun-90	31616	9500			00-Jan-00						pother1		7228
bayouwq	WOJ9006	25-Jun-90	31616	200000			00-Jan-00						pother1	HP	7224
bayouwq	WOG9006 WOD9006	25-Jun-90 25-Jun-90	31616 31616	23000 1500		15828 15829	00-Jan-00 00-Jan-00						pother l	HP HP	7220 7214
bayouwq bayouwq	WOC9006	25-Jun-90 25-Jun-90	31616	1300		15830	00-Jan-00						pother1	HP	7214
bayouwq	WOB9006	25-Jun-90	31616	9			00-Jan-00						pother1	HP	7210
bayouwq	WOL9025	26-Jun-90	31616	75000		15824	00-Jan-00						pother1	HP	11816
bayouwq	WOL9026	02-Jul-90	31616	100000		15824	00-Jan-00						pother1	HP	11887
bayouwq	WOL9028	17-Jul-90	31616	700000		15824	00-Jan-00						pother1	HP	12029
bayouwq	WOE9007	19-Jul-90	31616	3000		11390	00-Jan-00						pother1	HP	7267
bayouwq	WOF9007	19-Jul-90	31616	1500			00-Jan-00						pother1	HP	7269
bayouwq	WOL9029	19-Jul-90	31616	76000			00-Jan-00						pother1		7279
bayouwq	WOJ9007	19-Jul-90	31616	3700			00-Jan-00						pother1		7275
bayouwq	WOA9007	19-Jul-90	31616	2800			00-Jan-00						pother1		7273
bayouwq	WOG9007	19-Jul-90	31616	3300			00-Jan-00						pother1	HP	7271
bayouwq	WOD9007	19-Jul-90	31616	230			00-Jan-00						pother1	HP	7265
bayouwq	WOC9007 WOB9007	19-Jul-90 19-Jul-90	31616 31616	63 3500			00-Jan-00 00-Jan-00						pother1	HP HP	7263 7261
bayouwq	WOL9030	31-Jul-90	31616	78000			00-Jan-00						pother l		12171
	1												1		7328
bayouwq bayouwq	WOL9030 WOM9001	07-Aug-90	31616	960			00-Jan-00 00-Jan-00						potner1 pother1		٠

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CAL	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOE9008	07-Aug-90	31616	590			00-Jan-00							pother1	HP	7318
bayouwq	WOF9008	07-Aug-90	31616	740			00-Jan-00							pother1	HP	7320
bayouwq	WOK9005 WOJ9008	07-Aug-90 07-Aug-90	31616 31616	8100 1300			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	7330 7326
bayouwq bayouwq	WOA9008	07-Aug-90	31616	1600			00-Jan-00							pother1	HP	7324
bayouwq	WOG9008	07-Aug-90	31616	1800			00-Jan-00							pother1	HP	7322
bayouwq	WOD9008	07-Aug-90	31616	18			00-Jan-00							pother1	HP	7316
bayouwq	WOC9008	07-Aug-90	31616	18		15830	00-Jan-00							pother l	HP	7314
bayouwq	WOB9008	07-Aug-90	31616	1300		15831	00-Jan-00							pother1	HP	7312
bayouwq	WOL9031	28-Aug-90	31616	1000000		15824	00-Jan-00							pother1	HP	12463
bayouwq	WOL9032	04-Sep-90	31616	11000			00-Jan-00							pother l	HP	12536
bayouwq	WOM9002	11-Sep-90	31616	4600			00-Jan-00							pother1	HP	7381
bayouwq	WOE9009	11-Sep-90	31616	750			00-Jan-00							pother1	HP	7371
bayouwq	WOF9009 WOL9033	11-Sep-90	31616 31616	1200 19000			00-Jan-00							pother1	HP HP	7373 7385
bayouwq	WOK9006	11-Sep-90 11-Sep-90	31616	16000			00-Jan-00 00-Jan-00							pother1 pother1	HP	7383
bayouwq bayouwq	WOJ9009	11-Sep-90	31616	17000			00-Jan-00							pother1	HP	7379
bayouwq	WOA9009	11-Sep-90	31616	15000			00-Jan-00							pother1	HP	7377
bayouwq	WOG9009	11-Sep-90	31616	14000			00-Jan-00							pother1	HP	7375
bayouwq	WOD9009	11-Sep-90	31616	54			00-Jan-00							pother1	HP	7369
bayouwq	WOC9009	11-Sep-90	31616	45		15830	00-Jan-00							pother l	HP	7367
bayouwq	WOB9009	11-Sep-90	31616	2800		15831	00-Jan-00							pother1	HP	7365
bayouwq	WOL9034	25-Sep-90	31616	170000		15824	00-Jan-00							pother1	HP	12609
bayouwq	WOL9035	02-Oct-90	31616	19000		15824	00-Jan-00							pother1	HP	3597
bayouwq	WOL9036	08-Oct-90	31616	150000			00-Jan-00							pother1	HP	3671
bayouwq	WOM9003	10-Oct-90	31616	110000			00-Jan-00							pother1	HP	7434
bayouwq	WOE9010	10-Oct-90	31616	1300			00-Jan-00							pother1	HP	7424
bayouwq	WOF9010	10-Oct-90	31616	1000			00-Jan-00							pother1	HP	7426
bayouwq	WOL9037	10-Oct-90	31616	28000			00-Jan-00							pother1	HP	7438
bayouwq	WOJ9010	10-Oct-90	31616	63000 2000			00-Jan-00							pother1	HP HP	7432 7430
bayouwq	WOA9010 WOG9010	10-Oct-90 10-Oct-90	31616 31616	660			00-Jan-00 00-Jan-00							pother1 pother1	HP	7430
bayouwq bayouwq	WOD9010	10-Oct-90	31616	63			00-Jan-00							pother1	HP	7422
bayouwq	WOC9010	10-Oct-90	31616	140			00-Jan-00							pother1	HP	7420
bayouwq	WOB9010	10-Oct-90	31616	2200			00-Jan-00							pother1	HP	7418
bayouwq	WOL9039	23-Oct-90	31616	64000			00-Jan-00							pother1	HP	3818
bayouwq	WOM9004	11-Dec-90	31616	1900		11385	00-Jan-00							pother1	HP	7487
bayouwq	WOE9011	11-Dec-90	31616	9		11390	00-Jan-00							pother1	HP	7477
bayouwq	WOF9011	11-Dec-90	31616	160		11391	00-Jan-00							pother1	HP	7479
bayouwq	WOL9040	11-Dec-90	31616	76000		15824	00-Jan-00							pother1	HP	7491
bayouwq	WOJ9011	11-Dec-90	31616	64000			00-Jan-00							pother1	HP	7485
bayouwq	WOA9011	11-Dec-90	31616	50000			00-Jan-00							pother1	HP	7483
bayouwq	WOG9011	11-Dec-90	31616	180			00-Jan-00							pother1	HP	7481
bayouwq	WOD9011	11-Dec-90	31616	9			00-Jan-00							pother1	HP	7475
bayouwq	WOL9125	13-Aug-91	31616	180000			00-Jan-00							pbayou	HP HP	8463 8533
bayouwq	WOL9126 WOL9127	20-Aug-91	31616 31616	67000 14000			00-Jan-00 00-Jan-00							pbayou	HP	8603
bayouwq bayouwq	WOL9127 WOL9128	26-Aug-91 09-Sep-91	31616	3000			00-Jan-00							pbayou pbayou	HP	10252
bayouwq	WOL9128 WOM9107	10-Sep-91	31616	39000			00-Jan-00							pbayou	HP	10606
bayouwq	WOL9129	10-Sep-91	31616	12000			00-Jan-00							pbayou	HP	10610
bayouwq	WOK9105	10-Sep-91	31616	12000			00-Jan-00							pbayou	HP	10608
bayouwq	WOL9130	26-Sep-91	31616	6400			00-Jan-00							pbayou	HP	10333
bayouwq	WOL9131	07-Oct-91	31616	30000			00-Jan-00							pbayou	HP	11281
bayouwq	WOM9108	08-Oct-91	31616	2900		11385	00-Jan-00							pbayou	HP	11692
bayouwq	WOE9110	08-Oct-91	31616	45		11390	00-Jan-00							pbayou	HP	11682
bayouwq	WOF9110	08-Oct-91	31616	130			00-Jan-00							pbayou	HP	11684
bayouwq	WOL9132	08-Oct-91	31616	40000			00-Jan-00							pbayou	HP	11696
bayouwq	WOK9106	08-Oct-91	31616	9100		15825	00-Jan-00							pbayou	HP	11694

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC	. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOJ9110	08-Oct-91	31616	120			00-Jan-00							pbayou	HP	11690
bayouwq	WOA9110	08-Oct-91	31616	200			00-Jan-00							pbayou	HP	11688
bayouwq	WOG9110	08-Oct-91	31616	81			00-Jan-00							pbayou	HP	11686
bayouwq	WOD9110 WOC9110	08-Oct-91 08-Oct-91	31616 31616	9			00-Jan-00 00-Jan-00							pbayou	HP HP	11680 11678
bayouwq bayouwq	WOC9110 WOB9110	08-Oct-91	31616	200			00-Jan-00 00-Jan-00							pbayou pbayou	HP	11676
bayouwq	WOL9135	04-Nov-91	31616	190			00-Jan-00							pbayou	HP	12908
bayouwq	WOM9109	05-Nov-91	31616	26000			00-Jan-00							pbayou	HP	13172
bayouwq	WOE9111	05-Nov-91	31616	9			00-Jan-00							pbayou	HP	13162
bayouwq	WOF9111	05-Nov-91	31616	9		11391	00-Jan-00							pbayou	HP	13164
bayouwq	WOL9136	05-Nov-91	31616	9		15824	00-Jan-00							pbayou	HP	13176
bayouwq	WOK9107	05-Nov-91	31616	160		15825	00-Jan-00							pbayou	HP	13174
bayouwq	WOJ9111	05-Nov-91	31616	9			00-Jan-00							pbayou	HP	13170
bayouwq	WOA9111	05-Nov-91	31616	9			00-Jan-00							pbayou	HP	13168
bayouwq	WOG9111	05-Nov-91	31616	9			00-Jan-00							pbayou	HP	13166
bayouwq	WOD9111	05-Nov-91	31616	9			00-Jan-00							pbayou	HP	13160
bayouwq	WOC9111 WOB9111	05-Nov-91 05-Nov-91	31616 31616	9 3500			00-Jan-00 00-Jan-00							pbayou	HP HP	13158 13156
bayouwq	WOM9201	05-Nov-91 08-Apr-92	31616	350000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	2539
bayouwq bayouwq	WOE9201	08-Apr-92	31616	5500			00-Jan-00							pbayou	HP	2529
bayouwq	WOF9201	08-Apr-92	31616	5800			00-Jan-00							pbayou	HP	2531
bayouwq	WOL9201	08-Apr-92	31616	330000			00-Jan-00							pbayou	HP	2543
bayouwq	WOK9201	08-Apr-92	31616	210000			00-Jan-00							pbayou	HP	2541
bayouwq	WOJ9201	08-Apr-92	31616	4400		15826	00-Jan-00							pbayou	HP	2537
bayouwq	WOA9201	08-Apr-92	31616	5400		15827	00-Jan-00							pbayou	HP	2535
bayouwq	WOG9201	08-Apr-92	31616	5700		15828	00-Jan-00							pbayou	HP	2533
bayouwq	WOD9201	08-Apr-92	31616	1200		15829	00-Jan-00							pbayou	HP	2527
bayouwq	WOC9201	08-Apr-92	31616	840		15830	00-Jan-00							pbayou	HP	2525
bayouwq	WOB9201	08-Apr-92	31616	1100			00-Jan-00							pbayou	HP	2523
bayouwq	WOL9202	13-Apr-92	31616	4400			00-Jan-00							pbayou	HP	2320
bayouwq	WOM9202	16-Apr-92	31616	51000			00-Jan-00							pbayou	HP	2588
bayouwq	WOE9202	16-Apr-92	31616	300			00-Jan-00							pbayou	HP	2578
bayouwq	WOF9202	16-Apr-92	31616	410			00-Jan-00							pbayou	HP	2580
bayouwq	WOL9203 WOK9202	16-Apr-92 16-Apr-92	31616 31616	3700 1200			00-Jan-00 00-Jan-00							pbayou	HP HP	2592 2590
bayouwq bayouwq	WOK9202 WOJ9202	16-Apr-92	31616	200			00-Jan-00 00-Jan-00							pbayou pbayou	HP	2586
bayouwq	WOA9202	16-Apr-92	31616	430			00-Jan-00							pbayou	HP	2584
bayouwq	WOG9202	16-Apr-92	31616	430			00-Jan-00							pbayou	HP	2582
bayouwq	WOD9202	16-Apr-92	31616	140			00-Jan-00							pbayou	HP	2576
bayouwq	WOC9202	16-Apr-92	31616	210			00-Jan-00							pbayou	HP	2574
bayouwq	WOB9202	16-Apr-92	31616	290		15831	00-Jan-00							pbayou	HP	2572
bayouwq	WOM9203	28-Apr-92	31616	43000		11385	00-Jan-00							pbayou	HP	2639
bayouwq	WOE9203	28-Apr-92	31616	790		11390	00-Jan-00							pbayou	HP	2629
bayouwq	WOF9203	28-Apr-92	31616	850			00-Jan-00							pbayou	HP	2631
bayouwq	WOL9204	28-Apr-92	31616	3600			00-Jan-00							pbayou	HP	2643
bayouwq	WOK9203	28-Apr-92	31616	14000			00-Jan-00							pbayou	HP	2641
bayouwq	WOJ9203	28-Apr-92	31616	310			00-Jan-00							pbayou	HP	2637
bayouwq	WOA9203	28-Apr-92	31616	1000			00-Jan-00							pbayou	HP	2635
bayouwa	WOG9203 WOD9203	28-Apr-92 28-Apr-92	31616 31616	580 45			00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	2633 2627
	WOC9203	28-Apr-92 28-Apr-92	31616	45			00-Jan-00 00-Jan-00							pbayou	HP	2625
bayouwq	WOC9203 WOB9203	28-Apr-92	31616	20			00-Jan-00 00-Jan-00							pbayou	HP	2623
bayouwq	WOL9205	04-May-92	31616	1100			00-Jan-00							pbayou	HP	3821
bayouwq	WOM9204	07-May-92	31616	49000			00-Jan-00							pbayou	HP	4046
	WOE9204	07-May-92	31616	2800			00-Jan-00							pbayou	HP	4036
	WOF9204	07-May-92	31616	390			00-Jan-00							pbayou	HP	4038
	WOL9206	07-May-92		8100			00-Jan-00							pbayou	HP	4050
bayouwq	WOK9204	07-May-92	31616	7700		15825	00-Jan-00							pbayou	HP	4048

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CAL	C. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
	WOJ9204	07-May-92	31616	2800			00-Jan-00							pbayou	HP	4044
	WOG9204	07-May-92	31616	950			00-Jan-00							pbayou	HP	4040
	WOD9204	07-May-92	31616	180			00-Jan-00							pbayou	HP	4034 4032
	WOC9204 WOB9204	07-May-92 07-May-92	31616 31616	160 230			00-Jan-00 00-Jan-00							pbayou	HP HP	4032
	WOM9205	14-May-92	31616	63000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	4100
•	WOE9205	14-May-92	31616	7700			00-Jan-00							pbayou	HP	4090
bayouwq	WOF9205	14-May-92	31616	5900			00-Jan-00							pbayou	HP	4092
bayouwq	WOL9207	14-May-92	31616	4400			00-Jan-00							pbayou	HP	4104
bayouwq	WOK9205	14-May-92	31616	6000		15825	00-Jan-00							pbayou	HP	4102
bayouwq	WOJ9205	14-May-92	31616	1600		15826	00-Jan-00							pbayou	HP	4098
	WOA9204	14-May-92	31616	4800			00-Jan-00							pbayou	HP	4096
	WOG9205	14-May-92	31616	7500			00-Jan-00							pbayou	HP	4094
	WOD9205	14-May-92	31616	150			00-Jan-00							pbayou	HP	4088
bayouwq	WOC9205	14-May-92	31616	150			00-Jan-00							pbayou	HP	4086
* *	WOB9205	14-May-92	31616	390			00-Jan-00							pbayou	HP	4084
	WOM9206 WOE9206	21-May-92 21-May-92	31616 31616	47000 4600			00-Jan-00 00-Jan-00							pbayou	HP HP	4151 4141
	WOL9208	21-May-92 21-May-92	31616	21000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	4155
	WOK9206	21-May-92	31616	22000			00-Jan-00							pbayou	HP	4153
bayouwq	WOJ9206	21-May-92	31616	11000			00-Jan-00							pbayou	HP	4149
bayouwq	WOA9205	21-May-92	31616	11000			00-Jan-00							pbayou	HP	4147
bayouwq	WOG9206	21-May-92	31616	9900			00-Jan-00							pbayou	HP	4145
	WOD9206	21-May-92	31616	1600		15829	00-Jan-00							pbayou	HP	4139
	WOC9206	21-May-92	31616	6000		15830	00-Jan-00							pbayou	HP	4137
bayouwq	WOB9206	21-May-92	31616	1200		15831	00-Jan-00							pbayou	HP	4135
bayouwq	WOM9207	26-May-92	31616	27000		11385	00-Jan-00							pbayou	HP	4203
•	WOF9206	26-May-92	31616	6000			00-Jan-00							pbayou	HP	4195
	WOL9209	26-May-92	31616	6400			00-Jan-00							pbayou	HP	4207
* *	WOK9207	26-May-92	31616	24000			00-Jan-00							pbayou	HP	4205
	WOJ9207	26-May-92	31616	5600			00-Jan-00							pbayou	HP	4201
	WOA9206	26-May-92	31616	4700			00-Jan-00							pbayou	HP	4199
bayouwq	WOG9207 WOD9207	26-May-92 26-May-92	31616 31616	5600 5400			00-Jan-00 00-Jan-00							pbayou	HP HP	4197 4191
bayouwq	WOC9207	26-May-92	31616	7800			00-Jan-00 00-Jan-00							pbayou pbayou	HP	4191
	WOC9207 WOB9207	26-May-92	31616	570			00-Jan-00							pbayou	HP	4187
	WOM9208	11-Jun-92	31616	20000			00-Jan-00							pbayou	HP	5530
	WOE9207	11-Jun-92	31616	3700			00-Jan-00							pbayou	HP	5520
	WOF9207	11-Jun-92	31616	9800			00-Jan-00							pbayou	HP	5522
bayouwq	WOL9210	11-Jun-92	31616	47000		15824	00-Jan-00							pbayou	HP	5534
bayouwq	WOK9208	11-Jun-92	31616	21000		15825	00-Jan-00							pbayou	HP	5532
bayouwq	WOJ9208	11-Jun-92	31616	6600		15826	00-Jan-00							pbayou	HP	5528
bayouwq	WOA9207	11-Jun-92	31616	9400		15827	00-Jan-00							pbayou	HP	5526
	WOG9208	11-Jun-92	31616	11000			00-Jan-00							pbayou	HP	5524
	WOD9208	11-Jun-92	31616	8000			00-Jan-00							pbayou	HP	5518
bayouwq	WOC9208	11-Jun-92	31616	4500			00-Jan-00							pbayou	HP	5516
bayouwq	WOB9208	11-Jun-92	31616	2600			00-Jan-00							pbayou	HP	5514
	WOM9209	18-Jun-92	31616	91000			00-Jan-00							pbayou	HP	5580
* *	WOF9208 WOL9211	18-Jun-92 18-Jun-92	31616 31616	12000 20000			00-Jan-00 00-Jan-00			1				pbayou pbayou	HP HP	5572 5584
	WOK9209	18-Jun-92 18-Jun-92	31616	36000			00-Jan-00 00-Jan-00							pbayou	HP	5582
• •	WOK9209 WOJ9209	18-Jun-92	31616	790			00-Jan-00 00-Jan-00							pbayou	HP	5578
	WOJ9209 WOA9208	18-Jun-92	31616	750			00-Jan-00							pbayou	HP	5576
• •	WOG9209	18-Jun-92	31616	470			00-Jan-00							pbayou	HP	5574
• •	WOD9209	18-Jun-92	31616	3000			00-Jan-00							pbayou	HP	5568
	WOC9209	18-Jun-92	31616	140			00-Jan-00							pbayou	HP	5566
• •	WOB9209	18-Jun-92	31616	3400			00-Jan-00							pbayou	HP	5564
bayouwq	WOL9212	22-Jun-92	31616	14000		15824	00-Jan-00							pbayou	HP	5285

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOM9210	23-Jun-92	31616	77000		11385	00-Jan-00							pbayou	HP	5629
bayouwq	WOE9208	23-Jun-92	31616	33000			00-Jan-00							pbayou	HP	5619
bayouwq	WOF9209	23-Jun-92	31616	11000			00-Jan-00							pbayou	HP	5621
bayouwq	WOL9213	23-Jun-92	31616	57000			00-Jan-00							pbayou	HP	5633
bayouwq	WOA9209 WOG9210	23-Jun-92 23-Jun-92	31616 31616	8500 4300			00-Jan-00 00-Jan-00							pbayou	HP HP	5625 5623
bayouwq bayouwq	WOD9210	23-Jun-92	31616	7000			00-Jan-00							pbayou pbayou	HP	5617
bayouwq	WOC9210	23-Jun-92	31616	7500			00-Jan-00							pbayou	HP	5615
bayouwq	WOB9210	23-Jun-92	31616	49000			00-Jan-00							pbayou	HP	5613
bayouwq	WOM9211	30-Jun-92	31616	150000			00-Jan-00							pbayou	HP	5684
bayouwq	WOE9209	30-Jun-92	31616	4400		11390	00-Jan-00							pbayou	HP	5674
bayouwq	WOF9210	30-Jun-92	31616	2300		11391	00-Jan-00							pbayou	HP	5676
bayouwq	WOL9214	30-Jun-92	31616	123000		15824	00-Jan-00							pbayou	HP	5688
bayouwq	WOJ9210	30-Jun-92	31616	2800			00-Jan-00							pbayou	HP	5682
bayouwq	WOA9210	30-Jun-92	31616	3800			00-Jan-00							pbayou	HP	5680
bayouwq	WOG9211	30-Jun-92	31616	950			00-Jan-00							pbayou	HP	5678
bayouwq	WOD9211 WOC9211	30-Jun-92 30-Jun-92	31616 31616	410 730			00-Jan-00 00-Jan-00							pbayou	HP HP	5672 5670
bayouwq bayouwq	WOC9211 WOB9211	30-Jun-92	31616	890			00-Jan-00							pbayou pbayou	HP	5668
bayouwq	WOL9215	06-Jul-92	31616	350000			00-Jan-00							pbayou	HP	7297
bayouwq	WOM9212	07-Jul-92	31616	350000			00-Jan-00							pbayou	HP	7547
bayouwq	WOE9210	07-Jul-92	31616	670			00-Jan-00							pbayou	HP	7537
bayouwq	WOF9211	07-Jul-92	31616	830		11391	00-Jan-00							pbayou	HP	7539
bayouwq	WOL9216	07-Jul-92	31616	74000		15824	00-Jan-00							pbayou	HP	7551
bayouwq	WOJ9211	07-Jul-92	31616	970			00-Jan-00							pbayou	HP	7545
bayouwq	WOA9211	07-Jul-92	31616	880			00-Jan-00							pbayou	HP	7543
bayouwq	WOG9212	07-Jul-92	31616	990			00-Jan-00							pbayou	HP	7541
bayouwq	WOD9212	07-Jul-92	31616	1700			00-Jan-00							pbayou	HP	7535
bayouwq	WOC9212 WOB9212	07-Jul-92 07-Jul-92	31616 31616	3400 61000			00-Jan-00 00-Jan-00							pbayou	HP HP	7533 7531
bayouwq bayouwq	WOM9212 WOM9213	16-Jul-92	31616	22000			00-Jan-00							pbayou pbayou	HP	7597
bayouwq	WOF9212	16-Jul-92	31616	47000			00-Jan-00							pbayou	HP	7589
bayouwq	WOL9217	16-Jul-92	31616	57000			00-Jan-00							pbayou	HP	7601
bayouwq	WOJ9212	16-Jul-92	31616	44000			00-Jan-00							pbayou	HP	7595
bayouwq	WOA9212	16-Jul-92	31616	42000		15827	00-Jan-00							pbayou	HP	7593
bayouwq	WOG9213	16-Jul-92	31616	50000		15828	00-Jan-00							pbayou	HP	7591
bayouwq	WOD9213	16-Jul-92	31616	48000			00-Jan-00							pbayou	HP	7585
bayouwq	WOC9213	16-Jul-92	31616	36000			00-Jan-00							pbayou	HP	7583
bayouwq	WOB9213	16-Jul-92	31616	47000			00-Jan-00							pbayou	HP	7581
bayouwq	WOM9214	23-Jul-92	31616	230000			00-Jan-00							pbayou	HP	7699
bayouwq	WOE9212 WOL9218	23-Jul-92 23-Jul-92	31616 31616	21000 35000			00-Jan-00 00-Jan-00							pbayou	HP HP	7689 7703
bayouwq bayouwq	WOL9218 WOA9213	23-Jul-92 23-Jul-92	31616	13000			00-Jan-00							pbayou pbayou	HP	7695
bayouwq	WOC9214	23-Jul-92	31616	25000			00-Jan-00							pbayou	HP	7685
bayouwq	WOB9214	23-Jul-92	31616	15000			00-Jan-00							pbayou	HP	7683
bayouwq	WOM9215	06-Aug-92	31616	10000			00-Jan-00							pbayou	HP	9289
bayouwq	WOF9213	06-Aug-92	31616	12000		11391	00-Jan-00							pbayou	HP	9281
bayouwq	WOL9219	06-Aug-92	31616	38000		15824	00-Jan-00							pbayou	HP	9293
bayouwq	WOJ9213	06-Aug-92	31616	27000			00-Jan-00							pbayou	HP	9287
bayouwq	WOA9214	06-Aug-92	31616	11000			00-Jan-00							pbayou	HP	9285
bayouwq	WOG9214	06-Aug-92	31616	10000			00-Jan-00							pbayou	HP	9283
bayouwq	WOD9214	06-Aug-92	31616	840			00-Jan-00							pbayou	HP	9277
bayouwq	WOC9215	06-Aug-92	31616	710 2000			00-Jan-00 00-Jan-00							pbayou	HP	9275 9273
bayouwq	WOB9215 WOM9216	06-Aug-92	31616 31616	2000			00-Jan-00 00-Jan-00			1				pbayou	HP HP	9273
bayouwq bayouwq	WOE9213	13-Aug-92 13-Aug-92	31616	2400			00-Jan-00 00-Jan-00							pbayou pbayou	HP	9342
bayouwq	WOE9213 WOF9214	13-Aug-92		3100			00-Jan-00							pbayou	HP	9334
bayouwq	WOL9220	13-Aug-92		36000			00-Jan-00							pbayou	HP	9346
oayouwq	11 OL7440	13-Mug-92	31010	30000	l	13024	00-jan-00			1	<u> </u>			poayou	111	/540

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CAL	C. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOJ9214	13-Aug-92	31616	3800			00-Jan-00							pbayou	HP	9340
bayouwq	WOA9215	13-Aug-92	31616	6100			00-Jan-00							pbayou	HP	9338
bayouwq	WOD9215 WOC9216	13-Aug-92 13-Aug-92	31616 31616	780 2100			00-Jan-00 00-Jan-00							pbayou	HP HP	9330 9328
bayouwq bayouwq	WOC9216 WOB9216	13-Aug-92 13-Aug-92	31616	1000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	9326
bayouwq	WOL9221	17-Aug-92	31616	4200			00-Jan-00							pbayou	HP	9032
bayouwq	WOM9217	18-Aug-92	31616	2400			00-Jan-00							pbayou	HP	9395
bayouwq	WOE9214	18-Aug-92	31616	370		11390	00-Jan-00							pbayou	HP	9385
bayouwq	WOF9215	18-Aug-92	31616	230		11391	00-Jan-00							pbayou	HP	9387
bayouwq	WOL9222	18-Aug-92	31616	3500		15824	00-Jan-00							pbayou	HP	9399
bayouwq	WOK9210	18-Aug-92	31616	3200			00-Jan-00							pbayou	HP	9397
bayouwq	WOJ9215	18-Aug-92	31616	1000			00-Jan-00							pbayou	HP	9393
bayouwq	WOA9216	18-Aug-92	31616	1000			00-Jan-00							pbayou	HP	9391
bayouwq	WOG9215 WOD9216	18-Aug-92	31616 31616	1000 170			00-Jan-00							pbayou	HP HP	9389 9383
bayouwq	WOC9217	18-Aug-92 18-Aug-92	31616	770			00-Jan-00 00-Jan-00							pbayou pbayou	HP	9381
bayouwq bayouwq	WOC9217 WOB9217	18-Aug-92	31616	420			00-Jan-00							pbayou	HP	9379
bayouwq	WOM9218	27-Aug-92	31616	14000			00-Jan-00							pbayou	HP	9450
bayouwq	WOE9215	27-Aug-92	31616	14000			00-Jan-00							pbayou	HP	9440
bayouwq	WOF9216	27-Aug-92	31616	9600		11391	00-Jan-00							pbayou	HP	9442
bayouwq	WOL9223	27-Aug-92	31616	25000		15824	00-Jan-00							pbayou	HP	9454
bayouwq	WOJ9216	27-Aug-92	31616	72000			00-Jan-00							pbayou	HP	9448
bayouwq	WOA9217	27-Aug-92	31616	20000			00-Jan-00							pbayou	HP	9446
bayouwq	WOG9216	27-Aug-92	31616	5400			00-Jan-00							pbayou	HP	9444
bayouwq	WOD9217	27-Aug-92	31616	23000			00-Jan-00							pbayou	HP	9438
bayouwq	WOC9218 WOB9218	27-Aug-92 27-Aug-92	31616 31616	250000 2300			00-Jan-00 00-Jan-00							pbayou	HP HP	9436 9434
bayouwq bayouwq	WOB9218 WOM9219	31-Aug-92	31616	9100			00-Jan-00							pbayou pbayou	HP	9505
bayouwq	WOF9217	31-Aug-92	31616	5900			00-Jan-00							pbayou	HP	9497
bayouwq	WOL9224	31-Aug-92	31616	4600			00-Jan-00							pbayou	HP	9509
bayouwq	WOK9211	31-Aug-92	31616	21000		15825	00-Jan-00							pbayou	HP	9507
bayouwq	WOJ9217	31-Aug-92	31616	5100		15826	00-Jan-00							pbayou	HP	9503
bayouwq	WOA9218	31-Aug-92	31616	11000			00-Jan-00							pbayou	HP	9501
bayouwq	WOG9217	31-Aug-92	31616	3700			00-Jan-00							pbayou	HP	9499
bayouwq	WOD9218	31-Aug-92	31616	360			00-Jan-00							pbayou	HP	9493
bayouwq	WOC9219	31-Aug-92	31616	550 1100			00-Jan-00							pbayou	HP HP	9491 9489
bayouwq	WOB9219 WOM9220	31-Aug-92 10-Sep-92	31616 31616	5200			00-Jan-00 00-Jan-00							pbayou pbayou	HP	11026
bayouwq bayouwq	WOE9216	10-Sep-92	31616	10000			00-Jan-00							pbayou	HP	11016
bayouwq	WOF9218	10-Sep-92	31616	15000			00-Jan-00							pbayou	HP	11018
bayouwq	WOL9225	10-Sep-92	31616	17000			00-Jan-00							pbayou	HP	11030
bayouwq	WOK9212	10-Sep-92	31616	5500		15825	00-Jan-00							pbayou	HP	11028
bayouwq	WOJ9218	10-Sep-92	31616	4600		15826	00-Jan-00							pbayou	HP	11024
bayouwq	WOA9219	10-Sep-92	31616	4900			00-Jan-00							pbayou	HP	11022
bayouwq	WOG9218	10-Sep-92	31616	9100			00-Jan-00							pbayou	HP	11020
bayouwq	WOD9219	10-Sep-92	31616	3500			00-Jan-00							pbayou	HP	11014
bayouwq	WOC9220	10-Sep-92	31616	15000			00-Jan-00							pbayou	HP	11012
bayouwq	WOB9220 WOL9226	10-Sep-92 22-Sep-92	31616 31616	2400 23000			00-Jan-00 00-Jan-00							pbayou	HP HP	11010 10767
bayouwq bayouwq	WOL9226 WOM9221	22-Sep-92 24-Sep-92	31616	5800			00-Jan-00 00-Jan-00							pbayou pbayou	HP	11084
bayouwq	WOE9217	24-Sep-92 24-Sep-92	31616	1500			00-Jan-00 00-Jan-00							pbayou	HP	11074
bayouwq	WOF9219	24-Sep-92	31616	2800			00-Jan-00							pbayou	HP	11076
bayouwq	WOL9227	24-Sep-92	31616	16000			00-Jan-00							pbayou	HP	11088
bayouwq	WOK9213	24-Sep-92	31616	17000			00-Jan-00							pbayou	HP	11086
bayouwq	WOJ9219	24-Sep-92	31616	3700			00-Jan-00							pbayou	HP	11082
bayouwq	WOA9220	24-Sep-92	31616	2300			00-Jan-00							pbayou	HP	11080
bayouwq	WOG9219	24-Sep-92	31616	2400			00-Jan-00							pbayou	HP	11078
bayouwq	WOD9220	24-Sep-92	31616	570		15829	00-Jan-00							pbayou	HP	11072

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC	. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOC9221	24-Sep-92	31616	1500			00-Jan-00							pbayou	HP	11070
bayouwq	WOB9221	24-Sep-92	31616	530			00-Jan-00							pbayou	HP	11068
bayouwq	WOF9212	01-Oct-92	31616	1000 800			00-Jan-00							pbayou	HP	12099
bayouwq	WOE9218 WOL9228	01-Oct-92 01-Oct-92	31616 31616	140000			00-Jan-00 00-Jan-00							pbayou	HP HP	12089 12103
bayouwq bayouwq	WOK9214	01-Oct-92	31616	6000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	12103
bayouwq	WOJ9220	01-Oct-92	31616	9800			00-Jan-00							pbayou	HP	12097
bayouwq	WOA9221	01-Oct-92	31616	7300			00-Jan-00							pbayou	HP	12095
bayouwq	WOG9220	01-Oct-92	31616	7200			00-Jan-00							pbayou	HP	12093
bayouwq	WOD9221	01-Oct-92	31616	440		15829	00-Jan-00							pbayou	HP	12087
bayouwq	WOC9222	01-Oct-92	31616	340		15830	00-Jan-00							pbayou	HP	12085
bayouwq	WOB9222	01-Oct-92	31616	500		15831	00-Jan-00							pbayou	HP	12083
bayouwq	WOM9223	08-Oct-92	31616	4200			00-Jan-00							pbayou	HP	12152
bayouwq	WOE9219	08-Oct-92	31616	4800			00-Jan-00							pbayou		12142
bayouwq	WOF9220	08-Oct-92	31616	5300			00-Jan-00							pbayou	HP	12144
bayouwq	WOL9229	08-Oct-92	31616	4900			00-Jan-00							pbayou	HP	12156
bayouwq	WOK9215	08-Oct-92	31616	3900			00-Jan-00							pbayou	HP	12154
bayouwq	WOJ9221	08-Oct-92	31616	3100			00-Jan-00							pbayou	HP	12150
bayouwq	WOA9222 WOD9222	08-Oct-92 08-Oct-92	31616 31616	5500 9400			00-Jan-00							pbayou	HP HP	12148 12140
bayouwa	WOC9223	08-Oct-92	31616	21000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	12140
bayouwq bayouwq	WOC9223 WOB9223	08-Oct-92	31616	33000			00-Jan-00							pbayou	HP	12136
bayouwq	WOL9230	12-Oct-92	31616	20000			00-Jan-00							pbayou	HP	11848
bayouwq	WOM9224	13-Oct-92	31616	230		1	00-Jan-00							pbayou	HP	12202
bayouwq	WOE9220	13-Oct-92	31616	170			00-Jan-00							pbayou	HP	12192
bayouwq	WOF9221	13-Oct-92	31616	250			00-Jan-00							pbayou	HP	12194
bayouwq	WOL9231	13-Oct-92	31616	11000		15824	00-Jan-00							pbayou	HP	12206
bayouwq	WOK9216	13-Oct-92	31616	4700		15825	00-Jan-00							pbayou	HP	12204
bayouwq	WOJ9222	13-Oct-92	31616	90		15826	00-Jan-00							pbayou	HP	12200
bayouwq	WOA9223	13-Oct-92	31616	54		15827	00-Jan-00							pbayou	HP	12198
bayouwq	WOG9222	13-Oct-92	31616	72			00-Jan-00							pbayou	HP	12196
bayouwq	WOD9223	13-Oct-92	31616	27			00-Jan-00							pbayou	HP	12190
bayouwq	WOC9224	13-Oct-92	31616	140			00-Jan-00							pbayou	HP	12188
bayouwq	WOB9224	13-Oct-92	31616	140			00-Jan-00							pbayou	HP	12186
bayouwq	WOM9225	20-Oct-92	31616	3400			00-Jan-00							pbayou	HP	12251
bayouwq	WOE9221	20-Oct-92	31616	6300			00-Jan-00							pbayou	HP	12241
bayouwq	WOF9222	20-Oct-92 20-Oct-92	31616 31616	5900 91000		1	00-Jan-00							pbayou	HP HP	12243 12255
bayouwq bayouwq	WOL9232 WOK9217	20-Oct-92 20-Oct-92	31616	29000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	12253
bayouwq	WOK9217 WOJ9223	20-Oct-92	31616	8500			00-Jan-00							pbayou	HP	12249
bayouwq	WOA9224	20-Oct-92	31616	7500			00-Jan-00							pbayou	HP	12247
bayouwq	WOG9223	20-Oct-92	31616	8000			00-Jan-00							pbayou	HP	12245
bayouwq	WOD9224	20-Oct-92	31616	220			00-Jan-00							pbayou	HP	12239
bayouwq	WOC9225	20-Oct-92	31616	370		15830	00-Jan-00							pbayou	HP	12237
bayouwq	WOB9225	20-Oct-92	31616	520		15831	00-Jan-00							pbayou	HP	12235
bayouwq	WOM9226	27-Oct-92	31616	2600		11385	00-Jan-00							pbayou	HP	12301
bayouwq	WOE9222	27-Oct-92	31616	23000		11390	00-Jan-00							pbayou	HP	12291
bayouwq	WOF9223	27-Oct-92	31616	30000		11391	00-Jan-00							pbayou	HP	12293
bayouwq	WOL9233	27-Oct-92	31616	25000			00-Jan-00							pbayou	HP	12305
bayouwq	WOK9218	27-Oct-92	31616	24000			00-Jan-00					\perp		pbayou	HP	12303
bayouwq	WOJ9224	27-Oct-92	31616	56000			00-Jan-00							pbayou	HP	12299
bayouwq	WOA9225	27-Oct-92	31616	66000			00-Jan-00					+		pbayou	HP	12297
bayouwq	WOG9224	27-Oct-92	31616	37000			00-Jan-00					+		pbayou	HP	12295
bayouwq	WOD9225	27-Oct-92	31616	3900			00-Jan-00					+		pbayou	HP	12289
bayouwa	WOC9226 WOB9226	27-Oct-92 27-Oct-92	31616 31616	4100 1400			00-Jan-00 00-Jan-00					+		pbayou	HP HP	12287 12285
bayouwq bayouwq	WOB9226 WOM9227	05-Nov-92	31616	3800			00-Jan-00 00-Jan-00					+ -		pbayou pbayou		13582
	WOE9223	05-Nov-92 05-Nov-92		890			00-Jan-00 00-Jan-00					+ -		pbayou	HP	13572
bayouwq	11 OE9223	03-NOV-92	31010	690	<u> </u>	11390	oo-jan-00	<u> </u>		<u> </u>				poayou	1 III	13314

Septembrook WOL0224 05-Nov-92 31616 5800 15824 05-Jan-00	ayou ayou ayou ayou ayou ayou ayou ayou	HP HP HP HP HP HP HP HP	13574 13586 13584 13580 13578 13576 13570
Septembrook WOK0219 05-No-92 31616 5600 15825 00-Jan-00	ayou ayou ayou ayou ayou ayou ayou ayou	HP HP HP HP HP	13584 13580 13578 13576 13570
Depart	ayou ayou ayou ayou ayou ayou ayou ayou	HP HP HP HP	13580 13578 13576 13570
September WOA9226 OS-Nov-92 31616 2900 15827 OS-Jan-90 Puber Deput Deput	ayou ayou ayou ayou ayou ayou ayou ayou	HP HP HP HP	13578 13576 13570
Degrame WOG9225 05-Nov-92 31616 2300 15828 00-Jan-00	ayou ayou ayou ayou ayou ayou ayou ayou	HP HP HP	13576 13570
Description WODPS216 05-Nov-92 31616 1100 15829 00-Jan-00	ayou ayou ayou ayou ayou ayou ayou ayou	HP HP	13570
Sayonesq WOC9227 O.S. No92 31616 590 15830 O.J. Jan-00	ayou ayou ayou ayou ayou ayou ayou ayou	HP	
Depump WORD9212 05 - No92 31616 1500 15824 00-Jan-00	ayou ayou ayou ayou ayou ayou		
Page	ayou ayou ayou ayou ayou		13566
Daycowq WOL9236 08-Dec-92 31616 24000 15824 00-Jan-00 BM Phen Ph	ayou ayou ayou	HP	13326
Not	ayou ayou	HP	13619
Daysoung WOJ9301 12-Apr-93 31616 2900 15826 00-Jan-00	ayou	HP	3078
Bayonwq WOC9301 12-Apr-93 31616 350 15830 00-Jan-00 Day	•	HP	3080
Bayouwq WOB9301 12-Apr-93 31616 350 15831 00-Jan-00 Day	93/011	HP	3076
No.		HP	3070
Eagloung WOE9301 12-May-93 31616 2100 11390 00-Jan-00 Day	,	HP	3068
Description Payous WOF9301 12-May-93 31616 1300 11391 00-Jan-00	•	HP HP	4633 4623
Bayouwq WOK9302 12-May-93 31616 3300 15825 00-Jan-00	•	HP	4625
Dayouwq WOJ9302 12-May-93 31616 2000 15826 00-Jan-00 Dayouwq WOD9301 12-May-93 31616 860 15829 00-Jan-00 Dayouwq WOC9302 12-May-93 31616 820 15830 00-Jan-00 Dayouwq WOB9302 12-May-93 31616 2200 15831 00-Jan-00 Dayouwq WOM9303 28-May-93 31616 27000 11385 00-Jan-00 Dayouwq WOM9303 28-May-93 31616 27000 11385 00-Jan-00 Dayouwq WOM9303 28-May-93 31616 5700 15826 00-Jan-00 Dayouwq WOM9304 03-Jun-93 31616 16000 11385 00-Jan-00 Dayouwq WOM9304 03-Jun-93 31616 3000 15827 00-Jan-00 Dayouwq WOM9305 09-Jun-93 31616 3000 15827 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 30000 15827 00-Jan-00 Dayouwq WOM9304 09-Jun-93 31616 2100 15826 00-Jan-00 Dayouwq WOM9304 09-Jun-93 31616 2100 15826 00-Jan-00 Dayouwq WOM9304 09-Jun-93 31616 2100 15826 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 2100 15826 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 2100 15827 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 2000 15820 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 2000 15820 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 2600 11385 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 2600 11385 00-Jan-00 Dayouwq WOM9303 09-Jun-93 31616 2600 11385 00-Jan-00 Dayouwq WOM9304 10-Jun-93 31616 2000 15827 00-Jan-00 Dayouwq WOM9307 10-Jun-93 31616 2000 15827 00-Jan-00 Dayouwq WOM9307 10-Jun-93 31616 2000 1385 00-Jan-00 Dayouwq WOM9307 10-Jun-93 31616 2000 1385 00-Jan-00 Dayouwq WOM9307 10-Jun-93 31616 200	*	HP	4635
Bayouwq WOD9301 12-May-93 31616 860 15829 00-Jan-00 pba bayouwq WOC9302 12-May-93 31616 820 15830 00-Jan-00	,	HP	4631
bayouwq WOC9302 12-May-93 31616 820 15830 00-Jan-00	ayou	HP	4621
Dayouwq WOM9303 28-May-93 31616 27000 11385 00-Jan-00 BM pbar pb		HP	4619
Dayouwq WOJ9303 28-May-93 31616 5700 15826 00-Jan-00 BM pbar pba	ayou	HP	4617
bayouwq WOM9304 03-Jun-93 31616 16000 11385 00-Jan-00 BM pbayouwq bayouwq WOA9301 03-Jun-93 31616 3000 15827 00-Jan-00 BM pbayouwq bayouwq WOM9305 09-Jun-93 31616 11000 11385 00-Jan-00 Do-Jan-00 Do-Jan-00 <t< td=""><td>•</td><td>HP</td><td>4277</td></t<>	•	HP	4277
bayouwq WOA9301 03-Jun-93 31616 3000 15827 00-Jan-00 BM pba bayouwq WOM9305 09-Jun-93 31616 11000 11385 00-Jan-00 BM pba bayouwq WOK9303 09-Jun-93 31616 2100 15825 00-Jan-00 Description Description Description bayouwq WOA9302 09-Jun-93 31616 2000 15827 00-Jan-00 Description Description Description Description bayouwq WOD9302 09-Jun-93 31616 2000 15827 00-Jan-00 Description	•	HP	4279
bayouwq WOM9305 09-Jun-93 31616 11000 11385 00-Jan-00 pba bayouwq WOK9303 09-Jun-93 31616 30000 15825 00-Jan-00 Description bayouwq WOJ9304 09-Jun-93 31616 2100 15826 00-Jan-00 Description Description Description bayouwq WOA9302 09-Jun-93 31616 2000 15827 00-Jan-00 Description Description Description bayouwq WOC9303 09-Jun-93 31616 480 15829 00-Jan-00 Description Description Description Description bayouwq WOB9303 09-Jun-93 31616 520 15830 00-Jan-00 Description Descr	*	HP	5759
bayouwq WOK9303 09-Jun-93 31616 30000 15825 00-Jan-00 pba bayouwq WOJ9304 09-Jun-93 31616 2100 15826 00-Jan-00 Description bayouwq WOA9302 09-Jun-93 31616 2000 15827 00-Jan-00 Description Description bayouwq WOD9302 09-Jun-93 31616 480 15829 00-Jan-00 Description Description Description bayouwq WOB9303 09-Jun-93 31616 520 15830 00-Jan-00 Description Description Description bayouwq WOB9303 09-Jun-93 31616 260 11385 00-Jan-00 Description BM Description bayouwq WOM9306 10-Jun-93 31616 260 11385 00-Jan-00 Description BM Description bayouwq WOM9307 16-Jun-93 31616 4200 15827 00-Jan-00 Description BM Description	•	HP	5761
bayouwq WOJ9304 09-Jun-93 31616 2100 15826 00-Jan-00 pba bayouwq WOA9302 09-Jun-93 31616 2000 15827 00-Jan-00 Description bayouwq WOD9302 09-Jun-93 31616 480 15829 00-Jan-00 Description Description bayouwq WOB9303 09-Jun-93 31616 520 15830 00-Jan-00 Description Description Description bayouwq WOB9303 09-Jun-93 31616 260 11385 00-Jan-00 Description BM Description bayouwq WOA9304 10-Jun-93 31616 4200 15827 00-Jan-00 Description BM Description bayouwq WOM9307 16-Jun-93 31616 21000 11385 00-Jan-00 Description BM Description bayouwq WOA9304 16-Jun-93 31616 21000 11385 00-Jan-00 Description BM Description	•	HP HP	6306 6308
bayouwq WOA9302 09-Jun-93 31616 2000 15827 00-Jan-00 bayouwq bayouwq WOD9302 09-Jun-93 31616 480 15829 00-Jan-00 Description De		HP	6304
bayouwq WOD9302 09-Jun-93 31616 480 15829 00-Jan-00 pba bayouwq WOC9303 09-Jun-93 31616 520 15830 00-Jan-00 Description bayouwq WOB9303 09-Jun-93 31616 760 15831 00-Jan-00 Description BM pba bayouwq WOM9306 10-Jun-93 31616 260 11385 00-Jan-00 BM pba bayouwq WOA9303 10-Jun-93 31616 4200 15827 00-Jan-00 BM pba bayouwq WOM9307 16-Jun-93 31616 21000 11385 00-Jan-00 BM pba bayouwq WOA9304 16-Jun-93 31616 4500 15827 00-Jan-00 BM BM pba bayouwq WOA9304 16-Jun-93 31616 4500 15827 00-Jan-00 BM BM pba	•	HP	6300
bayouwq WOC9303 09-Jun-93 31616 520 15830 00-Jan-00 pba bayouwq WOB9303 09-Jun-93 31616 760 15831 00-Jan-00 BM pba bayouwq WOM9306 10-Jun-93 31616 260 11385 00-Jan-00 BM pba bayouwq WOA9303 10-Jun-93 31616 4200 15827 00-Jan-00 BM pba bayouwq WOM9307 16-Jun-93 31616 21000 11385 00-Jan-00 BM pba bayouwq WOA9304 16-Jun-93 31616 4500 15827 00-Jan-00 BM BM pba	•	HP	6292
bayouwq WOM9306 10-Jun-93 31616 260 11385 00-Jan-00 BM pbar bayouwq WOA9303 10-Jun-93 31616 4200 15827 00-Jan-00 BM pbar bayouwq WOM9307 16-Jun-93 31616 21000 11385 00-Jan-00 BM pbar bayouwq WOA9304 16-Jun-93 31616 4500 15827 00-Jan-00 BM pbar	-	HP	6290
bayouwq WOA9303 10-Jun-93 31616 4200 15827 00-Jan-00 BM pbayouwq bayouwq WOM9307 16-Jun-93 31616 21000 11385 00-Jan-00 BM pbayouwq bayouwq WOA9304 16-Jun-93 31616 4500 15827 00-Jan-00 BM pbayouwq	ayou	HP	6288
bayouwq WOM9307 16-Jun-93 31616 21000 11385 00-Jan-00 BM pba bayouwq WOA9304 16-Jun-93 31616 4500 15827 00-Jan-00 BM pba pba pba pba pba pba	ayou	HP	5806
bayouwq WOA9304 16-Jun-93 31616 4500 15827 00-Jan-00 BM pbay	•	HP	5808
		HP	5853
	•	HP	5855
	•	HP	5901
	*	HP HP	5903 7773
	•	HP	7775
	•	HP	7818
	-	HP	7820
	•	HP	7832
bayouwq WOM9311 26-Jul-93 31616 2700 11385 00-Jan-00 pba	ayou	HP	8233
	,	HP	8221
			8231
	•	HP	8227
	•		8217
	-		8215
	•	HP HP	7866 7868
	•	HP	9585
	93/011	HP	9585
7 1		HP	9599
bayouwq WOM9314 11-Aug-93 31616 820 11385 00-Jan-00 BM pbay	ayou		9633

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOA9311	11-Aug-93	31616	7200		15827	00-Jan-00								BM	pbayou	HP	9635
bayouwq	WOM9315	16-Aug-93	31616	3800			00-Jan-00									pbayou	HP	10089
bayouwq	WOE9303	16-Aug-93	31616	9700			00-Jan-00									pbayou	HP	10079
bayouwq	WOK9304	16-Aug-93	31616 31616	68000 2100			00-Jan-00									pbayou	HP HP	10091 10087
bayouwq bayouwq	WOJ9306 WOA9312	16-Aug-93 16-Aug-93	31616	2100			00-Jan-00 00-Jan-00									pbayou pbayou	HP	10087
bayouwq	WOC9305	16-Aug-93	31616	5700			00-Jan-00									pbayou	HP	10075
bayouwq	WOB9305	16-Aug-93	31616	8300			00-Jan-00									pbayou	HP	10073
bayouwq	WOM9316	18-Aug-93	31616	2100			00-Jan-00								BM	pbayou	HP	9679
bayouwq	WOA9313	18-Aug-93	31616	9400		15827	00-Jan-00								BM	pbayou	HP	9681
bayouwq	WOM9317	25-Aug-93	31616	7200		11385	00-Jan-00								BM	pbayou	HP	9725
bayouwq	WOA9314	25-Aug-93	31616	7800		15827	00-Jan-00								BM	pbayou	HP	9727
bayouwq	WOF9302	04-Oct-93	31616	2300			00-Jan-00									pbayou	HP	12732
bayouwq	WOK9305	04-Oct-93	31616	20000			00-Jan-00									pbayou	HP	12742
bayouwq	WOJ9307	04-Oct-93	31616	4300			00-Jan-00									pbayou	HP	12738
bayouwq	WOA9315	04-Oct-93	31616	5500			00-Jan-00									pbayou	HP	12736
bayouwq	WOD9303	04-Oct-93	31616	1000			00-Jan-00									pbayou	HP	12728
bayouwq	WOC9306	04-Oct-93 04-Oct-93	31616	700 1300			00-Jan-00									pbayou	HP HP	12726 12724
bayouwq	WOB9306 WOA9316	20-Oct-93	31616 31616	7400			00-Jan-00 00-Jan-00								BM	pbayou pbayou	HP	12724
bayouwq bayouwq	WOA9401	02-Feb-94	31616	7800			00-Jan-00 00-Jan-00								BM	9495a	HP	30
bayouwq	WOA9402	08-Feb-94	31616	21000			00-Jan-00								DIVI	9495a	HP	182
bayouwq	WOL9401	03-Mar-94	31616	950			00-Jan-00									9495a	HP	508
bayouwq	WOL9402	22-Mar-94	31616	4400			00-Jan-00									9495a	HP	575
bayouwq	WOL9403	30-Mar-94	31616	16000			00-Jan-00									9495a	HP	642
bayouwq	WOL9404	05-Apr-94	31616	21000		15824	00-Jan-00									9495a	HP	313
bayouwq	WOL9405	19-Apr-94	31616	20000		15824	00-Jan-00									9495a	HP	378
bayouwq	WOL9406	26-Apr-94	31616	3800		15824	00-Jan-00									9495a	HP	443
bayouwq	WOL9407	11-May-94	31616	4500		15824	00-Jan-00									9495a	HP	4196
bayouwq	WOL9408	17-May-94	31616	8700		15824	00-Jan-00									9495a	HP	4263
bayouwq	WOL9409	24-May-94	31616	2200			00-Jan-00									9495a	HP	4331
bayouwq	WOL9410	07-Jun-94	31616	5900			00-Jan-00									9495a	HP	879
bayouwq	WOM9401	08-Jun-94	31616	1900			00-Jan-00									9495a	HP	1251
bayouwq	WOE9401	08-Jun-94	31616	370			00-Jan-00									9495a	HP	1241
bayouwq	WOF9401	08-Jun-94	31616	390			00-Jan-00									9495a	HP	1243
bayouwq	WOL9411 WOK9401	08-Jun-94 08-Jun-94	31616 31616	1700 2800			00-Jan-00 00-Jan-00									9495a 9495a	HP HP	1255 1253
bayouwq bayouwq	WOK9401 WOJ9401	08-Jun-94	31616	450			00-Jan-00 00-Jan-00									9495a 9495a	HP	1233
bayouwq	WOA9403	08-Jun-94	31616	530			00-Jan-00									9495a	HP	1247
bayouwq	WOD9401	08-Jun-94	31616	490			00-Jan-00									9495a	HP	1239
bayouwq	WOC9401	08-Jun-94	31616	660			00-Jan-00									9495a	HP	1237
bayouwq	WOB9401	08-Jun-94	31616	1200			00-Jan-00									9495a	HP	1235
bayouwq	WOL9412	28-Jun-94	31616	3300		15824	00-Jan-00									9495a	HP	951
bayouwq	WOE9402	06-Jul-94	31616	89000		11390	00-Jan-00									9495a	HP	1759
bayouwq	WOF9402	06-Jul-94	31616	70000		11391	00-Jan-00									9495a	HP	1761
bayouwq	WOL9413	06-Jul-94	31616	200000		15824	00-Jan-00									9495a	HP	1773
bayouwq	WOK9402	06-Jul-94	31616	48000			00-Jan-00									9495a	HP	1771
bayouwq	WOJ9402	06-Jul-94	31616	180000			00-Jan-00									9495a	HP	1767
bayouwq	WOA9404	06-Jul-94	31616	110000			00-Jan-00									9495a	HP	1765
	WOD9402	06-Jul-94	31616	59000			00-Jan-00									9495a	HP	1757
	WOC9402	06-Jul-94	31616	86000			00-Jan-00									9495a	HP	1755
	WOB9402	06-Jul-94	31616	5700			00-Jan-00									9495a	HP	1753
	WOL9414	19-Jul-94	31616	780 1900			00-Jan-00									9495a 9495a	HP	1454
bayouwq	WOL9415 WOE9403	27-Jul-94	31616 31616	750			00-Jan-00 00-Jan-00									9495a 9495a	HP HP	1522 1813
	WOF9403	03-Aug-94 03-Aug-94	31616	4600			00-Jan-00 00-Jan-00									9495a 9495a	HP	1815
	WOL9416	03-Aug-94 03-Aug-94		15000			00-Jan-00 00-Jan-00									9495a 9495a	HP	1827
bayouwq	WOK9403	03-Aug-94		3600			00-Jan-00									9495a	HP	1825

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOJ9403	03-Aug-94	31616	2200		15826	00-Jan-00							9495a	HP	1821
bayouwq	WOA9405	03-Aug-94	31616	1900			00-Jan-00							9495a	HP	1819
bayouwq	WOD9403	03-Aug-94	31616	730			00-Jan-00							9495a	HP	1811
bayouwq	WOC9403	03-Aug-94	31616	740			00-Jan-00							9495a	HP	1809
bayouwq	WOB9403 WOL9417	03-Aug-94 06-Sep-94	31616 31616	780 5200			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	1807 1930
bayouwq bayouwq	WOE9404	07-Sep-94	31616	6700			00-Jan-00 00-Jan-00							9495a 9495a	HP	2336
bayouwq	WOF9404	07-Sep-94	31616	4800			00-Jan-00							9495a	HP	2338
bayouwq	WOL9418	07-Sep-94	31616	7000			00-Jan-00							9495a	HP	2350
bayouwq	WOK9404	07-Sep-94	31616	45000			00-Jan-00							9495a	HP	2348
bayouwq	WOJ9404	07-Sep-94	31616	9500		15826	00-Jan-00							9495a	HP	2344
bayouwq	WOA9406	07-Sep-94	31616	6800		15827	00-Jan-00							9495a	HP	2342
bayouwq	WOD9404	07-Sep-94	31616	3700		15829	00-Jan-00							9495a	HP	2334
bayouwq	WOC9404	07-Sep-94	31616	4500			00-Jan-00							9495a	HP	2332
bayouwq	WOB9404	07-Sep-94	31616	580			00-Jan-00							9495a	HP	2330
bayouwq	WOL9419	27-Sep-94	31616	4800			00-Jan-00							9495a	HP	2054
bayouwq	WOE9405 WOF9405	05-Oct-94 05-Oct-94	31616 31616	620 3800			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	2500 2502
bayouwq bayouwq	WOL9403 WOL9420	05-Oct-94	31616	3500			00-Jan-00 00-Jan-00							9495a 9495a	HP	2514
bayouwq	WOK9405	05-Oct-94	31616	8400			00-Jan-00							9495a	HP	2512
bayouwq	WOJ9405	05-Oct-94	31616	820			00-Jan-00							9495a	HP	2508
bayouwq	WOA9407	05-Oct-94	31616	1000			00-Jan-00							9495a	HP	2506
bayouwq	WOD9405	05-Oct-94	31616	730			00-Jan-00							9495a	HP	2498
bayouwq	WOC9405	05-Oct-94	31616	570		15830	00-Jan-00							9495a	HP	2496
bayouwq	WOB9405	05-Oct-94	31616	760		15831	00-Jan-00							9495a	HP	2494
bayouwq	WOL9421	15-Nov-94	31616	180		15824	00-Jan-00							9495a	HP	2726
bayouwq	WOM9402	16-Nov-94	31616	830			00-Jan-00						BM	9495a	HP	2551
bayouwq	WOA9408	16-Nov-94	31616	62000			00-Jan-00						BM	9495a	HP	2553
bayouwq	WOL9422	29-Nov-94	31616	3200			00-Jan-00							9495a	HP	2789
bayouwq	WOE9406	30-Nov-94	31616	3200			00-Jan-00						BM	9495a	HP	2658
bayouwq bayouwq	WOA9409 WOL9501	30-Nov-94 17-Jan-95	31616 31616	7500 4500			00-Jan-00 00-Jan-00						BM	9495a 9495a	HP HP	2650 2854
bayouwq	WOL9501 WOL9502	30-Jan-95	31616	25000			00-Jan-00 00-Jan-00							9495a 9495a	HP	2923
bayouwq	WOL9502 WOM9501	02-Feb-95	31616	1100			00-Jan-00						BM	9495a	HP	2966
bayouwq	WOA9501	02-Feb-95	31616	560			00-Jan-00						BM	9495a	HP	2968
bayouwq	WOL9503	07-Feb-95	31616	7500			00-Jan-00							9495a	HP	3084
bayouwq	WOM9502	08-Feb-95	31616	45000		11385	00-Jan-00						BM	9495a	HP	3011
bayouwq	WOA9502	08-Feb-95	31616	40000		15827	00-Jan-00						BM	9495a	HP	3013
bayouwq	WOL9504	27-Mar-95	31616	4800		15824	00-Jan-00							9495a	HP	3400
bayouwq	WOE9501	28-Mar-95	31616	1100			00-Jan-00							9495a	HP	3538
bayouwq	WOF9501	28-Mar-95	31616	940			00-Jan-00							9495a	HP	3540
bayouwq	WOL9505	28-Mar-95	31616	4800			00-Jan-00							9495a	HP	3552
bayouwq	WOJ9501	28-Mar-95	31616	590			00-Jan-00							9495a	HP	3546
bayouwq	WOA9503	28-Mar-95	31616	4700 4900			00-Jan-00							9495a	HP HP	3544 3536
bayouwq	WOD9501 WOC9501	28-Mar-95 28-Mar-95	31616 31616	4800			00-Jan-00 00-Jan-00							9495a 9495a	HP	3536
bayouwq bayouwq	WOE9501 WOB9501	28-Mar-95	31616	510			00-Jan-00 00-Jan-00							9495a 9495a	HP	3532
bayouwq	WOL9506	03-Apr-95	31616	3500			00-Jan-00							9495a	HP	3658
bayouwq	WOE9502	24-Apr-95	31616	2500			00-Jan-00							9495a		3894
bayouwq	WOF9502	24-Apr-95	31616	1200			00-Jan-00							9495a	HP	3896
bayouwq	WOL9507	24-Apr-95	31616	5200			00-Jan-00							9495a	HP	3908
bayouwq	WOK9501	24-Apr-95	31616	6200		15825	00-Jan-00							9495a	HP	3906
bayouwq	WOJ9502	24-Apr-95	31616	1000		15826	00-Jan-00							9495a	HP	3902
bayouwq	WOA9504	24-Apr-95	31616	2300			00-Jan-00							9495a	HP	3900
bayouwq	WOD9502	24-Apr-95	31616	820			00-Jan-00							9495a	HP	3892
bayouwq	WOC9502	24-Apr-95	31616	950			00-Jan-00							9495a	HP	3890
bayouwq	WOB9502	24-Apr-95	31616	2800			00-Jan-00							9495a	HP	3888
bayouwq	WOA9505	26-Apr-95	31616	590		15827	00-Jan-00					1	BM	9495a	HP	3591

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOL9508	01-May-95	31616	1020		15824	00-Jan-00							9495a	HP	4128
bayouwq	WOE9503	02-May-95	31616	9000			00-Jan-00							9495a	HP	4574
bayouwq	WOF9503	02-May-95	31616	19300			00-Jan-00							9495a	HP	4576
bayouwq	WOL9509	02-May-95	31616	1100			00-Jan-00							9495a	HP	4588
bayouwq	WOK9502 WOJ9503	02-May-95 02-May-95	31616 31616	4400 3200			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	4586 4582
bayouwq bayouwq	WOJ9505 WOA9506	02-May-95	31616	5300			00-Jan-00 00-Jan-00							9495a 9495a	HP	4580
bayouwq	WOD9503	02-May-95	31616	1000			00-Jan-00							9495a	HP	4572
bayouwq	WOC9503	02-May-95	31616	13000			00-Jan-00							9495a	HP	4570
bayouwq	WOB9503	02-May-95	31616	1400			00-Jan-00							9495a	HP	4568
bayouwq	WOA9507	23-May-95	31616	450		15827	00-Jan-00						BM	9495a	HP	3995
bayouwq	WOL9510	05-Jun-95	31616	7900		15824	00-Jan-00							9495b	HP	28
bayouwq	WOE9504	06-Jun-95	31616	7600		11390	00-Jan-00							9495a	HP	5279
bayouwq	WOF9504	06-Jun-95	31616	5800			00-Jan-00							9495a	HP	5281
bayouwq	WOL9511	06-Jun-95	31616	9200			00-Jan-00							9495a	HP	5293
bayouwq	WOK9503	06-Jun-95	31616	21000			00-Jan-00							9495a	HP	5291
bayouwq	WOJ9504 WOA9508	06-Jun-95 06-Jun-95	31616 31616	35000 65000			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	5287 5285
bayouwq bayouwq	WOD9504	06-Jun-95	31616	6500			00-Jan-00 00-Jan-00							9495a 9495a	HP	5277
bayouwq	WOC9504	06-Jun-95	31616	7500			00-Jan-00							9495a	HP	5275
bayouwq	WOB9504	06-Jun-95	31616	15000			00-Jan-00							9495a	HP	5273
bayouwq	WOA9509	27-Jun-95	31616	4100			00-Jan-00						BM	9495a	HP	4673
bayouwq	WOL9512	03-Jul-95	31616	4400		15824	00-Jan-00							9495a	HP	5510
bayouwq	WOE9505	05-Jul-95	31616	12000		11390	00-Jan-00							9495a	HP	5795
bayouwq	WOF9505	05-Jul-95	31616	21000			00-Jan-00							9495a	HP	5797
bayouwq	WOL9513	05-Jul-95	31616	200000			00-Jan-00							9495a	HP	5809
bayouwq	WOK9504	05-Jul-95	31616	10000			00-Jan-00							9495a	HP	5807
bayouwq	WOJ9505	05-Jul-95	31616	10000			00-Jan-00							9495a	HP	5803
bayouwq	WOA9510	05-Jul-95	31616	9700			00-Jan-00							9495a	HP	5801
bayouwq bayouwq	WOD9505 WOC9505	05-Jul-95 05-Jul-95	31616 31616	9900 11000			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	5793 5791
bayouwq	WOB9505	05-Jul-95	31616	15000			00-Jan-00							9495a	HP	5789
bayouwq	WOA9511	31-Jul-95	31616	67000			00-Jan-00						BM	9495a	HP	5379
bayouwq	WOE9506	10-Aug-95	31616	4100			00-Jan-00							9495a	HP	5915
bayouwq	WOF9506	10-Aug-95	31616	4000		11391	00-Jan-00							9495a	HP	5917
bayouwq	WOL9514	10-Aug-95	31616	1700		15824	00-Jan-00							9495a	HP	5929
bayouwq	WOK9505	10-Aug-95	31616	4900		15825	00-Jan-00							9495a	HP	5927
bayouwq	WOJ9506	10-Aug-95	31616	5700			00-Jan-00							9495a	HP	5923
bayouwq	WOA9512	10-Aug-95	31616	6800			00-Jan-00							9495a	HP	5921
bayouwq	WOD9506	10-Aug-95	31616	680			00-Jan-00							9495a	HP	5913
bayouwq	WOC9506	10-Aug-95	31616	900			00-Jan-00							9495a	HP	5911
bayouwq bayouwq	WOB9506 WOL9515	10-Aug-95 14-Aug-95	31616 31616	2900 8400			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	5909 5873
bayouwq	WOL9516	12-Sep-95	31616	200000			00-Jan-00							9495b	HP	64
bayouwq	WOL9517	11-Oct-95	31616	9500			00-Jan-00							9495b	HP	99
bayouwq	WOL9518	05-Dec-95	31616	5900			00-Jan-00							9495b	HP	139
bayouwq	WOL9601	23-Jan-96	31616	12000			00-Jan-00							xls96	HP	30
bayouwq	WOA9601	25-Jan-96	31616	16000		15827	00-Jan-00						BM	xls96	HP	57
bayouwq	WOL9602	05-Feb-96	31616	35000		15824	00-Jan-00							xls96	HP	97
bayouwq	WOE9601	08-Feb-96	31616	7200			00-Jan-00							xls96	HP	122
bayouwq	WOF9601	08-Feb-96	31616	4400			00-Jan-00							xls96	HP	123
bayouwq	WOL9603	08-Feb-96	31616	6600			00-Jan-00							xls96	HP	128
bayouwq	WOK9601	08-Feb-96	31616	6800			00-Jan-00							xls96	HP	127
bayouwq	WOJ9601	08-Feb-96	31616	11000 6000			00-Jan-00 00-Jan-00							xls96	HP	126
bayouwq	WOA9602 WOG9601	08-Feb-96 08-Feb-96	31616 31616	7700			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	125 124
bayouwq bayouwq	WOD9601	08-Feb-96	31616	590			00-Jan-00 00-Jan-00							xls96	HP	124
bayouwq	WOC9601	08-Feb-96	31616	580			00-Jan-00 00-Jan-00							xls96		120
bayouwq	** OC3001	00-1-00-90	31010	380	l	13030	oo-jan-00	11		1		1	L	A187U	111	120

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOB9601	08-Feb-96	31616	2000			00-Jan-00							xls96	HP	119
bayouwq	WOA9603	26-Feb-96	31616	140			00-Jan-00						BM	xls96	HP	286
bayouwq	WOL9604	04-Mar-96	31616	3100			00-Jan-00							xls96	HP	361
bayouwq	WOE9602	20-Mar-96	31616	6000 6500			00-Jan-00							xls96	HP	480 481
bayouwq bayouwq	WOF9602 WOL9605	20-Mar-96 20-Mar-96	31616 31616	10000		11391 15824	00-Jan-00 00-Jan-00							xls96 xls96	HP HP	481
bayouwq	WOK9602	20-Mar-96	31616	8800		15825	00-Jan-00							xls96	HP	485
bayouwq	WOJ9602	20-Mar-96	31616	5400		15826	00-Jan-00							xls96	HP	484
bayouwq	WOA9604	20-Mar-96	31616	6400		15827	00-Jan-00							xls96	HP	483
bayouwq	WOG9602	20-Mar-96	31616	4900		15828	00-Jan-00							xls96	HP	482
bayouwq	WOD9602	20-Mar-96	31616	22000		15829	00-Jan-00							xls96	HP	479
bayouwq	WOC9602	20-Mar-96	31616	200		15830	00-Jan-00							xls96		478
bayouwq	WOB9602	20-Mar-96	31616	160			00-Jan-00							xls96		477
bayouwq	WOA9605	28-Mar-96	31616	7100			00-Jan-00						BM	xls96		612
bayouwq	WOL9606	08-Apr-96	31616	3500			00-Jan-00							xls96	HP	692
bayouwq	WOE9603	17-Apr-96	31616	1200			00-Jan-00							xls96	HP	788
bayouwq	WOF9603	17-Apr-96	31616	960		11391	00-Jan-00							xls96	HP	789
bayouwq	WOL9607	17-Apr-96	31616	44000 62000			00-Jan-00							xls96	HP HP	793 792
bayouwq	WOK9603 WOJ9603	17-Apr-96 17-Apr-96	31616 31616	61000		15825 15826	00-Jan-00 00-Jan-00							xls96 xls96		792
bayouwq bayouwq	WOG9603	17-Apr-96 17-Apr-96	31616	2000		15828	00-Jan-00							xls96	HP	790
bayouwq	WOD9603	17-Apr-96	31616	1200		15829	00-Jan-00							xls96	HP	787
bayouwq	WOC9603	17-Apr-96	31616	450		15830	00-Jan-00							xls96		786
bayouwq	WOB9603	17-Apr-96	31616	340			00-Jan-00							xls96	HP	785
bayouwq	WOE9604	07-May-96	31616	1100			00-Jan-00							xls96		962
bayouwq	WOF9604	07-May-96	31616	1000			00-Jan-00							xls96	HP	963
bayouwq	WOL9608	07-May-96	31616	6300		15824	00-Jan-00							xls96	HP	968
bayouwq	WOK9604	07-May-96	31616	4000		15825	00-Jan-00							xls96	HP	967
bayouwq	WOJ9604	07-May-96	31616	900		15826	00-Jan-00							xls96	HP	966
bayouwq	WOA9606	07-May-96	31616	2800		15827	00-Jan-00							xls96	HP	965
bayouwq	WOG9604	07-May-96	31616	1100		15828	00-Jan-00							xls96	HP	964
bayouwq	WOD9604	07-May-96	31616	1000		15829	00-Jan-00							xls96		961
bayouwq	WOC9604	07-May-96	31616	910		15830	00-Jan-00							xls96	HP	960
bayouwq	WOB9604	07-May-96	31616	860		15831	00-Jan-00							xls96	HP	959
bayouwq	WOL9609	20-May-96	31616	450		15824	00-Jan-00						DM.	xls96	HP	1211
bayouwq	WOM9602 WOA9608	23-May-96	31616	420 2600			00-Jan-00 00-Jan-00						BM BM	xls96 xls96	HP HP	1236 1237
bayouwq	WOL9610	23-May-96 05-Jun-96	31616 31616	7900			00-Jan-00						BIVI	bayou95		26
bayouwq bayouwq	WOL9611	10-Jun-96	31616	1400			00-Jan-00							xls96	HP	1353
bayouwq	WOM9603	11-Jun-96	31616	1200			00-Jan-00							xls96	HP	1386
bayouwq	WOE9605	11-Jun-96	31616	1300			00-Jan-00							xls96	HP	1381
bayouwq	WOF9605	11-Jun-96	31616	2200		11391	00-Jan-00							xls96	HP	1382
bayouwq	WOL9612	11-Jun-96	31616	7200		15824	00-Jan-00							xls96	HP	1388
bayouwq	WOK9605	11-Jun-96	31616	5800		15825	00-Jan-00							xls96	HP	1387
bayouwq	WOJ9605	11-Jun-96	31616	990		15826	00-Jan-00							xls96	HP	1385
bayouwq	WOA9609	11-Jun-96	31616	3600		15827	00-Jan-00							xls96	HP	1384
bayouwq	WOG9605	11-Jun-96	31616	1200			00-Jan-00							xls96	HP	1383
bayouwq	WOD9605	11-Jun-96	31616	1200			00-Jan-00							xls96	HP	1380
bayouwq	WOC9605	11-Jun-96	31616	2000			00-Jan-00							xls96		1379
bayouwq	WOB9605	11-Jun-96	31616	1000			00-Jan-00							xls96		1378
bayouwq	WOL9613	15-Jul-96	31616	3100			00-Jan-00							xls96		1633
bayouwq	WOE0606	17-Jul-96	31616	200000			00-Jan-00							xls96	HP	1699
bayouwq	WOE9606 WOF9606	17-Jul-96 17-Jul-96	31616 31616	200000			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	1694 1695
bayouwq	WOL9614	17-Jul-96 17-Jul-96	31616	100000			00-Jan-00			1				xls96 xls96	HP	1701
bayouwq	WOK9606	17-Jul-96 17-Jul-96	31616	110000			00-Jan-00							xls96	HP	1701
bayouwq bayouwq	WOK9606 WOJ9606	17-Jul-96 17-Jul-96	31616	200000			00-Jan-00							xls96	HP	1698
oayouwq	WOJ9606 WOA9611	17-Jul-96 17-Jul-96	31616	200000		15827				1			1	A107U		1697

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOG9606	17-Jul-96	31616	200000		15828	00-Jan-00							xls96	HP	1696
	WOD9606	17-Jul-96	31616	200000			00-Jan-00							xls96	HP	1693
	WOC9606	17-Jul-96	31616	200000			00-Jan-00							xls96	HP	1692
bayouwq	WOB9606	17-Jul-96	31616	200000			00-Jan-00							xls96	HP	1691
bayouwq	WOE9607	21-Jul-96	31616	780			00-Jan-00							xls96	HP	1893
	WOC9607	21-Jul-96	31616	900			00-Jan-00						DM.	xls96	HP	1891
	WOM9606	29-Jul-96	31616	5200			00-Jan-00						BM	xls96	HP	1862
	WOA9612	29-Jul-96	31616 31616	29000 5500			00-Jan-00						BM	xls96 xls96	HP HP	1863 1940
	WOL9615 WOE9608	31-Jul-96 09-Aug-96	31616	4100			00-Jan-00 00-Jan-00								HP	58
	WOF9607	09-Aug-96	31616	4000			00-Jan-00							bayou95 bayou95		59
	WOL9616	09-Aug-96	31616	1700			00-Jan-00							bayou95		64
	WOK9607	09-Aug-96	31616	4900			00-Jan-00							bayou95		63
	WOJ9607	09-Aug-96	31616	5700			00-Jan-00							bayou95		62
	WOA9613	09-Aug-96	31616	6800			00-Jan-00							bayou95		61
bayouwq	WOG9607	09-Aug-96	31616	5800			00-Jan-00							bayou95	HP	60
bayouwq	WOD9607	09-Aug-96	31616	680			00-Jan-00							bayou95		57
	WOL9617	13-Aug-96	31616	26000			00-Jan-00							xls96	HP	2045
	WOL9618	14-Aug-96	31616	8400		15824	00-Jan-00							bayou95	HP	114
	WOM9607	15-Aug-96	31616	2500		11385	00-Jan-00							xls96	HP	2074
	WOE9609	15-Aug-96	31616	2100		11390	00-Jan-00							xls96	HP	2070
bayouwq	WOF9608	15-Aug-96	31616	3300		11391	00-Jan-00							xls96	HP	2071
bayouwq	WOL9619	15-Aug-96	31616	5400		15824	00-Jan-00							xls96	HP	2076
bayouwq	WOK9608	15-Aug-96	31616	5400		15825	00-Jan-00							xls96	HP	2075
bayouwq	WOJ9608	15-Aug-96	31616	24000		15826	00-Jan-00							xls96	HP	2073
bayouwq	WOG9608	15-Aug-96	31616	3900		15828	00-Jan-00							xls96	HP	2072
bayouwq	WOG9609	15-Aug-96	31616	4200		15828	00-Jan-00						QC	xls96	HP	2066
bayouwq	WOD9608	15-Aug-96	31616	2200		15829	00-Jan-00							xls96	HP	2069
bayouwq	WOC9608	15-Aug-96	31616	2100		15830	00-Jan-00							xls96	HP	2068
bayouwq	WOB9607	15-Aug-96	31616	2700			00-Jan-00							xls96	HP	2067
	WOM9608	10-Sep-96	31616	26000			00-Jan-00							xls96	HP	2299
	WOE9610	10-Sep-96	31616	3200			00-Jan-00							xls96	HP	2295
	WOF9609	10-Sep-96	31616	5900			00-Jan-00						0.0	xls96	HP	2296
	WOF9610	10-Sep-96	31616	4400			00-Jan-00						QC	xls96	HP	2291
bayouwq	WOL9620	10-Sep-96	31616	2500			00-Jan-00							xls96	HP	2301
* *	WOK9609	10-Sep-96	31616	160			00-Jan-00							xls96	HP	2300
	WOJ9609	10-Sep-96	31616	370			00-Jan-00							xls96	HP	2298
* *	WOG9610	10-Sep-96	31616	150			00-Jan-00							xls96	HP	2297 2294
	WOD9609	10-Sep-96	31616	4300 4600			00-Jan-00 00-Jan-00							xls96	HP HP	2294
	WOC9609 WOB9608	10-Sep-96 10-Sep-96	31616 31616	5900			00-Jan-00 00-Jan-00							xls96 xls96	HP	2293
bayouwa	WOL9621	10-Sep-96 12-Sep-96	31616	200000			00-Jan-00 00-Jan-00			1				bayou95	HP	187
bayouwq bayouwq	WOE9611	13-Sep-96	31616	15000			00-Jan-00			1				bayou95	HP	207
	WOF9611	13-Sep-96	31616	32000			00-Jan-00			1				bayou95	HP	208
	WOL9622	13-Sep-96	31616	31000			00-Jan-00							bayou95		213
	WOK9610	13-Sep-96	31616	37000			00-Jan-00							bayou95		212
	WOJ9610	13-Sep-96	31616	54000			00-Jan-00							bayou95	HP	211
	WOA9614	13-Sep-96	31616	57000			00-Jan-00			1				bayou95		210
	WOG9611	13-Sep-96	31616	56000			00-Jan-00			1				bayou95		209
	WOD9610	13-Sep-96	31616	2800			00-Jan-00							bayou95		206
	WOC9610	13-Sep-96	31616	3200			00-Jan-00							bayou95		205
, ,	WOB9609	13-Sep-96	31616	41000			00-Jan-00							bayou95		204
	WOM9609	26-Sep-96	31616	3800			00-Jan-00						BM	bayou95		320
	WOA9615	26-Sep-96	31616	4000			00-Jan-00						BM	bayou95		321
	WOL9623	27-Sep-96	31616	11000			00-Jan-00							bayou95	HP	356
	WOL9624	07-Oct-96	31616	4800		15824	00-Jan-00							xls96		2472
	WOE9612	09-Oct-96	31616	9100		11390	00-Jan-00							bayou95	HP	492
	WOF9612	09-Oct-96	31616	6700		11391	00-Jan-00							bayou95	HP	493

Database	TAG	END DATE	STORET CODE	GT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	WOL9625	09-Oct-96	31616	4700		15824	00-Jan-00							bayou95	HP	498
bayouwq	WOK9611	09-Oct-96	31616	7600			00-Jan-00							bayou95	HP	497
bayouwq	WOJ9611	09-Oct-96	31616	4000			00-Jan-00							bayou95	HP	496
bayouwq	WOA9616	09-Oct-96	31616	3600			00-Jan-00							bayou95	HP	495
bayouwq	WOG9612	09-Oct-96	31616	5600 9700			00-Jan-00							bayou95	HP	494
bayouwq bayouwq	WOD9611 WOC9611	09-Oct-96	31616 31616	8400			00-Jan-00 00-Jan-00							bayou95 bayou95	HP HP	491 490
bayouwq	WOC9611 WOB9610	09-Oct-96	31616	3000			00-Jan-00							bayou95	HP	489
bayouwq	WOL9626	11-Oct-96	31616	9500			00-Jan-00							bayou95	HP	548
bayouwq	WOM9610	23-Oct-96	31616	1200			00-Jan-00						BM	bayou95	HP	132
bayouwq	WOA9617	23-Oct-96	31616	26000		15827	00-Jan-00						BM	bayou95	HP	133
bayouwq	WOM9611	28-Oct-96	31616	6000		11385	00-Jan-00							xls96	HP	2606
bayouwq	WOE9613	28-Oct-96	31616	26000		11390	00-Jan-00							xls96	HP	2602
bayouwq	WOF9613	28-Oct-96	31616	8600			00-Jan-00							xls96	HP	2603
bayouwq	WOF9614	28-Oct-96	31616	22000			00-Jan-00						QC	xls96	HP	2598
bayouwq	WOL9627	28-Oct-96	31616	42500			00-Jan-00							xls96	HP	2608
bayouwq	WOK9612	28-Oct-96	31616	58000			00-Jan-00							xls96 xls96	HP HP	2607 2605
bayouwq	WOJ9612 WOG9613	28-Oct-96 28-Oct-96	31616 31616	27000 25000			00-Jan-00 00-Jan-00							xls96	HP	2604
bayouwq bayouwq	WOD9613	28-Oct-96	31616	2800			00-Jan-00 00-Jan-00							xls96	HP	2601
bayouwq	WOC9612	28-Oct-96	31616	3400			00-Jan-00							xls96	HP	2600
bayouwq	WOB9611	28-Oct-96	31616	3600			00-Jan-00							xls96	HP	2599
bayouwq	WOM9612	30-Oct-96	31616	5300			00-Jan-00						BM	xls96	HP	2697
bayouwq	WOL9628	04-Nov-96	31616	5900			00-Jan-00							xls96	HP	2740
bayouwq	WOM9613	05-Nov-96	31616	5900		11385	00-Jan-00							xls96	HP	2769
bayouwq	WOE9614	05-Nov-96	31616	3400		11390	00-Jan-00							xls96	HP	2765
bayouwq	WOF9615	05-Nov-96	31616	2700		11391	00-Jan-00							xls96	HP	2766
bayouwq	WOL9629	05-Nov-96	31616	200000			00-Jan-00							xls96	HP	2771
bayouwq	WOK9613	05-Nov-96	31616	5500			00-Jan-00							xls96	HP	2770
bayouwq	WOJ9613	05-Nov-96	31616	3200			00-Jan-00							xls96	HP	2768
bayouwq	WOG9614	05-Nov-96	31616	2400			00-Jan-00						QC	xls96	HP	2761
bayouwq	WOG9615 WOD9613	05-Nov-96 05-Nov-96	31616 31616	3300 580			00-Jan-00							xls96 xls96	HP HP	2767 2764
bayouwq bayouwq	WOC9613	05-Nov-96	31616	720			00-Jan-00 00-Jan-00							xls96	HP	2763
bayouwq	WOB9612	05-Nov-96	31616	760			00-Jan-00							xls96	HP	2762
bayouwq	WOL9630	06-Nov-96	31616	59000			00-Jan-00							bayou95	HP	653
bayouwq	WOE9615	07-Nov-96	31616	3700			00-Jan-00							bayou95	HP	675
bayouwq	WOF9616	07-Nov-96	31616	5700			00-Jan-00							bayou95	HP	676
bayouwq	WOL9631	07-Nov-96	31616	100000		15824	00-Jan-00							bayou95	HP	681
bayouwq	WOK9614	07-Nov-96	31616	45000		15825	00-Jan-00							bayou95	HP	680
bayouwq	WOJ9614	07-Nov-96	31616	110000		15826	00-Jan-00							bayou95	HP	679
bayouwq	WOA9618	07-Nov-96	31616	7100			00-Jan-00							bayou95	HP	678
bayouwq	WOG9616	07-Nov-96	31616	7500			00-Jan-00							bayou95	HP	677
bayouwq	WOD9614	07-Nov-96	31616	3500			00-Jan-00							bayou95	HP	674
bayouwq	WOC9614	07-Nov-96	31616	3600			00-Jan-00							bayou95	HP	673
bayouwq	WOB9613	07-Nov-96 20-Nov-96	31616	59000			00-Jan-00						DM	bayou95	HP HP	672 2956
bayouwq bayouwq	WOM9614 WOE9616	05-Dec-96	31616 31616	5300			00-Jan-00 00-Jan-00						BM	xls96 bayou95	HP	942
	WOF9617	05-Dec-96	31616	4100			00-Jan-00 00-Jan-00							bayou95	+	943
	WOL9633	05-Dec-96	31616	5900			00-Jan-00							bayou95		919
	WOK9615	05-Dec-96	31616	5600			00-Jan-00							bayou95	HP	947
bayouwq	WOJ9615	05-Dec-96	31616	1300			00-Jan-00							bayou95		946
	WOA9620	05-Dec-96	31616	1100			00-Jan-00							bayou95	HP	945
bayouwq	WOG9617	05-Dec-96	31616	3200			00-Jan-00							bayou95	HP	944
bayouwq	WOD9615	05-Dec-96	31616	640			00-Jan-00							bayou95	HP	941
bayouwq	WOC9615	05-Dec-96	31616	780		15830	00-Jan-00							bayou95	HP	940
bayouwq	WOB9614	05-Dec-96	31616	980			00-Jan-00							bayou95	HP	939
bayouwq	WOL9634	10-Dec-96	31616	1900		15824	00-Jan-00							xls96	HP	3101

* *			CODE	LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	1	SOURCE 2	PROGRAM
1	VOM9615	11-Dec-96	31616	2200		11385	00-Jan-00							xls96	HP	3133
	VOE9617	11-Dec-96	31616	3700			00-Jan-00							xls96	HP	3129
	VOF9618	11-Dec-96	31616	2100			00-Jan-00							xls96	HP	3130
	VOL9635	11-Dec-96	31616	100000			00-Jan-00							xls96	HP	3135
	VOK9616 VOJ9616	11-Dec-96 11-Dec-96	31616 31616	4600 2500			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	3134 3132
	VOG9618	11-Dec-96	31616	2700			00-Jan-00 00-Jan-00							xls96	HP	3131
	VOG9619	11-Dec-96	31616	2000			00-Jan-00						OC	xls96	HP	3125
	VOD9616	11-Dec-96	31616	480			00-Jan-00						- Control of the cont	xls96		3128
	VOC9616	11-Dec-96	31616	540			00-Jan-00							xls96	HP	3127
	VOB9615	11-Dec-96	31616	640		15831	00-Jan-00							xls96	HP	3126
bayouwq W0	VOM9616	18-Dec-96	31616	70000		11385	00-Jan-00						BM	xls96	HP	3222
bayouwq BU	UA8701	05-Jan-87	31616	900		11351	00-Jan-00							pother1	HP	9758
	UO8701	05-Jan-87	31616	750			00-Jan-00							pother1	HP	9756
	UM8701	05-Jan-87	31616	20			00-Jan-00							pother1	HP	9753
	UJ8701	05-Jan-87	31616	20			00-Jan-00							pother1	HP	9750
	UH8701 UD8701	05-Jan-87 05-Jan-87	31616 31616	40 30			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	9748 9746
	UX8701	05-Jan-87	31616	30			00-Jan-00 00-Jan-00							pother1	HP	9740
	UW8701	05-Jan-87	31616	11200			00-Jan-00							pother1	HP	9764
	UU8701	05-Jan-87	31616	34000			00-Jan-00							pother1	HP	9762
	US8701	05-Jan-87	31616	28000		15843	00-Jan-00							pother1	HP	9761
	UL8701	05-Jan-87	31616	840		15846	00-Jan-00							pother1	HP	9752
bayouwq BU	UG8701	05-Jan-87	31616	20		15847	00-Jan-00							pother1	HP	9747
	UB9001	05-Jan-90	31616	600			00-Jan-00							pother1	HP	10439
	UE9001	05-Jan-90	31616	640			00-Jan-00							pother1	HP	10443
	UA9001	05-Jan-90	31616	3200			00-Jan-00							pother1	HP	10463
	UO9001	05-Jan-90	31616	1300			00-Jan-00							pother1	HP	10459 10455
	UM9001 UK9001	05-Jan-90 05-Jan-90	31616 31616	18 370			00-Jan-00 00-Jan-00							pother1	HP HP	10455
	UJ9001	05-Jan-90	31616	230			00-Jan-00							pother1 pother1	HP	10431
	UH9001	05-Jan-90	31616	9			00-Jan-00							pother1	HP	10447
	UD9001	05-Jan-90	31616	280			00-Jan-00							pother1	HP	10441
bayouwq BU	UX9001	05-Jan-90	31616	9		15840	00-Jan-00							pother1	HP	10475
bayouwq BU	UW9001	05-Jan-90	31616	3000		15841	00-Jan-00							pother1	HP	10471
	UU9001	05-Jan-90	31616	5400			00-Jan-00							pother1	HP	10469
	US9001	05-Jan-90	31616	2800			00-Jan-00							pother1	HP	10465
	UQ9001	05-Jan-90	31616	1200			00-Jan-00							pother1	HP	10461
	UN9001	05-Jan-90	31616	1300			00-Jan-00							pother1	HP	10457
	UL9001	05-Jan-90 05-Jan-90	31616	140 870			00-Jan-00 00-Jan-00							pother1	HP HP	10453 10445
	UG9001 UA8501	05-Jan-90 08-Jan-85	31616 31616	34000			00-Jan-00 00-Jan-00							pother1 pother1	HP	9310
	UO8501	08-Jan-85	31616	30000			00-Jan-00							pother1	HP	9308
	UM8501	08-Jan-85	31616	122000			00-Jan-00							pother1	HP	9305
	UK8501	08-Jan-85	31616	100			00-Jan-00							pother1	HP	9303
	UJ8501	08-Jan-85	31616	1		11360	00-Jan-00							pother1	HP	9302
bayouwq BU	UH8501	08-Jan-85	31616	1		11362	00-Jan-00							pother1	HP	9300
bayouwq BU	UX8501	08-Jan-85	31616	1		15840	00-Jan-00							pother1	HP	9319
	UW8501	08-Jan-85	31616	56300			00-Jan-00							pother1		9316
	UU8501	08-Jan-85	31616	56300			00-Jan-00							pother1		9314
	US8501	08-Jan-85	31616	37300			00-Jan-00							pother1		9313
	UB9002	12-Jan-90	31616	91			00-Jan-00							pother1	HP	10510
	UE9002 UA9002	12-Jan-90 12-Jan-90	31616 31616	550 4300			00-Jan-00 00-Jan-00							pother1	HP HP	10514 10534
	UO9002	12-Jan-90 12-Jan-90	31616	110			00-Jan-00 00-Jan-00							pother1	HP	10534
	UM9002	12-Jan-90	31616	9			00-Jan-00 00-Jan-00							pother1	HP	10526
	UK9002	12-Jan-90	31616	54			00-Jan-00							pother1	HP	10520
	UJ9002	12-Jan-90	31616	18			00-Jan-00							pother1		10520

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUH9002	12-Jan-90	31616	230		11362	00-Jan-00									pother1	HP	10518
bayouwq	BUD9002	12-Jan-90	31616	840			00-Jan-00									pother1	HP	10512
bayouwq	BUX9002	12-Jan-90	31616	140			00-Jan-00									pother1	HP	10546
bayouwq	BUW9002	12-Jan-90	31616	2700			00-Jan-00									pother1	HP	10542
bayouwq	BUU9002	12-Jan-90	31616	5900			00-Jan-00									pother1	HP	10540
bayouwq	BUS9002 BUQ9002	12-Jan-90 12-Jan-90	31616 31616	11000 5300			00-Jan-00 00-Jan-00									pother1 pother1	HP HP	10536 10532
bayouwq bayouwq	BUN9002	12-Jan-90	31616	150			00-Jan-00									pother1	HP	10532
bayouwq	BUL9002	12-Jan-90	31616	9			00-Jan-00									pother1	HP	10524
bayouwq	BUG9002	12-Jan-90	31616	150		1	00-Jan-00									pother1	HP	10516
bayouwq	BUE9101	14-Jan-91	31616	730			00-Jan-00									pother1	HP	1427
bayouwq	BUA9101	14-Jan-91	31616	2800			00-Jan-00									pother1	HP	1449
bayouwq	BUO9101	14-Jan-91	31616	4000		11354	00-Jan-00									pother1	HP	1443
bayouwq	BUM9101	14-Jan-91	31616	3900		11357	00-Jan-00									pother1	HP	1439
bayouwq	BUK9101	14-Jan-91	31616	3500		11359	00-Jan-00									pother1	HP	1435
bayouwq	BUJ9101	14-Jan-91	31616	3300		11360	00-Jan-00									pother1	HP	1433
bayouwq	BUH9101	14-Jan-91	31616	710		11362	00-Jan-00									pother1	HP	1431
bayouwq	BUD9101	14-Jan-91	31616	930		11364	00-Jan-00									pother1	HP	1425
bayouwq	BUW9101	14-Jan-91	31616	3500			00-Jan-00									pother1	HP	1457
bayouwq	BUU9101	14-Jan-91	31616	3900			00-Jan-00									pother1	HP	1455
bayouwq	BUS9101	14-Jan-91	31616	3100			00-Jan-00									pother1	HP	1451
bayouwq	BUQ9101	14-Jan-91	31616	4700			00-Jan-00									pother1	HP	1447
bayouwq	BUN9101	14-Jan-91	31616	4800		1	00-Jan-00									pother1	HP	1441
bayouwq	BUL9101	14-Jan-91	31616	2500			00-Jan-00									pother1	HP	1437
bayouwq	BUG9101	14-Jan-91	31616	400			00-Jan-00									pother1	HP	1429 2820
	BUB9501	17-Jan-95	31616	320			00-Jan-00									9495a 9495a	HP HP	2826
bayouwq	BUE9501 BUV9501	17-Jan-95 17-Jan-95	31616 31616	610 1000			00-Jan-00 00-Jan-00									9495a 9495a	HP	2856
bayouwq bayouwq	BUA9501	17-Jan-95	31616	760			00-Jan-00 00-Jan-00								BM	9495a 9495a	HP	2850
bayouwq	BUP9501	17-Jan-95	31616	590		1	00-Jan-00								Divi	9495a	HP	2848
bayouwq	BUJ9501	17-Jan-95	31616	610			00-Jan-00									9495a	HP	2836
bayouwq	BUI9501	17-Jan-95	31616	480			00-Jan-00									9495a	HP	2834
bayouwq	BUH9501	17-Jan-95	31616	560			00-Jan-00									9495a	HP	2832
bayouwq	BUF9501	17-Jan-95	31616	620		11363	00-Jan-00									9495a	HP	2828
bayouwq	BUD9501	17-Jan-95	31616	400		11364	00-Jan-00									9495a	HP	2824
bayouwq	BUW9501	17-Jan-95	31616	900		15841	00-Jan-00									9495a	HP	2858
bayouwq	BUS9501	17-Jan-95	31616	870		15843	00-Jan-00									9495a	HP	2852
bayouwq	BUN9501	17-Jan-95	31616	750			00-Jan-00									9495a	HP	2844
bayouwq	BUL9501	17-Jan-95	31616	560			00-Jan-00									9495a	HP	2840
bayouwq	BUV8301	19-Jan-83	31616	28000			00-Jan-00									pother1	HP	8901
bayouwq	BUA8301	19-Jan-83	31616	20000			00-Jan-00									pother1	HP	8896
bayouwq	BUM8301	19-Jan-83	31616	18000			00-Jan-00									pother1	HP	8891
bayouwq	BUJ8301	19-Jan-83	31616	2000		1	00-Jan-00									pother1		8888 8886
	BUH8301 BUX8301	19-Jan-83 19-Jan-83	31616 31616	5000 2000			00-Jan-00 00-Jan-00									pother1		8905
bayouwq bayouwq	BUW8301	19-Jan-83	31616	33000			00-Jan-00 00-Jan-00									pother1 pother1	HP	8903
bayouwq	BUS8301	19-Jan-83	31616	26000		1	00-Jan-00									pother1	HP	8899
bayouwq	BUO8301	19-Jan-83		13000			00-Jan-00									pother1	HP	8895
bayouwq	BUA8601	22-Jan-86	31616	3900			00-Jan-00									pother1	HP	9566
	BUO8601	22-Jan-86	31616	12900			00-Jan-00									pother1	HP	9564
	BUM8601	22-Jan-86	31616	53000			00-Jan-00									pother1		9561
-	BUK8601	22-Jan-86	31616	40			00-Jan-00									pother1		9559
	BUJ8601	22-Jan-86	31616	410		11360	00-Jan-00									pother1	HP	9558
bayouwq	BUH8601	22-Jan-86	31616	1		11362	00-Jan-00									pother1	HP	9556
bayouwq	BUX8601	22-Jan-86	31616	10			00-Jan-00									pother1	HP	9575
• •	BUW8601	22-Jan-86	31616	1070			00-Jan-00									pother1	HP	9572
bayouwq	BUU8601	22-Jan-86		1610			00-Jan-00									pother1		9570
bayouwq	BUS8601	22-Jan-86	31616	3000		15843	00-Jan-00			<u> </u>						pother1	HP	9569

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUL8601	22-Jan-86	31616	290		15846	00-Jan-00							pother1	HP	9560
bayouwq	BUB9003	22-Jan-90	31616	680			00-Jan-00							pother1	HP	10581
bayouwq	BUE9003	22-Jan-90	31616	530			00-Jan-00							pother1	HP	10585
bayouwq	BUA9003	22-Jan-90	31616	850			00-Jan-00							pother1	HP	10605
bayouwq	BUO9003	22-Jan-90	31616	190			00-Jan-00							pother1	HP	10601
bayouwq	BUM9003	22-Jan-90	31616	9			00-Jan-00							pother1	HP	10597
bayouwq	BUK9003	22-Jan-90	31616	290			00-Jan-00							pother1	HP	10593
bayouwq	BUJ9003 BUH9003	22-Jan-90 22-Jan-90	31616 31616	27 54			00-Jan-00							pother1	HP HP	10591 10589
	BUD9003	22-Jan-90 22-Jan-90	31616	1600			00-Jan-00 00-Jan-00							pother1	HP	10589
bayouwq bayouwq	BUX9003	22-Jan-90 22-Jan-90	31616	480			00-Jan-00 00-Jan-00							pother1	HP	10617
bayouwq	BUW9003	22-Jan-90	31616	4900			00-Jan-00							pother1	HP	10613
bayouwq	BUU9003	22-Jan-90	31616	7000			00-Jan-00							pother1	HP	10611
bayouwq	BUS9003	22-Jan-90	31616	9300			00-Jan-00							pother1	HP	10607
	BUQ9003	22-Jan-90	31616	730			00-Jan-00							pother1	HP	10603
bayouwq	BUN9003	22-Jan-90	31616	1100			00-Jan-00							pother1	HP	10599
bayouwq	BUL9003	22-Jan-90	31616	72			00-Jan-00							pother1	HP	10595
bayouwq	BUG9003	22-Jan-90	31616	410			00-Jan-00							pother1	HP	10587
bayouwq	BUB9601	23-Jan-96	31616	2500		11142	00-Jan-00							xls96	HP	14
bayouwq	BUE9601	23-Jan-96	31616	2000		11163	00-Jan-00							xls96	HP	16
	BUV9601	23-Jan-96	31616	2500		11345	00-Jan-00							xls96	HP	31
bayouwq	BUA9601	23-Jan-96	31616	5700	BM	11351	00-Jan-00						BM	xls96	HP	28
bayouwq	BUP9601	23-Jan-96	31616	320		11353	00-Jan-00							xls96	HP	26
bayouwq	BUO9601	23-Jan-96	31616	1800		11354	00-Jan-00							xls96	HP	25
bayouwq	BUM9601	23-Jan-96	31616	2800		11357	00-Jan-00							xls96	HP	23
bayouwq	BUK9601	23-Jan-96	31616	490		11359	00-Jan-00							xls96	HP	21
bayouwq	BUJ9601	23-Jan-96	31616	550		11360	00-Jan-00							xls96	HP	20
bayouwq	BUI9601	23-Jan-96	31616	730		11361	00-Jan-00							xls96		19
bayouwq	BUH9601	23-Jan-96	31616	4400		11362	00-Jan-00							xls96	HP	18
bayouwq	BUF9601	23-Jan-96	31616	290			00-Jan-00							xls96		17
bayouwq	BUD9601	23-Jan-96	31616	210			00-Jan-00							xls96		15
bayouwq	BUX9601	23-Jan-96	31616	2700			00-Jan-00							xls96	_	32
bayouwq	BUS9601	23-Jan-96	31616	7500			00-Jan-00							xls96		29
	BUQ9601	23-Jan-96	31616	280			00-Jan-00							xls96	-	27
bayouwq	BUN9601	23-Jan-96	31616	3500			00-Jan-00							xls96		24
bayouwq	BUL9601	23-Jan-96	31616	590			00-Jan-00						DM	xls96	HP	22
bayouwq	BUA9602	25-Jan-96	31616	3400	BM		00-Jan-00						BM	xls96	-	53
bayouwq	BUB9004	29-Jan-90	31616	6200 3400			00-Jan-00							pother1	HP	10652
bayouwq	BUE9004	29-Jan-90	31616				00-Jan-00							pother1	HP HP	10656
	BUA9004 BUO9004	29-Jan-90 29-Jan-90	31616 31616	18500 3500			00-Jan-00 00-Jan-00							pother1	HP	10676 10672
bayouwq	BUM9004	29-Jan-90 29-Jan-90	31616	940			00-Jan-00 00-Jan-00							pother1 pother1	HP	10672
bayouwq bayouwq	BUK9004	29-Jan-90 29-Jan-90	31616	110			00-Jan-00 00-Jan-00							pother1	HP	10664
bayouwq	BUJ9004	29-Jan-90	31616	2100			00-Jan-00 00-Jan-00							pother1	HP	10662
bayouwq	BUH9004	29-Jan-90	31616	3400			00-Jan-00							pother1	HP	10660
bayouwq	BUD9004	29-Jan-90	31616	4300			00-Jan-00							pother1	HP	10654
bayouwq	BUX9004	29-Jan-90	31616	9			00-Jan-00							pother1	HP	10688
	BUW9004	29-Jan-90	31616	11000			00-Jan-00							pother1	HP	10684
, ,	BUU9004	29-Jan-90	31616	20000			00-Jan-00							pother1	+	10682
	BUS9004	29-Jan-90	31616	15000			00-Jan-00							pother1	HP	10678
	BUQ9004	29-Jan-90	31616	22000			00-Jan-00							pother1	HP	10674
	BUN9004	29-Jan-90	31616	2700			00-Jan-00							pother1	HP	10670
	BUL9004	29-Jan-90	31616	350			00-Jan-00							pother1	HP	10666
bayouwq	BUG9004	29-Jan-90	31616	200			00-Jan-00							pother1	HP	10658
	BUE9502	30-Jan-95	31616	560			00-Jan-00							9495a	HP	2893
	BUA9502	30-Jan-95	31616		BM		00-Jan-00						BM	9495a	HP	2919
	BUP9502	30-Jan-95	31616	540		11353	00-Jan-00							9495a	HP	2915
bayouwq	BUO9501	30-Jan-95	31616	360		11354	00-Jan-00							9495a	HP	2913

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUM9501	30-Jan-95	31616	340		11357	00-Jan-00									9495a	HP	2909
	BUK9501	30-Jan-95	31616	360			00-Jan-00									9495a	HP	2905
	BUJ9502	30-Jan-95	31616	340	-		00-Jan-00									9495a	HP	2903
	BUI9502	30-Jan-95	31616	380			00-Jan-00									9495a	HP	2901
	BUH9502 BUF9502	30-Jan-95 30-Jan-95	31616 31616	280 290			00-Jan-00 00-Jan-00									9495a 9495a	HP HP	2899 2895
	BUD9502	30-Jan-95	31616	270			00-Jan-00									9495a 9495a	HP	2891
bayouwq	BUX9501	30-Jan-95	31616	1400			00-Jan-00									9495a	HP	2929
	BUW9502	30-Jan-95	31616	2900			00-Jan-00									9495a	HP	2927
	BUS9502	30-Jan-95	31616	630			00-Jan-00									9495a	HP	2921
	BUQ9501	30-Jan-95	31616	530		15844	00-Jan-00									9495a	HP	2917
bayouwq	BUN9502	30-Jan-95	31616	440		15845	00-Jan-00									9495a	HP	2911
bayouwq	BUL9502	30-Jan-95	31616	400		15846	00-Jan-00									9495a	HP	2907
	BUG9501	30-Jan-95	31616	160			00-Jan-00									9495a	HP	2897
	BUV8401	31-Jan-84	31616	20000			00-Jan-00									pother1	HP	9123
	BUA8401	31-Jan-84	31616	8000			00-Jan-00									pother1	HP	9118
	BUO8401	31-Jan-84	31616	43000	-		00-Jan-00									pother1	HP	9116
	BUM8401	31-Jan-84	31616	1000			00-Jan-00									pother1	HP	9113
. * *	BUJ8401 BUH8401	31-Jan-84 31-Jan-84	31616 31616	2000			00-Jan-00 00-Jan-00									pother1 pother1	HP HP	9110 9108
bayouwq bayouwq	BUX8401	31-Jan-84	31616	1			00-Jan-00									pother1	HP	9108
bayouwq	BUS8401	31-Jan-84	31616	16000			00-Jan-00									pother1	HP	9121
bayouwq	BUB8902	02-Feb-89	31616	680			00-Jan-00									pother1	HP	10061
	BUA8902	02-Feb-89	31616	9800			00-Jan-00									pother1	HP	10069
	BUO8902	02-Feb-89	31616	740		11354	00-Jan-00									pother1	HP	10068
	BUM8902	02-Feb-89	31616	90		11357	00-Jan-00									pother1	HP	10067
bayouwq	BUJ8902	02-Feb-89	31616	10		11360	00-Jan-00									pother1	HP	10065
bayouwq	BUH8902	02-Feb-89	31616	110		11362	00-Jan-00									pother1	HP	10064
bayouwq	BUD8902	02-Feb-89	31616	540		11364	00-Jan-00									pother1	HP	10062
	BUX8902	02-Feb-89	31616	2900			00-Jan-00									pother1	HP	10074
. * *	BUU8902	02-Feb-89	31616	41000			00-Jan-00									pother1	HP	10072
	BUS8902	02-Feb-89	31616	23000			00-Jan-00									pother1	HP	10070
	BUL8902 BUG8902	02-Feb-89 02-Feb-89	31616 31616	1400			00-Jan-00									pother1	HP HP	10066 10063
	BUG8902 BUA9401	02-Feb-89 02-Feb-94	31616	3700			00-Jan-00 00-Jan-00								BM	pother1 9495a	HP	32
	BUA9503	02-Feb-94 02-Feb-95	31616		BM		00-Jan-00								BM	9495a 9495a	HP	2970
	BUE9602	05-Feb-96	31616	140			00-Jan-00								DIVI	xls96	HP	84
	BUV9602	05-Feb-96	31616	7500			00-Jan-00									xls96	HP	98
	BUA9603	05-Feb-96	31616	1100	-		00-Jan-00								QC	xls96	HP	82
	BUP9602	05-Feb-96	31616	2500	-		00-Jan-00									xls96	HP	93
bayouwq	BUO9602	05-Feb-96	31616	2100		11354	00-Jan-00									xls96	HP	92
bayouwq	BUM9602	05-Feb-96	31616	1800		11357	00-Jan-00									xls96	HP	90
bayouwq	BUK9602	05-Feb-96	31616	3700		11359	00-Jan-00									xls96	HP	88
bayouwq	BUJ9602	05-Feb-96	31616	1900		11360	00-Jan-00									xls96	HP	87
bayouwq	BUI9602	05-Feb-96	31616	1800	-		00-Jan-00									xls96	HP	86
bayouwq	BUH9602	05-Feb-96	31616	360			00-Jan-00									xls96	HP	85
bayouwq	BUD9602	05-Feb-96	31616	250			00-Jan-00									xls96	HP	83
<u> </u>	BUX9602	05-Feb-96	31616	420			00-Jan-00									xls96	HP	99
	BUS9602 BUQ9602	05-Feb-96 05-Feb-96	31616 31616	950 490			00-Jan-00 00-Jan-00									xls96 xls96	HP HP	96 94
	BUN9602	05-Feb-96	31616	2600			00-Jan-00 00-Jan-00									xls96	HP	91
	BUL9602	05-Feb-96	31616	2700	-		00-Jan-00									xls96	HP	89
	BUB9005	06-Feb-90	31616	1300			00-Jan-00									pother1	HP	10723
	BUE9005	06-Feb-90	31616	670	-		00-Jan-00									pother1	HP	10727
	BUA9005	06-Feb-90	31616	4600	-		00-Jan-00									pother1	HP	10747
	BUO9005	06-Feb-90	31616	150			00-Jan-00									pother1	HP	10743
	BUM9005	06-Feb-90	31616	9			00-Jan-00									pother1	HP	10739
bayouwq	BUH9005	06-Feb-90	31616	560		11362	00-Jan-00									pother1	HP	10731

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUD9005	06-Feb-90	31616	4500		11364	00-Jan-00							pother1	HP	10725
bayouwq	BUX9005	06-Feb-90	31616	99			00-Jan-00							pother1	HP	10759
bayouwq	BUW9005	06-Feb-90	31616	12000			00-Jan-00							pother1	HP	10755
bayouwq	BUU9005	06-Feb-90	31616	15000			00-Jan-00							pother1	HP	10753
bayouwq	BUS9005	06-Feb-90	31616	9900			00-Jan-00							pother1	HP	10749 10745
bayouwq bayouwq	BUQ9005 BUN9005	06-Feb-90 06-Feb-90	31616 31616	4600 600			00-Jan-00 00-Jan-00							pother1	HP HP	10743
bayouwq	BUG9005	06-Feb-90	31616	640			00-Jan-00							pother1	HP	10729
bayouwq	BUE9503	07-Feb-95	31616	220			00-Jan-00							9495a	HP	3054
bayouwq	BUV9502	07-Feb-95	31616	3300			00-Jan-00							9495a	HP	3086
bayouwq	BUA9504	07-Feb-95	31616	560	BM	11351	00-Jan-00						BM	9495a	HP	3080
bayouwq	BUP9503	07-Feb-95	31616	320		11353	00-Jan-00							9495a	HP	3076
bayouwq	BUO9502	07-Feb-95	31616	580		11354	00-Jan-00							9495a	HP	3074
bayouwq	BUM9502	07-Feb-95	31616	480			00-Jan-00							9495a	HP	3070
bayouwq	BUK9502	07-Feb-95	31616	1100			00-Jan-00							9495a	HP	3066
bayouwq	BUJ9503	07-Feb-95	31616	920			00-Jan-00							9495a	HP	3064
bayouwq	BUI9503	07-Feb-95	31616	1300			00-Jan-00							9495a 9495a	HP HP	3062 3060
bayouwq	BUH9503 BUF9503	07-Feb-95 07-Feb-95	31616 31616	2000 180			00-Jan-00 00-Jan-00							9495a 9495a	HP	3056
bayouwq bayouwq	BUD9503	07-Feb-95	31616	280			00-Jan-00							9495a 9495a	HP	3052
bayouwq	BUW9503	07-Feb-95	31616	1100			00-Jan-00							9495a	HP	3088
bayouwq	BUS9503	07-Feb-95	31616	3600			00-Jan-00							9495a	HP	3082
bayouwq	BUQ9502	07-Feb-95	31616	4000			00-Jan-00							9495a	HP	3078
bayouwq	BUN9503	07-Feb-95	31616	1100		15845	00-Jan-00							9495a	HP	3072
bayouwq	BUL9503	07-Feb-95	31616	710		15846	00-Jan-00							9495a	HP	3068
bayouwq	BUG9502	07-Feb-95	31616	120			00-Jan-00							9495a	HP	3058
bayouwq	BUA9402	08-Feb-94	31616	3100			00-Jan-00							9495a	HP	184
bayouwq	BUA9505	08-Feb-95	31616	25000	BM		00-Jan-00						BM	9495a	HP	3015
bayouwq	BUV9603	08-Feb-96	31616	2600			00-Jan-00							xls96	HP	129
bayouwq bayouwq	BUA9102 BUO9102	13-Feb-91 13-Feb-91	31616 31616	3000 550			00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	581 575
bayouwq	BUK9102	13-Feb-91	31616	200			00-Jan-00							pbayou	HP	567
bayouwq	BUJ9102	13-Feb-91	31616	240			00-Jan-00							pbayou	HP	565
bayouwq	BUH9102	13-Feb-91	31616	63			00-Jan-00							pbayou	HP	563
bayouwq	BUD9102	13-Feb-91	31616	27		11364	00-Jan-00							pbayou	HP	557
bayouwq	BUW9102	13-Feb-91	31616	3200		15841	00-Jan-00							pbayou	HP	589
bayouwq	BUS9102	13-Feb-91	31616	4500		15843	00-Jan-00							pbayou	HP	583
bayouwq	BUN9102	13-Feb-91	31616	300			00-Jan-00							pbayou	HP	573
bayouwq	BUL9102	13-Feb-91	31616	180			00-Jan-00							pbayou	HP	569
bayouwq	BUB9006	15-Feb-90	31616	2300			00-Jan-00							pother1	HP	10794
bayouwq	BUE9006	15-Feb-90	31616	880			00-Jan-00							pother l	HP	10798
bayouwq bayouwq	BUA9006 BUO9006	15-Feb-90 15-Feb-90	31616 31616	9850 140000			00-Jan-00 00-Jan-00							pother1	HP HP	10818 10814
bayouwq	BUM9006	15-Feb-90	31616	240			00-Jan-00							pother1	HP	10810
bayouwq	BUK9005	15-Feb-90	31616	2100			00-Jan-00							pother1	HP	10806
bayouwq	BUJ9005	15-Feb-90	31616	57000			00-Jan-00							pother1	HP	10804
bayouwq	BUH9006	15-Feb-90	31616	2300			00-Jan-00							pother1	HP	10802
bayouwq	BUD9006	15-Feb-90	31616	1500		11364	00-Jan-00							pother1	HP	10796
bayouwq	BUX9006	15-Feb-90	31616	800			00-Jan-00							pother1	HP	10830
bayouwq	BUW9006	15-Feb-90	31616	7200			00-Jan-00							pother1	HP	10826
bayouwq	BUU9006	15-Feb-90	31616	29000			00-Jan-00							pother1	HP	10824
bayouwq	BUS9006	15-Feb-90	31616	23000			00-Jan-00							pother1	HP	10820
bayouwq	BUQ9006	15-Feb-90	31616	11000			00-Jan-00							pother1	HP	10816
bayouwq	BUN9006 BUL9005	15-Feb-90 15-Feb-90	31616 31616	20000 52000			00-Jan-00 00-Jan-00			1				pother1	HP HP	10812 10808
bayouwq bayouwq	BUG9006	15-Feb-90 15-Feb-90	31616	14000			00-Jan-00 00-Jan-00							pother1	HP	10808
bayouwq	BUA9103	18-Feb-91	31616	9400			00-Jan-00							pbayou	HP	654
bayouwq	BUO9103	18-Feb-91	31616	400			00-Jan-00							pbayou	HP	648
oayouwq	D007103	10-1-00-91	31010	400	l	11334	00-jan-00	1 1		1		1	l .	Poayou	1	0-10

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUJ9103	18-Feb-91	31616	18		11360	00-Jan-00									pbayou	HP	638
bayouwq	BUH9103	18-Feb-91	31616	36			00-Jan-00									pbayou	HP	636
bayouwq	BUW9103	18-Feb-91	31616	2000			00-Jan-00									pbayou	HP	662
bayouwq	BUS9103	18-Feb-91	31616	5300			00-Jan-00									pbayou	HP	656
bayouwq	BUN9103 BUL9103	18-Feb-91 18-Feb-91	31616 31616	220 63			00-Jan-00 00-Jan-00									pbayou	HP HP	646 642
bayouwq bayouwq	BUB9007	23-Feb-90	31616	14000			00-Jan-00 00-Jan-00									pbayou pother1	HP	10865
bayouwq	BUE9007	23-Feb-90	31616	10000			00-Jan-00									pother1	HP	10869
bayouwq	BUA9007	23-Feb-90	31616	6000			00-Jan-00									pother1	HP	10889
bayouwq	BUO9007	23-Feb-90	31616	6900			00-Jan-00									pother1	HP	10885
bayouwq	BUM9007	23-Feb-90	31616	8400		11357	00-Jan-00									pother1	HP	10881
bayouwq	BUK9006	23-Feb-90	31616	5700		11359	00-Jan-00									pother1	HP	10877
bayouwq	BUJ9006	23-Feb-90	31616	5400		11360	00-Jan-00									pother1	HP	10875
bayouwq	BUH9007	23-Feb-90	31616	8500		11362	00-Jan-00									pother1	HP	10873
bayouwq	BUD9007	23-Feb-90	31616	9100			00-Jan-00									pother1	HP	10867
bayouwq	BUX9007	23-Feb-90	31616	4300			00-Jan-00									pother1	HP	10901
bayouwq	BUW9007	23-Feb-90	31616	8300			00-Jan-00									pother1	HP	10897
bayouwq	BUU9007	23-Feb-90	31616	4900		+	00-Jan-00									pother1	HP	10895
bayouwq	BUS9007	23-Feb-90	31616	7400			00-Jan-00									pother1	HP	10891
bayouwq	BUQ9007	23-Feb-90	31616	5400			00-Jan-00									pother1	HP	10887
bayouwq	BUN9007	23-Feb-90	31616	5300			00-Jan-00									pother1	HP	10883
bayouwq	BUL9006 BUG9007	23-Feb-90 23-Feb-90	31616 31616	5900 3400			00-Jan-00 00-Jan-00									pother1 pother1	HP HP	10879 10871
bayouwq	BUA8602	23-Feb-90 24-Feb-86	31616	5200			00-Jan-00 00-Jan-00									pother1	HP	9598
bayouwq bayouwq	BUO8602	24-Feb-86	31616	17600			00-Jan-00									pother1	HP	9596
bayouwq	BUM8602	24-Feb-86	31616	11300			00-Jan-00									pother1	HP	9593
bayouwq	BUJ8602	24-Feb-86	31616	10			00-Jan-00									pother1	HP	9590
bayouwq	BUH8602	24-Feb-86	31616	80			00-Jan-00									pother1	HP	9588
bayouwq	BUD8601	24-Feb-86	31616	50			00-Jan-00									pother1	HP	9586
bayouwq	BUX8602	24-Feb-86	31616	90		15840	00-Jan-00									pother1	HP	9607
bayouwq	BUW8602	24-Feb-86	31616	1200		15841	00-Jan-00									pother1	HP	9604
bayouwq	BUU8602	24-Feb-86	31616	5000		15842	00-Jan-00									pother1	HP	9602
bayouwq	BUS8602	24-Feb-86	31616	7000		15843	00-Jan-00									pother1	HP	9601
bayouwq	BUL8602	24-Feb-86	31616	30			00-Jan-00									pother1	HP	9592
bayouwq	BUA9104	25-Feb-91	31616	25000			00-Jan-00									pbayou	HP	727
bayouwq	BUO9104	25-Feb-91	31616	1800			00-Jan-00									pbayou	HP	721
bayouwq	BUJ9104	25-Feb-91	31616	1200			00-Jan-00									pbayou		711
bayouwq	BUH9104	25-Feb-91	31616	2700			00-Jan-00									pbayou	HP	709
bayouwq	BUD9103 BUW9104	25-Feb-91 25-Feb-91	31616 31616	680 7600			00-Jan-00 00-Jan-00									pbayou	HP HP	703 735
bayouwq	BUS9104	25-Feb-91 25-Feb-91	31616	12000		+	00-Jan-00 00-Jan-00									pbayou	HP	729
bayouwq bayouwq	BUN9104	25-Feb-91	31616	2600			00-Jan-00 00-Jan-00									pbayou pbayou	HP	719
bayouwq	BUL9104	25-Feb-91	31616	2500			00-Jan-00									pbayou		715
bayouwq	BUA9604	26-Feb-96	31616	4700		+	00-Jan-00								BM	xls96	HP	287
bayouwq	BUV8402	28-Feb-84	31616	500			00-Jan-00									pother1		9155
bayouwq	BUA8402	28-Feb-84	31616	40500			00-Jan-00									pother1	HP	9150
bayouwq	BUO8402	28-Feb-84	31616	12000		11354	00-Jan-00									pother1	HP	9148
bayouwq	BUM8402	28-Feb-84	31616	1500		11357	00-Jan-00									pother1	HP	9145
bayouwq	BUJ8402	28-Feb-84	31616	500		11360	00-Jan-00									pother1	HP	9142
bayouwq	BUH8402	28-Feb-84	31616	4000		11362	00-Jan-00									pother1	HP	9140
bayouwq	BUX8402	28-Feb-84	31616	1			00-Jan-00									pother1	HP	9159
bayouwq	BUW8401	28-Feb-84	31616	1			00-Jan-00									pother1	HP	9156
bayouwq	BUU8401	28-Feb-84	31616	8000			00-Jan-00									pother1	HP	9154
bayouwq	BUS8402	28-Feb-84	31616	26000			00-Jan-00									pother1	HP	9153
bayouwq	BUN8401	28-Feb-84	31616	1500			00-Jan-00									pother1	HP	9146
bayouwq	BUA8502	28-Feb-85	31616	16600			00-Jan-00									pother1	HP	9342
	BUM8502	28-Feb-85		8000			00-Jan-00									pother1	HP	9337
bayouwq	BUK8502	28-Feb-85	31616	1110		11359	00-Jan-00	1		L		<u> </u>	l			pother1	HP	9335

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUJ8502	28-Feb-85	31616	1400		11360	00-Jan-00									pother1	HP	9334
	BUH8502	28-Feb-85	31616	18000		11362	00-Jan-00									pother1	HP	9332
* *	BUX8502	28-Feb-85	31616	14100			00-Jan-00									pother1	HP	9351
-	BUW8502	28-Feb-85	31616	18000			00-Jan-00									pother1	HP	9348
*	BUU8502	28-Feb-85	31616	17600			00-Jan-00									pother1	HP	9346
. * *	BUS8502	28-Feb-85	31616	13300			00-Jan-00									pother1	HP	9345
	BUN8501	28-Feb-85	31616	13000			00-Jan-00									pother1	HP	9338
	BUL8501	28-Feb-85	31616	8000			00-Jan-00									pother1	HP	9336
	BUB9008	28-Feb-90	31616	400			00-Jan-00									pother1	HP	10936
	BUE9008 BUA9008	28-Feb-90 28-Feb-90	31616 31616	1200 2000			00-Jan-00 00-Jan-00									pother1	HP HP	10940 10960
	BUO9008	28-Feb-90	31616	1400			00-Jan-00 00-Jan-00									pother l	HP	10966
-	BUM9008	28-Feb-90	31616	1100			00-Jan-00									pother1	HP	10950
	BUK9007	28-Feb-90	31616	340			00-Jan-00									pother1	HP	10932
* *	BUJ9007	28-Feb-90	31616	340			00-Jan-00									pother1	HP	10946
-	BUH9008	28-Feb-90	31616	700			00-Jan-00									pother1	HP	10944
	BUD9008	28-Feb-90	31616	680			00-Jan-00									pother1	HP	10938
* *	BUX9008	28-Feb-90	31616	770			00-Jan-00									pother1	HP	10972
-	BUW9008	28-Feb-90	31616	30000			00-Jan-00									pother1	HP	10968
	BUU9008	28-Feb-90	31616	5000			00-Jan-00									pother1	HP	10966
bayouwq	BUS9008	28-Feb-90	31616	1100			00-Jan-00									pother1	HP	10962
bayouwq	BUQ9008	28-Feb-90	31616	1600		15844	00-Jan-00									pother1	HP	10958
bayouwq	BUN9008	28-Feb-90	31616	3400			00-Jan-00									pother1	HP	10954
	BUL9007	28-Feb-90	31616	300		15846	00-Jan-00									pother1	HP	10950
bayouwq	BUG9008	28-Feb-90	31616	730		15847	00-Jan-00									pother1	HP	10942
bayouwq	BUC9401	03-Mar-94	31616	230		11142	00-Jan-00									9495a	HP	478
bayouwq	BUV9401	03-Mar-94	31616	990		11345	00-Jan-00									9495a	HP	512
bayouwq	BUA9403	03-Mar-94	31616	1000		11351	00-Jan-00									9495a	HP	504
bayouwq	BUP9401	03-Mar-94	31616	340		11353	00-Jan-00									9495a	HP	500
bayouwq	BUO9401	03-Mar-94	31616	260		11354	00-Jan-00									9495a	HP	498
* *	BUM9401	03-Mar-94	31616	190			00-Jan-00									9495a	HP	494
-	BUK9401	03-Mar-94	31616	110			00-Jan-00									9495a	HP	490
	BUX9401	03-Mar-94	31616	3000			00-Jan-00									9495a	HP	516
-	BUW9401	03-Mar-94	31616	1100			00-Jan-00									9495a	HP	514
	BUU9401	03-Mar-94	31616	14000			00-Jan-00									9495a	HP	510
	BUS9401	03-Mar-94	31616	770			00-Jan-00									9495a	HP	506
	BUQ9401	03-Mar-94	31616	940			00-Jan-00									9495a	HP	502
	BUN9401	03-Mar-94	31616	280			00-Jan-00									9495a	HP	496
. * *	BUL9401	03-Mar-94	31616	220			00-Jan-00									9495a	HP	492
	BUG9401	03-Mar-94	31616	370			00-Jan-00									9495a	HP	484
*	BUB9101 BUE9102	04-Mar-91 04-Mar-91	31616 31616	450 550			00-Jan-00 00-Jan-00									pbayou	HP HP	1134 1138
	BUA9105	04-Mar-91	31616	7000			00-Jan-00 00-Jan-00									pbayou pbayou	HP	1160
	BUO9105	04-Mar-91	31616	2400			00-Jan-00									pbayou	HP	1154
	BUM9102	04-Mar-91	31616	940			00-Jan-00									pbayou	HP	1150
bayouwq	BUK9103	04-Mar-91	31616	1300			00-Jan-00									pbayou	HP	1146
bayouwq	BUJ9105	04-Mar-91	31616	530			00-Jan-00									pbayou	HP	1144
	BUH9105	04-Mar-91	31616	620			00-Jan-00									pbayou	HP	1142
	BUD9104	04-Mar-91	31616	330			00-Jan-00									pbayou	HP	1136
	BUW9105	04-Mar-91	31616	3100			00-Jan-00									pbayou	HP	1168
	BUS9105	04-Mar-91	31616	4200			00-Jan-00									pbayou	HP	1162
-	BUQ9102	04-Mar-91	31616	7000			00-Jan-00									pbayou	HP	1158
	BUN9105	04-Mar-91	31616	9000			00-Jan-00									pbayou	HP	1152
* *	BUL9105	04-Mar-91	31616	880			00-Jan-00									pbayou	HP	1148
	BUG9102	04-Mar-91	31616	260			00-Jan-00									pbayou	HP	1140
	BUE9603	04-Mar-96	31616	210			00-Jan-00									xls96	HP	348
* *	BUV9604	04-Mar-96	31616	1500			00-Jan-00									xls96	HP	362
	BUA9605	04-Mar-96	31616	1100	BM	11351	00-Jan-00								BM	xls96	HP	359

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUP9603	04-Mar-96	31616	930		11353	00-Jan-00							xls96	HP	357
bayouwq	BUO9603	04-Mar-96	31616	560			00-Jan-00							xls96	HP	356
bayouwq	BUM9603	04-Mar-96	31616	1000			00-Jan-00							xls96	HP	355
bayouwq	BUK9603	04-Mar-96	31616	2800			00-Jan-00							xls96	HP	353
bayouwq	BUJ9603	04-Mar-96	31616	2300			00-Jan-00							xls96	HP HP	352
bayouwq bayouwq	BUI9603 BUH9603	04-Mar-96 04-Mar-96	31616 31616	860 430			00-Jan-00 00-Jan-00							xls96 xls96	HP	365 351
bayouwq	BUF9602	04-Mar-96	31616	250			00-Jan-00							xls96	HP	349
bayouwq	BUD9603	04-Mar-96	31616	470			00-Jan-00							xls96		347
bayouwq	BUX9603	04-Mar-96	31616	34000			00-Jan-00							xls96	HP	364
bayouwq	BUW9601	04-Mar-96	31616	2100		15841	00-Jan-00							xls96	HP	363
bayouwq	BUS9603	04-Mar-96	31616	3600		15843	00-Jan-00							xls96	HP	360
bayouwq	BUQ9603	04-Mar-96	31616	840		15844	00-Jan-00							xls96	HP	358
bayouwq	BUN9603	04-Mar-96	31616	1100		15845	00-Jan-00							xls96	HP	366
bayouwq	BUL9603	04-Mar-96	31616	2000			00-Jan-00							xls96		354
bayouwq	BUG9601	04-Mar-96	31616	310			00-Jan-00							xls96	HP	350
bayouwq	BUB8903	06-Mar-89	31616	210 4900			00-Jan-00							pother l	HP	10084 10094
bayouwq	BUA8903 BUP8901	06-Mar-89 06-Mar-89	31616 31616	9900			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	10094
bayouwq bayouwq	BUM8903	06-Mar-89	31616	10			00-Jan-00 00-Jan-00							pother1	HP	10092
bayouwq	BUJ8903	06-Mar-89	31616	9			00-Jan-00							pother1	HP	10088
bayouwq	BUH8903	06-Mar-89	31616	780			00-Jan-00							pother1	HP	10087
bayouwq	BUX8903	06-Mar-89	31616	200			00-Jan-00							pother1	HP	10099
bayouwq	BUW8901	06-Mar-89	31616	5400		15841	00-Jan-00							pother1	HP	10098
bayouwq	BUU8903	06-Mar-89	31616	8900		15842	00-Jan-00							pother1	HP	10097
bayouwq	BUS8903	06-Mar-89	31616	10000			00-Jan-00							pother1	HP	10095
bayouwq	BUQ8901	06-Mar-89	31616	310			00-Jan-00							pother1	HP	10093
bayouwq	BUN8901	06-Mar-89	31616	210			00-Jan-00							pother l	HP	10091
bayouwq	BUL8903	06-Mar-89	31616	10			00-Jan-00							pother1	HP	10089
bayouwq	BUG8903 BUB9009	06-Mar-89 08-Mar-90	31616 31616	72 200			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	10086 11007
bayouwq bayouwq	BUE9009	08-Mar-90	31616	590		+	00-Jan-00 00-Jan-00							pother1	HP	11007
bayouwq	BUA9009	08-Mar-90	31616	800			00-Jan-00							pother1	HP	11031
bayouwq	BUO9009	08-Mar-90	31616	670			00-Jan-00							pother1	HP	11027
bayouwq	BUM9009	08-Mar-90	31616	18		11357	00-Jan-00							pother1	HP	11023
bayouwq	BUK9008	08-Mar-90	31616	22000		11359	00-Jan-00							pother1	HP	11019
bayouwq	BUJ9008	08-Mar-90	31616	25000		11360	00-Jan-00							pother1	HP	11017
bayouwq	BUH9009	08-Mar-90	31616	14000			00-Jan-00							pother1	HP	11015
bayouwq	BUD9009	08-Mar-90	31616	1800			00-Jan-00							pother1	HP	11009
bayouwq	BUX9009	08-Mar-90	31616	36			00-Jan-00							pother1	HP	11043
bayouwq	BUW9009	08-Mar-90	31616	8500			00-Jan-00							pother l	HP	11039
bayouwq	BUU9009 BUS9009	08-Mar-90 08-Mar-90	31616 31616	11000 2500			00-Jan-00 00-Jan-00							pother1	HP HP	11037 11033
bayouwq bayouwq	BUQ9009	08-Mar-90	31616	300			00-Jan-00							pother1	HP	11029
bayouwq	BUN9009	08-Mar-90	31616	760			00-Jan-00							pother1	HP	11025
bayouwq	BUL9008	08-Mar-90	31616	8000			00-Jan-00							pother1	HP	11021
bayouwq	BUG9009	08-Mar-90	31616	620			00-Jan-00							pother1	HP	11013
bayouwq	BUB9010	20-Mar-90	31616	570		11142	00-Jan-00							pother1	HP	11078
bayouwq	BUE9010	20-Mar-90	31616	230		11163	00-Jan-00							pother1	HP	11082
bayouwq	BUA9010	20-Mar-90	31616	4200			00-Jan-00							pother1		11102
bayouwq	BUO9010	20-Mar-90	31616	170			00-Jan-00							pother1		11098
bayouwq	BUM9010	20-Mar-90	31616	9			00-Jan-00							pother1		11094
bayouwq	BUK9009	20-Mar-90	31616	54			00-Jan-00							pother1		11090
bayouwq	BUJ9009	20-Mar-90	31616	390			00-Jan-00							pother1	HP	11088
bayouwg	BUH9010 BUD9010	20-Mar-90 20-Mar-90	31616 31616	260 140			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	11086 11080
bayouwq bayouwq	BUX9010	20-Mar-90 20-Mar-90	31616	99			00-Jan-00 00-Jan-00							potner1 pother1		11114
bayouwq	BUW9010	20-Mar-90 20-Mar-90	31616	27000			00-Jan-00 00-Jan-00							pother1		11114
bayouwq	DO 11 2010	20-ivial-90	31010	27000	l	13041	oo-jan-00	11		1	<u> </u>	1		Pomer i	111	11110

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUU9010	20-Mar-90	31616	130000		15842	00-Jan-00									pother1	HP	11108
	BUS9010	20-Mar-90	31616	3100			00-Jan-00									pother1	HP	11104
	BUQ9010	20-Mar-90	31616	2100			00-Jan-00									pother1	HP	11100
	BUN9010	20-Mar-90	31616	120			00-Jan-00									pother1	HP	11096
	BUL9009	20-Mar-90	31616	72 670			00-Jan-00									pother1	HP HP	11092
. * *	BUG9010 BUB9102	20-Mar-90 20-Mar-91	31616 31616	330			00-Jan-00 00-Jan-00									pother1 pbayou	HP	11084 1207
	BUE9103	20-Mar-91	31616	280			00-Jan-00									pbayou	HP	1211
	BUA9106	20-Mar-91	31616	5300			00-Jan-00									pbayou	HP	1233
	BUP9101	20-Mar-91	31616	3300			00-Jan-00									pbayou	HP	1229
	BUO9106	20-Mar-91	31616	3600			00-Jan-00									pbayou	HP	1227
	BUM9103	20-Mar-91	31616	660			00-Jan-00									pbayou	HP	1223
	BUK9104	20-Mar-91	31616	300		11359	00-Jan-00									pbayou	HP	1219
	BUJ9106	20-Mar-91	31616	18		11360	00-Jan-00									pbayou	HP	1217
bayouwq	BUH9106	20-Mar-91	31616	570		11362	00-Jan-00									pbayou	HP	1215
bayouwq	BUD9105	20-Mar-91	31616	410		11364	00-Jan-00									pbayou	HP	1209
bayouwq	BUW9106	20-Mar-91	31616	9200		15841	00-Jan-00									pbayou	HP	1241
bayouwq	BUU9102	20-Mar-91	31616	6400		15842	00-Jan-00									pbayou	HP	1239
bayouwq	BUS9106	20-Mar-91	31616	4800		15843	00-Jan-00									pbayou	HP	1235
bayouwq	BUQ9103	20-Mar-91	31616	4200			00-Jan-00									pbayou	HP	1231
bayouwq	BUN9106	20-Mar-91	31616	5700			00-Jan-00									pbayou	HP	1225
bayouwq	BUL9106	20-Mar-91	31616	260			00-Jan-00									pbayou	HP	1221
bayouwq	BUG9103	20-Mar-91	31616	240			00-Jan-00									pbayou	HP	1213
	BUE9604	21-Mar-96	31616	36			00-Jan-00									xls96	HP	511
	BUV9605	21-Mar-96	31616	370			00-Jan-00									xls96		524
	BUA9606	21-Mar-96	31616	1100	QC		00-Jan-00								QC	xls96		509
	BUP9604	21-Mar-96	31616	3600			00-Jan-00									xls96		520
. * *	BUO9604 BUM9604	21-Mar-96 21-Mar-96	31616 31616	8600 460			00-Jan-00									xls96 xls96		519 518
	BUK9604	21-Mar-96	31616	2700			00-Jan-00 00-Jan-00									xls96		516
	BUJ9604	21-Mar-96	31616	220000			00-Jan-00 00-Jan-00									xls96	HP	515
• •	BUI9604	21-Mar-96	31616	8500			00-Jan-00									xls96		527
	BUH9604	21-Mar-96	31616	43000			00-Jan-00									xls96	HP	514
	BUF9603	21-Mar-96	31616	9			00-Jan-00									xls96		512
• •	BUD9604	21-Mar-96	31616	9			00-Jan-00									xls96	HP	510
	BUX9604	21-Mar-96	31616	480			00-Jan-00									xls96	HP	526
bayouwq	BUW9602	21-Mar-96	31616	880		15841	00-Jan-00									xls96	HP	525
bayouwq	BUS9604	21-Mar-96	31616	16000		15843	00-Jan-00									xls96	HP	523
bayouwq	BUQ9604	21-Mar-96	31616	3100		15844	00-Jan-00									xls96	HP	521
bayouwq	BUN9604	21-Mar-96	31616	250		15845	00-Jan-00									xls96	HP	528
	BUL9604	21-Mar-96	31616	1000			00-Jan-00									xls96		517
	BUG9602	21-Mar-96	31616	9			00-Jan-00									xls96		513
	BUC9402	22-Mar-94	31616	110			00-Jan-00									9495a		545
	BUV9402	22-Mar-94	31616	1300			00-Jan-00									9495a		579
. * *	BUA9404	22-Mar-94	31616	540			00-Jan-00									9495a		571
bayouwq	BUP9402	22-Mar-94	31616	220			00-Jan-00									9495a	HP	567
bayouwq	BUO9402	22-Mar-94	31616	280			00-Jan-00									9495a 9495a	HP	565 561
	BUM9402	22-Mar-94	31616	220			00-Jan-00									9495a 9495a	HP	
	BUK9402 BUJ9402	22-Mar-94 22-Mar-94	31616 31616	270 290			00-Jan-00 00-Jan-00									9495a 9495a	HP HP	557 555
	BUH9402	22-Mar-94 22-Mar-94	31616	270			00-Jan-00 00-Jan-00									9495a 9495a		553
	BUW9402	22-Mar-94	31616	2900			00-Jan-00 00-Jan-00									9495a 9495a		581
	BUU9402	22-Mar-94	31616	1100			00-Jan-00									9495a	HP	577
, ,	BUS9402	22-Mar-94	31616	380			00-Jan-00									9495a		573
• •	BUQ9402	22-Mar-94	31616	520			00-Jan-00									9495a	HP	569
	BUN9402	22-Mar-94	31616	290			00-Jan-00									9495a	HP	563
• •	BUL9402	22-Mar-94	31616	120			00-Jan-00									9495a		559
• •	BUA8302	23-Mar-83		200000			00-Jan-00									pother1		8928

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUO8301	23-Mar-83	31616	11000		11354	00-Jan-00									pother1	HP	8926
bayouwq	BUM8302	23-Mar-83	31616	3000			00-Jan-00									pother1	HP	8923
bayouwq	BUK8301	23-Mar-83	31616	1			00-Jan-00									pother1	HP	8921
bayouwq	BUJ8302	23-Mar-83	31616	1			00-Jan-00									pother1	HP	8920
bayouwq	BUI8301 BUH8302	23-Mar-83 23-Mar-83	31616 31616	2000			00-Jan-00 00-Jan-00									pother1 pother1	HP HP	8919 8918
bayouwq bayouwq	BUQ8302	23-Mar-83	31616	2000			00-Jan-00 00-Jan-00									pother1	HP	8927
bayouwq	BUB9103	25-Mar-91	31616	140			00-Jan-00									pbayou	HP	1280
bayouwq	BUA9107	25-Mar-91	31616	5700			00-Jan-00									pbayou	HP	1306
bayouwq	BUP9102	25-Mar-91	31616	6700			00-Jan-00									pbayou	HP	1302
bayouwq	BUK9105	25-Mar-91	31616	930		11359	00-Jan-00									pbayou	HP	1292
bayouwq	BUJ9107	25-Mar-91	31616	9		11360	00-Jan-00									pbayou	HP	1290
bayouwq	BUH9107	25-Mar-91	31616	810		11362	00-Jan-00									pbayou	HP	1288
bayouwq	BUD9106	25-Mar-91	31616	72			00-Jan-00									pbayou	HP	1282
bayouwq	BUW9107	25-Mar-91	31616	3100			00-Jan-00									pbayou	HP	1314
bayouwq	BUS9107	25-Mar-91	31616	5500			00-Jan-00									pbayou	HP	1308
bayouwq	BUQ9104	25-Mar-91	31616	5300			00-Jan-00									pbayou	HP	1304
bayouwq	BUN9107	25-Mar-91	31616	5500			00-Jan-00									pbayou	HP	1298
bayouwq	BUL9107	25-Mar-91	31616	750			00-Jan-00									pbayou	HP	1294
bayouwq	BUB9011	27-Mar-90	31616	1200			00-Jan-00									pother1		11149
bayouwq	BUE9011	27-Mar-90	31616	550			00-Jan-00									pother1		11153 11173
bayouwq	BUA9011 BUO9011	27-Mar-90 27-Mar-90	31616 31616	26000 5500			00-Jan-00 00-Jan-00									pother1 pother1	HP HP	111/3
bayouwa	BUM9011	27-Mar-90 27-Mar-90	31616	18			00-Jan-00 00-Jan-00									pother l	HP	11165
bayouwq bayouwq	BUK9010	27-Mar-90	31616	760			00-Jan-00									pother1		11161
bayouwq	BUJ9010	27-Mar-90	31616	45			00-Jan-00									pother1		11159
bayouwq	BUH9011	27-Mar-90	31616	36			00-Jan-00									pother1		11157
bayouwq	BUD9011	27-Mar-90	31616	460			00-Jan-00									pother1		11151
bayouwq	BUX9011	27-Mar-90	31616	550			00-Jan-00									pother1		11185
bayouwq	BUW9011	27-Mar-90	31616	8000		15841	00-Jan-00									pother1	HP	11181
bayouwq	BUU9011	27-Mar-90	31616	66000		15842	00-Jan-00									pother1	HP	11179
bayouwq	BUS9011	27-Mar-90	31616	5500		15843	00-Jan-00									pother1	HP	11175
bayouwq	BUQ9011	27-Mar-90	31616	3000		15844	00-Jan-00									pother1	HP	11171
bayouwq	BUN9011	27-Mar-90	31616	690		15845	00-Jan-00									pother1	HP	11167
bayouwq	BUL9010	27-Mar-90	31616	370			00-Jan-00									pother1	HP	11163
bayouwq	BUG9011	27-Mar-90	31616	340			00-Jan-00									pother1		11155
bayouwq	BUE9504	27-Mar-95	31616	800			00-Jan-00									9495a	HP	3370
bayouwq	BUV9503	27-Mar-95	31616	1300	DM		00-Jan-00								DM.	9495a	HP	3402
bayouwq	BUA9506 BUP9504	27-Mar-95 27-Mar-95	31616 31616	8800 2700	BM		00-Jan-00 00-Jan-00								BM	9495a 9495a	HP HP	3396 3392
bayouwa	BUM9503	27-Mar-95	31616	1200			00-Jan-00 00-Jan-00									9495a 9495a	HP	3386
bayouwq bayouwq	BUK9503	27-Mar-95	31616	1100			00-Jan-00									9495a	HP	3382
bayouwq	BUJ9504	27-Mar-95	31616	420			00-Jan-00									9495a		3380
bayouwq	BUI9504	27-Mar-95	31616	540			00-Jan-00									9495a		3378
bayouwq	BUH9504	27-Mar-95	31616	350			00-Jan-00									9495a		3376
bayouwq	BUF9504	27-Mar-95	31616	440			00-Jan-00									9495a	HP	3372
bayouwq	BUD9504	27-Mar-95	31616	230		11364	00-Jan-00									9495a	HP	3368
bayouwq	BUS9504	27-Mar-95	31616	3900		15843	00-Jan-00									9495a	HP	3398
bayouwq	BUN9504	27-Mar-95	31616	4100		15845	00-Jan-00									9495a	HP	3388
bayouwq	BUL9504	27-Mar-95	31616	950			00-Jan-00									9495a	HP	3384
bayouwq	BUA8503	28-Mar-85	31616	4300			00-Jan-00									pother1		9374
bayouwq	BUM8503	28-Mar-85	31616	39000			00-Jan-00									pother1		9369
bayouwq	BUK8503	28-Mar-85	31616	930			00-Jan-00									pother1		9367
bayouwq	BUJ8503	28-Mar-85	31616	180			00-Jan-00									pother1		9366
	BUH8503	28-Mar-85	31616	140			00-Jan-00				-					pother1		9364
bayouwq	BUX8503	28-Mar-85	31616	1240			00-Jan-00				-					pother1	HP	9383
	BUW8503	28-Mar-85		13700 9300			00-Jan-00				 					pother1		9380
bayouwq	BUU8503	28-Mar-85	31616	9300	L	15842	00-Jan-00	1	1	1	1	l				pother1	пг	9378

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUS8503	28-Mar-85	31616	7300		15843	00-Jan-00							pother1	HP	9377
	BUL8502	28-Mar-85	31616	1640			00-Jan-00							pother1	HP	9368
	BUA9607	28-Mar-96	31616	2400	BM		00-Jan-00						BM	xls96	HP	609
	BUB9403	30-Mar-94	31616	400			00-Jan-00							9495a	HP	610
1 1	BUE9403	30-Mar-94	31616	210			00-Jan-00							9495a	HP	616
	BUV9403 BUA9405	30-Mar-94 30-Mar-94	31616 31616	66000 5000			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	646 638
	BUO9403	30-Mar-94	31616	930			00-Jan-00 00-Jan-00							9495a 9495a	HP	632
	BUM9403	30-Mar-94	31616	540			00-Jan-00							9495a	HP	628
	BUK9403	30-Mar-94	31616	310			00-Jan-00							9495a	HP	624
	BUJ9403	30-Mar-94	31616	340			00-Jan-00							9495a	HP	622
	BUH9403	30-Mar-94	31616	420		11362	00-Jan-00							9495a	HP	620
bayouwq	BUX9402	30-Mar-94	31616	200		15840	00-Jan-00							9495a	HP	650
bayouwq	BUW9403	30-Mar-94	31616	1400		15841	00-Jan-00							9495a	HP	648
	BUU9403	30-Mar-94	31616	11000			00-Jan-00							9495a	HP	644
	BUS9403	30-Mar-94	31616	2900			00-Jan-00							9495a	HP	640
	BUQ9403	30-Mar-94	31616	5200			00-Jan-00							9495a	HP	636
	BUN9403	30-Mar-94	31616	1400			00-Jan-00							9495a	HP	630
	BUL9403	30-Mar-94	31616	350			00-Jan-00							9495a	HP	626
	BUE9104 BUA9108	02-Apr-91 02-Apr-91	31616 31616	1000 2700			00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	1717 1739
	BUP9103	02-Apr-91	31616	860			00-Jan-00 00-Jan-00							pbayou	HP	1735
	BUM9104	02-Apr-91	31616	4400			00-Jan-00							pbayou	HP	1729
	BUK9106	02-Apr-91	31616	130			00-Jan-00							pbayou	HP	1725
	BUJ9108	02-Apr-91	31616	300			00-Jan-00							pbayou	HP	1723
	BUH9108	02-Apr-91	31616	4000			00-Jan-00							pbayou	HP	1721
bayouwq	BUD9107	02-Apr-91	31616	280		11364	00-Jan-00							pbayou	HP	1715
bayouwq	BUW9108	02-Apr-91	31616	5900		15841	00-Jan-00							pbayou	HP	1747
bayouwq	BUS9108	02-Apr-91	31616	7500		15843	00-Jan-00							pbayou	HP	1741
	BUQ9105	02-Apr-91	31616	2700			00-Jan-00							pbayou	HP	1737
	BUN9108	02-Apr-91	31616	6000			00-Jan-00							pbayou	HP	1731
, ,	BUL9108	02-Apr-91	31616	180			00-Jan-00							pbayou	HP	1727
	BUG9104	02-Apr-91	31616	210			00-Jan-00							pbayou	HP HP	1719 3626
	BUB9502 BUE9505	03-Apr-95 03-Apr-95	31616 31616	54 460			00-Jan-00 00-Jan-00							9495a 9495a	HP	3626
	BUA9507	03-Apr-95	31616		BM		00-Jan-00 00-Jan-00						BM	9495a 9495a	HP	3654
	BUP9505	03-Apr-95	31616	330			00-Jan-00						BW	9495a	HP	3650
	BUO9503	03-Apr-95	31616	90			00-Jan-00							9495a	HP	3648
	BUM9504	03-Apr-95	31616	130			00-Jan-00							9495a	HP	3646
	BUK9504	03-Apr-95	31616	190			00-Jan-00							9495a	HP	3642
bayouwq	BUJ9505	03-Apr-95	31616	230		11360	00-Jan-00							9495a	HP	3640
bayouwq	BUH9505	03-Apr-95	31616	240		11362	00-Jan-00							9495a	HP	3638
bayouwq	BUF9505	03-Apr-95	31616	120		11363	00-Jan-00							9495a	HP	3634
	BUD9505	03-Apr-95	31616	2500		11364	00-Jan-00							9495a	HP	3630
	BUW9504	03-Apr-95	31616	690			00-Jan-00							9495a	HP	3662
	BUS9505	03-Apr-95	31616	170			00-Jan-00							9495a	HP	3656
	BUL9505	03-Apr-95	31616	380			00-Jan-00							9495a	HP	3644
	BUG9503	03-Apr-95	31616	290			00-Jan-00							9495a	HP	3636
	BUB8904 BUA8904	04-Apr-89 04-Apr-89	31616 31616	580 20000			00-Jan-00 00-Jan-00							pother1	HP HP	10111 10121
	BUA8904 BUO8903	04-Apr-89 04-Apr-89	31616	2700			00-Jan-00 00-Jan-00							pother1 pother1	HP	10121
	BUM8904	04-Apr-89	31616	9			00-Jan-00 00-Jan-00							pother1	HP	10119
	BUJ8904	04-Apr-89	31616	18			00-Jan-00 00-Jan-00							pother1	HP	10117
	BUH8904	04-Apr-89	31616	950			00-Jan-00							pother1	HP	10113
	BUD8903	04-Apr-89	31616	410			00-Jan-00							pother1	HP	10112
	BUX8904	04-Apr-89	31616	4000			00-Jan-00							pother1	HP	10126
	BUW8902	04-Apr-89	31616	7500			00-Jan-00							pother1	HP	10125
	BUU8904	04-Apr-89	31616	1200		15842	00-Jan-00							pother1	HP	10124

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUS8904	04-Apr-89	31616	21000		15843	00-Jan-00							pother1	HP	10122
bayouwq	BUQ8902	04-Apr-89	31616	12000			00-Jan-00							pother1	HP	10120
bayouwq	BUN8902	04-Apr-89	31616	3500			00-Jan-00							pother1	HP	10118
bayouwq	BUL8904	04-Apr-89	31616	220			00-Jan-00							pother1	HP	10116
bayouwq	BUG8904	04-Apr-89	31616	1300			00-Jan-00							pother1	HP HP	10113 283
bayouwq bayouwq	BUB9404 BUE9404	05-Apr-94 05-Apr-94	31616 31616	210 280			00-Jan-00 00-Jan-00							9495a 9495a	HP	287
bayouwq	BUV9404	05-Apr-94	31616	200000			00-Jan-00							9495a		317
bayouwq	BUA9406	05-Apr-94	31616	330			00-Jan-00							9495a		309
bayouwq	BUP9404	05-Apr-94	31616	340			00-Jan-00							9495a	HP	305
bayouwq	BUO9404	05-Apr-94	31616	410		11354	00-Jan-00							9495a	HP	303
bayouwq	BUM9404	05-Apr-94	31616	720		11357	00-Jan-00							9495a	HP	299
bayouwq	BUK9404	05-Apr-94	31616	9500		11359	00-Jan-00							9495a	HP	295
bayouwq	BUJ9404	05-Apr-94	31616	34000		11360	00-Jan-00							9495a	HP	293
bayouwq	BUH9404	05-Apr-94	31616	220			00-Jan-00							9495a		291
bayouwq	BUX9403	05-Apr-94	31616	1100			00-Jan-00							9495a	HP	321
bayouwq	BUW9404	05-Apr-94	31616	4600			00-Jan-00							9495a 9495a	HP HP	319 315
bayouwq	BUU9404 BUS9404	05-Apr-94 05-Apr-94	31616 31616	33000 440			00-Jan-00 00-Jan-00							9495a 9495a		311
bayouwq bayouwq	BUQ9404	05-Apr-94	31616	290			00-Jan-00 00-Jan-00							9495a 9495a	HP	307
bayouwq	BUN9404	05-Apr-94	31616	900			00-Jan-00							9495a		301
bayouwq	BUL9404	05-Apr-94	31616	4900			00-Jan-00							9495a	HP	297
bayouwq	BUG9404	05-Apr-94	31616	220			00-Jan-00							9495a	HP	289
bayouwq	BUV8403	06-Apr-84	31616	35000		11345	00-Jan-00							pother1	HP	9187
bayouwq	BUA8403	06-Apr-84	31616	95000		11351	00-Jan-00							pother1	HP	9182
bayouwq	BUX8403	06-Apr-84	31616	2000			00-Jan-00							pother1	HP	9191
bayouwq	BUU8402	06-Apr-84	31616	21000			00-Jan-00							pother1	HP	9186
bayouwq	BUS8403	06-Apr-84	31616	30670			00-Jan-00							pother1	HP	9185
bayouwq	BUQ8401	06-Apr-84	31616	250000 7900			00-Jan-00							pother1	HP	9181
bayouwq bayouwq	BUA8702 BUO8702	06-Apr-87 06-Apr-87	31616 31616	11000			00-Jan-00 00-Jan-00							pother1	HP HP	9785 9784
bayouwq	BUM8702	06-Apr-87	31616	1000			00-Jan-00							pother1	HP	9783
bayouwq	BUJ8702	06-Apr-87	31616	10			00-Jan-00							pother1	HP	9781
bayouwq	BUH8702	06-Apr-87	31616	3400			00-Jan-00							pother1	HP	9780
bayouwq	BUD8702	06-Apr-87	31616	540		11364	00-Jan-00							pother1	HP	9778
bayouwq	BUX8702	06-Apr-87	31616	10		15840	00-Jan-00							pother1	HP	9789
bayouwq	BUW8702	06-Apr-87	31616	40000		15841	00-Jan-00							pother1	HP	9788
bayouwq	BUU8702	06-Apr-87	31616	9500			00-Jan-00							pother1	HP	9787
bayouwq	BUS8702	06-Apr-87	31616	12000			00-Jan-00							pother1	HP	9786
bayouwq	BUL8702	06-Apr-87	31616	60			00-Jan-00							pother1	HP	9782
bayouwq	BUG8702	06-Apr-87 08-Apr-96	31616	1180			00-Jan-00							pother1	HP HP	9779 680
bayouwq bayouwq	BUE9605 BUV9606	08-Apr-96	31616 31616	2700 960			00-Jan-00 00-Jan-00							xls96 xls96	HP	693
bayouwq	BUA9608	08-Apr-96	31616	20494	OC		00-Jan-00						QC	xls96	HP	678
bayouwq	BUP9605	08-Apr-96	31616	900	QC		00-Jan-00						<u>Ų</u> c	xls96	HP	688
bayouwq	BUO9605	08-Apr-96	31616	970			00-Jan-00							xls96	HP	687
bayouwq	BUM9605	08-Apr-96	31616	850			00-Jan-00							xls96	HP	686
bayouwq	BUK9605	08-Apr-96	31616	2200		11359	00-Jan-00							xls96	HP	684
bayouwq	BUI9605	08-Apr-96	31616	6300			00-Jan-00							xls96		696
bayouwq	BUH9605	08-Apr-96	31616	2300			00-Jan-00							xls96		683
bayouwq	BUF9604	08-Apr-96	31616	430			00-Jan-00							xls96		681
bayouwq	BUD9605	08-Apr-96	31616	340			00-Jan-00							xls96		679
bayouwq	BUX9605	08-Apr-96	31616	390 2300			00-Jan-00							xls96		695
bayouwq	BUW9603 BUS9605	08-Apr-96 08-Apr-96	31616 31616	2300			00-Jan-00 00-Jan-00			1				xls96 xls96	HP HP	694 691
bayouwq bayouwq	BUQ9605	08-Apr-96	31616	1100			00-Jan-00 00-Jan-00							xls96 xls96	HP	689
bayouwq	BUN9605	08-Apr-96	31616	9100			00-Jan-00							xls96	HP	697
bayouwq	BUL9605	08-Apr-96	31616	870			00-Jan-00							xls96		685
ouyouwq	DOL/003	00-Apr-30	31010	870	l	15040	00-Jan-00	11		1				A1070	***	003

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUG9603	08-Apr-96	31616	240		15847	00-Jan-00							xls96	HP	682
bayouwq	BUB9104	09-Apr-91	31616	260			00-Jan-00							pbayou	HP	1786
bayouwq	BUE9105	09-Apr-91	31616	590			00-Jan-00							pbayou	HP	1790
bayouwq	BUA9109	09-Apr-91	31616	1100			00-Jan-00							pbayou	HP	1812
bayouwq	BUP9104	09-Apr-91	31616	790			00-Jan-00							pbayou	HP	1808
bayouwq	BUM9105	09-Apr-91	31616	510			00-Jan-00							pbayou	HP	1802
bayouwq	BUK9107	09-Apr-91	31616	620			00-Jan-00							pbayou	HP	1798
bayouwq	BUJ9109	09-Apr-91	31616 31616	660 700			00-Jan-00							pbayou	HP HP	1796 1794
bayouwq	BUH9109 BUD9108	09-Apr-91 09-Apr-91	31616	260			00-Jan-00 00-Jan-00							pbayou	HP	1794
bayouwq	BUW9109	09-Apr-91	31616	15000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	1820
bayouwq bayouwq	BUS9109	09-Apr-91	31616	2000			00-Jan-00							pbayou	HP	1814
bayouwq	BUN9109	09-Apr-91	31616	800			00-Jan-00							pbayou	HP	1804
bayouwq	BUL9109	09-Apr-91	31616	580			00-Jan-00							pbayou	HP	1800
bayouwq	BUO8302	11-Apr-83	31616	5000			00-Jan-00							pother1	HP	8957
bayouwq	BUM8303	11-Apr-83	31616	160000			00-Jan-00							pother1	HP	8954
bayouwq	BUK8302	11-Apr-83	31616	1			00-Jan-00							pother1	HP	8952
bayouwq	BUJ8303	11-Apr-83	31616	1			00-Jan-00							pother1	HP	8951
bayouwq	BUI8302	11-Apr-83	31616	1		11361	00-Jan-00							pother1	HP	8950
bayouwq	BUH8303	11-Apr-83	31616	1		11362	00-Jan-00							pother1	HP	8949
bayouwq	BUN8302	11-Apr-83	31616	8000		15845	00-Jan-00							pother1	HP	8955
bayouwq	BUO8502	11-Apr-85	31616	30000		11354	00-Jan-00							pother1	HP	9404
bayouwq	BUM8504	11-Apr-85	31616	9600		11357	00-Jan-00							pother1	HP	9401
bayouwq	BUK8504	11-Apr-85	31616	70		11359	00-Jan-00							pother1	HP	9399
bayouwq	BUJ8504	11-Apr-85	31616	520		11360	00-Jan-00							pother1	HP	9398
bayouwq	BUH8504	11-Apr-85	31616	2700		11362	00-Jan-00							pother1	HP	9396
bayouwq	BUX8504	11-Apr-85	31616	1270			00-Jan-00							pother1	HP	9415
bayouwq	BUW8504	11-Apr-85	31616	238000			00-Jan-00							pother1	HP	9412
bayouwq	BUU8504	11-Apr-85	31616	25000		15842	00-Jan-00							pother1	HP	9410
bayouwq	BUS8504	11-Apr-85	31616	18700			00-Jan-00							pother1	HP	9409
bayouwq	BUB9012	12-Apr-90	31616	350			00-Jan-00							pother1	HP	11220
bayouwq	BUE9012	12-Apr-90	31616	1200			00-Jan-00							pother1	HP	11224
bayouwq	BUA9012	12-Apr-90	31616	4400			00-Jan-00							pother1	HP	11244
bayouwq	BUO9012	12-Apr-90	31616	2400			00-Jan-00							pother1	HP	11240
bayouwq	BUM9012	12-Apr-90	31616	980			00-Jan-00							pother1	HP	11236
bayouwq	BUK9011	12-Apr-90	31616 31616	450 620			00-Jan-00							pother1	HP HP	11232 11230
bayouwq	BUJ9011 BUH9012	12-Apr-90 12-Apr-90	31616	810			00-Jan-00 00-Jan-00							pother1	HP	11228
bayouwq bayouwq	BUD9012	12-Apr-90	31616	260			00-Jan-00							pother1 pother1	HP	11222
bayouwq	BUW9012	12-Apr-90	31616	4100			00-Jan-00							pother1	HP	11252
bayouwq	BUU9012	12-Apr-90	31616	16000			00-Jan-00							pother1	HP	11250
bayouwq	BUS9012	12-Apr-90	31616	3200			00-Jan-00							pother1	HP	11246
bayouwq	BUQ9012	12-Apr-90	31616	4000			00-Jan-00							pother1	HP	11242
bayouwq	BUN9012	12-Apr-90	31616	2200			00-Jan-00							pother1	HP	11238
bayouwq	BUL9011	12-Apr-90	31616	590			00-Jan-00							pother1	HP	11234
bayouwq	BUG9012	12-Apr-90	31616	3000			00-Jan-00							pother1	HP	11226
bayouwq	BUE9201	13-Apr-92	31616	3400			00-Jan-00							pbayou	HP	2294
bayouwq	BUV9201	13-Apr-92	31616	3500		11345	00-Jan-00							pbayou	HP	2324
bayouwq	BUA9201	13-Apr-92	31616	280		11351	00-Jan-00							pbayou	HP	2316
bayouwq	BUP9201	13-Apr-92	31616	440			00-Jan-00		·					pbayou	HP	2312
bayouwq	BUO9201	13-Apr-92	31616	400			00-Jan-00		•					pbayou	HP	2310
bayouwq	BUM9201	13-Apr-92	31616	450			00-Jan-00							pbayou	HP	2306
bayouwq	BUK9201	13-Apr-92	31616	810		11359	00-Jan-00							pbayou	HP	2302
bayouwq	BUJ9201	13-Apr-92	31616	26000			00-Jan-00							pbayou	HP	2300
bayouwq	BUH9201	13-Apr-92	31616	200			00-Jan-00							pbayou	HP	2298
bayouwq	BUD9201	13-Apr-92	31616	200			00-Jan-00							pbayou	HP	2292
bayouwq	BUW9201	13-Apr-92	31616	48000			00-Jan-00							pbayou	HP	2326
bayouwq	BUU9201	13-Apr-92	31616	8600		15842	00-Jan-00			1				pbayou	HP	2322

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUS9201	13-Apr-92	31616	21000		15843	00-Jan-00							pbayou	HP	2318
bayouwq	BUN9201	13-Apr-92	31616	550			00-Jan-00							pbayou	HP	2308
bayouwq	BUL9201	13-Apr-92	31616	970			00-Jan-00							pbayou	HP	2304
bayouwq	BUB9301	13-Apr-93	31616	63			00-Jan-00							pbayou	HP	2799
bayouwq	BUE9301	13-Apr-93	31616	190			00-Jan-00							pbayou	HP	2803
bayouwq	BUV9301 BUA9301	13-Apr-93 13-Apr-93	31616 31616	23000 790			00-Jan-00 00-Jan-00							pbayou	HP HP	2831 2825
bayouwq bayouwq	BUP9301	13-Apr-93	31616	880			00-Jan-00 00-Jan-00							pbayou pbayou	HP	2823
	BUO9301	13-Apr-93	31616	770			00-Jan-00							pbayou		2819
bayouwq	BUM9301	13-Apr-93	31616	710			00-Jan-00							pbayou	HP	2815
bayouwq	BUK9301	13-Apr-93	31616	210			00-Jan-00							pbayou	HP	2811
	BUJ9301	13-Apr-93	31616	110			00-Jan-00							pbayou	HP	2809
bayouwq	BUH9301	13-Apr-93	31616	260		11362	00-Jan-00							pbayou	HP	2807
bayouwq	BUD9301	13-Apr-93	31616	27		11364	00-Jan-00							pbayou	HP	2801
bayouwq	BUX9301	13-Apr-93	31616	7400			00-Jan-00							pbayou	HP	2835
bayouwq	BUW9301	13-Apr-93	31616	28000			00-Jan-00							pbayou	HP	2833
bayouwq	BUU9301	13-Apr-93	31616	20000			00-Jan-00							pbayou	HP	2829
bayouwq	BUS9301	13-Apr-93	31616	1000			00-Jan-00							pbayou	HP	2827
bayouwq	BUQ9301	13-Apr-93	31616	710			00-Jan-00							pbayou	HP HP	2823 2817
	BUN9301 BUL9301	13-Apr-93 13-Apr-93	31616 31616	560 230			00-Jan-00 00-Jan-00							pbayou pbayou	HP	2817
bayouwq bayouwq	BUG9301	13-Apr-93	31616	300			00-Jan-00 00-Jan-00							pbayou	HP	2805
bayouwq	BUB9405	19-Apr-94	31616	480			00-Jan-00							9495a	HP	348
bayouwq	BUC9404	19-Apr-94	31616	560			00-Jan-00							9495a	HP	350
	BUE9405	19-Apr-94	31616	420			00-Jan-00							9495a	HP	354
bayouwq	BUV9405	19-Apr-94	31616	4400		11345	00-Jan-00							9495a		382
bayouwq	BUA9407	19-Apr-94	31616	2100		11351	00-Jan-00							9495a	HP	374
bayouwq	BUP9405	19-Apr-94	31616	2300		11353	00-Jan-00							9495a	HP	372
bayouwq	BUO9405	19-Apr-94	31616	3600		11354	00-Jan-00							9495a	HP	370
bayouwq	BUM9405	19-Apr-94	31616	2400			00-Jan-00							9495a	HP	366
bayouwq	BUK9405	19-Apr-94	31616	6000			00-Jan-00							9495a	HP	362
bayouwq	BUJ9405	19-Apr-94	31616	3100			00-Jan-00							9495a	HP	360
	BUH9405	19-Apr-94	31616	2300			00-Jan-00							9495a 9495a	HP HP	358
	BUD9405 BUW9405	19-Apr-94 19-Apr-94	31616 31616	3500 7500			00-Jan-00 00-Jan-00							9495a 9495a	HP	352 384
bayouwq bayouwq	BUU9405	19-Apr-94	31616	2900			00-Jan-00 00-Jan-00							9495a 9495a	HP	380
bayouwq	BUS9405	19-Apr-94	31616	3700			00-Jan-00							9495a		376
bayouwq	BUN9405	19-Apr-94	31616	2400			00-Jan-00							9495a	HP	368
bayouwq	BUL9405	19-Apr-94	31616	3800			00-Jan-00							9495a	HP	364
	BUG9405	19-Apr-94	31616	350		15847	00-Jan-00							9495a	HP	356
bayouwq	BUA9013	23-Apr-90	31616	13000		11351	00-Jan-00							pother1	HP	11315
bayouwq	BUO9013	23-Apr-90	31616	42000		11354	00-Jan-00							pother1	HP	11311
bayouwq	BUM9013	23-Apr-90	31616	730		11357	00-Jan-00							pother1	HP	11307
bayouwq	BUN9013	23-Apr-90	31616	19000			00-Jan-00							pother1	HP	11309
bayouwq	BUV9504	24-Apr-95	31616	4100			00-Jan-00							9495a	HP	3910
bayouwq	BUA9609	24-Apr-96	31616	2300	BM		00-Jan-00						BM	xls96	HP	887
bayouwq	BUB9406	26-Apr-94	31616	500			00-Jan-00							9495a	HP HP	411
1	BUC9405	26-Apr-94	31616	590			00-Jan-00							9495a		
	BUE9406 BUV9406	26-Apr-94 26-Apr-94	31616 31616	360 930			00-Jan-00 00-Jan-00							9495a 9495a		417 447
	BUA9408	26-Apr-94 26-Apr-94	31616	5900			00-Jan-00 00-Jan-00							9495a 9495a		439
	BUP9406	26-Apr-94	31616	2100			00-Jan-00 00-Jan-00							9495a		437
	BUO9406	26-Apr-94	31616	2100			00-Jan-00							9495a	HP	435
bayouwq	BUM9406	26-Apr-94	31616	920			00-Jan-00							9495a		431
	BUK9406	26-Apr-94	31616	960			00-Jan-00							9495a	HP	427
	BUI9401	26-Apr-94	31616	1300			00-Jan-00							9495a	HP	425
	BUH9406	26-Apr-94	31616	5400			00-Jan-00							9495a	HP	423
bayouwq	BUF9401	26-Apr-94	31616	330		11363	00-Jan-00							9495a	HP	419

Database	TAG	END DATE	STORET	GT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUD9406	26-Apr-94	31616	570		11364	00-Jan-00							9495a	HP	415
bayouwq	BUX9404	26-Apr-94	31616	410			00-Jan-00							9495a	HP	451
bayouwq	BUW9406	26-Apr-94	31616	27000			00-Jan-00							9495a	HP	449
bayouwq	BUU9406	26-Apr-94	31616	860			00-Jan-00							9495a	HP	445
bayouwq	BUS9406	26-Apr-94	31616	930			00-Jan-00							9495a	HP	441
bayouwq	BUN9406 BUL9406	26-Apr-94 26-Apr-94	31616 31616	2200 680			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	433 429
bayouwq bayouwq	BUG9406	26-Apr-94	31616	4500			00-Jan-00 00-Jan-00							9495a 9495a	HP	429
bayouwq	BUA9508	26-Apr-95	31616	340	BM		00-Jan-00						BM	9495a	HP	3593
bayouwq	BUA8603	28-Apr-86	31616	5000	Divi		00-Jan-00							pother1	HP	9630
bayouwq	BUO8603	28-Apr-86	31616	5800			00-Jan-00							pother1	HP	9628
bayouwq	BUM8603	28-Apr-86	31616	20600			00-Jan-00							pother1	HP	9625
bayouwq	BUJ8603	28-Apr-86	31616	10		11360	00-Jan-00							pother1	HP	9622
bayouwq	BUH8603	28-Apr-86	31616	500		11362	00-Jan-00							pother1	HP	9620
bayouwq	BUX8603	28-Apr-86	31616	4100		15840	00-Jan-00							pother1	HP	9639
bayouwq	BUW8603	28-Apr-86	31616	9200			00-Jan-00							pother1	HP	9636
bayouwq	BUU8603	28-Apr-86	31616	85000			00-Jan-00							pother1	HP	9634
bayouwq	BUS8603	28-Apr-86	31616	32000			00-Jan-00							pother1	HP	9633
bayouwq	BUL8603	28-Apr-86	31616	90 27			00-Jan-00							pother1	HP HP	9624 1859
bayouwq	BUB9105 BUE9106	30-Apr-91 30-Apr-91	31616 31616	36			00-Jan-00 00-Jan-00							pbayou pbayou	HP	1863
bayouwq bayouwq	BUA9110	30-Apr-91	31616	660			00-Jan-00 00-Jan-00							pbayou	HP	1885
bayouwq	BUP9105	30-Apr-91	31616	420			00-Jan-00							pbayou	HP	1881
bayouwq	BUO9107	30-Apr-91	31616	280			00-Jan-00							pbayou	HP	1879
bayouwq	BUM9106	30-Apr-91	31616	240			00-Jan-00							pbayou	HP	1875
bayouwq	BUK9108	30-Apr-91	31616	110			00-Jan-00							pbayou	HP	1871
bayouwq	BUJ9110	30-Apr-91	31616	200		11360	00-Jan-00							pbayou	HP	1869
bayouwq	BUH9110	30-Apr-91	31616	45		11362	00-Jan-00							pbayou	HP	1867
bayouwq	BUD9109	30-Apr-91	31616	45		11364	00-Jan-00							pbayou	HP	1861
bayouwq	BUW9110	30-Apr-91	31616	2700			00-Jan-00							pbayou	HP	1893
bayouwq	BUU9103	30-Apr-91	31616	970			00-Jan-00							pbayou	HP	1891
bayouwq	BUS9110	30-Apr-91	31616	800			00-Jan-00							pbayou	HP	1887
bayouwq	BUQ9106 BUN9110	30-Apr-91 30-Apr-91	31616 31616	860 220			00-Jan-00 00-Jan-00							pbayou	HP HP	1883 1877
bayouwq bayouwq	BUL9110	30-Apr-91	31616	190			00-Jan-00 00-Jan-00							pbayou pbayou	HP	1873
bayouwq	BUG9106	30-Apr-91	31616	350			00-Jan-00							pbayou	HP	1865
bayouwq	BUA8905	01-May-89	31616	19000			00-Jan-00							pother1	HP	10147
bayouwq	BUO8904	01-May-89	31616	3300			00-Jan-00							pother1	HP	10145
bayouwq	BUM8905	01-May-89	31616	1400			00-Jan-00							pother1	HP	10143
bayouwq	BUJ8905	01-May-89	31616	110		11360	00-Jan-00							pother1	HP	10141
bayouwq	BUH8905	01-May-89	31616	48000		11362	00-Jan-00							pother1	HP	10140
bayouwq	BUD8904	01-May-89	31616	2200		11364	00-Jan-00							pother1	HP	10138
bayouwq	BUX8905	01-May-89	31616	8700			00-Jan-00							pother1	HP	10152
bayouwq	BUW8903	01-May-89	31616	9700			00-Jan-00							pother1	HP	10151
bayouwq	BUU8905	01-May-89	31616	20000			00-Jan-00							pother1	HP	10150
bayouwq	BUS8905	01-May-89	31616	23000			00-Jan-00							pother1	HP	10148
bayouwq	BUQ8903	01-May-89	31616	15000 2800			00-Jan-00							pother1	HP HP	10146 10144
bayouwq	BUN8903 BUL8905	01-May-89 01-May-89	31616 31616	600			00-Jan-00 00-Jan-00							pother1	HP	10144
bayouwq bayouwq	BUG8905	01-May-89	31616	2000			00-Jan-00 00-Jan-00							pother1	HP	10142
	BUC9501	01-May-95	31616	210			00-Jan-00							9495a	HP	4094
bayouwq	BUE9506	01-May-95	31616	150			00-Jan-00							9495a	HP	4098
bayouwq	BUV9505	01-May-95	31616	810			00-Jan-00							9495a	HP	4130
bayouwq	BUA9509	01-May-95	31616		BM		00-Jan-00						BM	9495a	HP	4124
bayouwq	BUO9504	01-May-95	31616	370			00-Jan-00							9495a	HP	4118
	BUM9505	01-May-95	31616	330		11357	00-Jan-00							9495a	HP	4114
	BUK9505	01-May-95	31616	530			00-Jan-00							9495a	HP	4110
bayouwq	BUJ9506	01-May-95	31616	450		11360	00-Jan-00							9495a	HP	4108

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUI9505	01-May-95	31616	380		11361	00-Jan-00							9495a	HP	4106
bayouwq	BUH9506	01-May-95	31616	360			00-Jan-00							9495a	HP	4104
bayouwq	BUF9506	01-May-95	31616	190			00-Jan-00							9495a	HP	4100
bayouwq	BUD9506	01-May-95	31616	360			00-Jan-00							9495a	HP	4096
bayouwq	BUW9505	01-May-95	31616	90			00-Jan-00							9495a	HP	4132
bayouwq	BUS9506	01-May-95 01-May-95	31616 31616	4200 220			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	4126 4122
bayouwq bayouwq	BUQ9503 BUN9505	01-May-95	31616	950			00-Jan-00							9495a 9495a	HP	4116
bayouwq	BUL9506	01-May-95	31616	350			00-Jan-00							9495a	HP	4112
bayouwq	BUV9506	02-May-95	31616	350			00-Jan-00							9495a	HP	4590
bayouwq	BUE9202	04-May-92	31616	72			00-Jan-00							pbayou	HP	3795
bayouwq	BUV9202	04-May-92	31616	390			00-Jan-00							pbayou	HP	3825
bayouwq	BUA9202	04-May-92	31616	210		11351	00-Jan-00							pbayou	HP	3817
bayouwq	BUP9202	04-May-92	31616	600			00-Jan-00							pbayou	HP	3813
bayouwq	BUO9202	04-May-92	31616	410		11354	00-Jan-00							pbayou	HP	3811
bayouwq	BUM9202	04-May-92	31616	500			00-Jan-00							pbayou	HP	3807
bayouwq	BUK9202	04-May-92	31616	530			00-Jan-00							pbayou	HP	3803
bayouwq	BUJ9202	04-May-92	31616	110			00-Jan-00							pbayou	HP	3801
bayouwq	BUH9202	04-May-92	31616	99			00-Jan-00							pbayou	HP	3799
bayouwq	BUD9202 BUW9202	04-May-92 04-May-92	31616 31616	490			00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	3793 3827
bayouwq	BUU9202	04-May-92	31616	430			00-Jan-00							pbayou	HP	3823
bayouwq bayouwq	BUS9202	04-May-92	31616	540			00-Jan-00							pbayou	HP	3819
bayouwq	BUQ9201	04-May-92	31616	330			00-Jan-00							pbayou	HP	3815
bayouwq	BUN9202	04-May-92	31616	360			00-Jan-00							pbayou	HP	3809
bayouwq	BUL9202	04-May-92	31616	600			00-Jan-00							pbayou	HP	3805
bayouwq	BUG9201	04-May-92	31616	310		15847	00-Jan-00							pbayou	HP	3797
bayouwq	BUA9111	06-May-91	31616	210		11351	00-Jan-00							pbayou	HP	3232
bayouwq	BUP9106	06-May-91	31616	180		11353	00-Jan-00							pbayou	HP	3228
bayouwq	BUJ9111	06-May-91	31616	130			00-Jan-00							pbayou	HP	3216
bayouwq	BUH9111	06-May-91	31616	200			00-Jan-00							pbayou	HP	3214
bayouwq	BUD9110	06-May-91	31616	63			00-Jan-00							pbayou	HP	3208
bayouwq	BUX9101	06-May-91	31616	930			00-Jan-00							pbayou	HP HP	3244 3240
bayouwq	BUW9111 BUU9104	06-May-91 06-May-91	31616 31616	1600 1100			00-Jan-00 00-Jan-00							pbayou	HP	3238
bayouwq bayouwq	BUS9111	06-May-91	31616	470			00-Jan-00							pbayou pbayou	HP	3234
bayouwq	BUN9111	06-May-91	31616	170			00-Jan-00							pbayou	HP	3224
bayouwq	BUE9606	06-May-96	31616	500			00-Jan-00							xls96	HP	994
bayouwq	BUV9607	06-May-96	31616	600			00-Jan-00							xls96	HP	1007
bayouwq	BUA9610	06-May-96	31616	305	QC	11351	00-Jan-00						QC	xls96	HP	992
bayouwq	BUP9606	06-May-96	31616	690		11353	00-Jan-00							xls96	HP	1003
bayouwq	BUO9606	06-May-96	31616	370		11354	00-Jan-00							xls96	HP	1002
bayouwq	BUM9606	06-May-96	31616	11000		11357	00-Jan-00							xls96	HP	1000
bayouwq	BUK9606	06-May-96	31616	3700			00-Jan-00							xls96	HP	998
bayouwq	BUI9606	06-May-96	31616	9100			00-Jan-00							xls96	HP	997
bayouwq	BUH9606	06-May-96	31616	950			00-Jan-00							xls96	HP	996
bayouwq	BUD9606	06-May-96	31616	500			00-Jan-00							xls96	HP	993
bayouwq	BUX9606	06-May-96	31616	380			00-Jan-00							xls96	HP	1009
bayouwq bayouwq	BUW9604 BUS9606	06-May-96 06-May-96	31616 31616	850 750			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	1008 1006
	BUQ9606	06-May-96	31616	590			00-Jan-00							xls96	HP	1006
bayouwq	BUN9606	06-May-96	31616	340			00-Jan-00							xls96	HP	1004
	BUL9606	06-May-96	31616	2800			00-Jan-00							xls96	HP	999
bayouwq	BUG9604	06-May-96	31616	580			00-Jan-00							xls96	HP	995
bayouwq	BUB9013	10-May-90	31616	81			00-Jan-00							pother1	HP	11362
bayouwq	BUE9013	10-May-90	31616	72			00-Jan-00							pother1	HP	11366
bayouwq	BUA9014	10-May-90	31616	620		11351	00-Jan-00							pother1	HP	11386
bayouwq	BUO9014	10-May-90	31616	630		11354	00-Jan-00							pother1	HP	11382

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUK9012	10-May-90	31616	260		11359	00-Jan-00							pother1	HP	11374
bayouwq	BUJ9012	10-May-90	31616	170			00-Jan-00							pother1	HP	11372
bayouwq	BUH9013	10-May-90	31616	160			00-Jan-00							pother1	HP	11370
bayouwq	BUD9013	10-May-90	31616	72			00-Jan-00							pother1	HP	11364
bayouwq	BUW9013	10-May-90	31616	860 780			00-Jan-00							pother1	HP HP	11394 11392
bayouwq bayouwq	BUU9013 BUS9013	10-May-90 10-May-90	31616 31616	960			00-Jan-00 00-Jan-00							pother1	HP	11392
	BUQ9013	10-May-90	31616	580		1	00-Jan-00							pother1	HP	11384
	BUL9012	10-May-90	31616	170			00-Jan-00							pother1	HP	11376
bayouwq	BUG9013	10-May-90	31616	320			00-Jan-00							pother1	HP	11368
bayouwq	BUB9407	11-May-94	31616	470		11142	00-Jan-00							9495a	HP	4160
bayouwq	BUC9406	11-May-94	31616	500		11142	00-Jan-00							9495a	HP	4162
bayouwq	BUE9407	11-May-94	31616	760		11163	00-Jan-00							9495a	HP	4166
bayouwq	BUV9407	11-May-94	31616	1300			00-Jan-00							9495a	HP	4200
bayouwq	BUA9409	11-May-94	31616	680			00-Jan-00							9495a	HP	4192
bayouwq	BUP9407	11-May-94	31616	590			00-Jan-00							9495a	HP	4188
bayouwq	BUO9407	11-May-94	31616	1600			00-Jan-00							9495a	HP	4186
bayouwq	BUM9407	11-May-94	31616	330			00-Jan-00							9495a 9495a	HP HP	4182 4178
bayouwq	BUK9407 BUJ9406	11-May-94 11-May-94	31616 31616	450 550			00-Jan-00 00-Jan-00							9495a 9495a	HP	4176
	BUI9402	11-May-94	31616	630			00-Jan-00 00-Jan-00							9495a 9495a	HP	4174
bayouwq	BUH9407	11-May-94	31616	1200		1	00-Jan-00							9495a	HP	4172
bayouwq	BUF9402	11-May-94	31616	770			00-Jan-00							9495a	HP	4168
bayouwq	BUX9405	11-May-94	31616	440			00-Jan-00							9495a	HP	4202
	BUU9407	11-May-94	31616	2100			00-Jan-00							9495a	HP	4198
bayouwq	BUS9407	11-May-94	31616	3800		15843	00-Jan-00							9495a	HP	4194
bayouwq	BUQ9405	11-May-94	31616	540		15844	00-Jan-00							9495a	HP	4190
bayouwq	BUN9407	11-May-94	31616	2400		15845	00-Jan-00							9495a	HP	4184
bayouwq	BUL9407	11-May-94	31616	420			00-Jan-00							9495a	HP	4180
bayouwq	BUG9407	11-May-94	31616	200			00-Jan-00							9495a	HP	4170
bayouwq	BUV9302	12-May-93	31616	2600			00-Jan-00							pbayou	HP	4637
bayouwq	BUE9302	13-May-93	31616	63			00-Jan-00							pbayou	HP	4364
bayouwq	BUV9303 BUA9302	13-May-93 13-May-93	31616 31616	1700 370			00-Jan-00 00-Jan-00							pbayou	HP HP	4392 4386
bayouwq	BUP9302	13-May-93	31616	680			00-Jan-00 00-Jan-00							pbayou pbayou	HP	4382
bayouwq bayouwq	BUO9302	13-May-93	31616	890			00-Jan-00							pbayou	HP	4382
bayouwq	BUK9302	13-May-93	31616	250			00-Jan-00							pbayou	HP	4372
bayouwq	BUJ9302	13-May-93	31616	210			00-Jan-00							pbayou	HP	4370
bayouwq	BUH9302	13-May-93	31616	200			00-Jan-00							pbayou	HP	4368
bayouwq	BUD9302	13-May-93	31616	110		11364	00-Jan-00							pbayou	HP	4362
bayouwq	BUS9302	13-May-93	31616	560		15843	00-Jan-00							pbayou	HP	4388
bayouwq	BUN9302	13-May-93	31616	2600		15845	00-Jan-00							pbayou	HP	4378
bayouwq	BUG9302	13-May-93	31616	800			00-Jan-00							pbayou	HP	4366
bayouwq	BUB9106	15-May-91	31616	36			00-Jan-00							pbayou	HP	3279
bayouwq	BUC9101	15-May-91	31616	9			00-Jan-00							pbayou	HP	3277
bayouwq	BUA9112	15-May-91	31616	81			00-Jan-00							pbayou	HP	3305
bayouwq	BUP9107 BUO9108	15-May-91	31616	170			00-Jan-00							pbayou	HP	3301
bayouwq		15-May-91	31616	110			00-Jan-00							pbayou	HP	3299
bayouwq bayouwq	BUK9109 BUJ9112	15-May-91 15-May-91	31616 31616	110 99			00-Jan-00 00-Jan-00							pbayou pbayou		3291 3289
	BUH9112	15-May-91	31616	54			00-Jan-00 00-Jan-00							pbayou	HP	3289
bayouwq	BUD9111	15-May-91	31616	9			00-Jan-00							pbayou		3281
bayouwq	BUW9112	15-May-91	31616	450			00-Jan-00							pbayou		3313
bayouwq	BUS9112	15-May-91	31616	350			00-Jan-00							pbayou		3307
bayouwq	BUN9112	15-May-91	31616	130			00-Jan-00							pbayou	HP	3297
bayouwq	BUL9112	15-May-91	31616	160			00-Jan-00							pbayou		3293
bayouwq	BUM8403	16-May-84	31616	20800			00-Jan-00							pother1		9209
bayouwq	BUK8401	16-May-84	31616	1		11359	00-Jan-00							pother1	HP	9207

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUJ8403	16-May-84	31616	1		11360	00-Jan-00									pother1	HP	9206
	BUN8402	16-May-84	31616	23000			00-Jan-00									pother1	HP	9211
	BUB9408	17-May-94	31616	31000			00-Jan-00									9495a	HP	4229
	BUC9407	17-May-94	31616	800			00-Jan-00									9495a	HP	4231
* *	BUE9408 BUV9408	17-May-94 17-May-94	31616 31616	2400 4500			00-Jan-00 00-Jan-00									9495a 9495a	HP HP	4235 4265
• •	BUA9410	17-May-94 17-May-94	31616	11000			00-Jan-00 00-Jan-00									9495a 9495a	HP	4259
• •	BUP9408	17-May-94	31616	7000			00-Jan-00									9495a	HP	4257
	BUO9408	17-May-94	31616	5000			00-Jan-00									9495a	HP	4255
• •	BUM9408	17-May-94	31616	7500			00-Jan-00									9495a	HP	4251
	BUK9408	17-May-94	31616	6700		11359	00-Jan-00									9495a	HP	4247
bayouwq	BUJ9407	17-May-94	31616	5500		11360	00-Jan-00									9495a	HP	4245
bayouwq	BUI9403	17-May-94	31616	8800		11361	00-Jan-00									9495a	HP	4243
• •	BUH9408	17-May-94	31616	6000			00-Jan-00									9495a	HP	4241
• •	BUF9403	17-May-94	31616	3200			00-Jan-00									9495a	HP	4237
* *	BUD9408	17-May-94	31616	1500			00-Jan-00									9495a	HP	4233
	BUX9406	17-May-94	31616	4700			00-Jan-00									9495a	HP	4269
	BUW9407	17-May-94	31616	6200 13000			00-Jan-00									9495a	HP HP	4267 4261
	BUS9408 BUN9408	17-May-94 17-May-94	31616 31616	8900			00-Jan-00 00-Jan-00									9495a 9495a	HP	4253
bayouwq bayouwq	BUL9408	17-May-94 17-May-94	31616	7600	-		00-Jan-00 00-Jan-00									9495a 9495a	HP	4249
bayouwq	BUG9408	17-May-94	31616	5700			00-Jan-00									9495a	HP	4239
	BUE9607	20-May-96	31616	490			00-Jan-00									xls96	HP	1198
bayouwq	BUV9608	20-May-96	31616	680			00-Jan-00									xls96	HP	1212
	BUA9611	20-May-96	31616		BM		00-Jan-00								BM	xls96	HP	1209
	BUP9607	20-May-96	31616	600		11353	00-Jan-00									xls96	HP	1207
bayouwq	BUO9607	20-May-96	31616	270		11354	00-Jan-00									xls96	HP	1206
bayouwq	BUK9607	20-May-96	31616	600		11359	00-Jan-00									xls96	HP	1203
bayouwq	BUI9607	20-May-96	31616	7600		11361	00-Jan-00									xls96	HP	1202
	BUH9607	20-May-96	31616	840			00-Jan-00									xls96	HP	1201
• •	BUF9605	20-May-96	31616	520			00-Jan-00									xls96	HP	1199
	BUD9607	20-May-96	31616	460			00-Jan-00									xls96		1197
	BUX9607	20-May-96	31616	425			00-Jan-00									xls96	HP	1214
	BUW9605	20-May-96	31616	730			00-Jan-00									xls96	HP	1213
• •	BUS9607 BUQ9607	20-May-96 20-May-96	31616 31616	730 650			00-Jan-00 00-Jan-00									xls96 xls96	HP HP	1210 1208
	BUN9607	20-May-96	31616	300			00-Jan-00 00-Jan-00									xls96	HP	1208
• •	BUL9607	20-May-96	31616	3600			00-Jan-00									xls96	HP	1204
, ,	BUG9605	20-May-96	31616	830			00-Jan-00									xls96	HP	1200
• •	BUB9014	21-May-90	31616	91	-		00-Jan-00									pother1	HP	11433
• •	BUE9014	21-May-90	31616	1000			00-Jan-00									pother1	HP	11437
	BUA9015	21-May-90	31616	9100		11351	00-Jan-00									pother1	HP	11457
bayouwq	BUO9015	21-May-90	31616	1700		11354	00-Jan-00									pother1	HP	11453
bayouwq	BUM9014	21-May-90	31616	2300		11357	00-Jan-00									pother1	HP	11449
• •	BUK9013	21-May-90	31616	1100	-	11359	00-Jan-00									pother1	HP	11445
bayouwq	BUJ9013	21-May-90	31616	1700		11360	00-Jan-00									pother1	HP	11443
bayouwq	BUH9014	21-May-90	31616	1400			00-Jan-00									pother1	HP	11441
, ,	BUD9014	21-May-90	31616	360			00-Jan-00									pother1	HP	11435
	BUW9014	21-May-90	31616	5200			00-Jan-00									pother1	HP	11465
	BUU9014	21-May-90	31616	6200			00-Jan-00		1							pother1	HP	11463
	BUQ9014 BUL9013	21-May-90	31616	13000 3500	-		00-Jan-00		 							pother1		11455 11447
* *	BUG9013	21-May-90 21-May-90	31616 31616	1200			00-Jan-00 00-Jan-00		1							pother1 pother1		11447
• •	BUO8503	21-May-90 23-May-85	31616	2900			00-Jan-00 00-Jan-00		1							potner1 pother1		9436
• •	BUM8505	23-May-85	31616	3500	-		00-Jan-00 00-Jan-00		+							pother l		9433
	BUK8505	23-May-85	31616	3300			00-Jan-00									pother1	HP	9431
• •	BUJ8505	23-May-85	31616	20			00-Jan-00		1							pother1		9430
• •	BUH8505	23-May-85		900	-		00-Jan-00		1							pother1		9428

Database	TAG	END DATE	STORET CODE	GT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUX8505	23-May-85	31616	500		15840	00-Jan-00							pother1	HP	9447
bayouwq	BUW8505	23-May-85	31616	5200			00-Jan-00							pother1	HP	9444
	BUU8505	23-May-85	31616	17200			00-Jan-00							pother1	HP	9442
bayouwq	BUS8505	23-May-85	31616	2500			00-Jan-00							pother1	HP	9441
bayouwq	BUA9510	23-May-95	31616		BM		00-Jan-00						BM	9495a	HP	3997
bayouwq	BUA9613	23-May-96	31616	2200	ВМ		00-Jan-00						BM	xls96	HP	1238
bayouwq	BUV9409	24-May-94	31616	300			00-Jan-00							9495a	HP	4333
bayouwq	BUA9411	24-May-94	31616 31616	130 350			00-Jan-00							9495a 9495a	HP HP	4327 4325
	BUP9409 BUO9409	24-May-94 24-May-94	31616	310			00-Jan-00 00-Jan-00							9495a 9495a	HP	4323
bayouwq bayouwq	BUK9409	24-May-94	31616	120			00-Jan-00 00-Jan-00							9495a 9495a	HP	4323
bayouwq	BUJ9408	24-May-94	31616	130			00-Jan-00							9495a	HP	4313
bayouwq	BUI9404	24-May-94	31616	140			00-Jan-00							9495a	HP	4311
bayouwq	BUX9407	24-May-94	31616	140			00-Jan-00							9495a	HP	4337
bayouwq	BUS9409	24-May-94	31616	200			00-Jan-00							9495a	HP	4329
bayouwq	BUN9409	24-May-94	31616	150			00-Jan-00							9495a	HP	4321
bayouwq	BUG9409	24-May-94	31616	340			00-Jan-00							9495a	HP	4307
bayouwq	BUA9303	28-May-93	31616	34000			00-Jan-00						BM	pbayou	HP	4281
bayouwq	BUB9107	29-May-91	31616	54		11142	00-Jan-00							pbayou	HP	3352
	BUC9102	29-May-91	31616	27		11142	00-Jan-00							pbayou	HP	3350
	BUA9113	29-May-91	31616	560		11351	00-Jan-00							pbayou	HP	3378
bayouwq	BUP9108	29-May-91	31616	730		11353	00-Jan-00							pbayou	HP	3374
bayouwq	BUJ9113	29-May-91	31616	200		11360	00-Jan-00							pbayou	HP	3362
bayouwq	BUH9113	29-May-91	31616	54		11362	00-Jan-00							pbayou	HP	3360
bayouwq	BUD9112	29-May-91	31616	72		11364	00-Jan-00							pbayou	HP	3354
bayouwq	BUS9113	29-May-91	31616	3300		15843	00-Jan-00							pbayou	HP	3380
bayouwq	BUN9113	29-May-91	31616	680		15845	00-Jan-00							pbayou	HP	3370
bayouwq	BUL9113	29-May-91	31616	2400		15846	00-Jan-00							pbayou	HP	3366
bayouwq	BUB9015	30-May-90	31616	550		11142	00-Jan-00							pother1	HP	11504
bayouwq	BUE9015	30-May-90	31616	580			00-Jan-00							pother1	HP	11508
bayouwq	BUA9016	30-May-90	31616	9400			00-Jan-00							pother1	HP	11528
bayouwq	BUO9016	30-May-90	31616	9400			00-Jan-00							pother1	HP	11524
	BUM9015	30-May-90	31616	1600			00-Jan-00							pother1	HP	11520
	BUK9014	30-May-90	31616	5700			00-Jan-00							pother1	HP	11516
bayouwq	BUJ9014	30-May-90	31616	950			00-Jan-00							pother1	HP	11514
bayouwq	BUH9015	30-May-90	31616	4400			00-Jan-00							pother1	HP	11512
bayouwq	BUD9015	30-May-90	31616	820			00-Jan-00							pother1	HP	11506
bayouwq	BUW9015	30-May-90	31616	3300			00-Jan-00							pother1	HP	11536
bayouwq	BUU9015 BUS9015	30-May-90 30-May-90	31616 31616	6400 6300			00-Jan-00 00-Jan-00							pother1	HP HP	11534 11530
	BUQ9015	30-May-90	31616	7700			00-Jan-00 00-Jan-00							•	HP	11526
bayouwq	BUN9016	30-May-90	31616	11000			00-Jan-00 00-Jan-00							pother1 pother1	HP	11520
bayouwq bayouwq	BUL9014	30-May-90	31616	530			00-Jan-00 00-Jan-00							pother1	HP	11518
bayouwq	BUG9014	30-May-90	31616	3400			00-Jan-00							pother1	HP	11510
	BUB8802	01-Jun-88	31616	450			00-Jan-00							pother1	HP	9868
bayouwq	BUA8802	01-Jun-88	31616	6600			00-Jan-00							pother1	HP	9876
bayouwq	BUO8802	01-Jun-88	31616	4700			00-Jan-00							pother1	HP	9875
	BUM8802	01-Jun-88	31616	10			00-Jan-00							pother1	HP	9874
, ,	BUJ8802	01-Jun-88	31616	10			00-Jan-00							pother1		9872
	BUH8802	01-Jun-88	31616	5200			00-Jan-00							pother1	HP	9871
	BUD8802	01-Jun-88	31616	360			00-Jan-00							pother1	HP	9869
	BUX8802	01-Jun-88	31616	990			00-Jan-00							pother1	HP	9880
	BUW8802	01-Jun-88	31616	4300			00-Jan-00							pother1	HP	9879
bayouwq	BUU8802	01-Jun-88	31616	43000			00-Jan-00							pother1	HP	9878
	BUS8802	01-Jun-88	31616	5000			00-Jan-00							pother1	HP	9877
	BUL8802	01-Jun-88	31616	10			00-Jan-00							pother1	HP	9873
	BUG8802	01-Jun-88	31616	17000		15847	00-Jan-00							pother1	HP	9870
bayouwq	BUA9304	03-Jun-93	31616	1000	BM	11351	00-Jan-00						BM	pbayou	HP	5763

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUB9016	04-Jun-90	31616	1100		11142	00-Jan-00									pother1	HP	11575
	BUE9016	04-Jun-90	31616	11000			00-Jan-00									pother1	HP	11579
	BUA9017	04-Jun-90	31616	1200			00-Jan-00									pother1	HP	11599
	BUM9016	04-Jun-90 04-Jun-90	31616 31616	740 18			00-Jan-00									pother1	HP HP	11591 11587
	BUK9015 BUJ9015	04-Jun-90	31616	9			00-Jan-00 00-Jan-00									pother l	HP	11587
* *	BUH9016	04-Jun-90	31616	1300			00-Jan-00									pother1	HP	11583
-	BUD9016	04-Jun-90	31616	530			00-Jan-00									pother1	HP	11577
	BUW9016	04-Jun-90	31616	1500			00-Jan-00									pother1	HP	11607
	BUU9016	04-Jun-90	31616	50000		15842	00-Jan-00									pother1	HP	11605
bayouwq	BUS9016	04-Jun-90	31616	6000		15843	00-Jan-00									pother1	HP	11601
bayouwq	BUQ9016	04-Jun-90	31616	5900		15844	00-Jan-00									pother1	HP	11597
	BUN9017	04-Jun-90	31616	2800			00-Jan-00									pother1	HP	11593
. * *	BUL9015	04-Jun-90	31616	45			00-Jan-00									pother1	HP	11589
	BUG9016	04-Jun-90	31616	140			00-Jan-00									pother1	HP	11581
*	BUB9503	05-Jun-95	31616	200			00-Jan-00									9495a	HP	4906
	BUC9502 BUE9507	05-Jun-95 05-Jun-95	31616 31616	940 260			00-Jan-00 00-Jan-00									9495b 9495b	HP HP	12 14
	BUV9507	05-Jun-95	31616	8500			00-Jan-00 00-Jan-00									9495b		29
	BUA9511	05-Jun-95	31616	200			00-Jan-00								QC	9495a	HP	4904
bayouwq	BUP9506	05-Jun-95	31616	3200	QC		00-Jan-00								QC	9495b	HP	23
bayouwq	BUO9505	05-Jun-95	31616	1600			00-Jan-00									9495a	HP	4932
bayouwq	BUM9506	05-Jun-95	31616	11000			00-Jan-00									9495a	HP	4928
	BUK9506	05-Jun-95	31616	1000			00-Jan-00									9495b	HP	19
	BUJ9507	05-Jun-95	31616	950		11360	00-Jan-00									9495b	HP	18
bayouwq	BUI9506	05-Jun-95	31616	5500		11361	00-Jan-00									9495b	HP	32
bayouwq	BUH9507	05-Jun-95	31616	550		11362	00-Jan-00									9495b	HP	17
bayouwq	BUF9507	05-Jun-95	31616	420		11363	00-Jan-00									9495b	HP	15
bayouwq	BUD9507	05-Jun-95	31616	140		11364	00-Jan-00									9495a	HP	4910
	BUX9502	05-Jun-95	31616	5700			00-Jan-00									9495b		31
. * *	BUW9506	05-Jun-95	31616	3800			00-Jan-00									9495b	HP	30
	BUU9501	05-Jun-95	31616	4900			00-Jan-00									9495b		27
	BUS9507	05-Jun-95	31616	2200			00-Jan-00									9495b	HP	26
	BUQ9504 BUN9506	05-Jun-95 05-Jun-95	31616 31616	1100 2100			00-Jan-00 00-Jan-00									9495a 9495b	HP HP	4936 22
	BUL9507	05-Jun-95	31616	1200			00-Jan-00 00-Jan-00									9495b		20
	BUG9504	05-Jun-95	31616	380			00-Jan-00									9495b	HP	16
-	BUB9602	05-Jun-96	31616	330			00-Jan-00									bayou95		9
	BUC9601	05-Jun-96	31616	940			00-Jan-00									bayou95		10
* *	BUE9608	05-Jun-96	31616	260			00-Jan-00									bayou95	HP	12
bayouwq	BUV9609	05-Jun-96	31616	8500		11345	00-Jan-00									bayou95	HP	27
bayouwq	BUA9614	05-Jun-96	31616	4200	BM	11351	00-Jan-00								BM	bayou95	HP	23
	BUP9608	05-Jun-96	31616	3200		11353	00-Jan-00									bayou95		21
bayouwq	BUO9608	05-Jun-96	31616	1600			00-Jan-00									bayou95		31
bayouwq	BUM9607	05-Jun-96	31616	1300			00-Jan-00									bayou95		19
bayouwq	BUK9608	05-Jun-96	31616	1000			00-Jan-00									bayou95	HP	17
bayouwq	BUJ9605	05-Jun-96	31616	950			00-Jan-00									bayou95	HP	16
	BUI9608	05-Jun-96	31616	5500			00-Jan-00									bayou95	HP	30
*	BUH9608	05-Jun-96	31616	550			00-Jan-00									bayou95		15
* *	BUF9606 BUD9608	05-Jun-96 05-Jun-96	31616 31616	420 1000			00-Jan-00 00-Jan-00				 					bayou95 bayou95		13 11
-	BUX9608	05-Jun-96 05-Jun-96	31616	5700			00-Jan-00 00-Jan-00									bayou95		29
	BUW9606	05-Jun-96	31616	3800			00-Jan-00 00-Jan-00									bayou95	HP	28
-	BUU9601	05-Jun-96	31616	4900			00-Jan-00									bayou95		25
-	BUS9608	05-Jun-96	31616	2200			00-Jan-00									bayou95	HP	24
	BUQ9608	05-Jun-96	31616	2400			00-Jan-00									bayou95	HP	22
* *	BUN9608	05-Jun-96	31616	2100			00-Jan-00									bayou95		20
bayouwq	BUL9608	05-Jun-96	31616	1200		15846	00-Jan-00									bayou95	HP	18

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUG9606	05-Jun-96	31616	380		15847	00-Jan-00							bayou95	HP	14
bayouwq	BUV9508	06-Jun-95	31616	6800			00-Jan-00							9495a		5295
bayouwq	BUB9410	07-Jun-94	31616	460			00-Jan-00							9495a		847
bayouwq	BUC9408	07-Jun-94	31616	480			00-Jan-00							9495a	HP	849
bayouwq	BUE9410	07-Jun-94	31616	2300 2100			00-Jan-00							9495a	HP HP	853
bayouwq bayouwq	BUV9410 BUA9412	07-Jun-94 07-Jun-94	31616 31616	1600			00-Jan-00 00-Jan-00							9495a 9495a		883 875
bayouwq	BUP9410	07-Jun-94	31616	500			00-Jan-00							9495a		871
bayouwq	BUO9410	07-Jun-94	31616	640			00-Jan-00							9495a		869
bayouwq	BUM9410	07-Jun-94	31616	560			00-Jan-00							9495a	HP	865
bayouwq	BUK9410	07-Jun-94	31616	2000		11359	00-Jan-00							9495a	HP	861
bayouwq	BUJ9409	07-Jun-94	31616	1300		11360	00-Jan-00							9495a	HP	859
bayouwq	BUI9405	07-Jun-94	31616	2100		11361	00-Jan-00							9495a	HP	857
bayouwq	BUH9410	07-Jun-94	31616	2600		11362	00-Jan-00							9495a	HP	855
bayouwq	BUD9410	07-Jun-94	31616	400			00-Jan-00							9495a		851
bayouwq	BUX9408	07-Jun-94	31616	4400			00-Jan-00							9495a	HP	885
bayouwq	BUU9408	07-Jun-94	31616	2300 1500			00-Jan-00							9495a 9495a	HP HP	881 877
bayouwq	BUS9410 BUQ9406	07-Jun-94 07-Jun-94	31616 31616	950			00-Jan-00 00-Jan-00							9495a 9495a	HP	873
bayouwq bayouwq	BUN9410	07-Jun-94	31616	610			00-Jan-00 00-Jan-00							9495a 9495a		867
bayouwq	BUL9410	07-Jun-94	31616	1000			00-Jan-00							9495a	HP	863
bayouwq	BUV9304	09-Jun-93	31616	8100			00-Jan-00							pbayou	HP	6310
bayouwq	BUA9305	09-Jun-93	31616	2600			00-Jan-00							pbayou	HP	6302
bayouwq	BUA9306	10-Jun-93	31616	4100	BM	11351	00-Jan-00						BM	pbayou	HP	5810
bayouwq	BUE9609	10-Jun-96	31616	180		11163	00-Jan-00							xls96	HP	1338
bayouwq	BUV9610	10-Jun-96	31616	580		11345	00-Jan-00							xls96	HP	1354
bayouwq	BUA9615	10-Jun-96	31616	1200	-		00-Jan-00						QC	xls96	HP	1336
bayouwq	BUP9609	10-Jun-96	31616	670			00-Jan-00							xls96	HP	1349
bayouwq	BUO9609	10-Jun-96	31616	520			00-Jan-00							xls96	HP	1348
bayouwq	BUM9608	10-Jun-96	31616	3300			00-Jan-00							xls96	HP	1346
bayouwq bayouwq	BUK9609 BUJ9606	10-Jun-96 10-Jun-96	31616 31616	2100 770			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	1344 1343
bayouwq	BUI9609	10-Jun-96	31616	590			00-Jan-00 00-Jan-00							xls96	HP	1343
bayouwq	BUH9609	10-Jun-96	31616	530			00-Jan-00							xls96	HP	1341
bayouwq	BUF9607	10-Jun-96	31616	560			00-Jan-00							xls96	HP	1339
bayouwq	BUD9609	10-Jun-96	31616	360			00-Jan-00							xls96	HP	1337
bayouwq	BUX9609	10-Jun-96	31616	2700		15840	00-Jan-00							xls96	HP	1356
bayouwq	BUW9607	10-Jun-96	31616	890		15841	00-Jan-00							xls96	HP	1355
bayouwq	BUS9609	10-Jun-96	31616	2800			00-Jan-00							xls96	HP	1352
bayouwq	BUQ9609	10-Jun-96	31616	590			00-Jan-00							xls96	HP	1350
bayouwq	BUN9609	10-Jun-96	31616	650			00-Jan-00							xls96	HP	1347
bayouwq	BUL9609	10-Jun-96	31616	1000			00-Jan-00							xls96	HP	1345
bayouwq	BUG9607 BUB9017	10-Jun-96 12-Jun-90	31616 31616	1000 6000			00-Jan-00 00-Jan-00							xls96	HP HP	1340 11646
bayouwq bayouwq	BUE9017	12-Jun-90	31616	310			00-Jan-00 00-Jan-00							pother l	HP	11650
bayouwq	BUM9017	12-Jun-90	31616	2700			00-Jan-00							pother1	HP	11662
bayouwq	BUK9016	12-Jun-90	31616	72			00-Jan-00							pother1	HP	11658
bayouwq	BUJ9016	12-Jun-90	31616	710			00-Jan-00							pother1	HP	11656
bayouwq	BUH9017	12-Jun-90	31616	3600		11362	00-Jan-00							pother1	HP	11654
bayouwq	BUD9017	12-Jun-90	31616	5300			00-Jan-00							pother1		11648
bayouwq	BUW9017	12-Jun-90	31616	40000		15841	00-Jan-00		•					pother1	HP	11678
bayouwq	BUU9017	12-Jun-90	31616	130000			00-Jan-00							pother1		11676
bayouwq	BUS9017	12-Jun-90	31616	15000			00-Jan-00							pother1		11672
bayouwq	BUQ9017	12-Jun-90	31616	3200			00-Jan-00							pother1	HP	11668
bayouwq	BUN9018	12-Jun-90	31616	4000			00-Jan-00							pother1	HP	11664
bayouwq	BUL9016	12-Jun-90	31616	910			00-Jan-00							pother1	HP	11660
	BUG9017	12-Jun-90	31616	4600			00-Jan-00							pother1	HP	11652
bayouwq	BUV8302	13-Jun-83	31616	38000		11345	00-Jan-00							pother1	HP	8996

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUA8303	13-Jun-83	31616	2000		11351	00-Jan-00									pother1	HP	8991
bayouwq	BUO8303	13-Jun-83	31616	1000			00-Jan-00									pother1	HP	8989
bayouwq	BUM8304	13-Jun-83	31616	3000			00-Jan-00									pother1	HP	8986
bayouwq	BUJ8304	13-Jun-83 13-Jun-83	31616 31616	1			00-Jan-00									pother1	HP HP	8983 8981
bayouwq bayouwq	BUH8304 BUX8302	13-Jun-83 13-Jun-83	31616	1			00-Jan-00 00-Jan-00									pother1 pother1	HP	9000
bayouwq	BUW8302	13-Jun-83	31616	9000			00-Jan-00									pother1	HP	8997
bayouwq	BUS8302	13-Jun-83	31616	32000			00-Jan-00									pother1	HP	8994
bayouwq	BUA8906	13-Jun-89	31616	560			00-Jan-00									pother1	HP	10172
bayouwq	BUO8905	13-Jun-89	31616	1100		11354	00-Jan-00									pother1	HP	10170
bayouwq	BUM8906	13-Jun-89	31616	200		11357	00-Jan-00									pother1	HP	10168
bayouwq	BUJ8906	13-Jun-89	31616	1400		11360	00-Jan-00									pother1	HP	10166
bayouwq	BUH8906	13-Jun-89	31616	840			00-Jan-00									pother1	HP	10165
bayouwq	BUD8905	13-Jun-89	31616	1100			00-Jan-00									pother1	HP	10163
bayouwq	BUX8906	13-Jun-89	31616	320			00-Jan-00									pother1	HP	10177
bayouwq	BUW8904	13-Jun-89	31616	260			00-Jan-00									pother1	HP	10176
bayouwq	BUU8906	13-Jun-89	31616	340			00-Jan-00									pother1	HP	10175
bayouwq	BUS8906	13-Jun-89	31616	850		1	00-Jan-00									pother1	HP	10173
bayouwq	BUQ8904	13-Jun-89	31616	410 2100			00-Jan-00									pother1	HP HP	10171
bayouwa	BUN8904 BUL8906	13-Jun-89 13-Jun-89	31616 31616	200			00-Jan-00 00-Jan-00									pother1 pother1	HP	10169 10167
bayouwa	BUG8906	13-Jun-89	31616	1900		1	00-Jan-00									pother1	HP	10167
bayouwq bayouwq	BUA9114	13-Jun-91	31616	2100			00-Jan-00									pbayou	HP	4787
bayouwq	BUP9109	13-Jun-91	31616	5100		1	00-Jan-00									pbayou	HP	4783
bayouwq	BUO9109	13-Jun-91	31616	3400			00-Jan-00									pbayou	HP	4781
bayouwq	BUM9107	13-Jun-91	31616	2800			00-Jan-00									pbayou	HP	4777
bayouwq	BUK9110	13-Jun-91	31616	3400			00-Jan-00									pbayou	HP	4773
bayouwq	BUJ9114	13-Jun-91	31616	1800			00-Jan-00									pbayou	HP	4771
bayouwq	BUW9113	13-Jun-91	31616	7000		15841	00-Jan-00									pbayou	HP	4795
bayouwq	BUU9105	13-Jun-91	31616	9000		15842	00-Jan-00									pbayou	HP	4793
bayouwq	BUS9114	13-Jun-91	31616	5500		15843	00-Jan-00									pbayou	HP	4789
bayouwq	BUQ9107	13-Jun-91	31616	2800		15844	00-Jan-00									pbayou	HP	4785
bayouwq	BUN9114	13-Jun-91	31616	6500		15845	00-Jan-00									pbayou	HP	4779
bayouwq	BUL9114	13-Jun-91	31616	8500			00-Jan-00									pbayou	HP	4775
bayouwq	BUA8703	15-Jun-87	31616	4800			00-Jan-00									pother1	HP	9807
bayouwq	BUO8703	15-Jun-87	31616	2600			00-Jan-00									pother1	HP	9806
bayouwq	BUM8703	15-Jun-87	31616	2400			00-Jan-00									pother1	HP	9805
bayouwq	BUJ8703	15-Jun-87	31616	510 3400			00-Jan-00									pother1	HP HP	9803 9802
bayouwa	BUH8703 BUD8703	15-Jun-87 15-Jun-87	31616 31616	270			00-Jan-00 00-Jan-00									pother1 pother1	HP	9802
bayouwq bayouwq	BUX8703	15-Jun-87	31616	480		1	00-Jan-00									pother1	HP	9811
bayouwq	BUW8703	15-Jun-87	31616	2300			00-Jan-00									pother1	HP	9810
bayouwq	BUU8703	15-Jun-87	31616	4600			00-Jan-00									pother1	HP	9809
bayouwq	BUS8703	15-Jun-87	31616	2100		1	00-Jan-00									pother1	HP	9808
bayouwq	BUL8703	15-Jun-87	31616	2600			00-Jan-00									pother1	HP	9804
bayouwq	BUG8703	15-Jun-87	31616	1400			00-Jan-00									pother1	HP	9801
bayouwq	BUV9305	15-Jun-93	31616	12000		11345	00-Jan-00									pbayou	HP	6022
bayouwq	BUA9307	15-Jun-93	31616	2500		11351	00-Jan-00									pbayou	HP	6016
bayouwq	BUP9303	15-Jun-93	31616	3700		11353	00-Jan-00									pbayou	HP	6012
	BUO9303	15-Jun-93	31616	2400			00-Jan-00									pbayou	HP	6010
bayouwq	BUJ9303	15-Jun-93	31616	540			00-Jan-00									pbayou	HP	6000
bayouwq	BUD9303	15-Jun-93	31616	430			00-Jan-00									pbayou	HP	5992
bayouwq	BUX9302	15-Jun-93	31616	590			00-Jan-00									pbayou	HP	6026
bayouwq	BUW9302	15-Jun-93	31616	11000			00-Jan-00									pbayou	HP	6024
bayouwq	BUS9303	15-Jun-93	31616	2600			00-Jan-00				-					pbayou	HP	6018
bayouwq	BUN9303	15-Jun-93	31616	3900			00-Jan-00				-					pbayou	HP	6008
	BUL9302	15-Jun-93	31616	680			00-Jan-00				-				DM	pbayou	HP	6004
bayouwq	BUA9308	16-Jun-93	31616	2700	вM	11351	00-Jan-00			<u> </u>	1		l		BM	pbayou	HP	5857

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUB9108	17-Jun-91	31616	6700		11142	00-Jan-00							pbayou	HP	4834
	BUE9107	17-Jun-91	31616	5400			00-Jan-00							pbayou	HP	4838
. * *	BUA9115	17-Jun-91	31616	22000			00-Jan-00							pbayou	HP	4860
	BUP9110	17-Jun-91	31616	23000			00-Jan-00							pbayou	HP	4856
	BUO9110 BUM9108	17-Jun-91 17-Jun-91	31616 31616	29000 7000			00-Jan-00 00-Jan-00							pbayou	HP HP	4854 4850
	BUK9111	17-Jun-91 17-Jun-91	31616	9600			00-Jan-00 00-Jan-00							pbayou pbayou	HP	4846
-	BUJ9115	17-Jun-91	31616	19000			00-Jan-00							pbayou	HP	4844
	BUH9114	17-Jun-91	31616	15000			00-Jan-00							pbayou	HP	4842
-	BUD9113	17-Jun-91	31616	8000		11364	00-Jan-00							pbayou	HP	4836
	BUW9114	17-Jun-91	31616	48000		15841	00-Jan-00							pbayou	HP	4868
bayouwq	BUU9106	17-Jun-91	31616	35000		15842	00-Jan-00							pbayou	HP	4866
bayouwq	BUS9115	17-Jun-91	31616	31000		15843	00-Jan-00							pbayou	HP	4862
	BUQ9108	17-Jun-91	31616	20000			00-Jan-00							pbayou	HP	4858
-	BUN9115	17-Jun-91	31616	25000			00-Jan-00							pbayou	HP	4852
	BUL9115	17-Jun-91	31616	15000			00-Jan-00							pbayou	HP	4848
	BUG9107 BUB9018	17-Jun-91 20-Jun-90	31616 31616	7800 48000			00-Jan-00 00-Jan-00							pbayou pother1	HP HP	4840 11717
-	BUE9018	20-Jun-90 20-Jun-90	31616	18000		_	00-Jan-00 00-Jan-00							pother1	HP	11717
	BUA9019	20-Jun-90	31616	2400			00-Jan-00							pother1	HP	11741
	BUO9017	20-Jun-90	31616	2200			00-Jan-00							pother1	HP	11737
-	BUK9017	20-Jun-90	31616	2800		11359	00-Jan-00							pother1	HP	11729
	BUJ9017	20-Jun-90	31616	2300		11360	00-Jan-00							pother1	HP	11727
bayouwq	BUH9018	20-Jun-90	31616	11000		11362	00-Jan-00							pother1	HP	11725
	BUD9018	20-Jun-90	31616	20000			00-Jan-00							pother1	HP	11719
-	BUX9012	20-Jun-90	31616	2700			00-Jan-00							pother1	HP	11753
	BUW9018	20-Jun-90	31616	4600			00-Jan-00							pother1	HP	11749
. * *	BUU9018	20-Jun-90	31616	9700			00-Jan-00							pother l	HP	11747
-	BUS9018 BUQ9018	20-Jun-90 20-Jun-90	31616 31616	14000 15000			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	11743 11739
	BUN9019	20-Jun-90	31616	3200			00-Jan-00 00-Jan-00							pother1	HP	11735
	BUL9017	20-Jun-90	31616	8900			00-Jan-00							pother1	HP	11731
, ,	BUG9018	20-Jun-90	31616	18000			00-Jan-00							pother1	HP	11723
	BUV9203	22-Jun-92	31616	71000			00-Jan-00							pbayou	HP	5289
bayouwq	BUA9203	22-Jun-92	31616	4500		11351	00-Jan-00							pbayou	HP	5281
bayouwq	BUP9203	22-Jun-92	31616	2300		11353	00-Jan-00							pbayou	HP	5277
-	BUO9203	22-Jun-92	31616	1500			00-Jan-00							pbayou	HP	5275
	BUM9203	22-Jun-92	31616	15000			00-Jan-00							pbayou	HP	5271
. * *	BUK9203	22-Jun-92	31616	19000			00-Jan-00							pbayou	HP	5267
-	BUJ9203	22-Jun-92	31616	2400			00-Jan-00							pbayou	HP	5265
	BUH9203 BUW9203	22-Jun-92 22-Jun-92	31616 31616	780 22000			00-Jan-00 00-Jan-00							pbayou	HP HP	5263 5291
	BUS9203	22-Jun-92	31616	4000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	5283
	BUN9203	22-Jun-92	31616	9900			00-Jan-00							pbayou	HP	5273
	BUB9019	26-Jun-90	31616	2200			00-Jan-00							pother1	HP	11788
	BUE9019	26-Jun-90	31616	100000			00-Jan-00							pother1	HP	11792
bayouwq	BUA9020	26-Jun-90	31616	150000		11351	00-Jan-00							pother1	HP	11812
bayouwq	BUM9019	26-Jun-90	31616	53000		11357	00-Jan-00							pother1	HP	11804
	BUK9018	26-Jun-90	31616	51000			00-Jan-00							pother1	HP	11800
	BUJ9018	26-Jun-90	31616	120000			00-Jan-00							pother1	HP	11798
	BUH9019	26-Jun-90	31616	130000			00-Jan-00							pother1	HP	11796
	BUD9019	26-Jun-90	31616	3400			00-Jan-00							pother1	HP	11790
	BUX9013 BUW9019	26-Jun-90 26-Jun-90	31616 31616	4600 150000			00-Jan-00 00-Jan-00					-		pother1	HP HP	11824 11820
	BUU9019	26-Jun-90 26-Jun-90	31616	190000			00-Jan-00 00-Jan-00							pother1 pother1	HP	11820
	BUS9019	26-Jun-90 26-Jun-90	31616	120000			00-Jan-00 00-Jan-00							pother1	HP	11818
	BUQ9019	26-Jun-90	31616	140000			00-Jan-00							pother l	HP	11810
-	BUN9020	26-Jun-90	31616	88000			00-Jan-00							pother1	HP	11806

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUL9018	26-Jun-90	31616	84000		15846	00-Jan-00									pother1	HP	11802
	BUG9019	26-Jun-90	31616	48000			00-Jan-00									pother1	HP	11794
	BUA9512	27-Jun-95	31616	3100	-		00-Jan-00								BM	9495a	HP	4675
	BUB9411	28-Jun-94 28-Jun-94	31616 31616	900			00-Jan-00									9495a 9495a	HP HP	915 917
	BUC9409 BUE9411	28-Jun-94 28-Jun-94	31616	490			00-Jan-00 00-Jan-00									9495a 9495a		921
• •	BUV9411	28-Jun-94	31616	3900			00-Jan-00									9495a		955
	BUA9413	28-Jun-94	31616	1000			00-Jan-00									9495a		947
	BUP9411	28-Jun-94	31616	310			00-Jan-00									9495a	HP	943
	BUO9411	28-Jun-94	31616	420		11354	00-Jan-00									9495a	HP	941
bayouwq	BUM9411	28-Jun-94	31616	370		11357	00-Jan-00									9495a	HP	937
bayouwq	BUK9411	28-Jun-94	31616	440		11359	00-Jan-00									9495a		933
	BUJ9410	28-Jun-94	31616	530			00-Jan-00									9495a		931
• •	BUI9406	28-Jun-94	31616	500	-		00-Jan-00									9495a		929
	BUH9411	28-Jun-94	31616	490			00-Jan-00									9495a		927
	BUF9406	28-Jun-94	31616	550			00-Jan-00									9495a		923
. * *	BUD9411	28-Jun-94	31616	1100		-	00-Jan-00									9495a		919
	BUX9409 BUW9408	28-Jun-94 28-Jun-94	31616 31616	1700 4200			00-Jan-00									9495a 9495a		959 957
	BUU9409	28-Jun-94 28-Jun-94	31616	3000		-	00-Jan-00 00-Jan-00									9495a 9495a		957
bayouwq bayouwq	BUS9411	28-Jun-94	31616	2700	-		00-Jan-00 00-Jan-00									9495a 9495a		949
bayouwq	BUQ9407	28-Jun-94	31616	480			00-Jan-00									9495a	HP	945
	BUN9411	28-Jun-94	31616	2700			00-Jan-00									9495a		939
• •	BUL9411	28-Jun-94	31616	450			00-Jan-00									9495a		935
	BUG9411	28-Jun-94	31616	750			00-Jan-00									9495a	HP	925
• •	BUA9309	29-Jun-93	31616	6800	BM	11351	00-Jan-00								BM	pbayou	HP	5905
bayouwq	BUB9109	01-Jul-91	31616	830		11142	00-Jan-00									pbayou	HP	6434
bayouwq	BUE9108	01-Jul-91	31616	130		11163	00-Jan-00									pbayou	HP	6438
bayouwq	BUA9116	01-Jul-91	31616	1100		11351	00-Jan-00									pbayou	HP	6460
	BUP9111	01-Jul-91	31616	690			00-Jan-00									pbayou	HP	6456
	BUO9111	01-Jul-91	31616	540			00-Jan-00									pbayou	HP	6454
	BUM9109	01-Jul-91	31616	6700			00-Jan-00									pbayou	HP	6450
	BUK9112	01-Jul-91	31616	430			00-Jan-00									pbayou	HP	6446
	BUJ9116	01-Jul-91	31616	400			00-Jan-00									pbayou	HP	6444
. *	BUH9115 BUD9114	01-Jul-91 01-Jul-91	31616 31616	290 700			00-Jan-00 00-Jan-00									pbayou	HP HP	6442 6436
	BUX9102	01-Jul-91	31616	1200			00-Jan-00 00-Jan-00									pbayou pbayou	HP	6472
	BUW9115	01-Jul-91	31616	9900			00-Jan-00									pbayou	HP	6468
	BUU9107	01-Jul-91	31616	1300			00-Jan-00									pbayou	HP	6466
• •	BUS9116	01-Jul-91	31616	1000	-		00-Jan-00									pbayou	HP	6462
	BUQ9109	01-Jul-91	31616	960			00-Jan-00									pbayou	HP	6458
	BUN9116	01-Jul-91	31616	660			00-Jan-00									pbayou	HP	6452
bayouwq	BUL9116	01-Jul-91	31616	480		15846	00-Jan-00									pbayou	HP	6448
bayouwq	BUG9108	01-Jul-91	31616	900		15847	00-Jan-00									pbayou	HP	6440
bayouwq	BUB9020	02-Jul-90	31616	2300		11142	00-Jan-00									pother1	HP	11859
bayouwq	BUE9020	02-Jul-90	31616	1000		11163	00-Jan-00									pother1	HP	11863
bayouwq	BUA9021	02-Jul-90	31616	3500			00-Jan-00									pother1	HP	11883
1	BUO9018	02-Jul-90		8900			00-Jan-00									pother1	HP	11879
	BUM9020	02-Jul-90	31616	4500			00-Jan-00									pother1	HP	11875
	BUK9019	02-Jul-90	31616	27000			00-Jan-00				-					pother1	HP	11871
	BUJ9019	02-Jul-90 02-Jul-90	31616	25000 2300	-	-	00-Jan-00				-					pother1	HP HP	11869 11867
	BUH9020 BUD9020	02-Jul-90 02-Jul-90	31616 31616	1800			00-Jan-00 00-Jan-00									pother1 pother1	HP	11867
• •	BUX9014	02-Jul-90 02-Jul-90	31616	660	-		00-Jan-00 00-Jan-00									potner1 pother1	HP	11895
	BUW9020	02-Jul-90	31616	2300	-		00-Jan-00 00-Jan-00									pother l	HP	11891
	BUU9020	02-Jul-90	31616	17000			00-Jan-00									pother1	HP	11889
• •	BUS9020	02-Jul-90	31616	2100	-		00-Jan-00									pother1		11885
	BUQ9020	02-Jul-90	31616	10000		-	00-Jan-00									pother1	HP	11881

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUN9021	02-Jul-90	31616	19000		15845	00-Jan-00							pother1	HP	11877
bayouwq	BUL9019	02-Jul-90	31616	100000			00-Jan-00							pother1	HP	11873
bayouwq	BUG9020	02-Jul-90	31616	3600			00-Jan-00							pother1	HP	11865
bayouwq	BUB9504	03-Jul-95	31616	200			00-Jan-00							9495a	HP	5472
bayouwq	BUC9503	03-Jul-95	31616	290			00-Jan-00							9495a	HP	5474
bayouwq	BUE9508 BUV9509	03-Jul-95 03-Jul-95	31616 31616	270 6900		l	00-Jan-00 00-Jan-00							9495a 9495a	HP HP	5478 5512
bayouwq bayouwq	BUA9513	03-Jul-95	31616	1300	BM		00-Jan-00 00-Jan-00						BM	9495a 9495a	HP	5504
bayouwq	BUP9507	03-Jul-95	31616	1400	DIVI		00-Jan-00						BW	9495a	HP	5500
bayouwq	BUO9506	03-Jul-95	31616	1600		l	00-Jan-00							9495a	HP	5498
bayouwq	BUM9507	03-Jul-95	31616	11000			00-Jan-00							9495a	HP	5494
bayouwq	BUK9507	03-Jul-95	31616	5000			00-Jan-00							9495a	HP	5490
bayouwq	BUJ9508	03-Jul-95	31616	2400		11360	00-Jan-00							9495a	HP	5488
bayouwq	BUI9507	03-Jul-95	31616	6500		11361	00-Jan-00							9495a	HP	5486
bayouwq	BUH9508	03-Jul-95	31616	20000		11362	00-Jan-00							9495a	HP	5484
bayouwq	BUF9508	03-Jul-95	31616	1100			00-Jan-00							9495a	HP	5480
bayouwq	BUD9508	03-Jul-95	31616	140			00-Jan-00							9495a	HP	5476
bayouwq	BUX9503	03-Jul-95	31616	5000		l	00-Jan-00							9495a	HP	5516
bayouwq	BUU9502	03-Jul-95	31616	9800			00-Jan-00							9495a	HP	5508
bayouwq	BUS9508	03-Jul-95	31616	1100			00-Jan-00							9495a	HP	5506
bayouwq	BUQ9505	03-Jul-95 03-Jul-95	31616 31616	1100 4000			00-Jan-00							9495a 9495a	HP HP	5502 5496
bayouwq	BUN9507 BUL9508	03-Jul-95	31616	8000			00-Jan-00 00-Jan-00							9495a 9495a	HP	5496
bayouwq	BUG9505	03-Jul-95	31616	270		l	00-Jan-00 00-Jan-00							9495a 9495a	HP	5482
bayouwq bayouwq	BUB9412	05-Jul-94	31616	560			00-Jan-00							9495a	HP	1347
bayouwq	BUC9410	05-Jul-94	31616	490			00-Jan-00							9495a	HP	1349
bayouwq	BUE9412	05-Jul-94	31616	460			00-Jan-00							9495a	HP	1353
bayouwq	BUV9412	05-Jul-94	31616	3100			00-Jan-00							9495a	HP	1387
bayouwq	BUA9414	05-Jul-94	31616	3000			00-Jan-00							9495a	HP	1379
bayouwq	BUP9412	05-Jul-94	31616	590		11353	00-Jan-00							9495a	HP	1375
bayouwq	BUO9412	05-Jul-94	31616	560		11354	00-Jan-00							9495a	HP	1373
bayouwq	BUM9412	05-Jul-94	31616	350		11357	00-Jan-00							9495a	HP	1369
bayouwq	BUK9412	05-Jul-94	31616	440			00-Jan-00							9495a	HP	1365
bayouwq	BUJ9411	05-Jul-94	31616	530		l	00-Jan-00							9495a	HP	1363
bayouwq	BUI9407	05-Jul-94	31616	600			00-Jan-00							9495a	HP	1361
bayouwq	BUH9412	05-Jul-94	31616	380			00-Jan-00							9495a	HP	1359
bayouwq	BUF9407	05-Jul-94	31616	580			00-Jan-00							9495a	HP	1355
bayouwq	BUD9412	05-Jul-94 05-Jul-94	31616	420 5400			00-Jan-00							9495a 9495a	HP HP	1351 1389
bayouwq bayouwq	BUW9409 BUS9412	05-Jul-94 05-Jul-94	31616 31616	83000		l	00-Jan-00 00-Jan-00							9495a 9495a	HP	1389
bayouwq	BUN9412	05-Jul-94	31616	610			00-Jan-00							9495a	HP	1371
bayouwq	BUL9412	05-Jul-94	31616	520			00-Jan-00							9495a	HP	1367
bayouwq	BUG9412	05-Jul-94	31616	450		l	00-Jan-00							9495a	HP	1357
bayouwq	BUV9510	05-Jul-95	31616	60000			00-Jan-00							9495a	HP	5811
bayouwq	BUB9201	06-Jul-92	31616	3700			00-Jan-00							pbayou	HP	7267
bayouwq	BUE9203	06-Jul-92	31616	730		11163	00-Jan-00							pbayou	HP	7271
bayouwq	BUV9204	06-Jul-92	31616	6000		11345	00-Jan-00							pbayou	HP	7301
bayouwq	BUA9204	06-Jul-92	31616	550		11351	00-Jan-00							pbayou	HP	7293
bayouwq	BUP9204	06-Jul-92	31616	1400			00-Jan-00							pbayou	HP	7289
bayouwq	BUO9204	06-Jul-92	31616	3200			00-Jan-00							pbayou	HP	7287
	BUK9204	06-Jul-92	31616	3500			00-Jan-00							pbayou	HP	7279
bayouwq	BUJ9204	06-Jul-92	31616	5000			00-Jan-00							pbayou	HP	7277
bayouwq	BUH9204	06-Jul-92	31616	8200			00-Jan-00							pbayou	HP	7275
bayouwq	BUD9203	06-Jul-92	31616	17000			00-Jan-00					-		pbayou	HP	7269
bayouwq	BUW9204	06-Jul-92	31616	1600			00-Jan-00							pbayou	HP	7303
bayouwq	BUS9204 BUN9204	06-Jul-92 06-Jul-92	31616 31616	2400 1000			00-Jan-00 00-Jan-00							pbayou	HP HP	7295 7285
bayouwq	BUL9203	06-Jul-92 06-Jul-92	31616	3700								1		pbayou		7285
bayouwq	DUL9203	00-Jul-92	31010	3/00		13846	00-Jan-00			1				pbayou	пґ	1401

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUG9202	06-Jul-92	31616	9700		15847	00-Jan-00									pbayou	HP	7273
	BUB8803	07-Jul-88	31616	12400		11142	00-Jan-00									pother1	HP	9891
• •	BUA8803	07-Jul-88	31616	47000			00-Jan-00									pother1	HP	9899
	BUO8803	07-Jul-88	31616	31000			00-Jan-00									pother1	HP	9898
	BUM8803	07-Jul-88	31616	4600			00-Jan-00									pother1	HP	9897
	BUJ8803	07-Jul-88	31616	10			00-Jan-00									pother1	HP	9895
	BUH8803	07-Jul-88	31616	1510			00-Jan-00									pother1	HP	9894
	BUD8803	07-Jul-88	31616	13700			00-Jan-00									pother1	HP	9892
	BUX8803	07-Jul-88	31616	260			00-Jan-00									pother1	HP	9904
	BUW8803	07-Jul-88	31616	25000			00-Jan-00									pother1	HP	9903
	BUU8803	07-Jul-88	31616	33000			00-Jan-00									pother1	HP	9902
	BUS8803	07-Jul-88	31616	38000			00-Jan-00									pother1	HP	9900
	BUL8803	07-Jul-88 07-Jul-88	31616	430 12300			00-Jan-00									pother1	HP HP	9896 9893
	BUG8803 BUA9310	07-Jul-88 07-Jul-93	31616 31616	14000	DM		00-Jan-00								BM	pother1	HP	7777
	BUB9110	07-Jul-93 09-Jul-91	31616	9300	DIVI		00-Jan-00 00-Jan-00								BIVI	pbayou	HP	6509
	BUE9109	09-Jul-91	31616	2100			00-Jan-00 00-Jan-00									pbayou pbayou	HP	6513
• •	BUA9117	09-Jul-91	31616	9500			00-Jan-00									pbayou	HP	6535
	BUP9112	09-Jul-91	31616	32000			00-Jan-00									pbayou	HP	6531
	BUO9112	09-Jul-91	31616	44000			00-Jan-00									pbayou	HP	6529
bayouwq	BUM9110	09-Jul-91	31616	7500			00-Jan-00									pbayou	HP	6525
	BUK9113	09-Jul-91	31616	8000			00-Jan-00									pbayou	HP	6521
bayouwq	BUJ9117	09-Jul-91	31616	9400			00-Jan-00									pbayou	HP	6519
	BUH9116	09-Jul-91	31616	23000			00-Jan-00									pbayou	HP	6517
	BUD9115	09-Jul-91	31616	9100			00-Jan-00									pbayou	HP	6511
	BUW9116	09-Jul-91	31616	77000		15841	00-Jan-00									pbayou	HP	6543
bayouwq	BUU9108	09-Jul-91	31616	100000		15842	00-Jan-00									pbayou	HP	6541
	BUS9117	09-Jul-91	31616	9000		15843	00-Jan-00									pbayou	HP	6537
bayouwq	BUQ9110	09-Jul-91	31616	9600		15844	00-Jan-00									pbayou	HP	6533
bayouwq	BUN9117	09-Jul-91	31616	21000		15845	00-Jan-00									pbayou	HP	6527
bayouwq	BUL9117	09-Jul-91	31616	7200		15846	00-Jan-00									pbayou	HP	6523
bayouwq	BUG9109	09-Jul-91	31616	81000		15847	00-Jan-00									pbayou	HP	6515
bayouwq	BUB9021	10-Jul-90	31616	4800		11142	00-Jan-00									pother1	HP	11930
	BUE9021	10-Jul-90	31616	1400			00-Jan-00									pother1	HP	11934
	BUA9022	10-Jul-90	31616	860			00-Jan-00									pother1	HP	11954
	BUO9019	10-Jul-90	31616	24000			00-Jan-00									pother1	HP	11950
	BUM9021	10-Jul-90	31616	4300			00-Jan-00									pother1	HP	11946
	BUK9020	10-Jul-90	31616	2800			00-Jan-00									pother1	HP	11942
	BUJ9020	10-Jul-90	31616	5300			00-Jan-00									pother1	HP	11940
	BUH9021	10-Jul-90	31616	1400			00-Jan-00									pother1	HP	11938
	BUD9021	10-Jul-90	31616	3400			00-Jan-00									pother1	HP	11932
	BUX9015 BUW9021	10-Jul-90 10-Jul-90	31616	680			00-Jan-00									pother1	HP HP	11966 11962
		10-Jul-90 10-Jul-90	31616	12000			00-Jan-00									pother1	HP	11962
	BUU9021 BUS9021	10-Jul-90 10-Jul-90	31616 31616	15000			00-Jan-00 00-Jan-00									pother1	HP	11960
	BUQ9021	10-Jul-90	31616	1800			00-Jan-00 00-Jan-00									pother1 pother1	HP	11950
bayouwq	BUN9022	10-Jul-90	31616	4050			00-Jan-00									pother1	HP	11932
bayouwq bayouwq	BUL9020	10-Jul-90		3300			00-Jan-00									pother1	HP	11944
, ,	BUG9021	10-Jul-90	31616	3300			00-Jan-00									pother1	HP	11936
	BUA8907	13-Jul-89	31616	530			00-Jan-00									pother l	HP	10197
	BUO8906	13-Jul-89	31616	230			00-Jan-00									pother1	HP	10195
	BUM8907	13-Jul-89	31616	520			00-Jan-00									pother1	HP	10193
	BUJ8907	13-Jul-89	31616	620			00-Jan-00									pother1	HP	10191
• •	BUH8907	13-Jul-89	31616	480			00-Jan-00									pother1	HP	10190
	BUX8907	13-Jul-89	31616	1400			00-Jan-00									pother1	HP	10202
	BUW8905	13-Jul-89	31616	1100			00-Jan-00									pother1	HP	10202
• •	BUU8907	13-Jul-89	31616	1300			00-Jan-00									pother1	HP	10200
	BUS8907	13-Jul-89		1700			00-Jan-00									pother1	HP	10198

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUQ8905	13-Jul-89	31616	290		15844	00-Jan-00									pother1	HP	10196
. * *	BUN8905	13-Jul-89	31616	350			00-Jan-00									pother1	HP	10194
	BUL8907	13-Jul-89	31616	4200	-		00-Jan-00									pother1	HP	10192
	BUG8907 BUA8604	13-Jul-89 14-Jul-86	31616 31616	12000 5200			00-Jan-00									pother1	HP HP	10189 9662
	BUA8604 BUO8604	14-Jul-86 14-Jul-86	31616	3900			00-Jan-00 00-Jan-00									pother1 pother1	HP	9662
	BUM8604	14-Jul-86	31616	1180			00-Jan-00									pother1	HP	9657
bayouwq	BUJ8604	14-Jul-86	31616	10			00-Jan-00									pother1	HP	9654
	BUH8604	14-Jul-86	31616	1720			00-Jan-00									pother1	HP	9652
	BUD8602	14-Jul-86	31616	420		11364	00-Jan-00									pother1	HP	9650
bayouwq	BUX8604	14-Jul-86	31616	1190		15840	00-Jan-00									pother1	HP	9671
bayouwq	BUW8604	14-Jul-86	31616	2300		15841	00-Jan-00									pother1	HP	9668
	BUU8604	14-Jul-86	31616	8200			00-Jan-00									pother1	HP	9666
. * *	BUS8604	14-Jul-86	31616	5100			00-Jan-00									pother1	HP	9665
	BUL8604	14-Jul-86	31616	120			00-Jan-00									pother1	HP	9656
	BUG8601	14-Jul-86	31616	160			00-Jan-00								nu .	pother1	HP	9651
	BUA9311 BUB9603	14-Jul-93 15-Jul-96	31616 31616	450	BM		00-Jan-00 00-Jan-00								BM	pbayou xls96	HP HP	7822 1615
	BUC9602	15-Jul-96	31616	2400			00-Jan-00 00-Jan-00									x1s96	HP	1616
	BUE9610	15-Jul-96	31616	360			00-Jan-00									xls96		1618
bayouwq	BUV9611	15-Jul-96	31616	1300	-		00-Jan-00									xls96	HP	1634
bayouwq	BUA9617	15-Jul-96	31616	2100			00-Jan-00								BM	xls96	HP	1631
bayouwq	BUP9610	15-Jul-96	31616	950			00-Jan-00									xls96	HP	1629
bayouwq	BUO9610	15-Jul-96	31616	910		11354	00-Jan-00									xls96	HP	1628
	BUM9609	15-Jul-96	31616	460		11357	00-Jan-00									xls96	HP	1626
bayouwq	BUK9610	15-Jul-96	31616	730		11359	00-Jan-00									xls96	HP	1624
bayouwq	BUJ9607	15-Jul-96	31616	1000		11360	00-Jan-00									xls96	HP	1623
bayouwq	BUI9610	15-Jul-96	31616	1300	-	11361	00-Jan-00									xls96	HP	1622
	BUH9610	15-Jul-96	31616	740			00-Jan-00									xls96	HP	1621
	BUF9608	15-Jul-96	31616	500			00-Jan-00									xls96	HP	1619
. * *	BUD9610	15-Jul-96	31616	330			00-Jan-00									xls96	HP	1617
	BUS9610	15-Jul-96	31616	1000			00-Jan-00									xls96	HP	1632
	BUQ9610	15-Jul-96	31616	1000			00-Jan-00									x1s96	HP	1630
	BUN9610 BUL9610	15-Jul-96 15-Jul-96	31616 31616	800 670			00-Jan-00 00-Jan-00									xls96 xls96	HP HP	1627 1625
	BUG9608	15-Jul-96	31616	430			00-Jan-00 00-Jan-00									x1s96	HP	1620
	BUB9111	16-Jul-91	31616	1100			00-Jan-00									pbayou	HP	6584
	BUE9110	16-Jul-91	31616	810			00-Jan-00									pbayou	HP	6588
	BUA9118	16-Jul-91	31616	1300			00-Jan-00									pbayou	HP	6610
	BUP9113	16-Jul-91	31616	2300	-		00-Jan-00									pbayou	HP	6606
bayouwq	BUO9113	16-Jul-91	31616	2100		11354	00-Jan-00									pbayou	HP	6604
bayouwq	BUM9111	16-Jul-91	31616	7500		11357	00-Jan-00									pbayou	HP	6600
bayouwq	BUK9114	16-Jul-91	31616	8100		11359	00-Jan-00									pbayou		6596
bayouwq	BUJ9118	16-Jul-91	31616	2200		11360	00-Jan-00									pbayou	HP	6594
bayouwq	BUH9117	16-Jul-91	31616	840	-		00-Jan-00									pbayou	HP	6592
bayouwq	BUD9116	16-Jul-91	31616	990			00-Jan-00									pbayou	HP	6586
bayouwq	BUW9117	16-Jul-91	31616	8300	-		00-Jan-00									pbayou	HP	6618
<u> </u>	BUU9109	16-Jul-91	31616	5500			00-Jan-00									pbayou	HP	6616
	BUS9118	16-Jul-91	31616	3400 2800			00-Jan-00									pbayou	HP	6612
	BUN9118 BUL9118	16-Jul-91 16-Jul-91	31616 31616	3000			00-Jan-00 00-Jan-00									pbayou pbayou	HP HP	6602 6598
	BUG9110	16-Jul-91 16-Jul-91	31616	2600	-		00-Jan-00 00-Jan-00									pbayou	HP	6590
	BUA9023	17-Jul-90	31616	27000			00-Jan-00 00-Jan-00									pother1	HP	12025
	BUO9020	17-Jul-90	31616	39000			00-Jan-00									pother1	HP	12023
	BUJ9021	17-Jul-90	31616	8000	-		00-Jan-00									pother1	HP	12011
	BUX9016	17-Jul-90	31616	2000			00-Jan-00									pother1	HP	12037
	BUW9022	17-Jul-90	31616	180000	-		00-Jan-00									pother1		12033
bayouwq	BUU9022	17-Jul-90	31616	200000		15842	00-Jan-00									pother1	HP	12031

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUS9022	17-Jul-90	31616	26000		15843	00-Jan-00							pother1	HP	12027
	BUQ9022	17-Jul-90	31616	33000			00-Jan-00							pother1	HP	12023
	BUN9023	17-Jul-90	31616	20000			00-Jan-00							pother1	HP	12019
bayouwq	BUX9611	17-Jul-96	31616	2300			00-Jan-00							xls96	HP	1745
	BUW9609 BUB9413	17-Jul-96 19-Jul-94	31616 31616	28000 170			00-Jan-00 00-Jan-00							xls96 9495a	HP HP	1744 1418
• •	BUC9411	19-Jul-94	31616	2900		-	00-Jan-00 00-Jan-00							9495a 9495a	HP	1420
	BUE9413	19-Jul-94	31616	770		1	00-Jan-00							9495a	HP	1424
	BUV9413	19-Jul-94	31616	870			00-Jan-00							9495a	HP	1458
	BUA9415	19-Jul-94	31616	3300			00-Jan-00							9495a	HP	1450
	BUP9413	19-Jul-94	31616	360		11353	00-Jan-00							9495a	HP	1446
bayouwq	BUO9413	19-Jul-94	31616	410		11354	00-Jan-00							9495a	HP	1444
bayouwq	BUM9413	19-Jul-94	31616	3000		11357	00-Jan-00							9495a	HP	1440
• •	BUK9413	19-Jul-94	31616	860			00-Jan-00							9495a	HP	1436
	BUJ9412	19-Jul-94	31616	2200			00-Jan-00							9495a	HP	1434
	BUI9408	19-Jul-94	31616	3700			00-Jan-00							9495a	HP	1432
	BUH9413 BUF9408	19-Jul-94 19-Jul-94	31616 31616	4300 700			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	1430 1426
	BUD9413	19-Jul-94	31616	700		1	00-Jan-00 00-Jan-00							9495a 9495a	HP	1420
	BUW9410	19-Jul-94	31616	850			00-Jan-00							9495a	HP	1460
, ,	BUS9413	19-Jul-94	31616	410			00-Jan-00							9495a	HP	1452
	BUN9413	19-Jul-94	31616	770		15845	00-Jan-00							9495a	HP	1442
	BUL9413	19-Jul-94	31616	890		15846	00-Jan-00							9495a	HP	1438
bayouwq	BUG9413	19-Jul-94	31616	920		15847	00-Jan-00							9495a	HP	1428
• •	BUV8303	20-Jul-83	31616	5000			00-Jan-00							pother1	HP	9028
• •	BUA8304	20-Jul-83	31616	3000			00-Jan-00							pother1	HP	9023
	BUO8304	20-Jul-83	31616	11000			00-Jan-00							pother1	HP	9021
	BUM8305	20-Jul-83	31616	6000			00-Jan-00							pother1	HP	9018
	BUJ8305 BUH8305	20-Jul-83 20-Jul-83	31616 31616	1			00-Jan-00 00-Jan-00							pother1	HP HP	9015 9013
bayouwq bayouwq	BUX8303	20-Jul-83	31616	1000			00-Jan-00 00-Jan-00							pother1 pother1	HP	9013
	BUW8303	20-Jul-83	31616	2000			00-Jan-00							pother1	HP	9029
, ,	BUS8303	20-Jul-83	31616	200000		1	00-Jan-00							pother l	HP	9026
	BUB8701	21-Jul-87	31616	300			00-Jan-00							pother1	HP	9822
bayouwq	BUA8704	21-Jul-87	31616	41000		11351	00-Jan-00							pother1	HP	9830
bayouwq	BUO8704	21-Jul-87	31616	27000		11354	00-Jan-00							pother1	HP	9829
	BUM8704	21-Jul-87	31616	9800			00-Jan-00							pother1	HP	9828
	BUJ8704	21-Jul-87	31616	10			00-Jan-00							pother1	HP	9826
• •	BUH8704	21-Jul-87	31616	13400			00-Jan-00							pother1	HP	9825
	BUD8704	21-Jul-87	31616	350			00-Jan-00							pother1	HP	9823
bayouwq	BUX8704 BUW8704	21-Jul-87 21-Jul-87	31616 31616	5800 38000			00-Jan-00 00-Jan-00							pother1 pother1	HP HP	9834 9833
• •	BUU8704	21-Jul-87	31616	30000			00-Jan-00 00-Jan-00							pother1	HP	9832
bayouwq	BUS8704	21-Jul-87	31616	56000		1	00-Jan-00							pother1	HP	9831
	BUL8704	21-Jul-87	31616	7000			00-Jan-00							pother1	HP	9827
• •	BUG8704	21-Jul-87	31616	87000			00-Jan-00							pother1	HP	9824
bayouwq	BUB9112	23-Jul-91	31616	8000		11142	00-Jan-00							pbayou	HP	6658
bayouwq	BUE9111	23-Jul-91	31616	1200		11163	00-Jan-00							pbayou	HP	6662
	BUA9119	23-Jul-91	31616	31000			00-Jan-00							pbayou	HP	6684
	BUP9114	23-Jul-91	31616	8900			00-Jan-00							pbayou	HP	6680
	BUO9114	23-Jul-91	31616	9500			00-Jan-00							pbayou	HP	6678
	BUM9112	23-Jul-91	31616	24000			00-Jan-00							pbayou	HP	6674
	BUK9115 BUJ9119	23-Jul-91 23-Jul-91	31616 31616	17000 12000			00-Jan-00 00-Jan-00							pbayou	HP HP	6670 6668
1	BUH9118	23-Jul-91 23-Jul-91	31616	7200			00-Jan-00 00-Jan-00							pbayou pbayou	HP	6666
	BUD9117	23-Jul-91 23-Jul-91	31616	9500			00-Jan-00 00-Jan-00							pbayou	HP	6660
, ,	BUW9118	23-Jul-91	31616	290000			00-Jan-00							pbayou	HP	6692
	BUU9110	23-Jul-91	31616	250000			00-Jan-00							pbayou	HP	6690

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CAL	C. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUS9119	23-Jul-91	31616	57000			00-Jan-00							pbayou	HP	6686
bayouwq	BUQ9111	23-Jul-91	31616	45000			00-Jan-00							pbayou	HP	6682
bayouwq	BUN9119 BUL9119	23-Jul-91 23-Jul-91	31616 31616	29000 22000			00-Jan-00 00-Jan-00							pbayou	HP HP	6676 6672
bayouwq bayouwq	BUG9111	23-Jul-91 23-Jul-91	31616	9700			00-Jan-00 00-Jan-00							pbayou pbayou	HP	6664
bayouwq	BUB9022	24-Jul-90	31616	5700			00-Jan-00							pother1	HP	12072
bayouwq	BUE9022	24-Jul-90	31616	12000			00-Jan-00							pother1	HP	12076
bayouwq	BUA9024	24-Jul-90	31616	28000		11351	00-Jan-00							pother1	HP	12096
bayouwq	BUO9021	24-Jul-90	31616	11000		11354	00-Jan-00							pother1	HP	12092
bayouwq	BUM9022	24-Jul-90	31616	260		11357	00-Jan-00							pother1	HP	12088
bayouwq	BUK9021	24-Jul-90	31616	950			00-Jan-00							pother1	HP	12084
bayouwq	BUJ9022	24-Jul-90	31616	29000			00-Jan-00							pother1	HP	12082
bayouwq	BUH9022	24-Jul-90	31616	3500			00-Jan-00							pother1	HP	12080
bayouwq	BUD9022 BUN9024	24-Jul-90 24-Jul-90	31616 31616	33000			00-Jan-00							pother1	HP HP	12074 12090
bayouwq	BUL9021	24-Jul-90 24-Jul-90	31616	820			00-Jan-00 00-Jan-00							pother1 pother1	HP	12090
bayouwq bayouwq	BUG9021	24-Jul-90	31616	15000			00-Jan-00							pother1	HP	12078
bayouwq	BUA9312	26-Jul-93	31616	3600			00-Jan-00							pbayou	HP	8229
bayouwq	BUV9306	27-Jul-93	31616	640		11345	00-Jan-00							pbayou	HP	7987
bayouwq	BUA9313	27-Jul-93	31616	2800		11351	00-Jan-00							pbayou	HP	7981
bayouwq	BUP9304	27-Jul-93	31616	420		11353	00-Jan-00							pbayou	HP	7977
bayouwq	BUM9302	27-Jul-93	31616	2000			00-Jan-00							pbayou	HP	7971
bayouwq	BUJ9304	27-Jul-93	31616	2000			00-Jan-00							pbayou	HP	7965
bayouwq	BUH9303	27-Jul-93	31616	7400			00-Jan-00							pbayou	HP	7963
bayouwq	BUD9304	27-Jul-93	31616	680			00-Jan-00							pbayou	HP	7957
bayouwq	BUW9303 BUS9304	27-Jul-93 27-Jul-93	31616 31616	260 2000			00-Jan-00 00-Jan-00							pbayou	HP HP	7989 7983
bayouwq bayouwq	BUN9304	27-Jul-93	31616	1500			00-Jan-00							pbayou pbayou	HP	7973
bayouwq	BUB9414	27-Jul-94	31616	1500			00-Jan-00							9495a	HP	1488
bayouwq	BUC9412	27-Jul-94	31616	350			00-Jan-00							9495a	HP	1490
bayouwq	BUE9414	27-Jul-94	31616	2300		11163	00-Jan-00							9495a	HP	1494
bayouwq	BUV9414	27-Jul-94	31616	3500		11345	00-Jan-00							9495a	HP	1526
bayouwq	BUA9416	27-Jul-94	31616	3000			00-Jan-00							9495a	HP	1518
bayouwq	BUP9414	27-Jul-94	31616	950			00-Jan-00							9495a	HP	1516
bayouwq	BUO9414	27-Jul-94	31616	3700			00-Jan-00							9495a	HP	1514
bayouwq	BUM9414 BUK9414	27-Jul-94 27-Jul-94	31616	2800 22000			00-Jan-00							9495a 9495a	HP HP	1510 1506
bayouwq	BUJ9413	27-Jul-94 27-Jul-94	31616 31616	2900			00-Jan-00 00-Jan-00							9495a 9495a	HP	1504
bayouwq bayouwq	BUI9409	27-Jul-94 27-Jul-94	31616	3600			00-Jan-00							9495a	HP	1502
bayouwq	BUH9414	27-Jul-94	31616	35000			00-Jan-00							9495a	HP	1500
bayouwq	BUF9409	27-Jul-94	31616	3000			00-Jan-00							9495a	HP	1496
bayouwq	BUD9414	27-Jul-94	31616	260			00-Jan-00							9495a	HP	1492
bayouwq	BUX9410	27-Jul-94	31616	330		15840	00-Jan-00							9495a	HP	1530
bayouwq	BUW9411	27-Jul-94	31616	1300		15841	00-Jan-00							9495a	HP	1528
bayouwq	BUU9410	27-Jul-94	31616	3200			00-Jan-00							9495a	HP	1524
bayouwq	BUS9414	27-Jul-94	31616	4400			00-Jan-00							9495a	HP	1520
bayouwq	BUN9414 BUL9414	27-Jul-94	31616	1600 3600			00-Jan-00							9495a 9495a	HP HP	1512 1508
bayouwq bayouwq	BUG9414	27-Jul-94 27-Jul-94	31616 31616	2200			00-Jan-00 00-Jan-00							9495a 9495a	HP	1508
bayouwq	BUA9314	28-Jul-93	31616	790			00-Jan-00 00-Jan-00						BM	pbayou	HP	7870
	BUB9113	29-Jul-91	31616	1100			00-Jan-00							pbayou	HP	6734
bayouwq	BUE9112	29-Jul-91	31616	680			00-Jan-00							pbayou	HP	6738
bayouwq	BUV9101	29-Jul-91	31616	890			00-Jan-00							pbayou	HP	6770
bayouwq	BUA9120	29-Jul-91	31616	2700		11351	00-Jan-00							pbayou	HP	6762
bayouwq	BUP9115	29-Jul-91	31616	4000			00-Jan-00							pbayou	HP	6758
bayouwq	BUO9115	29-Jul-91	31616	2800			00-Jan-00							pbayou	HP	6756
	BUM9113	29-Jul-91	31616	3600			00-Jan-00							pbayou	HP	6752
bayouwq	BUK9116	29-Jul-91	31616	5900		11359	00-Jan-00							pbayou	HP	6748

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUJ9120	29-Jul-91	31616	1200		11360	00-Jan-00							pbayou	HP	6746
bayouwq	BUI9101	29-Jul-91	31616	890			00-Jan-00							pbayou	HP	6744
bayouwq	BUH9119	29-Jul-91	31616	720			00-Jan-00							pbayou		6742
bayouwq	BUD9118	29-Jul-91	31616	990			00-Jan-00							pbayou	HP	6736
bayouwq	BUX9103	29-Jul-91	31616	200			00-Jan-00							pbayou	HP	6776
bayouwq	BUW9119	29-Jul-91	31616	3000			00-Jan-00							pbayou	HP	6772
bayouwq	BUU9111	29-Jul-91	31616 31616	2900 1100			00-Jan-00							pbayou	HP HP	6768 6764
bayouwq	BUS9120	29-Jul-91 29-Jul-91	31616	3300			00-Jan-00 00-Jan-00							pbayou	HP	6760
bayouwq	BUQ9112 BUN9120	29-Jul-91 29-Jul-91	31616	1500			00-Jan-00 00-Jan-00							pbayou	HP	6754
bayouwq bayouwq	BUL9120	29-Jul-91	31616	5200			00-Jan-00							pbayou pbayou	HP	6750
bayouwq	BUG9112	29-Jul-91	31616	1500			00-Jan-00							pbayou	HP	6740
bayouwq	BUA9618	29-Jul-96	31616	3700	BM	1	00-Jan-00						BM	xls96	HP	1859
bayouwq	BUA8504	30-Jul-85	31616	104000	DIVI		00-Jan-00							pother1	HP	9470
bayouwq	BUO8504	30-Jul-85	31616	223000			00-Jan-00							pother1	HP	9468
bayouwq	BUM8506	30-Jul-85	31616	34000			00-Jan-00							pother1	HP	9465
bayouwq	BUK8506	30-Jul-85	31616	1410		11359	00-Jan-00							pother1	HP	9463
bayouwq	BUJ8506	30-Jul-85	31616	6600		11360	00-Jan-00							pother1	HP	9462
bayouwq	BUH8506	30-Jul-85	31616	38000		11362	00-Jan-00							pother1	HP	9460
bayouwq	BUX8506	30-Jul-85	31616	4600		15840	00-Jan-00							pother1	HP	9479
bayouwq	BUW8506	30-Jul-85	31616	41000		15841	00-Jan-00							pother1	HP	9476
bayouwq	BUU8506	30-Jul-85	31616	123000		15842	00-Jan-00							pother1	HP	9474
bayouwq	BUS8506	30-Jul-85	31616	79000		15843	00-Jan-00							pother1	HP	9473
bayouwq	BUN8502	30-Jul-85	31616	81000		15845	00-Jan-00							pother1	HP	9466
bayouwq	BUL8503	30-Jul-85	31616	60			00-Jan-00							pother1	HP	9464
bayouwq	BUB9023	31-Jul-90	31616	3900		-	00-Jan-00							pother1	HP	12143
bayouwq	BUE9023	31-Jul-90	31616	52000			00-Jan-00							pother1	HP	12147
bayouwq	BUA9025	31-Jul-90	31616	130000			00-Jan-00							pother1	HP	12167
bayouwq	BUO9022	31-Jul-90	31616	140000			00-Jan-00							pother1	HP	12163
bayouwq	BUM9023	31-Jul-90	31616	69000			00-Jan-00							pother1	HP	12159
bayouwq	BUK9022	31-Jul-90	31616	90000			00-Jan-00							pother1	HP	12155
bayouwq	BUJ9023	31-Jul-90 31-Jul-90	31616 31616	45000 75000			00-Jan-00							pother1	HP HP	12153 12151
bayouwq	BUH9023 BUD9023	31-Jul-90 31-Jul-90	31616	14000			00-Jan-00 00-Jan-00							pother l		12131
bayouwq	BUW9023	31-Jul-90 31-Jul-90	31616	72000		1	00-Jan-00 00-Jan-00							pother1	HP	12175
bayouwq bayouwq	BUS9023	31-Jul-90	31616	99000			00-Jan-00 00-Jan-00							pother1	HP	12173
bayouwq	BUQ9023	31-Jul-90	31616	130000			00-Jan-00							pother1	HP	12165
bayouwq	BUN9025	31-Jul-90	31616	150000		1	00-Jan-00							pother1	HP	12161
bayouwq	BUL9022	31-Jul-90	31616	130000			00-Jan-00							pother1	HP	12157
bayouwq	BUG9023	31-Jul-90	31616	57000			00-Jan-00							pother1		12149
bayouwq	BUA9514	31-Jul-95	31616	100000	BM		00-Jan-00						BM	9495a	HP	5381
bayouwq	BUB9604	31-Jul-96	31616	4900			00-Jan-00							xls96	HP	1922
bayouwq	BUC9603	31-Jul-96	31616	4400			00-Jan-00							xls96	HP	1923
bayouwq	BUE9611	31-Jul-96	31616	520		11163	00-Jan-00							xls96	HP	1925
bayouwq	BUV9612	31-Jul-96	31616	2600		11345	00-Jan-00							xls96	HP	1941
bayouwq	BUA9619	31-Jul-96	31616	7900	BM	11351	00-Jan-00						BM	xls96	HP	1938
bayouwq	BUP9611	31-Jul-96	31616	3700		11353	00-Jan-00							xls96	HP	1936
bayouwq	BUO9611	31-Jul-96	31616	3100		11354	00-Jan-00							xls96	HP	1935
bayouwq	BUM9610	31-Jul-96	31616	5600			00-Jan-00							xls96		1933
bayouwq	BUK9611	31-Jul-96	31616	7600			00-Jan-00							xls96	HP	1931
	BUJ9608	31-Jul-96	31616	5500			00-Jan-00							xls96	HP	1930
bayouwq	BUI9611	31-Jul-96	31616	4500			00-Jan-00							xls96	HP	1929
-	BUH9611	31-Jul-96	31616	4000			00-Jan-00							xls96	HP	1928
bayouwq	BUF9609	31-Jul-96	31616	2900			00-Jan-00							xls96	HP	1926
bayouwq	BUD9611	31-Jul-96	31616	2000			00-Jan-00							xls96	HP	1924
bayouwq	BUX9612	31-Jul-96	31616	1000			00-Jan-00							xls96	HP	1943
bayouwq	BUW9610	31-Jul-96	31616	4000			00-Jan-00			1				xls96	HP	1942
bayouwq	BUS9611	31-Jul-96	31616	4600		15843	00-Jan-00			1				xls96	HP	1939

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUQ9611	31-Jul-96	31616	7000		15844	00-Jan-00							xls96	HP	1937
bayouwq	BUN9611	31-Jul-96	31616	4600			00-Jan-00							xls96	HP	1934
bayouwq	BUL9611	31-Jul-96	31616	7500			00-Jan-00							xls96	HP	1932
bayouwq	BUG9609	31-Jul-96	31616	3200			00-Jan-00							xls96	HP	1927
bayouwq	BUB8804	01-Aug-88	31616	500			00-Jan-00							pother1	HP HP	9915 9922
bayouwq bayouwq	BUO8804 BUM8804	01-Aug-88 01-Aug-88	31616 31616	2400 160			00-Jan-00 00-Jan-00							pother1	HP	9922
bayouwq	BUJ8804	01-Aug-88	31616	100			00-Jan-00							pother1	HP	9919
bayouwq	BUH8804	01-Aug-88	31616	20			00-Jan-00							pother1	HP	9918
bayouwq	BUD8804	01-Aug-88	31616	310			00-Jan-00							pother1	HP	9916
bayouwq	BUX8804	01-Aug-88	31616	130		15840	00-Jan-00							pother1	HP	9928
bayouwq	BUW8804	01-Aug-88	31616	25000		15841	00-Jan-00							pother1	HP	9927
bayouwq	BUU8804	01-Aug-88	31616	8800		15842	00-Jan-00							pother1	HP	9926
bayouwq	BUS8804	01-Aug-88	31616	40000			00-Jan-00							pother1	HP	9924
bayouwq	BUL8804	01-Aug-88	31616	260			00-Jan-00							pother1	HP	9920
bayouwq	BUG8804	01-Aug-88	31616	3400			00-Jan-00							pother1	HP	9917
bayouwq	BUV8404	04-Aug-84	31616	144000			00-Jan-00							pother l	HP HP	9251 9246
bayouwq	BUA8404 BUO8403	04-Aug-84 04-Aug-84	31616 31616	24167 3100			00-Jan-00 00-Jan-00							pother1	HP	9246
bayouwq bayouwq	BUM8404	04-Aug-84	31616	7670			00-Jan-00 00-Jan-00							pother1	HP	9244
bayouwq	BUJ8404	04-Aug-84	31616	1			00-Jan-00							pother1	HP	9238
bayouwq	BUH8403	04-Aug-84	31616	800			00-Jan-00							pother1	HP	9236
bayouwq	BUX8404	04-Aug-84	31616	94			00-Jan-00							pother1	HP	9255
bayouwq	BUS8404	04-Aug-84	31616	34167		15843	00-Jan-00							pother1	HP	9249
bayouwq	BUA9315	04-Aug-93	31616	11000	BM	11351	00-Jan-00						BM	pbayou	HP	9589
bayouwq	BUB9114	05-Aug-91	31616	660			00-Jan-00							pbayou	HP	8355
bayouwq	BUE9113	05-Aug-91	31616	520			00-Jan-00							pbayou	HP	8359
bayouwq	BUV9102	05-Aug-91	31616	20000			00-Jan-00							pbayou	HP	8389
bayouwq	BUA9121	05-Aug-91	31616	1800			00-Jan-00							pbayou	HP	8381
bayouwq bayouwq	BUP9116 BUO9116	05-Aug-91 05-Aug-91	31616 31616	4700 2500			00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	8377 8375
bayouwq	BUM9114	05-Aug-91	31616	2000			00-Jan-00							pbayou	HP	8371
bayouwq	BUK9117	05-Aug-91	31616	3000			00-Jan-00							pbayou	HP	8367
bayouwq	BUJ9121	05-Aug-91	31616	1800			00-Jan-00							pbayou	HP	8365
bayouwq	BUH9120	05-Aug-91	31616	1000		11362	00-Jan-00							pbayou	HP	8363
bayouwq	BUD9119	05-Aug-91	31616	610		11364	00-Jan-00							pbayou	HP	8357
bayouwq	BUX9104	05-Aug-91	31616	1300		15840	00-Jan-00							pbayou	HP	8395
bayouwq	BUW9120	05-Aug-91	31616	20000			00-Jan-00							pbayou	HP	8391
bayouwq	BUU9112	05-Aug-91	31616	15000			00-Jan-00							pbayou	HP	8387
bayouwq	BUS9121	05-Aug-91	31616	1500			00-Jan-00							pbayou	HP	8383
bayouwq	BUQ9113	05-Aug-91 05-Aug-91	31616	1400			00-Jan-00							pbayou	HP	8379 8373
bayouwq bayouwq	BUN9121 BUL9121	05-Aug-91 05-Aug-91	31616 31616	2000 2000			00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	8369
bayouwq	BUG9113	05-Aug-91	31616	3500			00-Jan-00							pbayou	HP	8361
bayouwq	BUB9024	06-Aug-90	31616	1200			00-Jan-00							pother1	HP	12214
bayouwq	BUE9024	06-Aug-90	31616	1400			00-Jan-00							pother1	HP	12218
bayouwq	BUA9026	06-Aug-90	31616	5900		11351	00-Jan-00							pother1	HP	12240
bayouwq	BUP9001	06-Aug-90	31616	2400		11353	00-Jan-00							pother1	HP	12236
bayouwq	BUO9023	06-Aug-90	31616	2600			00-Jan-00							pother1	HP	12234
bayouwq	BUM9024	06-Aug-90	31616	970			00-Jan-00							pother1	HP	12230
bayouwq	BUK9023	06-Aug-90	31616	9100			00-Jan-00							pother1	HP	12226
bayouwq	BUJ9024	06-Aug-90	31616	320			00-Jan-00							pother1	HP	12224
bayouwq	BUH9024	06-Aug-90	31616	940			00-Jan-00							pother1	HP	12222
bayouwq	BUD9024	06-Aug-90	31616	380 12000			00-Jan-00 00-Jan-00							pother1	HP	12216 12248
bayouwq bayouwq	BUW9024 BUU9023	06-Aug-90 06-Aug-90	31616 31616	5500			00-Jan-00 00-Jan-00							pother1	HP HP	12248
bayouwq	BUS9024	06-Aug-90	31616	8600			00-Jan-00							pother1	HP	12240
	BUQ9024	06-Aug-90	31616	4200			00-Jan-00							pother1		12238
oayouwq	D U Q9024	00-Aug-90	31016	4200	1	13844	oo-jan-00			1		1	<u>L</u>	рошегі	lije.	12230

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUN9026	06-Aug-90	31616	2500		15845	00-Jan-00							pother1	HP	12232
	BUL9023	06-Aug-90	31616	5200			00-Jan-00							pother1	HP	12228
	BUG9024	06-Aug-90	31616	7900			00-Jan-00							pother1	HP	12220
bayouwq	BUV9613	09-Aug-96	31616	2100			00-Jan-00							bayou95	HP	65
* *	BUV9511 BUA9316	10-Aug-95 11-Aug-93	31616 31616	2100 8500			00-Jan-00 00-Jan-00						BM	9495a	HP HP	5931 9637
•	BUB9115	13-Aug-91	31616	910			00-Jan-00 00-Jan-00						Bivi	pbayou pbayou	HP	8433
	BUE9114	13-Aug-91	31616	1200			00-Jan-00							pbayou	HP	8437
	BUV9103	13-Aug-91	31616	52000			00-Jan-00							pbayou	HP	8467
•	BUA9122	13-Aug-91	31616	5900			00-Jan-00							pbayou	HP	8459
	BUP9117	13-Aug-91	31616	7300		11353	00-Jan-00							pbayou	HP	8455
bayouwq	BUO9117	13-Aug-91	31616	6500		11354	00-Jan-00							pbayou	HP	8453
bayouwq	BUM9115	13-Aug-91	31616	1500		11357	00-Jan-00							pbayou	HP	8449
•	BUK9118	13-Aug-91	31616	1000			00-Jan-00							pbayou	HP	8445
	BUJ9122	13-Aug-91	31616	1300			00-Jan-00							pbayou	HP	8443
	BUH9121	13-Aug-91	31616	670			00-Jan-00							pbayou	HP	8441
	BUD9120 BUX9105	13-Aug-91 13-Aug-91	31616 31616	1800 9400			00-Jan-00 00-Jan-00							pbayou	HP HP	8435 8473
	BUW9121	13-Aug-91	31616	160000			00-Jan-00 00-Jan-00							pbayou pbayou	HP	8469
	BUS9122	13-Aug-91	31616	2700			00-Jan-00							pbayou	HP	8461
•	BUQ9114	13-Aug-91	31616	6500			00-Jan-00							pbayou	HP	8457
	BUN9122	13-Aug-91	31616	1200			00-Jan-00							pbayou	HP	8451
	BUL9122	13-Aug-91	31616	1200		15846	00-Jan-00							pbayou	HP	8447
bayouwq	BUG9114	13-Aug-91	31616	2200		15847	00-Jan-00							pbayou	HP	8439
•	BUB9605	13-Aug-96	31616	2500			00-Jan-00							xls96	HP	2027
	BUC9604	13-Aug-96	31616	2900			00-Jan-00							xls96	HP	2028
	BUE9612	13-Aug-96	31616	5600			00-Jan-00							xls96	HP	2030
•	BUV9614	13-Aug-96	31616	21000			00-Jan-00						DM	xls96	HP	2046 2043
	BUA9620 BUP9612	13-Aug-96 13-Aug-96	31616 31616	5600 5600			00-Jan-00 00-Jan-00						BM	xls96 xls96	HP HP	2043
	BUO9612	13-Aug-96	31616	6000			00-Jan-00 00-Jan-00							xls96	HP	2041
•	BUM9611	13-Aug-96	31616	5800			00-Jan-00							xls96	HP	2038
	BUK9612	13-Aug-96	31616	3500			00-Jan-00							xls96	HP	2036
	BUJ9609	13-Aug-96	31616	3100		11360	00-Jan-00							xls96	HP	2035
bayouwq	BUI9612	13-Aug-96	31616	4000		11361	00-Jan-00							xls96	HP	2034
bayouwq	BUH9612	13-Aug-96	31616	3600		11362	00-Jan-00							xls96	HP	2033
	BUF9610	13-Aug-96	31616	2600			00-Jan-00							xls96	HP	2031
	BUD9612	13-Aug-96	31616	400			00-Jan-00							xls96	HP	2029
	BUX9613	13-Aug-96	31616	5950			00-Jan-00							xls96	HP	2048
	BUW9611	13-Aug-96	31616	5900 5000			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	2047 2044
	BUS9612 BUQ9612	13-Aug-96 13-Aug-96	31616 31616	5700			00-Jan-00 00-Jan-00							xls96	HP	2044
•	BUN9612	13-Aug-96	31616	4800			00-Jan-00 00-Jan-00							xls96	HP	2042
	BUL9612	13-Aug-96	31616	4300			00-Jan-00							xls96	HP	2037
	BUG9610	13-Aug-96	31616	8000			00-Jan-00							xls96	HP	2032
•	BUB9025	14-Aug-90	31616	740		11142	00-Jan-00							pother1	HP	12287
bayouwq	BUE9025	14-Aug-90	31616	210		11163	00-Jan-00		•					pother1	HP	12291
	BUA9027	14-Aug-90	31616	1400			00-Jan-00							pother1	HP	12313
	BUP9002	14-Aug-90	31616	790			00-Jan-00							pother1	HP	12309
	BUO9024	14-Aug-90	31616	330			00-Jan-00							pother1	HP	12307
	BUM9025	14-Aug-90	31616	9			00-Jan-00							pother1	HP	12303
	BUK9024	14-Aug-90 14-Aug-90	31616	770			00-Jan-00 00-Jan-00							pother1	HP	12299
	BUJ9025 BUH9025	14-Aug-90 14-Aug-90	31616 31616	780			00-Jan-00 00-Jan-00							pother1	HP HP	12297 12295
	BUD9025	14-Aug-90 14-Aug-90	31616	450			00-Jan-00 00-Jan-00							pother1 pother1	HP	12295
	BUW9025	14-Aug-90 14-Aug-90	31616	12000			00-Jan-00 00-Jan-00							pother1	HP	12321
	BUS9025	14-Aug-90	31616	1200			00-Jan-00							pother1	HP	12315
• •	BUQ9025	14-Aug-90	31616	2300			00-Jan-00							pother1	HP	12311

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUN9027	14-Aug-90	31616	570		15845	00-Jan-00									pother1	HP	12305
bayouwq	BUG9025	14-Aug-90	31616	1200			00-Jan-00									pother1	HP	12293
bayouwq	BUB9505	14-Aug-95	31616	3200	-		00-Jan-00									9495a	HP	5835
bayouwq	BUC9504	14-Aug-95	31616	710			00-Jan-00									9495a	HP	5837
bayouwq	BUE9509	14-Aug-95	31616	10000	DM		00-Jan-00								DM	9495a	HP	5841
bayouwq	BUA9515 BUP9508	14-Aug-95	31616 31616	5300 7600	-		00-Jan-00 00-Jan-00								BM	9495a 9495a	HP HP	5867 5863
bayouwq	BUO9507	14-Aug-95 14-Aug-95	31616	11000			00-Jan-00 00-Jan-00									9495a	HP	5861
bayouwq bayouwq	BUM9508	14-Aug-95	31616	7300			00-Jan-00									9495a	HP	5857
bayouwq	BUK9508	14-Aug-95	31616	8000			00-Jan-00									9495a	HP	5853
bayouwq	BUJ9509	14-Aug-95	31616	9400			00-Jan-00									9495a	HP	5851
bayouwq	BUH9509	14-Aug-95	31616	7500			00-Jan-00									9495a	HP	5847
bayouwq	BUF9509	14-Aug-95	31616	7100			00-Jan-00									9495a	HP	5843
bayouwq	BUD9509	14-Aug-95	31616	780			00-Jan-00									9495a	HP	5839
bayouwq	BUW9507	14-Aug-95	31616	11000	-		00-Jan-00									9495a	HP	5877
bayouwq	BUS9509	14-Aug-95	31616	4000		15843	00-Jan-00									9495a	HP	5869
bayouwq	BUQ9506	14-Aug-95	31616	8500		15844	00-Jan-00									9495a	HP	5865
bayouwq	BUN9508	14-Aug-95	31616	11000		15845	00-Jan-00									9495a	HP	5859
bayouwq	BUL9509	14-Aug-95	31616	6600		15846	00-Jan-00									9495a	HP	5855
bayouwq	BUG9506	14-Aug-95	31616	9600		15847	00-Jan-00									9495a	HP	5845
bayouwq	BUB9606	14-Aug-96	31616	3200		11142	00-Jan-00									bayou95	HP	98
bayouwq	BUC9605	14-Aug-96	31616	710		11142	00-Jan-00									bayou95	HP	99
bayouwq	BUE9613	14-Aug-96	31616	10000		11163	00-Jan-00									bayou95		101
bayouwq	BUA9621	14-Aug-96	31616	5300			00-Jan-00								BM	bayou95	HP	112
bayouwq	BUP9613	14-Aug-96	31616	7600			00-Jan-00									bayou95		110
bayouwq	BUO9613	14-Aug-96	31616	11000			00-Jan-00									bayou95	HP	109
bayouwq	BUM9612	14-Aug-96	31616	7300			00-Jan-00									bayou95	HP	108
bayouwq	BUK9613	14-Aug-96	31616	8000			00-Jan-00									bayou95		106
bayouwq	BUJ9610	14-Aug-96	31616	9400			00-Jan-00									bayou95	HP	105
bayouwq	BUH9613	14-Aug-96	31616	7500			00-Jan-00									bayou95	HP	104
	BUF9611	14-Aug-96	31616	7100			00-Jan-00									bayou95	HP	102
	BUD9613	14-Aug-96	31616	780 11000			00-Jan-00									bayou95	HP HP	100
bayouwq	BUW9612 BUS9613	14-Aug-96 14-Aug-96	31616 31616	4000			00-Jan-00 00-Jan-00									bayou95 bayou95		116 113
bayouwq	BUQ9613	14-Aug-96	31616	8500			00-Jan-00									bayou95		111
bayouwq bayouwq	BUN9613	14-Aug-96	31616	11000			00-Jan-00									bayou95		118
bayouwq	BUL9613	14-Aug-96	31616	6600			00-Jan-00									bayou95		107
	BUG9611	14-Aug-96	31616	9600			00-Jan-00									bayou95	HP	103
bayouwq	BUB9202	17-Aug-92	31616	470			00-Jan-00									pbayou	HP	9002
bayouwq	BUE9204	17-Aug-92	31616	1400	-		00-Jan-00									pbayou	HP	9006
bayouwq	BUV9205	17-Aug-92	31616	1400			00-Jan-00									pbayou	HP	9036
	BUA9205	17-Aug-92	31616	950			00-Jan-00									pbayou	HP	9028
bayouwq	BUP9205	17-Aug-92	31616	1200		11353	00-Jan-00									pbayou	HP	9024
bayouwq	BUO9205	17-Aug-92	31616	5000		11354	00-Jan-00									pbayou	HP	9022
bayouwq	BUM9204	17-Aug-92	31616	1100		11357	00-Jan-00									pbayou	HP	9018
bayouwq	BUK9205	17-Aug-92	31616	950		11359	00-Jan-00									pbayou	HP	9014
bayouwq	BUJ9205	17-Aug-92	31616	890		11360	00-Jan-00									pbayou	HP	9012
bayouwq	BUH9205	17-Aug-92	31616	550		11362	00-Jan-00									pbayou	HP	9010
bayouwq	BUD9204	17-Aug-92	31616	520			00-Jan-00									pbayou	HP	9004
<u> </u>	BUW9205	17-Aug-92	31616	990			00-Jan-00									pbayou	HP	9038
	BUS9205	17-Aug-92		950	-		00-Jan-00									pbayou	HP	9030
-	BUQ9202	17-Aug-92	31616	950			00-Jan-00									pbayou	HP	9026
	BUN9205	17-Aug-92	31616	1100			00-Jan-00									pbayou	HP	9020
	BUL9204	17-Aug-92	31616	1000	-		00-Jan-00									pbayou	HP	9016
	BUG9203	17-Aug-92		720			00-Jan-00									pbayou	HP	9008
<u> </u>	BUV9307	17-Aug-93	31616	13000	-		00-Jan-00									pbayou	HP	9848
	BUA9317	17-Aug-93		4000			00-Jan-00									pbayou		9840
bayouwq	BUP9305	17-Aug-93	31616	1600	1	11353	00-Jan-00	1	1	L						pbayou	HP	9836

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUJ9305	17-Aug-93	31616	11000		11360	00-Jan-00									pbayou	HP	9824
. *	BUD9305	17-Aug-93	31616	2000			00-Jan-00									pbayou	HP	9816
	BUW9304	17-Aug-93	31616	4600	-		00-Jan-00									pbayou	HP	9850
	BUN9305 BUL9303	17-Aug-93 17-Aug-93	31616 31616	4000 30000			00-Jan-00 00-Jan-00									pbayou	HP HP	9832 9828
	BUA9318	17-Aug-93 18-Aug-93	31616	4400	BM		00-Jan-00 00-Jan-00								BM	pbayou pbayou	HP	9683
•	BUB9116	20-Aug-91	31616	1400			00-Jan-00								DIVI	pbayou	HP	8503
	BUE9115	20-Aug-91	31616	1100			00-Jan-00									pbayou	HP	8507
	BUA9123	20-Aug-91	31616	9400			00-Jan-00									pbayou	HP	8529
	BUP9118	20-Aug-91	31616	710		11353	00-Jan-00									pbayou	HP	8525
bayouwq	BUO9118	20-Aug-91	31616	980		11354	00-Jan-00									pbayou	HP	8523
bayouwq	BUM9116	20-Aug-91	31616	2800		11357	00-Jan-00									pbayou	HP	8519
	BUK9119	20-Aug-91	31616	8500			00-Jan-00									pbayou	HP	8515
•	BUJ9123	20-Aug-91	31616	78000			00-Jan-00									pbayou	HP	8513
. * *	BUH9122	20-Aug-91	31616	1100			00-Jan-00									pbayou	HP	8511
	BUD9121	20-Aug-91	31616	1200			00-Jan-00									pbayou	HP	8505
	BUW9122	20-Aug-91	31616	95000	-		00-Jan-00									pbayou	HP	8537
	BUS9123	20-Aug-91	31616	35000 10000			00-Jan-00									pbayou	HP HP	8531 8527
	BUQ9115 BUN9123	20-Aug-91 20-Aug-91	31616 31616	980			00-Jan-00 00-Jan-00									pbayou pbayou	HP	8521
•	BUL9123	20-Aug-91 20-Aug-91	31616	1200	-		00-Jan-00									pbayou	HP	8517
	BUG9115	20-Aug-91	31616	3300			00-Jan-00									pbayou	HP	8509
	BUE9026	21-Aug-90	31616	700			00-Jan-00									pother1	HP	12364
	BUA9028	21-Aug-90	31616	1700			00-Jan-00									pother1	HP	12386
	BUO9025	21-Aug-90	31616	1500			00-Jan-00									pother1	HP	12380
•	BUM9026	21-Aug-90	31616	81	-	11357	00-Jan-00									pother1	HP	12376
bayouwq	BUK9025	21-Aug-90	31616	3500		11359	00-Jan-00									pother1	HP	12372
bayouwq	BUJ9026	21-Aug-90	31616	1200		11360	00-Jan-00									pother1	HP	12370
bayouwq	BUH9026	21-Aug-90	31616	250		11362	00-Jan-00									pother1	HP	12368
bayouwq	BUW9026	21-Aug-90	31616	2800		15841	00-Jan-00									pother1	HP	12394
•	BUS9026	21-Aug-90	31616	3100			00-Jan-00									pother1	HP	12388
	BUQ9026	21-Aug-90	31616	3200			00-Jan-00									pother1	HP	12384
. *	BUN9028	21-Aug-90	31616	1100			00-Jan-00									pother1	HP	12378
. * *	BUL9024	21-Aug-90	31616	4200			00-Jan-00									pother1	HP	12374
	BUG9026	21-Aug-90	31616	6600			00-Jan-00								DM	pother1	HP	12366
	BUA9319 BUB9117	25-Aug-93 26-Aug-91	31616 31616	15000 140			00-Jan-00 00-Jan-00								BM	pbayou pbayou	HP HP	9729 8573
	BUE9116	26-Aug-91	31616	140			00-Jan-00									pbayou	HP	8577
_ ,	BUV9104	26-Aug-91	31616	950			00-Jan-00									pbayou	HP	8607
•	BUA9124	26-Aug-91	31616	740	-		00-Jan-00									pbayou	HP	8599
	BUP9119	26-Aug-91	31616	1100			00-Jan-00									pbayou	HP	8595
	BUO9119	26-Aug-91	31616	860			00-Jan-00									pbayou	HP	8593
	BUM9117	26-Aug-91	31616	810		11357	00-Jan-00									pbayou	HP	8589
bayouwq	BUK9120	26-Aug-91	31616	3000		11359	00-Jan-00									pbayou	HP	8585
bayouwq	BUJ9124	26-Aug-91	31616	920		11360	00-Jan-00									pbayou	HP	8583
bayouwq	BUH9123	26-Aug-91	31616	920		11362	00-Jan-00									pbayou	HP	8581
	BUD9122	26-Aug-91	31616	690	-		00-Jan-00									pbayou	HP	8575
	BUW9123	26-Aug-91	31616	380			00-Jan-00									pbayou	HP	8609
	BUS9124	26-Aug-91	31616	640			00-Jan-00									pbayou	HP	8601
	BUQ9116	26-Aug-91	31616	960			00-Jan-00									pbayou	HP	8597
	BUN9124	26-Aug-91	31616	500	-		00-Jan-00									pbayou	HP	8591
	BUL9124	26-Aug-91	31616	730			00-Jan-00				-					pbayou	HP	8587
•	BUG9116	26-Aug-91	31616	91 1100			00-Jan-00									pbayou pother1	HP	8579
	BUB9026 BUE9027	28-Aug-90	31616 31616	400	-		00-Jan-00 00-Jan-00									pother1	HP HP	12433 12437
	BUA9029	28-Aug-90 28-Aug-90	31616	5200			00-Jan-00 00-Jan-00									pother1 pother1	HP	12437
•	BUP9003	28-Aug-90 28-Aug-90	31616	2400	-		00-Jan-00 00-Jan-00									pother1	HP	12459
ouyouwq	2017003	28-Aug-90 28-Aug-90		4400	-		00-Jan-00		1		1			1		pother1	HP	12453

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUM9027	28-Aug-90	31616	9700		11357	00-Jan-00							pother1	HP	12449
bayouwq	BUK9026	28-Aug-90	31616	7400			00-Jan-00							pother1	HP	12445
bayouwq	BUJ9027	28-Aug-90	31616	940			00-Jan-00							pother1	HP	12443
bayouwq	BUH9027	28-Aug-90	31616	1300			00-Jan-00							pother1	HP	12441
bayouwq	BUD9026	28-Aug-90	31616	920			00-Jan-00							pother1	HP	12435
bayouwq	BUW9027	28-Aug-90	31616 31616	9300 100000			00-Jan-00							pother1	HP HP	12467 12465
bayouwq	BUU9024 BUS9027	28-Aug-90 28-Aug-90	31616	8500			00-Jan-00 00-Jan-00							pother1	HP	12463
bayouwq bayouwq	BUQ9027	28-Aug-90 28-Aug-90	31616	8700			00-Jan-00 00-Jan-00							pother1	HP	12461
bayouwq	BUN9029	28-Aug-90	31616	2900			00-Jan-00							pother1	HP	12451
bayouwq	BUL9025	28-Aug-90	31616	9			00-Jan-00							pother1	HP	12447
bayouwq	BUG9027	28-Aug-90	31616	7500			00-Jan-00							pother1	HP	12439
bayouwq	BUA8505	29-Aug-85	31616	36500			00-Jan-00							pother1	HP	9502
bayouwq	BUO8505	29-Aug-85	31616	17000			00-Jan-00							pother1	HP	9500
bayouwq	BUM8507	29-Aug-85	31616	58000		11357	00-Jan-00							pother1	HP	9497
bayouwq	BUK8507	29-Aug-85	31616	210		11359	00-Jan-00							pother1	HP	9495
bayouwq	BUI8501	29-Aug-85	31616	2240		11361	00-Jan-00							pother1	HP	9493
bayouwq	BUH8507	29-Aug-85	31616	790		11362	00-Jan-00							pother1	HP	9492
bayouwq	BUX8507	29-Aug-85	31616	5030		15840	00-Jan-00							pother1	HP	9511
bayouwq	BUW8507	29-Aug-85	31616	3700		15841	00-Jan-00							pother1	HP	9508
bayouwq	BUU8507	29-Aug-85	31616	37100		15842	00-Jan-00							pother1	HP	9506
bayouwq	BUS8507	29-Aug-85	31616	48000			00-Jan-00							pother1	HP	9505
bayouwq	BUN8503	29-Aug-85	31616	2700			00-Jan-00							pother1	HP	9498
bayouwq	BUL8504	29-Aug-85	31616	1500			00-Jan-00							pother1	HP	9496
bayouwq	BUA9206	31-Aug-92	31616	7100			00-Jan-00							pbayou	HP	9511
bayouwq	BUB8805	01-Sep-88	31616	12300			00-Jan-00							pother1	HP	9940
bayouwq	BUA8805	01-Sep-88	31616	120000			00-Jan-00							pother1	HP	9948
bayouwq	BUO8805	01-Sep-88	31616	7100			00-Jan-00							pother1	HP	9947
bayouwq	BUM8805	01-Sep-88	31616	2800			00-Jan-00							pother1	HP	9946
bayouwq	BUJ8805 BUH8805	01-Sep-88	31616 31616	3900			00-Jan-00 00-Jan-00							pother1	HP HP	9944 9943
bayouwq bayouwq	BUD8805	01-Sep-88 01-Sep-88	31616	10800			00-Jan-00 00-Jan-00							pother1	HP	9943
bayouwq	BUX8805	01-Sep-88	31616	114000			00-Jan-00							pother1	HP	9953
bayouwq	BUW8805	01-Sep-88	31616	4100			00-Jan-00							pother1	HP	9952
bayouwq	BUS8805	01-Sep-88	31616	23000			00-Jan-00							pother1	HP	9949
bayouwq	BUL8805	01-Sep-88	31616	410			00-Jan-00							pother1	HP	9945
bayouwq	BUG8805	01-Sep-88	31616	3100			00-Jan-00							pother1	HP	9942
bayouwq	BUV8304	04-Sep-83	31616	4000			00-Jan-00							pother1	HP	9060
bayouwq	BUA8305	04-Sep-83	31616	1			00-Jan-00							pother1	HP	9055
bayouwq	BUO8305	04-Sep-83	31616	1		11354	00-Jan-00							pother1	HP	9053
bayouwq	BUM8306	04-Sep-83	31616	6000		11357	00-Jan-00							pother1	HP	9050
bayouwq	BUJ8306	04-Sep-83	31616	1000		11360	00-Jan-00		·					pother1	HP	9047
bayouwq	BUH8306	04-Sep-83	31616	1		11362	00-Jan-00							pother1	HP	9045
bayouwq	BUX8304	04-Sep-83	31616	2000		15840	00-Jan-00							pother1	HP	9064
bayouwq	BUW8304	04-Sep-83	31616	6000			00-Jan-00							pother1	HP	9061
bayouwq	BUS8304	04-Sep-83	31616	4000			00-Jan-00							pother1	HP	9058
bayouwq	BUB9027	04-Sep-90	31616	14000			00-Jan-00							pother1	HP	12506
bayouwq	BUE9028	04-Sep-90	31616	1800			00-Jan-00							pother1	HP	12510
	BUA9030	04-Sep-90	31616	2900			00-Jan-00							pother1	HP	12532
bayouwq	BUP9004	04-Sep-90	31616	1500			00-Jan-00							pother1	HP	12528
	BUO9027	04-Sep-90	31616	1700			00-Jan-00							pother1	HP	12526
bayouwq	BUM9028	04-Sep-90	31616	18			00-Jan-00 00-Jan-00					 		pother1	HP	12522
bayouwq	BUK9027	04-Sep-90	31616	28000 300			00-Jan-00 00-Jan-00					 		pother1	HP	12518
bayouwq	BUJ9028 BUH9028	04-Sep-90 04-Sep-90	31616 31616	1400			00-Jan-00 00-Jan-00					\vdash		pother1	HP HP	12516 12514
bayouwg	BUD9027	04-Sep-90 04-Sep-90	31616	20000			00-Jan-00 00-Jan-00							pother1	HP	12514
bayouwq bayouwq	BUW9028	04-Sep-90	31616	2000			00-Jan-00 00-Jan-00							pother1	HP	12508
	BUU9025	04-Sep-90	31616	7300			00-Jan-00 00-Jan-00							pother1		12538
oayouwq	D U U 7023	04-3ep-90	31010	7300	l	13042	oo-jaii-00			1	<u> </u>			Pomer r	111	12330

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUS9028	04-Sep-90	31616	4000		15843	00-Jan-00							pother1	HP	12534
bayouwq	BUQ9028	04-Sep-90	31616	5900		15844	00-Jan-00							pother1	HP	12530
bayouwq	BUN9030	04-Sep-90	31616	3700			00-Jan-00							pother1	HP	12524
bayouwq	BUL9026	04-Sep-90	31616	29000			00-Jan-00							pother1	HP	12520
* *	BUG9028	04-Sep-90	31616	17000			00-Jan-00							pother1	HP	12512
	BUB9415 BUC9413	06-Sep-94 06-Sep-94	31616 31616	520 5800			00-Jan-00 00-Jan-00							9495a 9495a	HP HP	1900 1902
	BUE9415	06-Sep-94	31616	640		+	00-Jan-00							9495a 9495a	HP	1902
	BUV9415	06-Sep-94	31616	310			00-Jan-00							9495a	HP	1932
	BUA9417	06-Sep-94	31616		BM		00-Jan-00						BM	9495a	HP	1926
	BUP9415	06-Sep-94	31616	750			00-Jan-00							9495a	HP	1924
	BUO9415	06-Sep-94	31616	480			00-Jan-00							9495a	HP	1922
bayouwq	BUM9415	06-Sep-94	31616	770		11357	00-Jan-00							9495a	HP	1918
bayouwq	BUK9415	06-Sep-94	31616	3900		11359	00-Jan-00							9495a	HP	1914
bayouwq	BUI9410	06-Sep-94	31616	4700		11361	00-Jan-00							9495a	HP	1912
	BUH9415	06-Sep-94	31616	4800			00-Jan-00							9495a	HP	1910
	BUF9410	06-Sep-94	31616	560			00-Jan-00							9495a	HP	1908
<u> </u>	BUD9415	06-Sep-94	31616	490		+	00-Jan-00							9495a	HP	1904
	BUW9412	06-Sep-94	31616	2300			00-Jan-00							9495a	HP	1934
	BUS9415 BUN9415	06-Sep-94 06-Sep-94	31616 31616	2600 2300			00-Jan-00							9495a 9495a	HP HP	1928 1920
	BUL9415	06-Sep-94 06-Sep-94	31616	2900		+	00-Jan-00 00-Jan-00							9495a 9495a	HP	1916
	BUB9607	06-Sep-96	31616	2400			00-Jan-00							xls96	HP	2238
	BUC9606	06-Sep-96	31616	340			00-Jan-00							xls96	HP	2239
	BUE9614	06-Sep-96	31616	1400			00-Jan-00							xls96	HP	2241
•	BUA9622	06-Sep-96	31616	2000	OC		00-Jan-00						QC	xls96	HP	2237
	BUP9614	06-Sep-96	31616	1200			00-Jan-00							xls96	HP	2252
	BUO9614	06-Sep-96	31616	490		11354	00-Jan-00							xls96	HP	2251
bayouwq	BUM9613	06-Sep-96	31616	4500		11357	00-Jan-00							xls96	HP	2249
bayouwq	BUK9614	06-Sep-96	31616	140		11359	00-Jan-00							xls96	HP	2247
•	BUJ9611	06-Sep-96	31616	9			00-Jan-00							xls96	HP	2246
	BUI9613	06-Sep-96	31616	330			00-Jan-00							xls96	HP	2245
	BUH9614	06-Sep-96	31616	310			00-Jan-00							xls96	HP	2244
	BUF9612	06-Sep-96	31616	920			00-Jan-00							xls96	HP	2242
	BUD9614	06-Sep-96	31616	680			00-Jan-00							xls96	HP	2240 2255
	BUS9614 BUQ9614	06-Sep-96 06-Sep-96	31616 31616	8200 1600			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	2253
	BUN9614	06-Sep-96	31616	1200			00-Jan-00							xls96	HP	2250
	BUL9614	06-Sep-96	31616	72			00-Jan-00							xls96	HP	2248
•	BUG9612	06-Sep-96	31616	350			00-Jan-00							xls96	HP	2243
	BUA8605	08-Sep-86	31616	3990			00-Jan-00							pother1	HP	9694
	BUO8605	08-Sep-86	31616	6700		11354	00-Jan-00							pother1	HP	9692
	BUM8605	08-Sep-86	31616	1		11357	00-Jan-00							pother1	HP	9689
bayouwq	BUJ8605	08-Sep-86	31616	730		11360	00-Jan-00							pother1	HP	9686
bayouwq	BUH8605	08-Sep-86	31616	2050		11362	00-Jan-00							pother1	HP	9684
bayouwq	BUD8603	08-Sep-86	31616	4020		11364	00-Jan-00							pother1	HP	9682
	BUX8605	08-Sep-86	31616	760			00-Jan-00							pother1	HP	9703
	BUW8605	08-Sep-86	31616	1070			00-Jan-00							pother1	HP	9700
	BUU8605	08-Sep-86	31616	1990			00-Jan-00							pother1		9698
	BUS8605	08-Sep-86	31616	4150			00-Jan-00							pother1		9697
1	BUL8605	08-Sep-86	31616	2720			00-Jan-00 00-Jan-00							pother1	HP	9688
	BUG8602 BUB9118	08-Sep-86 09-Sep-91	31616 31616	2730 160			00-Jan-00 00-Jan-00							pother1 pbayou	HP HP	9683 10222
• •	BUE9117	09-Sep-91	31616	3600			00-Jan-00 00-Jan-00							pbayou	HP	10222
	BUV9105	09-Sep-91	31616	4000			00-Jan-00							pbayou	HP	10256
	BUA9125	09-Sep-91	31616	2300			00-Jan-00							pbayou	HP	10238
•	BUP9120	09-Sep-91	31616	820			00-Jan-00							pbayou	HP	10244
	BUO9120	09-Sep-91	31616	670			00-Jan-00							pbayou		10242

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CA	ALC. TYPI	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUM9118	09-Sep-91	31616	1300			00-Jan-00							pbayou	HP	10238
bayouwq	BUK9121	09-Sep-91	31616	1400			00-Jan-00							pbayou	HP	10234
bayouwq	BUJ9125	09-Sep-91	31616	1300			00-Jan-00							pbayou	HP	10232 10230
bayouwq	BUH9124 BUD9123	09-Sep-91 09-Sep-91	31616 31616	1500 310			00-Jan-00 00-Jan-00						+	pbayou	HP HP	10230
bayouwq bayouwq	BUX9106	09-Sep-91	31616	880			00-Jan-00 00-Jan-00							pbayou pbayou	HP	10224
bayouwq	BUW9124	09-Sep-91	31616	5600			00-Jan-00							pbayou	HP	10258
bayouwq	BUU9113	09-Sep-91	31616	4700			00-Jan-00							pbayou	HP	10254
bayouwq	BUS9125	09-Sep-91	31616	1900			00-Jan-00							pbayou	HP	10250
bayouwq	BUQ9117	09-Sep-91	31616	1100			00-Jan-00							pbayou	HP	10246
bayouwq	BUN9125	09-Sep-91	31616	860		15845	00-Jan-00							pbayou	HP	10240
bayouwq	BUL9125	09-Sep-91	31616	1500		15846	00-Jan-00							pbayou	HP	10236
bayouwq	BUG9117	09-Sep-91	31616	7500		15847	00-Jan-00							pbayou	HP	10228
bayouwq	BUA9207	10-Sep-92	31616	5100		11351	00-Jan-00							pbayou	HP	11032
bayouwq	BUV9615	10-Sep-96	31616	570		11345	00-Jan-00							xls96	HP	2270
bayouwq	BUX9614	10-Sep-96	31616	2100		15840	00-Jan-00							xls96	HP	2272
bayouwq	BUW9613	10-Sep-96	31616	240		15841	00-Jan-00							xls96	HP	2271
bayouwq	BUB9506	12-Sep-95	31616	58000		11142	00-Jan-00							9495b	HP	48
bayouwq	BUC9505	12-Sep-95	31616	1600			00-Jan-00							9495b	HP	49
bayouwq	BUE9510	12-Sep-95	31616	800			00-Jan-00							9495b		51
bayouwq	BUV9512	12-Sep-95	31616	200000			00-Jan-00							9495b	HP	65
bayouwq	BUA9516	12-Sep-95	31616	95000	BM		00-Jan-00						BM	9495b	HP	62
bayouwq	BUP9509	12-Sep-95	31616	99000			00-Jan-00							9495b	HP	60
bayouwq	BUO9508	12-Sep-95	31616	6500			00-Jan-00							9495b	HP	59
bayouwq	BUM9509	12-Sep-95	31616	5000			00-Jan-00							9495b	HP	58
bayouwq	BUK9509	12-Sep-95	31616	7300			00-Jan-00							9495b	HP	56
bayouwq	BUJ9510	12-Sep-95	31616	7300			00-Jan-00							9495b	HP	55
bayouwq	BUH9510 BUF9510	12-Sep-95 12-Sep-95	31616 31616	7000 770			00-Jan-00							9495b 9495b	HP HP	54 52
bayouwq	BUD9510	12-Sep-95 12-Sep-95	31616	1200			00-Jan-00 00-Jan-00						_	9495b	HP	50
bayouwq bayouwq	BUX9504	12-Sep-95	31616	200000			00-Jan-00							9495b	HP	67
bayouwq	BUW9508	12-Sep-95	31616	60000			00-Jan-00							9495b		66
bayouwq	BUS9510	12-Sep-95	31616	99000			00-Jan-00							9495b	HP	63
bayouwq	BUQ9507	12-Sep-95	31616	89000			00-Jan-00							9495b		61
bayouwq	BUN9509	12-Sep-95	31616	24000			00-Jan-00							9495b	HP	68
bayouwq	BUL9510	12-Sep-95	31616	5500			00-Jan-00							9495b		57
bayouwq	BUG9507	12-Sep-95	31616	880		15847	00-Jan-00							9495b		53
bayouwq	BUB9608	12-Sep-96	31616	58000		11142	00-Jan-00							bayou95	HP	171
bayouwq	BUC9607	12-Sep-96	31616	1600		11142	00-Jan-00							bayou95	HP	172
bayouwq	BUE9615	12-Sep-96	31616	800		11163	00-Jan-00							bayou95	HP	174
bayouwq	BUV9616	12-Sep-96	31616	200000		11345	00-Jan-00							bayou95	HP	188
bayouwq	BUA9623	12-Sep-96	31616	95000	BM		00-Jan-00						BM	bayou95	HP	185
bayouwq	BUP9615	12-Sep-96	31616	99000			00-Jan-00							bayou95	HP	183
bayouwq	BUO9615	12-Sep-96	31616	6500			00-Jan-00							bayou95	HP	182
bayouwq	BUM9614	12-Sep-96	31616	5000			00-Jan-00							bayou95		181
bayouwq	BUK9615	12-Sep-96	31616	7300			00-Jan-00							bayou95	HP	179
bayouwq	BUJ9612	12-Sep-96	31616	7300			00-Jan-00						_	bayou95	HP	178
bayouwq	BUH9615	12-Sep-96		7000			00-Jan-00						_	bayou95	HP	177
bayouwq	BUF9613	12-Sep-96	31616	770			00-Jan-00							bayou95	HP	175
bayouwq	BUD9615	12-Sep-96	31616	1200			00-Jan-00							bayou95	HP	173
	BUX9615	12-Sep-96	31616	200000			00-Jan-00							bayou95	HP	190
bayouwq	BUW9614	12-Sep-96	31616	60000			00-Jan-00						-	bayou95	HP	189
bayouwq	BUS9615	12-Sep-96	31616 31616	99000 89000			00-Jan-00 00-Jan-00							bayou95	HP HP	186 184
bayouwq	BUQ9615	12-Sep-96		24000									1	bayou95		191
bayouwa	BUN9615 BUL9615	12-Sep-96	31616 31616	5500			00-Jan-00 00-Jan-00						1	bayou95	HP HP	180
bayouwq bayouwq	BUG9613	12-Sep-96 12-Sep-96		880			00-Jan-00 00-Jan-00						1	bayou95 bayou95		176
	BUA8405	12-Sep-90 18-Sep-84		21000			00-Jan-00 00-Jan-00							pother1		9278
bayouwq	DUA0403	10-sep-84	31010	21000		11331	oo-jan-00							pomer i	III	7410

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUO8404	18-Sep-84	31616	36200		11354	00-Jan-00							pother1	HP	9276
bayouwq	BUM8405	18-Sep-84	31616	13000			00-Jan-00							pother1	HP	9273
bayouwq	BUJ8405	18-Sep-84	31616	1			00-Jan-00							pother1	HP	9270
bayouwq	BUH8404	18-Sep-84	31616	1300			00-Jan-00							pother1	HP	9268
bayouwq	BUS8405	18-Sep-84	31616	19800 1400			00-Jan-00							pother1	HP HP	9281 10737
bayouwq bayouwq	BUB9203 BUE9205	22-Sep-92 22-Sep-92	31616 31616	1400			00-Jan-00 00-Jan-00							pbayou pbayou	HP	10737
bayouwq	BUV9206	22-Sep-92	31616	3700			00-Jan-00							pbayou	HP	10771
bayouwq	BUA9208	22-Sep-92	31616	1300			00-Jan-00							pbayou	HP	10763
bayouwq	BUP9206	22-Sep-92	31616	480			00-Jan-00							pbayou	HP	10759
bayouwq	BUO9206	22-Sep-92	31616	2000		11354	00-Jan-00							pbayou	HP	10757
bayouwq	BUM9205	22-Sep-92	31616	1900		11357	00-Jan-00							pbayou	HP	10753
bayouwq	BUJ9206	22-Sep-92	31616	1800		11360	00-Jan-00							pbayou	HP	10747
bayouwq	BUH9206	22-Sep-92	31616	2900			00-Jan-00							pbayou	HP	10745
bayouwq	BUD9205	22-Sep-92	31616	1700			00-Jan-00							pbayou	HP	10739
bayouwq	BUW9206	22-Sep-92	31616	2900			00-Jan-00							pbayou	HP	10773
bayouwq	BUS9206	22-Sep-92	31616	2700 1300			00-Jan-00							pbayou	HP	10765 10761
bayouwq	BUQ9203 BUN9206	22-Sep-92 22-Sep-92	31616 31616	1500			00-Jan-00 00-Jan-00							pbayou	HP HP	10755
bayouwq bayouwq	BUL9205	22-Sep-92 22-Sep-92	31616	1500			00-Jan-00 00-Jan-00							pbayou pbayou	HP	10753
bayouwq	BUG9204	22-Sep-92	31616	1700			00-Jan-00							pbayou	HP	10743
bayouwq	BUA9209	24-Sep-92	31616	3900			00-Jan-00							pbayou	HP	11090
bayouwq	BUA9031	25-Sep-90	31616	9100			00-Jan-00							pother1	HP	12605
bayouwq	BUO9028	25-Sep-90	31616	3100		11354	00-Jan-00							pother1	HP	12599
bayouwq	BUK9028	25-Sep-90	31616	1200		11359	00-Jan-00							pother1	HP	12591
bayouwq	BUJ9029	25-Sep-90	31616	90			00-Jan-00							pother1	HP	12589
bayouwq	BUD9028	25-Sep-90	31616	1900			00-Jan-00							pother1	HP	12581
bayouwq	BUW9029	25-Sep-90	31616	38000			00-Jan-00							pother1	HP	12613
bayouwq	BUS9029	25-Sep-90	31616	15000			00-Jan-00							pother1	HP	12607 12597
bayouwq bayouwq	BUN9031 BUL9027	25-Sep-90 25-Sep-90	31616 31616	930 330			00-Jan-00 00-Jan-00							pother l	HP HP	12597
bayouwq	BUB9119	26-Sep-91	31616	7300			00-Jan-00							pbayou	HP	10303
bayouwq	BUE9118	26-Sep-91	31616	8700			00-Jan-00							pbayou	HP	10307
bayouwq	BUV9106	26-Sep-91	31616	5700			00-Jan-00							pbayou	HP	10337
bayouwq	BUA9126	26-Sep-91	31616	13000		11351	00-Jan-00							pbayou	HP	10329
bayouwq	BUP9121	26-Sep-91	31616	11000		11353	00-Jan-00							pbayou	HP	10325
bayouwq	BUO9121	26-Sep-91	31616	8400		11354	00-Jan-00							pbayou	HP	10323
bayouwq	BUM9119	26-Sep-91	31616	11000			00-Jan-00							pbayou	HP	10319
bayouwq	BUK9122	26-Sep-91	31616	9800			00-Jan-00							pbayou	HP	10315
bayouwq	BUJ9126	26-Sep-91	31616	12000			00-Jan-00							pbayou	HP	10313
bayouwq	BUH9125	26-Sep-91	31616	7300			00-Jan-00							pbayou	HP	10311 10305
bayouwq bayouwq	BUD9124 BUU9114	26-Sep-91 26-Sep-91	31616 31616	11000 4900			00-Jan-00 00-Jan-00							pbayou pbayou	HP HP	10305
bayouwq	BUS9126	26-Sep-91	31616	14000			00-Jan-00							pbayou	HP	10333
bayouwq	BUQ9118	26-Sep-91	31616	9100			00-Jan-00							pbayou	HP	10327
bayouwq	BUN9126	26-Sep-91	31616	12000			00-Jan-00							pbayou	HP	10321
bayouwq	BUL9126	26-Sep-91	31616	7900			00-Jan-00							pbayou	HP	10317
bayouwq	BUG9118	26-Sep-91	31616	7500		15847	00-Jan-00							pbayou	HP	10309
bayouwq	BUA9624	26-Sep-96	31616	9200			00-Jan-00						BM	bayou95		322
bayouwq	BUB9416	27-Sep-94	31616	590			00-Jan-00							9495a		2022
	BUC9414	27-Sep-94	31616	470			00-Jan-00							9495a	HP	2024
bayouwq	BUE9416	27-Sep-94	31616	1100			00-Jan-00							9495a		2028
bayouwq	BUV9416	27-Sep-94	31616	5400			00-Jan-00						DM	9495a	HP	2056
bayouwq	BUA9418 BUP9416	27-Sep-94 27-Sep-94	31616 31616	4600 2300			00-Jan-00 00-Jan-00						BM	9495a 9495a	HP HP	2050 2048
bayouwq bayouwq	BUO9416	27-Sep-94 27-Sep-94	31616	2300			00-Jan-00 00-Jan-00							9495a 9495a	HP	2048
	BUM9416	27-Sep-94	31616	740			00-Jan-00							9495a	HP	2040
	BUK9416		31616	4000			00-Jan-00							9495a		2038
bayouwq	BUK9416	27-Sep-94	31616	4000		11359	00-Jan-00							9495a	HP	2038

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUJ9414	27-Sep-94	31616	20000		11360	00-Jan-00							9495a	HP	2036
bayouwq	BUI9411	27-Sep-94	31616	8600			00-Jan-00							9495a	HP	2034
bayouwq	BUH9416	27-Sep-94	31616	8900			00-Jan-00							9495a	HP	2032
bayouwq	BUF9411	27-Sep-94	31616	630			00-Jan-00							9495a	HP	2030
bayouwq	BUD9416	27-Sep-94	31616	570 2300			00-Jan-00							9495a	HP HP	2026 2058
bayouwq bayouwq	BUW9413 BUS9416	27-Sep-94 27-Sep-94	31616 31616	480			00-Jan-00 00-Jan-00							9495a 9495a	HP	2058
bayouwq	BUN9416	27-Sep-94	31616	3400		1	00-Jan-00							9495a	HP	2044
bayouwq	BUL9416	27-Sep-94	31616	810			00-Jan-00							9495a		2040
bayouwq	BUB9609	27-Sep-96	31616	4400			00-Jan-00							bayou95	HP	339
bayouwq	BUC9608	27-Sep-96	31616	4400		11142	00-Jan-00							bayou95	HP	340
bayouwq	BUE9616	27-Sep-96	31616	2900		11163	00-Jan-00							bayou95	HP	342
bayouwq	BUV9617	27-Sep-96	31616	5800		11345	00-Jan-00							bayou95	HP	357
bayouwq	BUA9625	27-Sep-96	31616	11000	BM		00-Jan-00						BM	bayou95	HP	353
bayouwq	BUP9616	27-Sep-96	31616	2600			00-Jan-00							bayou95		351
bayouwq	BUO9616	27-Sep-96	31616	3900			00-Jan-00							bayou95	HP	350
bayouwq	BUM9615	27-Sep-96	31616	5900 6600			00-Jan-00							bayou95	HP	349 347
bayouwq	BUK9616 BUJ9613	27-Sep-96 27-Sep-96	31616 31616	7500		1	00-Jan-00 00-Jan-00							bayou95	HP HP	346
bayouwq bayouwq	BUI9614	27-Sep-96	31616	7800			00-Jan-00							bayou95 bayou95	HP	360
bayouwq	BUH9616	27-Sep-96	31616	3300			00-Jan-00							bayou95	HP	345
bayouwq	BUF9614	27-Sep-96	31616	2600		1	00-Jan-00							bayou95	HP	343
bayouwq	BUD9616	27-Sep-96	31616	4100			00-Jan-00							bayou95	HP	341
bayouwq	BUX9616	27-Sep-96	31616	4000		15840	00-Jan-00							bayou95	HP	359
bayouwq	BUW9615	27-Sep-96	31616	3700		15841	00-Jan-00							bayou95	HP	358
bayouwq	BUU9602	27-Sep-96	31616	6700			00-Jan-00							bayou95		355
bayouwq	BUS9616	27-Sep-96	31616	20000			00-Jan-00							bayou95		354
bayouwq	BUQ9616	27-Sep-96	31616	1600			00-Jan-00							bayou95		352
bayouwq	BUN9616	27-Sep-96	31616	5500			00-Jan-00							bayou95	HP	361
bayouwq bayouwq	BUL9616 BUG9614	27-Sep-96 27-Sep-96	31616 31616	5300 2300			00-Jan-00 00-Jan-00							bayou95 bayou95	HP HP	348 344
bayouwq	BUA9210	01-Oct-92	31616	5300			00-Jan-00							pbayou	HP	12105
bayouwq	BUB9028	02-Oct-90	31616	8600		1	00-Jan-00							pother1	HP	12652
bayouwq	BUE9029	02-Oct-90	31616	1200			00-Jan-00							pother1		12656
bayouwq	BUA9032	02-Oct-90	31616	7200		11351	00-Jan-00							pother1	HP	3593
bayouwq	BUP9005	02-Oct-90	31616	3700		11353	00-Jan-00							pother1	HP	12674
bayouwq	BUO9029	02-Oct-90	31616	8100		11354	00-Jan-00							pother1	HP	12672
bayouwq	BUM9029	02-Oct-90	31616	910			00-Jan-00							pother1	HP	12668
bayouwq	BUK9029	02-Oct-90	31616	400			00-Jan-00							pother1	HP	12664
bayouwq	BUJ9030	02-Oct-90	31616	9			00-Jan-00							pother1	HP	12662
bayouwq	BUH9029	02-Oct-90	31616	1000			00-Jan-00							pother1	HP	12660
bayouwq	BUD9029 BUW9030	02-Oct-90 02-Oct-90	31616 31616	1100 81000			00-Jan-00 00-Jan-00							pother l	HP HP	12654 3601
bayouwq bayouwq	BUU9026	02-Oct-90	31616	9000		1	00-Jan-00							pother1	HP	3599
bayouwq	BUS9030	02-Oct-90	31616	6300			00-Jan-00							pother1	HP	3595
bayouwq	BUQ9029	02-Oct-90	31616	6900			00-Jan-00							pother1	HP	12676
bayouwq	BUN9032	02-Oct-90	31616	1400			00-Jan-00							pother1	HP	12670
bayouwq	BUL9028	02-Oct-90	31616	390		15846	00-Jan-00							pother1	HP	12666
bayouwq	BUG9029	02-Oct-90	31616	13000			00-Jan-00							pother1		12658
bayouwq	BUC9301	05-Oct-93	31616	450			00-Jan-00			1				pbayou	HP	12463
bayouwq	BUE9303	05-Oct-93	31616	70			00-Jan-00							pbayou	HP	12467
bayouwq	BUV9308	05-Oct-93	31616	3300			00-Jan-00			1				pbayou	HP	12497
bayouwq	BUA9320	05-Oct-93	31616	560			00-Jan-00							pbayou	HP	12489
bayouwq	BUP9306 BUO9304	05-Oct-93 05-Oct-93	31616 31616	2400 3900			00-Jan-00 00-Jan-00			1				pbayou	HP HP	12485 12483
bayouwq bayouwq	BUM9303	05-Oct-93	31616	10000			00-Jan-00 00-Jan-00			1				pbayou pbayou	HP	12483
bayouwq	BUK9303	05-Oct-93	31616	770			00-Jan-00			1				pbayou	HP	12479
bayouwq	BUJ9306	05-Oct-93	31616	600			00-Jan-00			1				pbayou		12473
oayouwq	D 037300	03-001-93	31010	000	L	11300	50-Jan-00	11		1	L			poayou	111	12413

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUH9304	05-Oct-93	31616	6400		11362	00-Jan-00							pbayou	HP	12471
bayouwq	BUD9306	05-Oct-93	31616	1100			00-Jan-00							pbayou	HP	12465
bayouwq	BUW9305	05-Oct-93	31616	2500			00-Jan-00							pbayou	HP	12499
bayouwq	BUS9306	05-Oct-93	31616	4000			00-Jan-00							pbayou	HP	12491
bayouwq	BUN9306 BUL9304	05-Oct-93 05-Oct-93	31616 31616	5200 1300			00-Jan-00 00-Jan-00							pbayou	HP HP	12481 12477
bayouwq bayouwq	BUG9303	05-Oct-93	31616	27			00-Jan-00 00-Jan-00							pbayou pbayou	HP	12477
	BUB9120	07-Oct-91	31616	2000			00-Jan-00							pbayou	HP	11251
	BUE9119	07-Oct-91	31616	180			00-Jan-00							pbayou	HP	11255
bayouwq	BUV9107	07-Oct-91	31616	3800			00-Jan-00							pbayou	HP	11285
bayouwq	BUA9127	07-Oct-91	31616	640		11351	00-Jan-00							pbayou	HP	11277
bayouwq	BUP9122	07-Oct-91	31616	330		11353	00-Jan-00							pbayou	HP	11273
bayouwq	BUO9122	07-Oct-91	31616	490		11354	00-Jan-00							pbayou	HP	11271
bayouwq	BUM9120	07-Oct-91	31616	250			00-Jan-00							pbayou	HP	11267
	BUK9123	07-Oct-91	31616	8600			00-Jan-00							pbayou	HP	11263
bayouwq	BUJ9127	07-Oct-91	31616	240			00-Jan-00							pbayou	HP	11261
bayouwq	BUH9126 BUD9125	07-Oct-91 07-Oct-91	31616 31616	360 870			00-Jan-00 00-Jan-00							pbayou	HP HP	11259 11253
bayouwq bayouwq	BUW9126	07-Oct-91	31616	5900			00-Jan-00 00-Jan-00							pbayou pbayou	HP	11233
	BUU9115	07-Oct-91	31616	4000			00-Jan-00							pbayou	HP	11283
	BUS9127	07-Oct-91	31616	480			00-Jan-00							pbayou	HP	11279
bayouwq	BUQ9119	07-Oct-91	31616	340			00-Jan-00							pbayou	HP	11275
bayouwq	BUN9127	07-Oct-91	31616	330		15845	00-Jan-00							pbayou	HP	11269
bayouwq	BUL9127	07-Oct-91	31616	3700		15846	00-Jan-00							pbayou	HP	11265
bayouwq	BUG9119	07-Oct-91	31616	150			00-Jan-00							pbayou	HP	11257
bayouwq	BUB9610	07-Oct-96	31616	200			00-Jan-00							xls96	HP	2454
	BUC9609	07-Oct-96	31616	290			00-Jan-00							xls96		2455
bayouwq	BUE9617	07-Oct-96	31616	680 2500			00-Jan-00							xls96		2457
bayouwq	BUV9618 BUA9626	07-Oct-96 07-Oct-96	31616 31616	655	OC		00-Jan-00 00-Jan-00						QC	xls96 xls96	HP HP	2473 2453
bayouwq bayouwq	BUP9617	07-Oct-96	31616	270	QC		00-Jan-00						QC .	xls96	HP	2468
bayouwq	BUO9617	07-Oct-96	31616	280			00-Jan-00							xls96	HP	2467
bayouwq	BUM9616	07-Oct-96	31616	230			00-Jan-00							xls96	HP	2465
bayouwq	BUK9617	07-Oct-96	31616	650		11359	00-Jan-00							xls96	HP	2463
bayouwq	BUJ9614	07-Oct-96	31616	3400		11360	00-Jan-00							xls96	HP	2462
bayouwq	BUI9615	07-Oct-96	31616	430		11361	00-Jan-00							xls96	HP	2461
bayouwq	BUH9617	07-Oct-96	31616	520			00-Jan-00							xls96	HP	2460
bayouwq	BUF9615	07-Oct-96	31616	320			00-Jan-00							xls96	HP	2458
bayouwq	BUD9617	07-Oct-96	31616	360			00-Jan-00							xls96	HP	2456
	BUX9617 BUW9616	07-Oct-96 07-Oct-96	31616 31616	1990 2400			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	2475 2474
bayouwq bayouwq	BUS9617	07-Oct-96	31616	2300			00-Jan-00 00-Jan-00							xls96	HP	2474
bayouwq	BUQ9617	07-Oct-96	31616	490			00-Jan-00							xls96	HP	2469
bayouwq	BUN9617	07-Oct-96	31616	320			00-Jan-00							xls96	HP	2466
	BUL9617	07-Oct-96	31616	72			00-Jan-00							xls96	HP	2464
bayouwq	BUG9615	07-Oct-96	31616	3100		15847	00-Jan-00							xls96	HP	2459
bayouwq	BUB9029	08-Oct-90	31616	910		11142	00-Jan-00							pother1	HP	3641
	BUE9030	08-Oct-90	31616	3200			00-Jan-00							pother1	HP	3645
	BUA9033	08-Oct-90	31616	4200			00-Jan-00							pother1		3667
	BUP9006	08-Oct-90	31616	35000			00-Jan-00							pother1	HP	3663
	BUO9030	08-Oct-90	31616	10000			00-Jan-00							pother1	HP	3661
	BUM9030 BUK9030	08-Oct-90 08-Oct-90	31616 31616	29000 9400			00-Jan-00 00-Jan-00							pother l	HP HP	3657 3653
bayouwq	BUJ9031	08-Oct-90	31616	1500			00-Jan-00 00-Jan-00							pother1	HP	3651
	BUH9030	08-Oct-90	31616	2200			00-Jan-00							pother1	HP	3649
	BUD9030	08-Oct-90	31616	33000			00-Jan-00							pother1	HP	3643
- 7 - 1	BUW9031	08-Oct-90	31616	10000			00-Jan-00							pother1	HP	3675
	BUS9031	08-Oct-90	31616	9000		15843	00-Jan-00							pother1	HP	3669

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUQ9030	08-Oct-90	31616	21000		15844	00-Jan-00							pother1	HP	3665
bayouwq	BUN9033	08-Oct-90	31616	20000			00-Jan-00							pother1	HP	3659
bayouwq	BUL9029	08-Oct-90	31616	9100			00-Jan-00							pother1	HP	3655
bayouwq	BUG9030	08-Oct-90	31616	10000			00-Jan-00							pother1	HP	3647
bayouwq	BUA9211 BUV9619	08-Oct-92 09-Oct-96	31616 31616	2000 4400			00-Jan-00 00-Jan-00							pbayou bayou05	HP HP	12158 499
bayouwq bayouwq	BUA8806	10-Oct-88	31616	3500			00-Jan-00 00-Jan-00							bayou95 pother1	HP	9972
bayouwq	BUO8806	10-Oct-88	31616	19700			00-Jan-00							pother1	HP	9971
bayouwq	BUM8806	10-Oct-88	31616	41			00-Jan-00							pother1	HP	9970
bayouwq	BUJ8806	10-Oct-88	31616	1			00-Jan-00							pother1	HP	9968
bayouwq	BUH8806	10-Oct-88	31616	2100		11362	00-Jan-00							pother1	HP	9967
bayouwq	BUX8806	10-Oct-88	31616	2200		15840	00-Jan-00							pother1	HP	9977
bayouwq	BUW8806	10-Oct-88	31616	20100		15841	00-Jan-00							pother1	HP	9976
bayouwq	BUU8806	10-Oct-88	31616	17700			00-Jan-00							pother1	HP	9975
bayouwq	BUS8806	10-Oct-88	31616	5100			00-Jan-00							pother l	HP	9973
bayouwq	BUL8806	10-Oct-88	31616	6			00-Jan-00							pother1	HP	9969
bayouwq	BUG8806 BUV8305	10-Oct-88 11-Oct-83	31616 31616	650 28000			00-Jan-00 00-Jan-00							pother1	HP HP	9966 9091
bayouwq bayouwq	BUA8306	11-Oct-83	31616	4000			00-Jan-00 00-Jan-00							pother1	HP	9091
bayouwq	BUO8306	11-Oct-83	31616	9000			00-Jan-00							pother1	HP	9084
bayouwq	BUM8307	11-Oct-83	31616	53000			00-Jan-00							pother1	HP	9081
bayouwq	BUJ8307	11-Oct-83	31616	1			00-Jan-00							pother1	HP	9078
bayouwq	BUH8307	11-Oct-83	31616	1			00-Jan-00							pother1	HP	9076
bayouwq	BUX8305	11-Oct-83	31616	1		15840	00-Jan-00							pother1	HP	9095
bayouwq	BUU8301	11-Oct-83	31616	43000		15842	00-Jan-00							pother1	HP	9090
bayouwq	BUS8305	11-Oct-83	31616	67000		15843	00-Jan-00							pother1	HP	9089
bayouwq	BUB9507	11-Oct-95	31616	34000			00-Jan-00							9495b	HP	82
bayouwq	BUC9506	11-Oct-95	31616	700			00-Jan-00							9495b	HP	83
bayouwq	BUE9511	11-Oct-95	31616	430			00-Jan-00							9495b	HP	85
bayouwq	BUV9513	11-Oct-95	31616	3400			00-Jan-00						nu .	9495b	HP	100
bayouwq bayouwq	BUA9517 BUP9510	11-Oct-95 11-Oct-95	31616 31616	10000 710	ВМ		00-Jan-00 00-Jan-00						BM	9495b 9495b	HP HP	96 94
bayouwq	BUO9509	11-Oct-95	31616	2000			00-Jan-00 00-Jan-00							9495b	HP	93
bayouwq	BUM9510	11-Oct-95	31616	3000			00-Jan-00							9495b	HP	92
bayouwq	BUK9510	11-Oct-95	31616	3400			00-Jan-00							9495b	HP	90
bayouwq	BUJ9511	11-Oct-95	31616	3800			00-Jan-00							9495b	HP	89
bayouwq	BUH9511	11-Oct-95	31616	2800		11362	00-Jan-00							9495b	HP	88
bayouwq	BUF9511	11-Oct-95	31616	1400		11363	00-Jan-00							9495b	HP	86
bayouwq	BUD9511	11-Oct-95	31616	950		11364	00-Jan-00							9495b	HP	84
bayouwq	BUX9505	11-Oct-95	31616	980			00-Jan-00							9495b	HP	102
bayouwq	BUW9509	11-Oct-95	31616	1000			00-Jan-00							9495b	HP	101
bayouwq	BUS9511	11-Oct-95	31616	12000			00-Jan-00							9495b	HP	97
bayouwq	BUQ9508	11-Oct-95	31616	720			00-Jan-00							9495b	HP	95 103
bayouwq	BUN9510 BUL9511	11-Oct-95 11-Oct-95	31616 31616	730 1200			00-Jan-00 00-Jan-00							9495b 9495b	HP HP	91
bayouwq bayouwq	BUG9508	11-Oct-95	31616	5200			00-Jan-00							9495b	HP	87
bayouwq	BUB9611	11-Oct-96	31616	34000			00-Jan-00							bayou95	HP	531
bayouwq	BUC9610	11-Oct-96	31616	700			00-Jan-00							bayou95	HP	532
	BUE9618	11-Oct-96	31616	430			00-Jan-00							bayou95	HP	534
bayouwq	BUV9620	11-Oct-96	31616	3400		11345	00-Jan-00							bayou95	HP	549
bayouwq	BUA9627	11-Oct-96	31616	10000	BM	11351	00-Jan-00						BM	bayou95	HP	545
bayouwq	BUP9618	11-Oct-96	31616	710			00-Jan-00							bayou95	HP	543
bayouwq	BUO9618	11-Oct-96	31616	2000			00-Jan-00							bayou95	HP	542
bayouwq	BUM9617	11-Oct-96	31616	3000			00-Jan-00							bayou95	HP	541
bayouwq	BUK9618	11-Oct-96	31616	3400			00-Jan-00							bayou95	HP	539
bayouwq	BUJ9615	11-Oct-96	31616	3800			00-Jan-00							bayou95	HP	538
bayouwq	BUH9618	11-Oct-96	31616	2800			00-Jan-00							bayou95	HP	537
bayouwq	BUF9616	11-Oct-96	31616	1400		11363	00-Jan-00			1		1		bayou95	HP	535

	TAG	END DATE	CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq B	BUD9618	11-Oct-96	31616	950		11364	00-Jan-00							bayou95	HP	533
	BUX9618	11-Oct-96	31616	980			00-Jan-00							bayou95		551
. * * -	BUW9617	11-Oct-96	31616	1000			00-Jan-00							bayou95	HP	550
	BUS9618	11-Oct-96	31616	12000			00-Jan-00							bayou95	HP	546 544
	BUQ9618 BUN9618	11-Oct-96 11-Oct-96	31616 31616	720 730			00-Jan-00 00-Jan-00							bayou95	HP HP	552
	BUL9618	11-Oct-96	31616	1200		l	00-Jan-00 00-Jan-00							bayou95 bayou95	HP	540
	BUG9616	11-Oct-96	31616	5200			00-Jan-00							bayou95	HP	536
	BUB9204	12-Oct-92	31616	280			00-Jan-00							pbayou	HP	11818
	BUE9206	12-Oct-92	31616	250		l	00-Jan-00							pbayou	HP	11822
	3UV9207	12-Oct-92	31616	2800		11345	00-Jan-00							pbayou	HP	11852
bayouwq B	BUA9212	12-Oct-92	31616	53000		11351	00-Jan-00							pbayou	HP	11844
bayouwq B	BUP9207	12-Oct-92	31616	1100		11353	00-Jan-00							pbayou	HP	11840
	BUO9207	12-Oct-92	31616	3700			00-Jan-00							pbayou	HP	11838
	BUM9206	12-Oct-92	31616	4700			00-Jan-00							pbayou	HP	11834
	BUK9206	12-Oct-92	31616	23000			00-Jan-00							pbayou	HP	11830
	BUJ9207 BUH9207	12-Oct-92 12-Oct-92	31616 31616	6600 260			00-Jan-00 00-Jan-00							pbayou	HP HP	11828 11826
	BUD9206	12-Oct-92	31616	510			00-Jan-00 00-Jan-00							pbayou pbayou	HP	11820
	BUW9207	12-Oct-92	31616	2800			00-Jan-00							pbayou	HP	11854
	BUS9207	12-Oct-92	31616	5500		l	00-Jan-00							pbayou	HP	11846
	3UQ9204	12-Oct-92	31616	45000		15844	00-Jan-00							pbayou	HP	11842
	BUN9207	12-Oct-92	31616	2000		15845	00-Jan-00							pbayou	HP	11836
bayouwq B	BUL9206	12-Oct-92	31616	7500		15846	00-Jan-00							pbayou	HP	11832
	BUG9205	12-Oct-92	31616	370			00-Jan-00							pbayou	HP	11824
	BUA9213	13-Oct-92	31616	2600		l	00-Jan-00							pbayou	HP	12208
	BUA9214	20-Oct-92	31616	2700			00-Jan-00							pbayou	HP	12257
. * * -	BUA9321	20-Oct-93	31616	7600	ВМ		00-Jan-00						BM	pbayou	HP	12378
	BUB9031 BUE9032	23-Oct-90 23-Oct-90	31616 31616	3500 830			00-Jan-00 00-Jan-00							pother1	HP HP	3788 3792
	BUA9035	23-Oct-90	31616	14000			00-Jan-00							pother1	HP	3814
	BUP9008	23-Oct-90	31616	1500		l	00-Jan-00							pother1	HP	3810
	BUO9032	23-Oct-90	31616	2300			00-Jan-00							pother1	HP	3808
	BUM9031	23-Oct-90	31616	25000		11357	00-Jan-00							pother1	HP	3804
bayouwq B	BUK9032	23-Oct-90	31616	1500		11359	00-Jan-00							pother1	HP	3800
bayouwq B	BUJ9033	23-Oct-90	31616	1000		11360	00-Jan-00							pother1	HP	3798
	BUH9032	23-Oct-90	31616	690			00-Jan-00							pother1	HP	3796
	BUD9032	23-Oct-90	31616	3600			00-Jan-00							pother1	HP	3790
. * * -	BUW9032	23-Oct-90	31616	12000			00-Jan-00							pother1	HP	3822
	BUU9027	23-Oct-90 23-Oct-90	31616	30000 4500			00-Jan-00 00-Jan-00							pother1	HP HP	3820 3816
	BUS9033 BUQ9032	23-Oct-90	31616 31616	2700			00-Jan-00 00-Jan-00							pother1 pother1	HP	3812
-	BUN9035	23-Oct-90	31616	9400		l	00-Jan-00							pother1	HP	3806
	BUL9031	23-Oct-90	31616	1100			00-Jan-00							pother1	HP	3802
	3UG9031	23-Oct-90	31616	5100			00-Jan-00							pother1	HP	3794
	BUA9628	23-Oct-96	31616	5600	BM	11351	00-Jan-00						BM	bayou95	HP	129
bayouwq B	BUA9215	27-Oct-92	31616	6000		11351	00-Jan-00							pbayou	HP	12307
bayouwq B	BUA9629	30-Oct-96	31616	580	BM	11351	00-Jan-00						BM	xls96	HP	2698
	BUA8807	03-Nov-88	31616	16306			00-Jan-00							pother1		9996
	BUO8807	03-Nov-88	31616	5400			00-Jan-00							pother1		9995
	BUM8807	03-Nov-88	31616	3900			00-Jan-00							pother1	HP	9994
	BUJ8807	03-Nov-88	31616	10			00-Jan-00							pother1	HP	9992
L L	BUH8807 BUD8807	03-Nov-88 03-Nov-88	31616 31616	718 3000			00-Jan-00 00-Jan-00							pother1	HP HP	9991 9989
	BUX8807	03-Nov-88	31616	1029			00-Jan-00 00-Jan-00							pother1	HP	10001
	BUU8807	03-Nov-88	31616	3100			00-Jan-00 00-Jan-00							pother1	HP	9999
	BUS8807	03-Nov-88	31616	5500			00-Jan-00							pother1	HP	9997
	BUL8807	03-Nov-88	31616	420		l	00-Jan-00							pother1		9993

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUG8807	03-Nov-88	31616	3100		15847	00-Jan-00							pother1	HP	9990
	BUB9122	04-Nov-91	31616	1200			00-Jan-00							pbayou	HP	12878
bayouwq	BUE9121	04-Nov-91	31616	510			00-Jan-00							pbayou	HP	12882
bayouwq	BUV9109	04-Nov-91	31616	73000			00-Jan-00							pbayou	HP	12912
	BUA9130	04-Nov-91	31616	8100			00-Jan-00							pbayou	HP	12904
	BUP9124	04-Nov-91	31616	3000			00-Jan-00							pbayou	HP	12900
	BUO9125	04-Nov-91	31616	2200			00-Jan-00							pbayou	HP	12898
	BUM9122	04-Nov-91	31616	1900			00-Jan-00							pbayou	HP	12894
	BUK9125	04-Nov-91	31616	1200			00-Jan-00							pbayou	HP	12890
	BUJ9130 BUH9129	04-Nov-91 04-Nov-91	31616 31616	820 790			00-Jan-00 00-Jan-00							pbayou	HP HP	12888 12886
	BUD9127	04-Nov-91	31616	910			00-Jan-00 00-Jan-00							pbayou pbayou	HP	12880
	BUW9129	04-Nov-91	31616	5800			00-Jan-00 00-Jan-00							pbayou	HP	12914
	BUU9117	04-Nov-91	31616	3500			00-Jan-00							pbayou	HP	12910
	BUS9130	04-Nov-91	31616	7800			00-Jan-00							pbayou	HP	12906
	BUQ9121	04-Nov-91	31616	9100			00-Jan-00							pbayou	HP	12902
	BUN9130	04-Nov-91	31616	2200			00-Jan-00							pbayou	HP	12896
	BUL9130	04-Nov-91	31616	1200			00-Jan-00							pbayou	HP	12892
	BUG9121	04-Nov-91	31616	430			00-Jan-00							pbayou	HP	12884
	BUE9619	04-Nov-96	31616	490			00-Jan-00							xls96	HP	2725
	BUV9621	04-Nov-96	31616	2700			00-Jan-00							xls96	HP	2741
	BUA9630	04-Nov-96	31616	560	BM	11351	00-Jan-00						BM	xls96	HP	2738
	BUP9619	04-Nov-96	31616	360			00-Jan-00							xls96	HP	2736
bayouwq	BUO9619	04-Nov-96	31616	4100		11354	00-Jan-00							xls96	HP	2735
bayouwq	BUM9618	04-Nov-96	31616	4600		11357	00-Jan-00							xls96	HP	2733
bayouwq	BUK9619	04-Nov-96	31616	460		11359	00-Jan-00							xls96	HP	2731
bayouwq	BUJ9616	04-Nov-96	31616	4600		11360	00-Jan-00							xls96	HP	2730
bayouwq	BUI9616	04-Nov-96	31616	710		11361	00-Jan-00							xls96	HP	2729
bayouwq	BUH9619	04-Nov-96	31616	490		11362	00-Jan-00							xls96	HP	2728
	BUF9617	04-Nov-96	31616	460			00-Jan-00							xls96	HP	2726
	BUD9619	04-Nov-96	31616	670			00-Jan-00							xls96	HP	2724
	BUX9619	04-Nov-96	31616	5200			00-Jan-00							xls96	HP	2743
	BUW9618	04-Nov-96	31616	2400			00-Jan-00							xls96	HP	2742
	BUS9619	04-Nov-96	31616	390			00-Jan-00							xls96	HP	2739
	BUQ9619	04-Nov-96	31616	410			00-Jan-00							xls96	HP	2737
	BUN9619	04-Nov-96	31616	3600			00-Jan-00							xls96	HP	2734
	BUL9619	04-Nov-96	31616	390			00-Jan-00							xls96	HP	2732
	BUG9617	04-Nov-96	31616	660			00-Jan-00							xls96	HP	2727
	BUA9216	05-Nov-92	31616	5500			00-Jan-00							pbayou	HP	13588
	BUE9620	06-Nov-96	31616	870 23000			00-Jan-00							bayou95	HP HP	638 654
	BUV9622 BUA9631	06-Nov-96 06-Nov-96	31616 31616	2400			00-Jan-00							bayou95	HP	651
	BUA9632	06-Nov-96	31616	1200	OC		00-Jan-00 00-Jan-00						QC	bayou95	HP	634
	BUP9620	06-Nov-96	31616	2400	QC.		00-Jan-00 00-Jan-00						QC .	bayou95 bayou95	HP	649
	BUO9620	06-Nov-96	31616	4600			00-Jan-00 00-Jan-00							bayou95 bayou95	HP	648
	BUM9619	06-Nov-96	31616	2300			00-Jan-00							bayou95	HP	646
	BUK9620	06-Nov-96	31616	2000			00-Jan-00							bayou95	HP	644
	BUJ9617	06-Nov-96	31616	3000			00-Jan-00							bayou95	HP	643
	BUI9617	06-Nov-96	31616	5000			00-Jan-00							bayou95	+	642
	BUH9620	06-Nov-96	31616	3700			00-Jan-00							bayou95		641
	BUF9618	06-Nov-96	31616	5000			00-Jan-00							bayou95	HP	639
	BUD9620	06-Nov-96	31616	4100			00-Jan-00							bayou95		637
	BUX9620	06-Nov-96	31616	3200			00-Jan-00							bayou95	HP	656
•	BUW9619	06-Nov-96	31616	4400			00-Jan-00							bayou95	HP	655
	BUS9620	06-Nov-96	31616	5000			00-Jan-00							bayou95	HP	652
	BUQ9620	06-Nov-96	31616	2300			00-Jan-00							bayou95	HP	650
	BUN9620	06-Nov-96	31616	4600			00-Jan-00							bayou95	HP	647
	BUL9620	06-Nov-96	31616	9100		15846	00-Jan-00							bayou95	HP	645

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUV9623	07-Nov-96	31616	7000		11345	00-Jan-00							bayou95	HP	682
bayouwq	BUE9417	15-Nov-94	31616	54			00-Jan-00							9495a	HP	2698
bayouwq	BUV9417	15-Nov-94	31616	5900			00-Jan-00							9495a	HP	2728
bayouwq	BUA9419	15-Nov-94	31616		BM		00-Jan-00						BM	9495a	HP	2722
bayouwq	BUP9417	15-Nov-94	31616	230			00-Jan-00							9495a	HP HP	2720 2718
bayouwq bayouwq	BUO9417 BUM9417	15-Nov-94 15-Nov-94	31616 31616	160			00-Jan-00 00-Jan-00							9495a 9495a	HP	2714
bayouwq	BUK9417	15-Nov-94	31616	81			00-Jan-00							9495a	HP	2710
bayouwq	BUJ9415	15-Nov-94	31616	72			00-Jan-00							9495a	HP	2708
bayouwq	BUI9412	15-Nov-94	31616	99			00-Jan-00							9495a	HP	2706
bayouwq	BUH9417	15-Nov-94	31616	220		11362	00-Jan-00							9495a	HP	2704
bayouwq	BUF9412	15-Nov-94	31616	63		11363	00-Jan-00							9495a	HP	2700
bayouwq	BUD9417	15-Nov-94	31616	180		11364	00-Jan-00							9495a	HP	2696
bayouwq	BUW9414	15-Nov-94	31616	820		15841	00-Jan-00							9495a	HP	2730
bayouwq	BUS9417	15-Nov-94	31616	140			00-Jan-00							9495a	HP	2724
bayouwq	BUN9417	15-Nov-94	31616	99			00-Jan-00							9495a	HP	2716
bayouwq	BUL9417	15-Nov-94	31616	36			00-Jan-00							9495a	HP	2712
bayouwq	BUG9415	15-Nov-94	31616	160 6500			00-Jan-00							9495a	HP HP	2702 13330
bayouwq bayouwq	BUV9208 BUA9217	16-Nov-92 16-Nov-92	31616 31616	2100			00-Jan-00 00-Jan-00							pbayou pbayou	HP	13322
bayouwq	BUP9208	16-Nov-92	31616	1900			00-Jan-00							pbayou	HP	13318
bayouwq	BUK9207	16-Nov-92	31616	4500			00-Jan-00							pbayou	HP	13308
bayouwq	BUJ9208	16-Nov-92	31616	2100			00-Jan-00							pbayou	HP	13306
bayouwq	BUH9208	16-Nov-92	31616	3400			00-Jan-00							pbayou	HP	13304
bayouwq	BUD9207	16-Nov-92	31616	1400		11364	00-Jan-00							pbayou	HP	13298
bayouwq	BUW9208	16-Nov-92	31616	7700		15841	00-Jan-00							pbayou	HP	13332
bayouwq	BUS9208	16-Nov-92	31616	4000		15843	00-Jan-00							pbayou	HP	13324
bayouwq	BUN9208	16-Nov-92	31616	2500			00-Jan-00							pbayou	HP	13314
bayouwq	BUL9207	16-Nov-92	31616	4400			00-Jan-00							pbayou	HP	13310
bayouwq	BUA9420	16-Nov-94	31616	2100			00-Jan-00						BM	9495a	HP	2555
bayouwq	BUA9633	20-Nov-96	31616		BM		00-Jan-00						BM	xls96	HP	2957
bayouwq	BUA8506 BUO8506	26-Nov-85 26-Nov-85	31616 31616	16300 3900			00-Jan-00							pother l	HP HP	9534 9532
bayouwq bayouwq	BUM8508	26-Nov-85	31616	16600			00-Jan-00 00-Jan-00							pother1 pother1	HP	9529
bayouwq	BUK8508	26-Nov-85	31616	2500			00-Jan-00							pother1	HP	9527
bayouwq	BUJ8507	26-Nov-85	31616	670			00-Jan-00							pother1	HP	9526
bayouwq	BUH8508	26-Nov-85	31616	1110			00-Jan-00							pother1	HP	9524
bayouwq	BUX8508	26-Nov-85	31616	3400			00-Jan-00							pother1	HP	9543
bayouwq	BUW8508	26-Nov-85	31616	9600		15841	00-Jan-00							pother1	HP	9540
bayouwq	BUU8508	26-Nov-85	31616	11300		15842	00-Jan-00							pother1	HP	9538
bayouwq	BUS8508	26-Nov-85	31616	11400		15843	00-Jan-00							pother1	HP	9537
bayouwq	BUL8505	26-Nov-85	31616	600			00-Jan-00							pother1	HP	9528
bayouwq	BUE9418	29-Nov-94	31616	350			00-Jan-00							9495a	HP	2763
bayouwq	BUV9418	29-Nov-94	31616	700			00-Jan-00							9495a	HP	2791
bayouwq	BUA9421	29-Nov-94	31616	2100			00-Jan-00						BM	9495a	HP	2785
bayouwq	BUP9418	29-Nov-94 29-Nov-94	31616 31616	8400 8000			00-Jan-00							9495a 9495a	HP HP	2783 2781
bayouwq bayouwq	BUO9418 BUM9418	29-Nov-94 29-Nov-94	31616	2200			00-Jan-00 00-Jan-00							9495a 9495a	HP	2777
	BUK9418	29-Nov-94	31616	660			00-Jan-00							9495a	HP	2773
bayouwq	BUJ9416	29-Nov-94	31616	840			00-Jan-00 00-Jan-00							9495a	HP	2771
	BUH9418	29-Nov-94	31616	950			00-Jan-00							9495a	HP	2769
bayouwq	BUF9413	29-Nov-94	31616	490			00-Jan-00							9495a	HP	2765
	BUD9418	29-Nov-94	31616	250			00-Jan-00							9495a	HP	2761
bayouwq	BUW9415	29-Nov-94	31616	240			00-Jan-00							9495a	HP	2793
bayouwq	BUS9418	29-Nov-94	31616	2500		15843	00-Jan-00							9495a	HP	2787
bayouwq	BUN9418	29-Nov-94	31616	14000		15845	00-Jan-00							9495a	HP	2779
* *	BUL9418	29-Nov-94	31616	390		15846	00-Jan-00							9495a	HP	2775
bayouwq	BUG9416	29-Nov-94	31616	580		15847	00-Jan-00							9495a	HP	2767

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUA9422	30-Nov-94	31616	2800	BM	11351	00-Jan-00						BM	9495a	HP	2652
bayouwq	BUB8905	04-Dec-89	31616	150			00-Jan-00							pother1	HP	10234
bayouwq	BUE8901	04-Dec-89	31616	63			00-Jan-00							pother1	HP	10238
bayouwq	BUA8908	04-Dec-89	31616	6200			00-Jan-00							pother1	HP	10258
bayouwq	BUO8907	04-Dec-89	31616	36			00-Jan-00							pother1	HP	10254 10250
bayouwq bayouwq	BUM8908 BUK8901	04-Dec-89 04-Dec-89	31616 31616	9			00-Jan-00 00-Jan-00							pother1	HP HP	10230
bayouwq	BUJ8908	04-Dec-89	31616	9			00-Jan-00							pother1	HP	10244
bayouwq	BUH8908	04-Dec-89	31616	1100			00-Jan-00							pother1	HP	10242
bayouwq	BUD8907	04-Dec-89	31616	770			00-Jan-00							pother1	HP	10236
bayouwq	BUX8908	04-Dec-89	31616	150		15840	00-Jan-00							pother1	HP	10270
bayouwq	BUW8906	04-Dec-89	31616	5700		15841	00-Jan-00							pother1	HP	10266
bayouwq	BUU8908	04-Dec-89	31616	5100		15842	00-Jan-00							pother1	HP	10264
bayouwq	BUS8908	04-Dec-89	31616	1700		15843	00-Jan-00							pother1	HP	10260
bayouwq	BUQ8906	04-Dec-89	31616	6400			00-Jan-00							pother1	HP	10256
bayouwq	BUN8906	04-Dec-89	31616	18			00-Jan-00							pother1	HP	10252
bayouwq	BUL8908	04-Dec-89	31616	500			00-Jan-00							pother l	HP HP	10248 10240
bayouwq	BUG8908 BUB9508	04-Dec-89 05-Dec-95	31616 31616	590 980			00-Jan-00 00-Jan-00							pother1 9495b	HP	121
bayouwq bayouwq	BUC9507	05-Dec-95	31616	220			00-Jan-00 00-Jan-00							9495b	HP	122
bayouwq	BUE9512	05-Dec-95	31616	270			00-Jan-00							9495b	HP	124
bayouwq	BUV9514	05-Dec-95	31616	610			00-Jan-00							9495b	HP	140
bayouwq	BUA9518	05-Dec-95	31616	2000			00-Jan-00							9495b	HP	137
bayouwq	BUA9519	05-Dec-95	31616	9500	QC	11351	00-Jan-00						QC	9495b	HP	120
bayouwq	BUP9511	05-Dec-95	31616	3200		11353	00-Jan-00							9495b	HP	135
bayouwq	BUO9510	05-Dec-95	31616	26000			00-Jan-00							9495b		134
bayouwq	BUM9511	05-Dec-95	31616	340			00-Jan-00							9495b	HP	132
bayouwq	BUK9511	05-Dec-95	31616	460			00-Jan-00							9495b		130
bayouwq	BUJ9512	05-Dec-95	31616	290			00-Jan-00							9495b	HP	129
bayouwq bayouwq	BUI9508 BUH9512	05-Dec-95 05-Dec-95	31616 31616	370 270			00-Jan-00 00-Jan-00							9495b 9495b	HP HP	128 127
bayouwq	BUF9512	05-Dec-95	31616	870			00-Jan-00							9495b	HP	125
bayouwq	BUD9512	05-Dec-95	31616	330			00-Jan-00							9495b	HP	123
bayouwq	BUX9506	05-Dec-95	31616	385			00-Jan-00							9495b	HP	142
bayouwq	BUW9510	05-Dec-95	31616	2000		15841	00-Jan-00							9495b	HP	141
bayouwq	BUS9512	05-Dec-95	31616	3800		15843	00-Jan-00							9495b	HP	138
bayouwq	BUQ9509	05-Dec-95	31616	980		15844	00-Jan-00							9495b	HP	136
bayouwq	BUN9511	05-Dec-95	31616	22000			00-Jan-00							9495b	HP	133
bayouwq	BUL9512	05-Dec-95	31616	430			00-Jan-00							9495b		131
bayouwq	BUG9509	05-Dec-95	31616	370			00-Jan-00							9495b		126
bayouwq	BUB9613	05-Dec-96	31616	980			00-Jan-00							bayou95		901 902
bayouwq bayouwq	BUC9612 BUE9622	05-Dec-96 05-Dec-96	31616 31616	220 270			00-Jan-00 00-Jan-00							bayou95 bayou95	HP HP	902
bayouwq	BUV9625	05-Dec-96	31616	2400			00-Jan-00							bayou95	HP	949
bayouwq	BUA9637	05-Dec-96	31616	2000			00-Jan-00							bayou95		917
bayouwq	BUA9638	05-Dec-96	31616	9500	QC		00-Jan-00						QC	bayou95	HP	900
bayouwq	BUP9622	05-Dec-96	31616	3200			00-Jan-00							bayou95	HP	915
bayouwq	BUO9622	05-Dec-96	31616	26000		11354	00-Jan-00							bayou95	HP	914
bayouwq	BUM9621	05-Dec-96	31616	340			00-Jan-00							bayou95		912
bayouwq	BUK9622	05-Dec-96	31616	460			00-Jan-00							bayou95		910
	BUJ9619	05-Dec-96	31616	290			00-Jan-00							bayou95	HP	909
bayouwq	BUI9619	05-Dec-96	31616	370			00-Jan-00							bayou95		908
	BUH9622	05-Dec-96	31616	270 870			00-Jan-00							bayou95		907
bayouwq	BUF9620 BUD9622	05-Dec-96 05-Dec-96	31616 31616	330			00-Jan-00 00-Jan-00							bayou95	HP HP	905 903
bayouwq bayouwq	BUX9622	05-Dec-96 05-Dec-96	31616	330			00-Jan-00 00-Jan-00							bayou95 bayou95		903
	BUW9621	05-Dec-96	31616	2000			00-Jan-00 00-Jan-00							bayou95		922
				3800												918
bayouwq	BUS9622	05-Dec-96	31616	3800		15843	00-Jan-00					1		bayou95	HP	918

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CAL	C. TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUQ9622	05-Dec-96	31616	980			00-Jan-00							bayou95	HP	916
bayouwq	BUN9622	05-Dec-96	31616	22000			00-Jan-00							bayou95	HP	913
bayouwq	BUL9622	05-Dec-96	31616	430			00-Jan-00							bayou95	HP	911
bayouwq	BUG9619	05-Dec-96	31616 31616	370 500			00-Jan-00							bayou95	HP HP	906 9726
bayouwq bayouwq	BUA8606 BUO8606	08-Dec-86 08-Dec-86	31616	350			00-Jan-00 00-Jan-00							pother1 pother1	HP	9726
bayouwq	BUM8606	08-Dec-86	31616	10			00-Jan-00							pother1	HP	9721
bayouwq	BUJ8606	08-Dec-86	31616	10			00-Jan-00							pother1	HP	9718
bayouwq	BUH8606	08-Dec-86	31616	260			00-Jan-00							pother1	HP	9716
bayouwq	BUD8604	08-Dec-86	31616	320		11364	00-Jan-00							pother1	HP	9714
bayouwq	BUX8606	08-Dec-86	31616	1080		15840	00-Jan-00							pother1	HP	9735
bayouwq	BUW8606	08-Dec-86	31616	9800			00-Jan-00							pother1	HP	9732
bayouwq	BUU8606	08-Dec-86	31616	24000			00-Jan-00							pother1	HP	9730
bayouwq	BUS8606	08-Dec-86	31616	730			00-Jan-00							pother1	HP	9729
bayouwq	BUL8606	08-Dec-86	31616	10			00-Jan-00							pother1	HP	9720
bayouwq	BUG8603	08-Dec-86 08-Dec-92	31616 31616	180	DM		00-Jan-00						BM	pother1	HP	9715 13621
bayouwq bayouwq	BUA9218 BUA9036	10-Dec-90	31616	5100 13000	BM		00-Jan-00 00-Jan-00						ВМ	pbayou pother1	HP HP	3954
bayouwq	BUO9033	10-Dec-90	31616	46000			00-Jan-00							pother1	HP	3948
bayouwq	BUM9032	10-Dec-90	31616	27000			00-Jan-00							pother1	HP	3944
bayouwq	BUK9033	10-Dec-90	31616	8000			00-Jan-00							pother1	HP	3940
bayouwq	BUH9033	10-Dec-90	31616	320			00-Jan-00							pother1	HP	3936
bayouwq	BUD9033	10-Dec-90	31616	940			00-Jan-00							pother1	HP	3930
bayouwq	BUW9033	10-Dec-90	31616	2200		15841	00-Jan-00							pother1	HP	3962
bayouwq	BUS9034	10-Dec-90	31616	24000		15843	00-Jan-00							pother1	HP	3956
bayouwq	BUN9036	10-Dec-90	31616	57000		15845	00-Jan-00							pother l	HP	3946
bayouwq	BUL9032	10-Dec-90	31616	11000		15846	00-Jan-00							pother1	HP	3942
bayouwq	BUE9623	10-Dec-96	31616	770			00-Jan-00							xls96	HP	3086
bayouwq	BUV9626	10-Dec-96	31616	7600			00-Jan-00							xls96	HP	3102
bayouwq	BUA9639	10-Dec-96	31616	9100	BM		00-Jan-00						BM	xls96	HP	3099
	BUP9623	10-Dec-96	31616	3800			00-Jan-00							xls96	HP	3097
. * *	BUO9623	10-Dec-96	31616	2900 1000			00-Jan-00 00-Jan-00							xls96 xls96	HP HP	3096 3094
bayouwa	BUM9622 BUK9623	10-Dec-96 10-Dec-96	31616 31616	530			00-Jan-00 00-Jan-00							xls96	HP	3094
bayouwq bayouwq	BUJ9620	10-Dec-96	31616	5100			00-Jan-00							xls96	HP	3092
bayouwq	BUI9620	10-Dec-96	31616	900			00-Jan-00							xls96	HP	3090
bayouwq	BUH9623	10-Dec-96	31616	580			00-Jan-00							xls96	HP	3089
	BUF9621	10-Dec-96	31616	750			00-Jan-00							xls96	HP	3087
	BUD9623	10-Dec-96	31616	580		11364	00-Jan-00							xls96	HP	3085
bayouwq	BUX9623	10-Dec-96	31616	5100		15840	00-Jan-00							xls96	HP	3104
bayouwq	BUW9622	10-Dec-96	31616	1300		15841	00-Jan-00							xls96	HP	3103
-	BUS9623	10-Dec-96	31616	37000			00-Jan-00							xls96	HP	3100
bayouwq	BUQ9623	10-Dec-96	31616	1400		15844	00-Jan-00							xls96	HP	3098
bayouwq	BUN9623	10-Dec-96	31616	290			00-Jan-00							xls96	HP	3095
bayouwq	BUL9623	10-Dec-96	31616	460			00-Jan-00							xls96	HP	3093
bayouwq	BUG9620	10-Dec-96	31616	610			00-Jan-00							xls96	HP	3088
bayouwq	BUB8808	12-Dec-88	31616	757			00-Jan-00							pother1	HP	10012
bayouwq	BUA8808 BUO8808	12-Dec-88	31616	973 450			00-Jan-00							pother1	HP HP	10020 10019
bayouwq bayouwq	BUM8808	12-Dec-88 12-Dec-88	31616 31616	10			00-Jan-00 00-Jan-00							pother1 pother1	HP	10019
• •	BUJ8808	12-Dec-88	31616	10			00-Jan-00 00-Jan-00							pother1	HP	10016
-	BUH8808	12-Dec-88	31616	171			00-Jan-00							pother1	HP	10015
	BUD8808	12-Dec-88	31616	793			00-Jan-00							pother1	HP	10013
• •	BUX8808	12-Dec-88	31616	1259			00-Jan-00							pother1	HP	10025
	BUU8808	12-Dec-88	31616	1559			00-Jan-00							pother1	HP	10023
	BUS8808	12-Dec-88	31616	1550			00-Jan-00							pother1	HP	10021
bayouwq	BUL8808	12-Dec-88	31616	18		15846	00-Jan-00							pother1	HP	10017
bayouwq	BUG8808	12-Dec-88	31616	108		15847	00-Jan-00							pother1	HP	10014

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUA9640	18-Dec-96	31616	8300	BM	11351	00-Jan-00								BM	xls96	HP	3223
	BUB8906	21-Dec-89	31616	36		11142	00-Jan-00									pother1	HP	10301
	BUE8902	21-Dec-89	31616	72			00-Jan-00									pother1	HP	10305
	BUA8909	21-Dec-89	31616	2000			00-Jan-00									pother1	HP	10325
	BUO8908	21-Dec-89	31616	9			00-Jan-00									pother1	HP	10321
• •	BUM8909	21-Dec-89	31616	9			00-Jan-00									pother l	HP	10317
	BUK8902	21-Dec-89	31616	9			00-Jan-00									pother1	HP	10313
bayouwq	BUJ8909	21-Dec-89	31616	9			00-Jan-00									pother l	HP	10311
	BUH8909	21-Dec-89	31616	9			00-Jan-00									pother1	HP	10309
· ·	BUD8908	21-Dec-89	31616	81			00-Jan-00									pother1	HP	10303
bayouwq	BUX8909	21-Dec-89	31616	27			00-Jan-00									pother1	HP	10337
	BUW8907	21-Dec-89	31616	2600			00-Jan-00									pother1	HP	10333
	BUU8909	21-Dec-89 21-Dec-89	31616	1100 2200			00-Jan-00									pother1	HP HP	10331 10327
. * *	BUS8909 BUQ8907	21-Dec-89 21-Dec-89	31616 31616	1000			00-Jan-00									pother1	HP	10327
	BUN8907	21-Dec-89 21-Dec-89	31616	9			00-Jan-00 00-Jan-00									pother1 pother1	HP	10323
	BUL8909	21-Dec-89	31616	9			00-Jan-00									pother1	HP	10319
• •	BUG8909	21-Dec-89	31616	9			00-Jan-00									pother1	HP	10313
	BUB8907	28-Dec-89	31616	72			00-Jan-00									pother1	HP	10370
	BUE8903	28-Dec-89	31616	260			00-Jan-00									pother1	HP	10374
bayouwq	BUA8910	28-Dec-89	31616	160			00-Jan-00									pother1	HP	10394
bayouwq	BUO8909	28-Dec-89	31616	9			00-Jan-00									pother1	HP	10390
	BUM8910	28-Dec-89	31616	9			00-Jan-00									pother1	HP	10386
• •	BUK8903	28-Dec-89	31616	9			00-Jan-00									pother1	HP	10382
	BUJ8910	28-Dec-89	31616	18			00-Jan-00									pother1	HP	10380
	BUH8910	28-Dec-89	31616	9		11362	00-Jan-00									pother1	HP	10378
bayouwq	BUD8909	28-Dec-89	31616	54		11364	00-Jan-00									pother1	HP	10372
	BUX8910	28-Dec-89	31616	9		15840	00-Jan-00									pother1	HP	10406
bayouwq	BUW8908	28-Dec-89	31616	3800		15841	00-Jan-00									pother1	HP	10402
bayouwq	BUU8910	28-Dec-89	31616	2200		15842	00-Jan-00									pother1	HP	10400
bayouwq	BUS8910	28-Dec-89	31616	3600		15843	00-Jan-00									pother 1	HP	10396
bayouwq	BUQ8908	28-Dec-89	31616	140		15844	00-Jan-00									pother1	HP	10392
bayouwq	BUN8908	28-Dec-89	31616	9		15845	00-Jan-00									pother1	HP	10388
bayouwq	BUL8910	28-Dec-89	31616	9		15846	00-Jan-00									pother l	HP	10384
	BUG8910	28-Dec-89	31616	300			00-Jan-00									pother1	HP	10376
	BUB8901	01-Jan-89	31616	620			00-Jan-00								Exact date unknown. Default to the		HP	10036
	BUA8901	01-Jan-89	31616	62000			00-Jan-00								Exact date unknown. Default to th		HP	10044
, ,	BUO8901	01-Jan-89	31616	1505			00-Jan-00								Exact date unknown. Default to th		HP	10043
	BUM8901	01-Jan-89	31616	135			00-Jan-00								Exact date unknown. Default to th		HP	10042
	BUJ8901	01-Jan-89	31616	360			00-Jan-00								Exact date unknown. Default to th		HP	10040
	BUH8901	01-Jan-89	31616	310			00-Jan-00								Exact date unknown. Default to the		HP	10039
• •	BUD8901	01-Jan-89	31616	460 570			00-Jan-00								Exact date unknown. Default to the		HP HP	10037 10049
	BUX8901 BUU8901	01-Jan-89	31616 31616	69000			00-Jan-00								Exact date unknown. Default to the	•	HP	10049
	BUS8901	01-Jan-89 01-Jan-89	31616	77000			00-Jan-00 00-Jan-00								Exact date unknown. Default to the Exact date unknown. Default to the		HP	10047
. * *	BUL8901	01-Jan-89	31616	30			00-Jan-00								Exact date unknown. Default to the	•	HP	10043
bayouwq	BUG8901	01-Jan-89	31616	580			00-Jan-00								Exact date unknown. Default to the		HP	10038
bayouwq bayouwq	BUB8801	01-May-88	31616	1310			00-Jan-00								Exact date unknown. Default to the		HP	9845
	BUA8801	01-May-88	31616	3800			00-Jan-00								Exact date unknown. Default to the	-	HP	9853
	BUO8801	01-May-88	31616	4500			00-Jan-00								Exact date unknown. Default to the		HP	9852
	BUM8801	01-May-88	31616	370			00-Jan-00								Exact date unknown. Default to the	*	HP	9851
• •	BUJ8801	01-May-88	31616	15300			00-Jan-00								Exact date unknown. Default to the	•	HP	9849
	BUH8801	01-May-88	31616	5300			00-Jan-00		1						Exact date unknown. Default to the	*	HP	9848
• •	BUD8801	01-May-88	31616	1200			00-Jan-00								Exact date unknown. Default to the		HP	9846
• •	BUX8801	01-May-88	31616	2800			00-Jan-00								Exact date unknown. Default to the		HP	9857
	BUW8801	01-May-88	31616	2700			00-Jan-00								Exact date unknown. Default to th		HP	9856
• •	BUU8801	01-May-88	31616	1530			00-Jan-00								Exact date unknown. Default to th		HP	9855
	BUS8801	01-May-88		4100			00-Jan-00		1						Exact date unknown. Default to th		HP	9854

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
bayouwq	BUL8801	01-May-88		330		15846	00-Jan-00							Exact date unknown. Default to the	epother1		9850
bayouwq	BUG8801	01-May-88		2100			00-Jan-00							Exact date unknown. Default to the	*		9847
НН		13-May-96		6600			00-Jan-00									НН	
НН		15-May-96		560	-		00-Jan-00									НН	
НН		15-May-96		11000			00-Jan-00									НН	
HH		15-May-96		2800	-		00-Jan-00									НН	
HH		15-May-96		2100	-		00-Jan-00									HH	
HH		15-May-96		2300			00-Jan-00									HH	1
HH		21-May-96		260	-		00-Jan-00									HH	1
HH		21-May-96		1800			00-Jan-00									HH	
HH		21-May-96		880			00-Jan-00									HH	
HH		21-May-96		680	-		00-Jan-00									HH	
HH		21-May-96		2000	-		00-Jan-00									HH	
HH		23-May-96		540 19000			00-Jan-00									HH	
HH		23-May-96		720	-		00-Jan-00									HH HH	
HH HH		23-May-96		610			00-Jan-00									нн НН	
нн НН		23-May-96 23-May-96		10000	-		00-Jan-00 00-Jan-00									нн НН	
																нн НН	
HH HH		13-May-96 13-May-96		> 160000 5000			00-Jan-00 00-Jan-00									HH	
нн НН		03-Jun-96		160000	-		00-Jan-00 00-Jan-00									HH	
нн НН		03-Jun-96		24000			00-Jan-00 00-Jan-00									нн Н	
нн НН		19-Mar-96		< 200			00-Jan-00 00-Jan-00									HH	
нн НН		19-Mar-96		50000			00-Jan-00 00-Jan-00									нн Н	
HH		19-Mar-96		< 200			00-Jan-00 00-Jan-00									HH	
HH		19-Mar-96		400			00-Jan-00									HH	
НН		19-Mar-96		3000			00-Jan-00									HH	
HH		04-Jan-95		800			00-Jan-00									HH	
HH		04-Jan-95		900			00-Jan-00									НН	
НН		04-Jan-95		1300	-		00-Jan-00									НН	
HH		04-Jan-95		13000			00-Jan-00									НН	
HH		04-Jan-95		3000	-		00-Jan-00									HH	
НН		19-Jan-95		1700	-		00-Jan-00									НН	
НН		19-Jan-95		3000			00-Jan-00									НН	
НН		19-Jan-95		8000			00-Jan-00									НН	
нн		19-Jan-95		30000			00-Jan-00									HH	
НН		19-Jan-95		17000			00-Jan-00]	НН	
НН		16-Feb-95		8000		11387	00-Jan-00]	НН	
НН		16-Feb-95		22000		11148	00-Jan-00]	НН	
НН		03-Feb-95		> 160000		11148	00-Jan-00]	НН	
НН		03-Feb-95		5000		11387	00-Jan-00]	НН	
НН		17-Feb-95		3000		11387	00-Jan-00]	HH	
НН		05-Jan-96		> 160000		11148	00-Jan-00]	HH	
НН		05-Jan-96		24000		11387	00-Jan-00]	HH	
НН		19-Jan-96		> 160000		11148	00-Jan-00]	НН	
НН		19-Jan-96		22000		11387	00-Jan-00									НН	
НН		02-Feb-96		13000		11148	00-Jan-00]	HH	
НН		02-Feb-96		13000		11387	00-Jan-00]	HH	
НН		09-Feb-95		2200			00-Jan-00									HH	
НН		09-Feb-95		8000			00-Jan-00									НН	
НН		09-Feb-95		1700			00-Jan-00									НН	
НН		09-Feb-95		17000			00-Jan-00									НН	
НН		09-Feb-95		3000			00-Jan-00									НН	
НН		24-Feb-95		> 160000			00-Jan-00									HH	
НН		10-Mar-95		50000			00-Jan-00									НН	
НН		17-Mar-95		700			00-Jan-00									HH	
HH		24-Mar-95		1100	-		00-Jan-00									HH	
HH		31-Mar-95		28000		11387	00-Jan-00			<u> </u>]	HH	

Database	TAG	END DATE	STORET CODE	GT LT	VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH		CALC. TYPE	COMMENT		SOURCE 2	PROGRAM
НН		07-Apr-95			17000			00-Jan-00									НН	
НН		28-Apr-95			3000		11387										HH	
НН		01-Mar-95			30000			00-Jan-00									НН	
НН		01-Mar-95			30000			00-Jan-00									HH	
НН		01-Mar-95			30000			00-Jan-00									HH	
НН		01-Mar-95			24000			00-Jan-00									НН	
НН		01-Mar-95			30000			00-Jan-00									HH	
НН		30-Mar-95			90000			00-Jan-00									НН	
НН		30-Mar-95			24000			00-Jan-00									НН	
НН		30-Mar-95			13000			00-Jan-00									HH	
НН		30-Mar-95			24000			00-Jan-00									НН	
НН		30-Mar-95			160000			00-Jan-00									HH	
НН		11-Apr-95		<	200			00-Jan-00									HH	
НН		11-Apr-95			1700			00-Jan-00									НН	
НН		11-Apr-95			11000			00-Jan-00									НН	
НН		11-Apr-95			24000			00-Jan-00									НН	
НН		11-Apr-95			24000			00-Jan-00									НН	
НН		19-May-95			22000			00-Jan-00									HH	
НН		19-May-95			1300			00-Jan-00									НН	
НН		05-May-95			50000			00-Jan-00									HH	
НН		05-May-95			90000			00-Jan-00									HH	
НН		18-May-95			200			00-Jan-00									НН	
НН		18-May-95			200			00-Jan-00									НН	
НН		18-May-95			200			00-Jan-00									НН	
НН		18-May-95			200		11351	00-Jan-00									HH	
НН		18-May-95			3000			00-Jan-00									НН	
НН		25-May-95			800			00-Jan-00									HH	
НН		25-May-95			30000			00-Jan-00									НН	
НН		25-May-95			400			00-Jan-00									НН	
HH		25-May-95			1300			00-Jan-00									HH	\vdash
HH		25-May-95			13000			00-Jan-00									HH	1
HH		09-Jun-95			160000			00-Jan-00									HH	\vdash
HH		09-Jun-95			1100			00-Jan-00									HH	
HH		23-Jun-95		>	160000			00-Jan-00									HH	
HH		23-Jun-95			2700		11387										HH	
HH		07-Jul-95		>	160000			00-Jan-00									HH	
HH		07-Jul-95			11000		11387										HH	
HH		21-Jul-95			1300		11148										HH	
HH		21-Jul-95		>	160000		11387	00-Jan-00									HH	
HH		04-Aug-95			30000			00-Jan-00									HH	
HH		04-Aug-95			30000		11387										HH	
HH		07-Jun-95		<	200			00-Jan-00									HH	
HH		07-Jun-95			200			00-Jan-00									HH	1
HH		07-Jun-95			1300			00-Jan-00									HH	1
HH		07-Jun-95			1100			00-Jan-00					 				HH	
HH		07-Jun-95			14000			00-Jan-00				-	1				HH	
HH HH		13-Jul-95 13-Jul-95		1	400 30000			00-Jan-00 00-Jan-00				1	1			 	HH HH	
		13-Jul-95 13-Jul-95		1	90000			00-Jan-00 00-Jan-00				1	1				нн НН	
HH HH		13-Jul-95 13-Jul-95			30000			00-Jan-00 00-Jan-00				-	1				HH HH	
HH HH		13-Jul-95 13-Jul-95		1	30000			00-Jan-00				1	1				нн НН	
		13-Jui-95 15-Jun-95		_	200			00-Jan-00				1	1				нн НН	\vdash
HH		15-Jun-95 15-Jun-95		<	200			00-Jan-00 00-Jan-00				-	1				HH HH	
HH HH		15-Jun-95 15-Jun-95		1	400			00-Jan-00				1	1				нн НН	
		15-Jun-95 15-Jun-95		1	1700			00-Jan-00 00-Jan-00				1	1				нн НН	\vdash
HH HH		15-Jun-95 15-Jun-95			1700			00-Jan-00									нн НН	
HH HH		15-Jun-95 18-Aug-95		_	160000			00-Jan-00				1	1				нн НН	
				/								1	1					
HH		18-Aug-95	<u> </u>	<u> </u>	5000		11387	00-Jan-00	1			1				L	HH	

Database	TAG	END DATE STORE	GT VALUE remark	STATION ID EN		END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC	TYPE	COMMENT	SOURCE 1 2	PROGRAM
HH		01-Sep-95	> 160000	11148 00-Ja								HH	
НН		01-Sep-95	160000		an-00							HH	
HH		15-Sep-95	> 160000		an-00							HH	
HH		15-Sep-95	800		an-00							HH	
HH		03-Aug-95	900	11142 00-Ja								HH	
HH HH		03-Aug-95	24000 50000	11360 00-Ja 11356 00-Ja								HH HH	
		03-Aug-95	30000	11350 00-Ja								HH	
HH HH		03-Aug-95 03-Aug-95	50000	11331 00-Ja								HH	
нн НН		13-Sep-95	200	11347 00-Ja								НН	
HH		13-Sep-95	17000	11360 00-Ja								HH	
НН		13-Sep-95	35000	11356 00-Ja								HH	
HH		13-Sep-95	50000	11351 00-Ja								HH	
НН		13-Sep-95	17000		an-00							НН	
НН		28-Sep-95	400		an-00							НН	
НН		28-Sep-95	3000		an-00							НН	
НН		28-Sep-95	1700	11356 00-Ja								НН	
HH		28-Sep-95	4700	11351 00-Ja								НН	
НН		28-Sep-95	1700	11347 00-Ja	an-00							НН	
НН		20-Oct-95	> 160000	11148 00-Ja								НН	
НН		20-Oct-95	17000	11387 00-Ja	an-00							НН	
НН		03-Nov-95	160000	11148 00-Ja	an-00							НН	
НН		03-Nov-95	30000	11387 00-Ja	an-00							НН	
HH		05-Oct-95	3000	11142 00-Ja	an-00							НН	
НН		05-Oct-95	2300	11360 00-Ja	an-00							НН	
НН		05-Oct-95	3700	11356 00-Ja	an-00							НН	
HH		05-Oct-95	3000	11351 00-Ja	an-00							HH	
HH		05-Oct-95	5000		an-00							HH	
НН		18-Oct-95	400		an-00							HH	
НН		18-Oct-95	700	11142 00-Ja								НН	
HH		18-Oct-95	1300	11356 00-Ja								НН	
HH		18-Oct-95	3000	11351 00-Ja								HH	
HH		18-Oct-95	1300	11347 00-Ja								HH	
HH		01-Dec-95	> 160000	11148 00-Ja								HH	
HH		01-Dec-95	24000	11387 00-Ja								HH	
HH HH		09-Nov-95 09-Nov-95	< 200 200	11142 00-Ja 11360 00-Ja								HH HH	
		09-Nov-95										HH	
HH HH		09-Nov-95	1300		an-00 an-00							HH	
HH		09-Nov-95	1300		an-00							НН	
НН		16-Nov-95	400	11347 00-Ja								НН	
HH		16-Nov-95	2200		an-00							НН	
HH		16-Nov-95	5000	11356 00-Ja								НН	
НН		16-Nov-95	11000	11351 00-Ja								НН	
НН		16-Nov-95	11000	11347 00-Ja								НН	
HH		15-Dec-95	13000	11148 00-Ja								НН	
НН		15-Dec-95	13000	11387 00-Ja								НН	
НН		05-Dec-95	< 200	11142 00-Ja								НН	
НН		05-Dec-95	400	11360 00-Ja								НН	
НН		05-Dec-95	1100	11356 00-Ja								НН	
НН		05-Dec-95	5000	11351 00-Ja								НН	
НН		05-Dec-95	3000	11347 00-Ja								НН	
HH		14-Dec-95	200	11142 00-Ja								НН	
НН		14-Dec-95	1300	11360 00-Ja								HH	
НН		14-Dec-95	2700	11356 00-Ja								HH	
НН		14-Dec-95	3000	11351 00-Ja								НН	
НН		14-Dec-95	2300	11347 00-Ja								HH	
HH		16-Feb-96	50000	11148 00-Ja	an-00							НН	

Database	TAG END DATE STORET CODE	GT LT VALUE	remark S	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY	CALC. TYPE	COMMENT	SOURCE 1 2	PROGRAM
НН	16-Feb-96	200		11387	00-Jan-00							НН	
HH	01-Mar-96	> 160000		11148	00-Jan-00							HH	
НН	03-Jan-96	400		11142	00-Jan-00							HH	
НН	03-Jan-96	1700			00-Jan-00							HH	
НН	03-Jan-96	2300			00-Jan-00							НН	
НН	03-Jan-96	8000		11351	00-Jan-00							НН	
НН	03-Jan-96	90000										НН	
HH	30-Jan-96	200			00-Jan-00							HH	
HH	30-Jan-96	800			00-Jan-00							HH	
HH	30-Jan-96	1100			00-Jan-00							HH	
HH	30-Jan-96 30-Jan-96	8000		11351	00-Jan-00							HH	
HH		24000		11347	00-Jan-00							HH	
HH	08-Feb-96 08-Feb-96	800 400		11142 11360	00-Jan-00 00-Jan-00							HH HH	
HH HH	08-Feb-96	1100		11356	00-Jan-00							HH	
HH	08-Feb-96	8000		11350	00-Jan-00							HH	
нн НН	08-Feb-96	2200			00-Jan-00							HH	
HH	21-Feb-96	200			00-Jan-00							HH	
НН	21-Feb-96	2200			00-Jan-00							HH	
НН	21-Feb-96	30000			00-Jan-00							HH	
HH	21-Feb-96	13000			00-Jan-00							НН	
НН	21-Feb-96	800		11347	00-Jan-00							НН	
НН	04-Mar-96	7000		11387	00-Jan-00							НН	
НН	18-Mar-96	> 160000		11148	00-Jan-00							НН	
НН	18-Mar-96	800		11387	00-Jan-00							НН	
НН	12-Apr-96	24000		11148	00-Jan-00							НН	
НН	12-Apr-96	2200		11387	00-Jan-00							НН	
НН	09-Apr-96	< 200		11142	00-Jan-00							НН	
НН	09-Apr-96	1100		11360	00-Jan-00							НН	
НН	09-Apr-96	11000		11356	00-Jan-00							НН	
НН	09-Apr-96	1300		11351	00-Jan-00							HH	
НН	09-Apr-96	24000		11347	00-Jan-00							НН	
НН	23-Apr-96	22000		11142	00-Jan-00							НН	
НН	23-Apr-96	13000			00-Jan-00							HH	
HH	23-Apr-96	25000		11356	00-Jan-00							HH	
НН	23-Apr-96	60000		11351	00-Jan-00							HH	
НН	23-Apr-96	71000		11347	00-Jan-00							НН	
НН	06-May-96	50000		11148	00-Jan-00							HH	
HH	06-May-96	2300		11387	00-Jan-00							HH	
HH	01-May-96	1600		11142	00-Jan-00							HH	
HH	01-May-96	4900		11360	00-Jan-00							HH	
HH	01-May-96	2100			00-Jan-00							HH	
HH	01-May-96	2000		11351	00-Jan-00							HH	
HH	01-May-96	5000 140										HH	
HH HH	09-May-96 09-May-96	2700		11142	00-Jan-00 00-Jan-00							HH HH	
		310											
HH HH	09-May-96 09-May-96	670			00-Jan-00 00-Jan-00							HH HH	1
HH	09-May-96	4800			00-Jan-00							HH	1
нн НН	13-May-96	1600			00-Jan-00							HH	
HH	13-May-96	6600			00-Jan-00							HH	1
HH	13-May-96	3900			00-Jan-00							HH	
HH	13-May-96	3400			00-Jan-00							HH	
НН	27-Mar-96	< 20			00-Jan-00							HH	
НН	27-Mar-96	5000			00-Jan-00							НН	
НН	27-Mar-96	230			00-Jan-00							HH	
НН	27-Mar-96	9000		11351	00-Jan-00							НН	
НН	27-Mar-96	5000			00-Jan-00							НН	

Database	TAG END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CALC. TYPE	COMMENT	SOURCE SOURCE	
НН	14-May-96		780			00-Jan-00						HH	
HH	14-May-96		3600		11360	00-Jan-00						HH	
НН	14-May-96		3200		11356	00-Jan-00						НН	
HH	14-May-96		2800		11351	00-Jan-00						НН	
НН	14-May-96		4600		11347	00-Jan-00						HH	
HH	16-May-96		580		11360	00-Jan-00						HH	
HH	16-May-96		310		11142	00-Jan-00						HH	
HH	16-May-96		600		11356	00-Jan-00						HH	
HH	16-May-96		2500		11351	00-Jan-00						HH	
HH	16-May-96		2300 340		11347	00-Jan-00						HH	
HH HH	20-May-96 20-May-96		15000		11142	00-Jan-00 00-Jan-00						HH HH	
HH	20-May-96		730			00-Jan-00						HH	
нн НН	20-May-96		680		11350	00-Jan-00						HH	
HH	20-May-96		930		11331	00-Jan-00						HH	
НН	22-May-96		200			00-Jan-00						HH	
HH	22-May-96		6600		11360	00-Jan-00						HH	<u> </u>
НН	22-May-96		270		11356	00-Jan-00						HH	<u> </u>
НН	22-May-96		2000		11351	00-Jan-00						НН	
НН	22-May-96		5800		11347	00-Jan-00						НН	
НН	17-Jun-96		1300		11387	00-Jan-00						НН	
НН	17-Jun-96		160000		11148	00-Jan-00						НН	
НН	01-Jul-96		30000		11148	00-Jan-00						НН	
НН	01-Jul-96		1700		11387	00-Jan-00						НН	
НН	12-Jun-96		120		11142	00-Jan-00						НН	
НН	12-Jun-96		960		11360	00-Jan-00						HH	
НН	12-Jun-96		620		11356	00-Jan-00						НН	
НН	12-Jun-96		470		11351	00-Jan-00						НН	
HH	12-Jun-96		800			00-Jan-00						HH	
HH	25-Jun-96		23000		11142							HH	
НН	25-Jun-96		82000		11360	00-Jan-00						НН	
HH	25-Jun-96		> 200000		11356	00-Jan-00						НН	
HH	25-Jun-96		6800		11351	00-Jan-00						HH	
HH	25-Jun-96		120000		11347	00-Jan-00						HH	
HH	15-Jul-96		7000		11148	00-Jan-00						HH	
HH	15-Jul-96 02-Jul-96		800 1500		11387	00-Jan-00						HH HH	
HH HH	02-Jul-96 02-Jul-96		310			00-Jan-00 00-Jan-00						HH	
нн НН	02-Jul-96		270			00-Jan-00						HH	
HH	02-Jul-96		420		11350	00-Jan-00						HH	
HH	02-Jul-96		2500		11331	00-Jan-00						HH	
НН	16-Jul-96		420			00-Jan-00						HH	
НН	16-Jul-96		90		11360	00-Jan-00						НН	
НН	16-Jul-96		17000		11356	00-Jan-00						НН	
НН	16-Jul-96		2100		11351	00-Jan-00						НН	
НН	16-Jul-96		44000		11347	00-Jan-00						НН	
НН	24-Jul-96		150			00-Jan-00						НН	
НН	24-Jul-96		380			00-Jan-00						НН	
НН	24-Jul-96		99		11356	00-Jan-00		-				НН	
НН	24-Jul-96		7200			00-Jan-00						НН	
HH	24-Jul-96		3200			00-Jan-00						НН	
НН	09-Aug-96		50000			00-Jan-00						НН	
НН	09-Aug-96		2300			00-Jan-00						НН	
НН	23-Aug-96		90000			00-Jan-00						НН	1
HH	23-Aug-96		30000			00-Jan-00						НН	
HH	22-Aug-96		24000			00-Jan-00			1			HH	
HH	21-Aug-96		7000			00-Jan-00			1			HH	-
HH	21-Aug-96		3000		11356	00-Jan-00						HH	

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
HH		19-Aug-96		3000			00-Jan-00								HH	
НН		06-Aug-96		90			00-Jan-00								HH	
HH		06-Aug-96		550			00-Jan-00								HH	
HH		06-Aug-96		2100			00-Jan-00								HH	
HH		06-Aug-96		430			00-Jan-00								HH	-
HH		06-Aug-96		1100			00-Jan-00								HH	-
HH		15-Aug-96		1100			00-Jan-00								HH HH	<u> </u>
HH		15-Aug-96		1300 1700			00-Jan-00									-
HH HH		15-Aug-96		51000			00-Jan-00 00-Jan-00								HH HH	-
нн НН		15-Aug-96 15-Aug-96		4500			00-Jan-00								НН	
нн НН		26-Aug-96		800			00-Jan-00								НН	
HH		26-Aug-96		5000			00-Jan-00								НН	
HH		27-Aug-96		160000			00-Jan-00								HH	
НН		28-Aug-96		160000			00-Jan-00								HH	
НН		28-Aug-96		> 160000			00-Jan-00								НН	
НН		29-Aug-96		> 160000			00-Jan-00								НН	
НН		29-Aug-96		4000			00-Jan-00								HH	<u> </u>
HH		05-Sep-96		5000			00-Jan-00								НН	
НН		05-Sep-96		5000			00-Jan-00								НН	
НН		03-Sep-96		200			00-Jan-00								НН	
НН		03-Sep-96		700			00-Jan-00								НН	
НН		03-Sep-96		1300			00-Jan-00								НН	
НН		09-Sep-96		< 200			00-Jan-00								НН	
НН		10-Sep-96		200			00-Jan-00								НН	
НН		11-Sep-96		1300			00-Jan-00								НН	
НН		11-Sep-96		1700		11351	00-Jan-00								НН	
НН		12-Sep-96		< 200		11142	00-Jan-00								HH	
НН		12-Sep-96		800		11360	00-Jan-00								HH	
НН		12-Sep-96		400		11356	00-Jan-00								НН	
НН		23-Sep-96		7000		11347	00-Jan-00								HH	
НН		23-Sep-96		8000		11351	00-Jan-00								HH	
НН		24-Sep-96		< 200		11142	00-Jan-00								HH	
НН		24-Sep-96		400		11360	00-Jan-00								HH	
НН		25-Sep-96		8000			00-Jan-00								HH	
HH		25-Sep-96		30000			00-Jan-00								HH	
HH		26-Sep-96		50000			00-Jan-00								HH	
НН		16-Sep-96		30000			00-Jan-00								HH	
HH		16-Sep-96		3000			00-Jan-00								НН	
HH		17-Sep-96		8000			00-Jan-00								HH	-
HH		17-Sep-96		5000			00-Jan-00								HH	-
HH		18-Sep-96		50000			00-Jan-00								HH	-
HH		19-Sep-96		30000			00-Jan-00								HH	-
HH HH		19-Sep-96 19-Sep-96		160000 90000			00-Jan-00 00-Jan-00								HH HH	
HH HH		30-Sep-96		< 2600 < 200			00-Jan-00								HH HH	-
		30-Sep-96		< 200 1100			00-Jan-00								нн НН	+
HH HH		01-Oct-96 01-Oct-96		7000			00-Jan-00 00-Jan-00								нн НН	+
нн НН		01-Oct-96		6000			00-Jan-00 00-Jan-00								нн НН	+
нн НН		01-Oct-96 02-Oct-96		800			00-Jan-00 00-Jan-00								нн НН	+
HH		02-Oct-96		3000			00-Jan-00								НН	
нн НН		11-Oct-96		24000			00-Jan-00								НН	
HH		11-Oct-96		24000			00-Jan-00								HH	
НН		25-Oct-96		> 160000			00-Jan-00								НН	
нн НН		25-Oct-96		160000			00-Jan-00								НН	
НН		30-Oct-96		1700			00-Jan-00								HH	<u> </u>
НН		30-Oct-96		700			00-Jan-00								НН	

Database	TAG	END DATE	STORET	GT LT	VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH		CALC. TYPE	COMMENT		PROGRAM
НН		24-Oct-96		>	160000			00-Jan-00								НН	
НН		24-Oct-96			5000			00-Jan-00								HH	
НН		24-Oct-96			800			00-Jan-00								НН	
НН		23-Oct-96			7000			00-Jan-00								HH	
НН		23-Oct-96			800			00-Jan-00								HH	
НН		22-Oct-96			90000			00-Jan-00								НН	
НН		22-Oct-96			200			00-Jan-00								HH	
НН		21-Oct-96			35000			00-Jan-00								НН	
НН		12-Nov-96			50000			00-Jan-00								НН	
НН		12-Nov-96			8000			00-Jan-00								НН	
HH		12-Nov-96			9000			00-Jan-00								НН	
НН		13-Nov-96			3000			00-Jan-00								HH	
НН		13-Nov-96			400			00-Jan-00								HH	
НН		04-Nov-96			400			00-Jan-00								HH	
НН		04-Nov-96		<	200			00-Jan-00								НН	
HH		05-Nov-96			1300			00-Jan-00								НН	
НН		06-Nov-96			13000			00-Jan-00								НН	
НН		06-Nov-96		>	160000			00-Jan-00								HH	
НН		07-Nov-96			28000			00-Jan-00								НН	
НН		07-Nov-96			90000			00-Jan-00								HH	
НН		07-Nov-96			90000			00-Jan-00								HH	
HH		08-Nov-96		>	160000			00-Jan-00								HH	
НН		08-Nov-96			90000			00-Jan-00								HH	
HH		10-Dec-96			3000			00-Jan-00								НН	
НН		10-Dec-96			8000			00-Jan-00								HH	
НН		09-Dec-96			700			00-Jan-00								HH	
HH		09-Dec-96		<	200			00-Jan-00								НН	
НН		09-Dec-96		<	200			00-Jan-00								HH	
НН		11-Dec-96			5000			00-Jan-00								НН	
HH		11-Dec-96			24000			00-Jan-00								HH	\vdash
HH		12-Dec-96			1300			00-Jan-00								HH	
HH		02-Dec-96		>	160000			00-Jan-00								HH	\vdash
HH		02-Dec-96			5000			00-Jan-00								HH	
HH		26-Dec-96			2300			00-Jan-00								HH	
HH		26-Dec-96			1400			00-Jan-00								HH	-
HH		26-Dec-96			30000			00-Jan-00								HH	
HH		18-Dec-96			24000			00-Jan-00								HH	
HH		18-Dec-96			22000			00-Jan-00								HH	-
HH		31-Dec-96			50000			00-Jan-00								HH	
HH		31-Dec-96			28000			00-Jan-00								HH	
HH		31-Dec-96		1	28000			00-Jan-00				-				HH HH	
HH		23-Dec-96 23-Dec-96			800 30000			00-Jan-00 00-Jan-00				1				нн НН	
HH								00-Jan-00				-					
HH		15-Oct-96 15-Oct-96		>	160000 28000							-				HH HH	
HH HH					28000			00-Jan-00 00-Jan-00				1				нн НН	
		16-Oct-96		<	1400			00-Jan-00				1				нн НН	
HH HH		16-Oct-96 16-Oct-96			3000			00-Jan-00								HH	+
нн НН		14-Oct-96			2100			00-Jan-00								нн НН	+
нн НН		14-Oct-96			2300			00-Jan-00				-				нн НН	
нн НН		02-Jan-97			5000			00-Jan-00								нн НН	
нн НН		02-Jan-97 02-Jan-97			3000			00-Jan-00								нн НН	
нн НН		02-Jan-97 02-Jan-97			8000			00-Jan-00								нн НН	
нн НН		02-Jan-97 09-Jan-97			13000			00-Jan-00								нн НН	
нн НН		09-Jan-97 08-Jan-97			400			00-Jan-00								нн НН	
нн НН		08-Jan-97 06-Jan-97			200			00-Jan-00								нн НН	+
нн НН		06-Jan-97 06-Jan-97		_	700		11142	00-Jan-00								нн НН	
нн НН					13000			00-Jan-00								нн НН	
пп		07-Jan-97			13000		1134/	00-jan-00	1				1			пп	

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE SOURCE	PROGRAM
НН		07-Jan-97		1700		11351	00-Jan-00							НН	
НН		09-Jan-97		13000		11356	00-Jan-00							НН	
HH		14-Jan-97		50000			00-Jan-00							НН	
HH		14-Jan-97		24000			00-Jan-00							HH	
HH		15-Jan-97		13000			00-Jan-00							HH	
НН		15-Jan-97		24000			00-Jan-00							НН	
НН		15-Jan-97		24000			00-Jan-00							НН	
HH		15-Jan-97		2300			00-Jan-00							HH	
HH		02-Jan-97		3000			00-Jan-00							HH	
HH		08-Jan-97		13000			00-Jan-00							HH	
HH HH		23-Jan-97 02-Jan-97		5000 160000			00-Jan-00 00-Jan-00							HH HH	
НН		02-Jan-97 08-Jan-97		> 160000			00-Jan-00 00-Jan-00							НН	
HH		15-Jan-97		> 160000			00-Jan-00 00-Jan-00							НН	
HH		23-Jan-97		> 160000			00-Jan-00							НН	
НН		23-Jan-97		1100			00-Jan-00							НН	
НН		22-Jan-97		4000			00-Jan-00							НН	
HH		22-Jan-97		17000			00-Jan-00							НН	
НН		22-Jan-97		17000			00-Jan-00							НН	
HH		21-Jan-97		50000			00-Jan-00							НН	
НН		21-Jan-97		90000			00-Jan-00							НН	
НН		16-Jan-97		8000		11351	00-Jan-00							НН	
НН		16-Jan-97		8000		11347	00-Jan-00							НН	
НН		30-Jan-97		9000		11351	00-Jan-00							НН	
HH		30-Jan-97		35000		11347	00-Jan-00							НН	
НН		29-Jan-97		5000		11356	00-Jan-00							НН	
HH		29-Jan-97		5000		11360	00-Jan-00							НН	
HH		29-Jan-97		5000		11142	00-Jan-00							НН	
HH		28-Jan-97		90000		11347	00-Jan-00							HH	
HH		28-Jan-97		30000			00-Jan-00							HH	
HH		27-Jan-97		800			00-Jan-00							HH	
НН		27-Jan-97		1300			00-Jan-00							HH	
HH		30-Jan-97		160000			00-Jan-00							HH	
HH		10-Feb-97		30000			00-Jan-00							HH	
HH		29-Jan-97		8000			00-Jan-00							HH	
HH		04-Feb-97		5000			00-Jan-00							HH	
HH		10-Feb-97		13000 5000			00-Jan-00							HH HH	
HH HH		11-Feb-97 11-Feb-97		1300			00-Jan-00 00-Jan-00							HH	
HH		10-Feb-97		< 200			00-Jan-00 00-Jan-00							НН	
HH		10-Feb-97		400			00-Jan-00 00-Jan-00							НН	
HH		10-Feb-97		2100			00-Jan-00							НН	
HH		13-Feb-97		160000			00-Jan-00							HH	
НН		03-Feb-97		400			00-Jan-00							HH	
НН		03-Feb-97		800			00-Jan-00							НН	
НН		04-Feb-97		3000			00-Jan-00							НН	
НН		04-Feb-97		3000			00-Jan-00							НН	
НН		05-Feb-97		1700			00-Jan-00							НН	
НН		06-Feb-97		17000			00-Jan-00							НН	
НН		06-Feb-97		7000			00-Jan-00							НН	
НН	-	07-Mar-97		24000			00-Jan-00							HH	
НН	•	06-Mar-97		800			00-Jan-00							HH	
НН		06-Mar-97		200			00-Jan-00							НН	
НН		04-Mar-97		1300			00-Jan-00							HH	
НН		04-Mar-97		2200			00-Jan-00							HH	
НН		03-Mar-97		< 200			00-Jan-00							HH	
HH		03-Mar-97		< 200			00-Jan-00							HH	
HH		03-Mar-97		< 200		11356	00-Jan-00			1				HH	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE S	SOURCE 2	PROGRAM
НН		07-Mar-97		50000			00-Jan-00										IH	
НН		10-Mar-97		13000			00-Jan-00										IH	
НН		10-Mar-97		1700			00-Jan-00										IH	
HH		10-Mar-97		700			00-Jan-00										IH XX	
HH		10-Mar-97		400			00-Jan-00										IH	
HH HH		10-Mar-97 14-Mar-97		< 200 24000			00-Jan-00 00-Jan-00										IH IH	
нн НН		14-Mar-97		160000			00-Jan-00 00-Jan-00										IH IH	
HH		14-Mar-97		30000			00-Jan-00										H H	
НН		19-Feb-97		5000			00-Jan-00										H H	
НН		19-Feb-97		5000			00-Jan-00										H H	
НН		03-Mar-97		13000			00-Jan-00										IH .	
НН		25-Feb-97		13000			00-Jan-00										ΙΗ	
НН		03-Mar-97		2300			00-Jan-00										Н	
НН		21-Mar-97		24000			00-Jan-00										Н	
НН		21-Mar-97		22000		16675	00-Jan-00									Н	ΙΗ	
НН		24-Mar-97		< 200		16591	00-Jan-00									Н	Ή	
НН		24-Mar-97		5000		90007	00-Jan-00									Н	H	
НН		24-Mar-97		400		90010	00-Jan-00									Н	H	
НН		24-Mar-97		1100		15847	00-Jan-00									Н	ΙΗ	
НН		24-Mar-97		200		11188	00-Jan-00									Н	H	
НН		28-Mar-97		2100		90013	00-Jan-00										H	
HH		28-Mar-97		1300			00-Jan-00										H	
HH		28-Mar-97		1300			00-Jan-00										H	
НН		20-Mar-97		1700			00-Jan-00										IH	
НН		20-Mar-97		900			00-Jan-00										H	
HH		20-Mar-97		200			00-Jan-00										IH	
HH		17-Mar-97		17000			00-Jan-00										IH	
HH		17-Mar-97		11000			00-Jan-00										IH TY	
HH HH		17-Mar-97		2300			00-Jan-00										IH IH	
нн НН		27-Mar-97 27-Mar-97		24000 13000			00-Jan-00 00-Jan-00										IH IH	
нн НН		24-Mar-97		2300			00-Jan-00										IH	
HH		24-Mar-97		1700			00-Jan-00										H H	
НН		10-Mar-97		2700			00-Jan-00										TH .	
НН		10-Mar-97		1000			00-Jan-00										H H	
НН		20-Mar-97		5000			00-Jan-00										IH .	
НН		20-Mar-97		50000			00-Jan-00										ΙΗ	
НН		31-Mar-97		2300			00-Jan-00										TH .	
НН		31-Mar-97		30000			00-Jan-00										Н	
НН		31-Mar-97		11000		11356	00-Jan-00									Н	Ή	
НН		04-Apr-97		90000		16675	00-Jan-00									Н	Ή	
НН		04-Apr-97		160000		16649	00-Jan-00									Н	ΙΉ	
НН		01-Apr-97		7000		11387	00-Jan-00									Н	ΙΗ	
НН		07-Apr-97		2900		11387	00-Jan-00									Н	ΙΗ	
HH		02-Apr-97		5000			00-Jan-00									Н	H	
HH		07-Apr-97		16000			00-Jan-00										Н	
НН		07-Apr-97		1700			00-Jan-00										H	
HH		07-Apr-97		1700			00-Jan-00										IH	
HH		07-Apr-97		< 200			00-Jan-00										IH	
HH		07-Apr-97		3000			00-Jan-00										IH XX	
HH		07-Apr-97		400			00-Jan-00						1	\vdash			IH	
HH		08-Apr-97		700			00-Jan-00							+			IH	
HH		08-Apr-97		800			00-Jan-00										IH III	
HH		08-Apr-97		2200			00-Jan-00										IH III	
HH HH		02-Apr-97		24000 160000			00-Jan-00 00-Jan-00										IH IH	
пп		02-Apr-97		400			00-Jan-00 00-Jan-00						1			Н		

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	COMMENT		PROGRAM
НН		03-Apr-97		11000			00-Jan-00						НН	
HH		03-Apr-97		90000			00-Jan-00						HH	
НН		14-Apr-97		800			00-Jan-00						HH	
HH		14-Apr-97		< 200			00-Jan-00						HH	
HH		17-Apr-97		200			00-Jan-00						HH	
HH		17-Apr-97		< 200 < 200			00-Jan-00						HH	
HH		17-Apr-97					00-Jan-00						HH	
HH		10-Apr-97		3000 2300			00-Jan-00 00-Jan-00						HH HH	
HH HH		10-Apr-97 17-Mar-97		26000			00-Jan-00						нн НН	-
HH		17-Mar-97		24000			00-Jan-00						нн НН	
НН		28-Apr-97		3300			00-Jan-00						НН	
НН		28-Apr-97		1200			00-Jan-00						НН	
НН		28-Apr-97		2800			00-Jan-00						НН	
НН		28-Apr-97		2400			00-Jan-00						НН	
НН		28-Apr-97		1600			00-Jan-00						НН	
НН		23-Apr-97		30000			00-Jan-00						НН	
НН		23-Apr-97		24000			00-Jan-00						НН	
НН		24-Apr-97		3000		11387	00-Jan-00						НН	
НН		24-Apr-97		13000		11148	00-Jan-00						НН	
НН		04-Apr-97		94000		93151	00-Jan-00						НН	
HH		04-Apr-97		21000		16595	00-Jan-00						HH	
НН		04-Apr-97		48000		16594	00-Jan-00						HH	
НН		04-Apr-97		22000		16593	00-Jan-00						HH	
НН		23-Apr-97		< 200		11360	00-Jan-00						HH	
HH		23-Apr-97		3000		11356	00-Jan-00						HH	
HH		23-Apr-97		3300			00-Jan-00						HH	
HH		23-Apr-97		7000			00-Jan-00						HH	
НН		28-Apr-97		22000			00-Jan-00						HH	
HH		01-May-97		1100			00-Jan-00						НН	
HH		01-May-97		200			00-Jan-00						HH	
HH		01-May-97		< 200			00-Jan-00						HH	
HH		01-May-97		400			00-Jan-00						HH	
HH		21-Apr-97		5000			00-Jan-00						HH	
HH		21-Apr-97		3000			00-Jan-00						HH	
HH HH		11-Apr-97 11-Apr-97		50000 24000			00-Jan-00 00-Jan-00						HH HH	-
HH		11-Apr-97		90000			00-Jan-00						НН	
нн НН		02-May-97		90000			00-Jan-00						нн НН	
HH		02-May-97		8000			00-Jan-00						HH	
НН		02-May-97		950			00-Jan-00						НН	
НН		02-May-97		900			00-Jan-00						НН	
НН		07-May-97		1700			00-Jan-00						НН	
НН		07-May-97		13000			00-Jan-00						НН	
НН		07-May-97		< 200			00-Jan-00						НН	
HH		07-May-97		1400		16595	00-Jan-00						НН	
НН		07-May-97		1100			00-Jan-00						НН	
НН		05-May-97		1400			00-Jan-00						НН	
НН		05-May-97		400			00-Jan-00						НН	
НН	·	07-Mar-97		2200			00-Jan-00						НН	
НН		07-Mar-97		> 200000			00-Jan-00						НН	
НН	-	07-Mar-97		7400			00-Jan-00						НН	
HH		07-Mar-97		680			00-Jan-00						HH	
HH		07-Mar-97		4300			00-Jan-00						HH	
HH		19-Mar-97		90000			00-Jan-00						HH	
НН		19-Mar-97		90000			00-Jan-00						HH	
HH		19-Mar-97		50000			00-Jan-00						НН	
НН		19-Mar-97		50000		16595	00-Jan-00						HH	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE S		PROGRAM
НН		19-Mar-97		13000	-		00-Jan-00										IH	
HH		05-May-97		< 200			00-Jan-00										IH	
НН		05-May-97		800			00-Jan-00										IH	
HH		05-May-97		200			00-Jan-00										IH ····	
HH		09-May-97		30000			00-Jan-00										IH	
HH HH		09-May-97 16-May-97		13000 5000	-		00-Jan-00 00-Jan-00										IH IH	
HH		16-May-97 16-May-97		160000	-		00-Jan-00 00-Jan-00										ih IH	
HH		16-May-97 12-May-97		1200			00-Jan-00 00-Jan-00										ih IH	
HH		12-May-97		1000			00-Jan-00										IH	
НН		05-May-97		1900			00-Jan-00										IH	
НН		05-May-97		400			00-Jan-00										IH	
НН		06-May-97		< 200			00-Jan-00										IH	
НН		06-May-97		200			00-Jan-00										IH	
НН		06-May-97		900			00-Jan-00										ΙΗ	
НН		06-May-97		1300		11351	00-Jan-00									I	ΙΗ	
НН		07-May-97		1300		11347	00-Jan-00									I	ΙΗ	
НН		21-May-97		24000		93151	00-Jan-00									H	ΙΗ	
НН		21-May-97		1700		16595	00-Jan-00									H	ΙΗ	
НН		21-May-97		90000			00-Jan-00									F	IH	
НН		21-May-97		13000		16593	00-Jan-00										ΙΗ	
HH		21-May-97		8000			00-Jan-00										ΙΗ	
HH		12-May-97		< 200			00-Jan-00										ΙΗ	
HH		12-May-97		30000			00-Jan-00										IH	
HH		12-May-97		200			00-Jan-00										IH	
НН		12-May-97		2100			00-Jan-00										IH	
HH		13-May-97		90000			00-Jan-00										IH	
HH		14-May-97		400			00-Jan-00										IH	
HH		14-May-97		400			00-Jan-00										IH ····	
HH HH		14-May-97 15-May-97		200 24000			00-Jan-00										IH IH	
нн НН		15-May-97 15-May-97		24000	-		00-Jan-00 00-Jan-00										ih IH	
HH		19-May-97		22000	-		00-Jan-00 00-Jan-00										in IH	
HH		19-May-97		17000			00-Jan-00 00-Jan-00										in IH	
НН		19-May-97		700	-		00-Jan-00										IH	
НН		19-May-97		8000			00-Jan-00										IH	
HH		19-May-97		28000			00-Jan-00										IH	
НН		23-May-97		30000			00-Jan-00										IH	
НН		23-May-97		90000			00-Jan-00										IH	
НН		23-May-97		50000			00-Jan-00										ΙΗ	
НН		28-May-97		50000		11387	00-Jan-00									I	ΙΗ	
НН		28-May-97		90000		11148	00-Jan-00									H	ΙΗ	
НН		30-May-97		580		11148	00-Jan-00									F	ΙΗ	
НН		06-Jun-97		580		11387	00-Jan-00									ŀ	ΙΗ	
НН		06-Jun-97		130000		11148	00-Jan-00										ΙΗ	
HH		12-Jun-97		700		11387	00-Jan-00										ΙΗ	
HH		12-Jun-97		> 160000			00-Jan-00										ΙΗ	
НН		18-Jun-97		> 160000			00-Jan-00										IH	
НН		18-Jun-97		9000			00-Jan-00										IH	
HH		18-Jun-97		90000			00-Jan-00						1				IH	
HH		18-Jun-97		30000			00-Jan-00										IH ····	
HH		18-Jun-97		90000			00-Jan-00						1				IH	
HH		19-Jun-97		8000			00-Jan-00						1				IH	
HH		19-Jun-97		160000			00-Jan-00						1				IH	
HH		03-Jul-97		3000			00-Jan-00						1				IH	
HH HH		03-Jul-97 30-Jun-97		30000 < 200			00-Jan-00 00-Jan-00						1				IH IH	
		30-Jun-9/		I	1	11142	uu-Jan-UU	1	1	1	1	l	1			1 1	ш	I

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE SO	OURCE 2	PROGRAM
НН		01-Jul-97		400	-		00-Jan-00									HH		
НН		01-Jul-97		200			00-Jan-00									HH		
НН		01-Jul-97		200			00-Jan-00									HH		
НН		23-Jun-97		2300			00-Jan-00									HH		
HH		23-Jun-97		17000			00-Jan-00									HH		
HH		23-Jun-97		2300	-		00-Jan-00									HH		
HH		23-Jun-97		1700	-		00-Jan-00									HH		
HH		24-Jun-97		200 3000			00-Jan-00									HH		
HH		25-Jun-97 25-Jun-97		800	-		00-Jan-00 00-Jan-00									HH		
HH HH		25-Jun-97		700			00-Jan-00 00-Jan-00									HH		
HH		25-Jun-97		400	-		00-Jan-00									HH		
HH		23-Jun-97		4700	-		00-Jan-00									HH		
HH		23-Jun-97		2900	-		00-Jan-00									HH		
НН		11-Jul-97		1400	-		00-Jan-00									HH		
НН		11-Jul-97		1500			00-Jan-00									НН		
НН		14-Jul-97		700			00-Jan-00									HH		
НН		14-Jul-97		11000	-		00-Jan-00									HH		
НН		14-Jul-97		> 160000			00-Jan-00									НН		
НН		14-Jul-97		50000			00-Jan-00									HH	I	
НН		16-Jul-97		200		11142	00-Jan-00									HH	I	
НН		07-Jul-97		< 200		11142	00-Jan-00									HH	I	
НН		08-Jul-97		13000		11347	00-Jan-00									НН	I	
НН		08-Jul-97		7000		11351	00-Jan-00									НН	I	
НН		08-Jul-97		400		11356	00-Jan-00									HH	I	
НН		09-Jul-97		> 160000		11142	00-Jan-00									HH	I	
НН		08-Jul-97		160000		11356	00-Jan-00									HH	I	
НН		30-Jun-97		630		93151	00-Jan-00									HH		
HH		30-Jun-97		8400	-	16595	00-Jan-00									HH		
HH		17-Jul-97		2300			00-Jan-00									HH		
НН		17-Jul-97		90000	-		00-Jan-00									HH		
НН		28-Jul-97		1200	-		00-Jan-00									HH		ļ
НН		28-Jul-97		7900			00-Jan-00									HH		
НН		29-Jul-97		13000			00-Jan-00									HH		
HH		29-Jul-97		8000			00-Jan-00									HH		
HH		29-Jul-97		> 160000			00-Jan-00									HH		
HH		29-Jul-97		> 160000			00-Jan-00									HH		
HH		29-Jul-97		50000			00-Jan-00									HH		
HH HH		28-Jul-97 28-Jul-97		30000 5000			00-Jan-00 00-Jan-00									HH		
HH		23-Jul-97 23-Jul-97		50000	-		00-Jan-00 00-Jan-00									HH		
HH		23-Jul-97		5000			00-Jan-00									HH		
HH		23-Jul-97		2700	-		00-Jan-00									HH		
HH		23-Jul-97		36000	-		00-Jan-00									HH		
HH		24-Jul-97		200			00-Jan-00									HH		
HH		02-Jun-97		> 160000	-		00-Jan-00									HH		
НН		02-Jun-97		2100			00-Jan-00									HH		
НН		06-Jun-97		13000			00-Jan-00									HH		
НН		06-Jun-97		50000			00-Jan-00									НН		
НН		06-Jun-97		< 200			00-Jan-00									HH		
НН		06-Jun-97		800			00-Jan-00									НН		
HH		06-Jun-97		1100			00-Jan-00									НН		
НН		20-Jun-97		30000			00-Jan-00									HH		
НН		20-Jun-97		8000			00-Jan-00									HH		
НН		20-Jun-97		8000			00-Jan-00									HH		
НН		23-Jun-97		17000			00-Jan-00									HH		
НН		23-Jun-97		160000			00-Jan-00									HH		
НН		23-Jun-97		1700		90010	00-Jan-00									НН	I	

HH HH HH HH	23-Jun-97	LT	VALUE	Temark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START	CATEGORY	CALC. TYPE	COMMENT	1	SOURCE 2	PROGRAM
HH HH HH			2300			00-Jan-00									HH	
HH HH	23-Jun-97		2300		11188										HH	
НН	07-Jul-97	>	160000			00-Jan-00									HH	
	07-Jul-97 11-Jul-97		3000 50000		90013	00-Jan-00 00-Jan-00									HH HH	
HH	11-Jul-97 11-Jul-97		17000		16597										нн НН	
HH	18-Jul-97		160000			00-Jan-00									НН	
НН	18-Jul-97	>	160000		16675	00-Jan-00									НН	
НН	21-Jul-97		200			00-Jan-00									НН	
НН	21-Jul-97		800			00-Jan-00									НН	
НН	21-Jul-97		200			00-Jan-00									НН	
HH	21-Jul-97		1300		90007	00-Jan-00									НН	
HH	21-Jul-97		160000		16591	00-Jan-00									НН	
НН	25-Jul-97		14000			00-Jan-00									HH	
HH	25-Jul-97		90000			00-Jan-00									HH	
HH	25-Jul-97		7000			00-Jan-00									HH	
НН	01-Aug-97	>	160000			00-Jan-00									HH	
HH	01-Aug-97	>	160000			00-Jan-00									HH	
HH	04-Aug-97		1300			00-Jan-00									HH	
HH	04-Aug-97		700			00-Jan-00									HH	
HH	04-Aug-97		800 3000		15847	00-Jan-00 00-Jan-00									HH HH	
HH HH	04-Aug-97 04-Aug-97		8000			00-Jan-00									нн НН	
HH	04-Aug-97		160000		90013										нн НН	
HH	08-Aug-97		160000			00-Jan-00									НН	
НН	08-Aug-97	>	160000			00-Jan-00									НН	
НН	15-Aug-97	>	160000		16649	00-Jan-00									НН	
НН	15-Aug-97		1700			00-Jan-00									НН	
НН	12-Aug-97		1100			00-Jan-00									НН	
НН	12-Aug-97	>	160000		16595	00-Jan-00									НН	
HH	12-Aug-97		200		16594										HH	
НН	12-Aug-97		30000		16593	00-Jan-00									HH	
HH	08-Aug-97		53000		11387	00-Jan-00									HH	
HH	08-Aug-97		91000			00-Jan-00									HH	
HH	04-Aug-97		2100		11387										НН	
HH	04-Aug-97		2600			00-Jan-00									HH	
HH	15-Aug-97		1000			00-Jan-00									HH	
HH	15-Aug-97		3300 730			00-Jan-00 00-Jan-00									HH HH	
HH HH	11-Aug-97 11-Aug-97		2100			00-Jan-00									нн НН	
HH	18-Aug-97		160000			00-Jan-00									НН	
НН	18-Aug-97		800			00-Jan-00									НН	
HH	18-Aug-97		3000		15847	00-Jan-00									НН	
НН	18-Aug-97		5000		90007	00-Jan-00									НН	
НН	18-Aug-97		200		16591	00-Jan-00									НН	
HH	22-Aug-97		30000		90013	00-Jan-00									НН	
HH	22-Aug-97		1400			00-Jan-00									НН	
НН	 21-Aug-97		200			00-Jan-00									НН	
НН	21-Aug-97		200			00-Jan-00									НН	
НН	29-Aug-97	>	160000			00-Jan-00									HH	
НН	02-Sep-97		3000			00-Jan-00									НН	<u> </u>
HH	05-Sep-97	<	200			00-Jan-00									HH	
HH	05-Sep-97		400			00-Jan-00									HH	
HH	05-Sep-97		1300			00-Jan-00									HH	\vdash
HH	05-Sep-97		1700 800			00-Jan-00 00-Jan-00									HH	
HH HH	05-Sep-97 22-Aug-97		2900			00-Jan-00 00-Jan-00									HH HH	
HH	22-Aug-97 22-Aug-97		1700			00-Jan-00									нн НН	

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE SOURCE	PROGRAM
НН		26-Aug-97		13000		11347	00-Jan-00							НН	
HH		26-Aug-97		5000			00-Jan-00							HH	
HH		26-Aug-97		3000			00-Jan-00							HH	
НН		27-Aug-97		5000			00-Jan-00							HH	
НН		27-Aug-97		5000			00-Jan-00							HH	
НН		08-Sep-97		800			00-Jan-00							НН	
НН		08-Sep-97		200			00-Jan-00							HH	
НН		26-Aug-97		7000			00-Jan-00							HH	
HH		26-Aug-97		22000			00-Jan-00							HH	
HH		26-Aug-97		< 200			00-Jan-00							HH	
HH		26-Aug-97		13000			00-Jan-00							HH	
HH		27-Aug-97		2700			00-Jan-00							HH	
HH HH		27-Aug-97 05-Sep-97		80000 1800			00-Jan-00 00-Jan-00							HH HH	
нн НН		05-Sep-97 05-Sep-97		14000			00-Jan-00 00-Jan-00							HH	
НН		02-Sep-97		50000			00-Jan-00							НН	
HH		02-Sep-97		5000			00-Jan-00							НН	
НН		02-Sep-97		> 160000			00-Jan-00							НН	
НН		04-Sep-97		200			00-Jan-00							HH	
HH		04-Sep-97		800			00-Jan-00							НН	
НН		09-Sep-97		1100			00-Jan-00							НН	
НН		09-Sep-97		2700			00-Jan-00							НН	
НН		09-Sep-97		8000			00-Jan-00							НН	
НН		10-Sep-97		> 160000			00-Jan-00							НН	
НН		10-Sep-97		> 160000			00-Jan-00							НН	
НН		10-Sep-97		> 160000			00-Jan-00							НН	
НН		10-Sep-97		30000			00-Jan-00							НН	
НН		10-Sep-97		> 160000		16648	00-Jan-00							НН	
НН		09-Sep-97		1700		11387	00-Jan-00							НН	
НН		09-Sep-97		5000		11148	00-Jan-00							НН	
НН		15-Sep-97		> 160000		16649	00-Jan-00							НН	
HH		15-Sep-97		90000		16675	00-Jan-00							HH	
HH		19-Sep-97		> 160000			00-Jan-00							HH	
НН		19-Sep-97		900			00-Jan-00							HH	
НН		19-Sep-97		50000			00-Jan-00							HH	
НН		19-Sep-97		8000			00-Jan-00							HH	
HH		19-Sep-97		8000			00-Jan-00							HH	
HH		15-Sep-97		2100			00-Jan-00							НН	
HH		15-Sep-97		1100			00-Jan-00							HH	
HH		23-Sep-97		> 160000			00-Jan-00							HH	
HH		23-Sep-97		> 160000 > 160000			00-Jan-00							HH HH	
HH HH		23-Sep-97 23-Sep-97		> 160000			00-Jan-00 00-Jan-00							HH	
НН		23-Sep-97 22-Sep-97		91000			00-Jan-00							НН	
HH		22-Sep-97		145000			00-Jan-00							HH	
НН		19-Sep-97		4700			00-Jan-00							НН	
НН		19-Sep-97		95000			00-Jan-00							НН	
НН		11-Aug-97		200			00-Jan-00							НН	
НН		11-Aug-97		50000			00-Jan-00							НН	
НН		12-Aug-97		13000			00-Jan-00							НН	
НН		13-Aug-97		50000		11347	00-Jan-00							НН	
НН		13-Aug-97		30000			00-Jan-00							НН	
НН		13-Aug-97		50000			00-Jan-00							НН	
НН		17-Oct-97		4500			00-Jan-00							НН	
НН		17-Oct-97		11000			00-Jan-00							НН	
НН		30-Sep-97		7000			00-Jan-00							НН	
НН		30-Sep-97		17000			00-Jan-00							НН	
НН		02-Oct-97		2300			00-Jan-00							НН	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE SO	OURCE 2	PROGRAM
НН		02-Oct-97		> 160000			00-Jan-00									HH		
НН		09-Oct-97		> 160000			00-Jan-00									HI		—
НН		09-Oct-97		30000			00-Jan-00									HI		—
HH		10-Oct-97		34000			00-Jan-00									HI		
HH		10-Oct-97		23000			00-Jan-00									HE		
HH		10-Oct-97		11000	-		00-Jan-00									H		
HH		10-Oct-97		990			00-Jan-00									H		
HH HH		10-Oct-97 09-Oct-97		63000 90000			00-Jan-00 00-Jan-00									HH		
HH		09-Oct-97		160000			00-Jan-00 00-Jan-00									H		
HH		09-Oct-97		> 160000			00-Jan-00									H		
HH		01-Oct-97		400			00-Jan-00									H		
НН		01-Oct-97		5000	-		00-Jan-00									HH		
НН		01-Oct-97		11000			00-Jan-00									H		
HH		02-Oct-97		30000			00-Jan-00									HI		
НН		02-Oct-97		160000			00-Jan-00									HI		
НН		24-Oct-97		8000			00-Jan-00									HH		
НН		24-Oct-97		160000			00-Jan-00									HH		
НН		24-Oct-97		90000		90013	00-Jan-00									HH	ł	
НН		24-Oct-97		> 160000		16649	00-Jan-00									HE	I	
НН		22-Oct-97		8000		11347	00-Jan-00									H	ł	
НН		22-Oct-97		2100		11351	00-Jan-00									HE	I	
НН		22-Oct-97		200		11356	00-Jan-00									HH	ł	
НН		22-Oct-97		3000		93151	00-Jan-00									HE	ł	
НН		20-Oct-97		< 200		11142	00-Jan-00									HH	I	
HH		20-Oct-97		< 200		11360	00-Jan-00									HE	ł	
HH		22-Oct-97		30000			00-Jan-00									HE		
HH		22-Oct-97		800			00-Jan-00									HE		
НН		22-Sep-97		160000			00-Jan-00									HE		
НН		22-Sep-97		> 160000			00-Jan-00									HE		—
HH		22-Sep-97		90000			00-Jan-00									HI		—
HH		29-Sep-97		30000			00-Jan-00									HH		
HH		29-Sep-97		90000			00-Jan-00									HH		
HH		29-Oct-97		3000			00-Jan-00									H		
HH		29-Oct-97		13000			00-Jan-00									HE		
HH HH		29-Oct-97 30-Oct-97		13000 400			00-Jan-00 00-Jan-00									HH		
нн НН		30-Oct-97		700	-											H		
нн НН		23-Oct-97		3000	-		00-Jan-00 00-Jan-00									HH		
HH		23-Oct-97		< 200			00-Jan-00 00-Jan-00									H		
HH		31-Oct-97		> 160000	-		00-Jan-00									HH		
HH		31-Oct-97		30000			00-Jan-00									HE		
HH		31-Oct-97		200			00-Jan-00									HH		
HH		31-Oct-97		30000			00-Jan-00									HH		
НН		31-Oct-97		> 160000			00-Jan-00									H		
НН		05-Nov-97		30000	-		00-Jan-00									HH		
НН		05-Nov-97		160000			00-Jan-00									HI		
НН		03-Nov-97		22000			00-Jan-00									HE		
НН		03-Nov-97		3000			00-Jan-00									HI		
НН		05-Nov-97		160000			00-Jan-00									HI		
НН		05-Nov-97		90000			00-Jan-00									HE		
НН		03-Nov-97		32000	-		00-Jan-00									HE		
НН		03-Nov-97		110000			00-Jan-00									HE		
НН		30-Oct-97		50000		11387	00-Jan-00									HE		
НН		30-Oct-97		> 160000		11148	00-Jan-00									HE		
НН		24-Oct-97		11000		11387	00-Jan-00									HH		
НН	-	24-Oct-97		110000			00-Jan-00									HI	H	
НН		14-Nov-97		5000		11188	00-Jan-00									HE	- I	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	COMMENT		PROGRAM
НН		14-Nov-97		3000			00-Jan-00						НН	
НН		14-Nov-97		7000			00-Jan-00						HH	
HH		14-Nov-97		3000			00-Jan-00						HH	
HH		14-Nov-97		400			00-Jan-00						HH	
HH		17-Nov-97		72			00-Jan-00						HH	
HH		17-Nov-97		76000			00-Jan-00						HH	
НН		10-Nov-97		22000			00-Jan-00						HH	
HH		10-Nov-97 24-Nov-97		27000 850			00-Jan-00						HH HH	
HH HH		24-Nov-97 24-Nov-97		> 200000			00-Jan-00 00-Jan-00						нн НН	-
HH		10-Nov-97		> 160000			00-Jan-00						нн НН	
HH		10-Nov-97		160000			00-Jan-00						нн НН	
HH		17-Nov-97		30000			00-Jan-00						НН	
HH		17-Nov-97		5000			00-Jan-00						НН	
НН		17-Nov-97		1100			00-Jan-00						НН	
НН		26-Nov-97		> 160000		+	00-Jan-00						НН	
HH		26-Nov-97		24000			00-Jan-00						НН	
HH		01-Dec-97		1700			00-Jan-00						НН	
НН		01-Dec-97		5000		+	00-Jan-00						НН	
НН		01-Dec-97		5000		90010	00-Jan-00						НН	
НН		01-Dec-97		1100		90007	00-Jan-00						НН	
НН		01-Dec-97		3000		16591	00-Jan-00						НН	
НН		05-Dec-97		30000		90013	00-Jan-00						НН	
НН		05-Dec-97		13000		16597	00-Jan-00						НН	
НН		05-Dec-97		1700		90012	00-Jan-00						HH	
НН		01-Dec-97		4500		11387	00-Jan-00						HH	
НН		01-Dec-97		48000		11148	00-Jan-00						HH	
НН		02-Dec-97		7000			00-Jan-00						HH	
НН		02-Dec-97		1700			00-Jan-00						HH	
НН		02-Dec-97		8000			00-Jan-00						HH	
НН		02-Dec-97		2700			00-Jan-00						HH	
HH		14-Nov-97		5000			00-Jan-00						HH	
HH		14-Nov-97		9000			00-Jan-00						HH	
HH		14-Nov-97		5000			00-Jan-00						HH	
HH		14-Nov-97		28000			00-Jan-00						HH	
HH		14-Nov-97		22000			00-Jan-00						HH	
HH		10-Dec-97		160000			00-Jan-00						HH	
HH HH		10-Dec-97 10-Dec-97		14000 14000			00-Jan-00 00-Jan-00						HH HH	-
нн НН		10-Dec-97 11-Dec-97		1700			00-Jan-00						нн НН	-
нн НН		11-Dec-97		1300			00-Jan-00						нн НН	+
нн НН		22-Dec-97		160000			00-Jan-00 00-Jan-00						нн НН	
HH		22-Dec-97 22-Dec-97		160000			00-Jan-00						HH	
HH		17-Dec-97		> 160000		+	00-Jan-00						НН	
НН		17-Dec-97		2100			00-Jan-00						НН	
HH		17-Dec-97		90000			00-Jan-00						НН	
НН		15-Dec-97		1100			00-Jan-00						НН	
HH		22-Dec-97		30000			00-Jan-00						НН	
HH		22-Dec-97		5000			00-Jan-00						НН	
HH		22-Dec-97		24000			00-Jan-00						НН	
НН		22-Dec-97		160000			00-Jan-00						НН	
HH		22-Dec-97		> 160000			00-Jan-00						НН	
НН		23-Dec-97		50000			00-Jan-00						НН	
НН		23-Dec-97		50000			00-Jan-00						НН	
НН		23-Dec-97		24000			00-Jan-00						НН	
HH		23-Dec-97		22000			00-Jan-00						НН	
НН		23-Dec-97		24000		16597	00-Jan-00						НН	
НН		23-Dec-97	·	50000		90012	00-Jan-00						НН	

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.		COMMENT	SOURCE 1	SOURCE 2	PROGRAM
HH		16-Dec-97		> 160000			00-Jan-00								HH	
НН		17-Dec-97		17000			00-Jan-00								HH	<u> </u>
HH		17-Dec-97		2200			00-Jan-00								HH	
HH		15-Dec-97		2300			00-Jan-00								HH	<u> </u>
HH		29-Dec-97		< 200			00-Jan-00								HH	
HH		29-Dec-97		< 200			00-Jan-00								HH	
HH		09-Dec-97		30000			00-Jan-00								HH	
HH		09-Dec-97		3000			00-Jan-00								HH	
HH HH		15-Dec-97 15-Dec-97		1900 > 200000			00-Jan-00 00-Jan-00								HH HH	
нн НН		22-Dec-97		13000			00-Jan-00								НН	
нн НН		22-Dec-97 22-Dec-97		98000			00-Jan-00								НН	+
HH		10-Mar-97		5000			00-Jan-00								HH	+
HH		10-Mar-97		1300			00-Jan-00								HH	+
НН		10-Mar-97		3000			00-Jan-00								HH	
НН		12-Mar-97		90000			00-Jan-00								НН	+
НН		12-Mar-97		50000			00-Jan-00								НН	
HH		26-Feb-97		5000			00-Jan-00								HH	†
HH		26-Feb-97		5000		l	00-Jan-00								НН	†
НН		26-Feb-97		1400			00-Jan-00								НН	1
НН		25-Feb-97		8000			00-Jan-00								НН	
НН		25-Feb-97		13000			00-Jan-00								НН	
НН		24-Feb-97		3000			00-Jan-00								НН	
НН		24-Feb-97		1700			00-Jan-00								НН	
НН		27-Feb-97		24000			00-Jan-00								НН	
НН		27-Feb-97		5000			00-Jan-00								НН	
НН		05-Jan-98		81000		11148	00-Jan-00								НН	
НН		05-Jan-98		21000		11387	00-Jan-00								НН	
НН		06-Jan-98		> 160000		93151	00-Jan-00								НН	
НН		06-Jan-98		90000		16595	00-Jan-00								НН	
НН		06-Jan-98		> 160000		16594	00-Jan-00								HH	
НН		06-Jan-98		50000		16593	00-Jan-00								HH	
НН		12-Jan-98		3500		11387	00-Jan-00								HH	
НН		12-Jan-98		9400		11148	00-Jan-00								HH	
НН		15-Jan-98		13000			00-Jan-00								HH	
HH		21-Jan-98		30000			00-Jan-00								HH	
HH		20-Jan-98		24000			00-Jan-00								HH	
НН		05-Feb-98		90000			00-Jan-00								HH	
НН		20-Jan-98		17000			00-Jan-00								НН	
HH		20-Jan-98		> 160000			00-Jan-00					-			HH	
HH		20-Jan-98		8000			00-Jan-00								HH	-
HH		30-Jan-98		36000			00-Jan-00								HH	-
HH		30-Jan-98		250			00-Jan-00								HH	+
HH HH		05-Feb-98 05-Feb-98		> 3000 > 160000			00-Jan-00								HH HH	
							00-Jan-00									
HH		05-Feb-98		17000	-	16593	00-Jan-00								HH	+
HH HH		03-Feb-98 03-Feb-98		8000 3000			00-Jan-00 00-Jan-00								HH HH	+
нн НН		03-Feb-98 03-Feb-98		24000			00-Jan-00								нн НН	+
нн НН		05-Jan-98		30000			00-Jan-00								HH	+
нн НН		05-Jan-98 05-Jan-98		50000			00-Jan-00								НН	+
HH		05-Jan-98		24000			00-Jan-00					+ +			HH	+
нн НН		03-Jan-98 08-Jan-98		30000			00-Jan-00					+ +			НН	+
HH		08-Jan-98		30000			00-Jan-00					+ +			HH	+
нн НН		21-Jan-98		3000			00-Jan-00					+ +			HH	+
нн НН		21-Jan-98 21-Jan-98		11000			00-Jan-00								НН	<u> </u>
НН		21-Jan-98		3000			00-Jan-00								HH	<u> </u>
НН		28-Jan-98		8000			00-Jan-00								НН	1

Database	TAG		STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END S	START DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE SO	URCE 2	PROGRAM
НН		28-Jan-98		2200			00-Jan-00									НН		
HH		04-Feb-98		200			00-Jan-00									HH		
НН		04-Feb-98		28000			00-Jan-00									НН		
НН		04-Feb-98		700			00-Jan-00									НН		ļ
НН		02-Jan-98		200			00-Jan-00									НН		
НН		02-Jan-98		< 200			00-Jan-00									НН		
НН		02-Jan-98		200			00-Jan-00									НН		
HH		02-Jan-98		50000			00-Jan-00									HH		
HH		02-Jan-98		> 160000			00-Jan-00									HH		
HH		05-Jan-98		> 160000			00-Jan-00									HH		
HH		05-Jan-98		24000			00-Jan-00									HH		
HH		05-Jan-98		8000			00-Jan-00									HH		
HH		12-Jan-98		90000			00-Jan-00									HH		
HH HH		12-Jan-98 23-Jan-98		30000 5000			00-Jan-00 00-Jan-00									HH		
HH		23-Jan-98		5000			00-Jan-00 00-Jan-00									НН		
HH		23-Jan-98		1300			00-Jan-00 00-Jan-00									HH		
HH		23-Jan-98		3000			00-Jan-00									HH		
HH		23-Jan-98		5000			00-Jan-00									HH		
HH		26-Jan-98		24000			00-Jan-00									HH		
HH		26-Jan-98		1400			00-Jan-00									НН		
НН		26-Jan-98		1700			00-Jan-00									НН		
НН		10-Feb-98		14000			00-Jan-00									НН		
НН		10-Feb-98		1700			00-Jan-00									НН		
НН		10-Feb-98		1100			00-Jan-00									НН		
НН		11-Feb-98		90000		11142	00-Jan-00									НН		
НН		11-Feb-98		160000		11360	00-Jan-00									НН		
НН		02-Feb-98		2300		16649	00-Jan-00									НН		
НН		02-Feb-98		50000		16675	00-Jan-00									НН		
НН		06-Feb-98		24000		11188	00-Jan-00									НН		
НН		06-Feb-98		30000		15847	00-Jan-00									НН		į.
НН		06-Feb-98		160000		90010	00-Jan-00									НН		
HH		06-Feb-98		24000		90007	00-Jan-00									HH		
НН		06-Feb-98		3000		16591	00-Jan-00									HH		
HH		09-Feb-98		50000			00-Jan-00									HH		
НН		09-Feb-98		1300			00-Jan-00									HH		ļ
НН		16-Feb-98		22000			00-Jan-00									НН		
HH		18-Feb-98		1300			00-Jan-00									НН		
HH		20-Feb-98		1700			00-Jan-00									HH		
HH		20-Feb-98		> 160000			00-Jan-00									HH		
HH		20-Feb-98		1300			00-Jan-00									HH		
HH		20-Feb-98		200			00-Jan-00									HH		
HH		20-Feb-98		1300			00-Jan-00									HH		
HH		18-Feb-98		30000			00-Jan-00									HH		
HH		18-Feb-98		24000 3000			00-Jan-00									HH		
HH HH		19-Feb-98 19-Feb-98		3000			00-Jan-00									НН		
HH		16-Feb-98		19000			00-Jan-00 00-Jan-00									HH		
HH		16-Feb-98		21000			00-Jan-00									НН		
HH		16-Feb-98		15000			00-Jan-00									HH		
HH		17-Feb-98		17000			00-Jan-00 00-Jan-00									HH		
HH		18-Feb-98		24000			00-Jan-00									НН		
HH		19-Feb-98		5000			00-Jan-00									HH		
HH		19-Feb-98		160000			00-Jan-00									HH		
HH		09-Feb-98		5500			00-Jan-00									НН		
HH		09-Feb-98		35000			00-Jan-00									HH		
HH		26-Jan-98		620			00-Jan-00									HH		
HH		26-Jan-98		20000			00-Jan-00									НН		

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	COMMENT			PROGRAM
HH		23-Feb-98		5000			00-Jan-00							HH	
НН		23-Feb-98		24000			00-Jan-00							HH	
HH		23-Feb-98		30000			00-Jan-00							HH	
HH		25-Feb-98		5000			00-Jan-00							HH	<u> </u>
HH		25-Feb-98		2300			00-Jan-00							HH	
HH		25-Feb-98		8000			00-Jan-00							HH	
HH		25-Feb-98		24000			00-Jan-00							HH	
HH		24-Feb-98		8000			00-Jan-00							HH	-
HH HH		24-Feb-98 02-Mar-98		160000 5000			00-Jan-00							HH HH	-
нн НН		02-Mar-98 02-Mar-98		8000			00-Jan-00 00-Jan-00							HH	
нн НН		06-Mar-98		200			00-Jan-00							НН	
HH		06-Mar-98		2300			00-Jan-00							HH	
HH		06-Mar-98		< 200			00-Jan-00							HH	
НН		06-Mar-98		24000			00-Jan-00							НН	
НН		06-Mar-98		24000		+	00-Jan-00							НН	
НН		04-Mar-98		2300			00-Jan-00						<u> </u>	НН	
HH		04-Mar-98		2300			00-Jan-00							HH	<u> </u>
HH		04-Mar-98		2300		+	00-Jan-00							НН	
НН		09-Mar-98		< 200			00-Jan-00							НН	
НН		09-Mar-98		9000			00-Jan-00							НН	
НН		17-Mar-98		8000		11142	00-Jan-00							НН	
НН		17-Mar-98		13000			00-Jan-00							НН	
НН		18-Mar-98		17000		11347	00-Jan-00							НН	
НН		18-Mar-98		5000		11351	00-Jan-00							НН	
HH		18-Mar-98		2300		11356	00-Jan-00							НН	
НН		16-Mar-98		160000		16649	00-Jan-00							НН	
HH		16-Mar-98		160000		16675	00-Jan-00							HH	
НН		20-Mar-98		17000		11188	00-Jan-00							HH	
НН		20-Mar-98		8000		15847	00-Jan-00							HH	
HH		20-Mar-98		800			00-Jan-00							HH	
HH		20-Mar-98		1300			00-Jan-00							HH	
НН		20-Mar-98		8000			00-Jan-00							HH	
HH		05-Mar-98		5000			00-Jan-00							НН	
НН		05-Mar-98		17000			00-Jan-00							HH	
HH		12-Mar-98		8000			00-Jan-00							HH	
HH		12-Mar-98		5000			00-Jan-00							HH	
HH		12-Mar-98		8000			00-Jan-00							HH	
HH		12-Mar-98		> 160000			00-Jan-00							HH	
HH		27-Feb-98		59000			00-Jan-00						1	HH	
HH		27-Feb-98 19-Mar-98		7200 160000			00-Jan-00						1	HH HH	+
HH HH		19-Mar-98 19-Mar-98		9000			00-Jan-00 00-Jan-00						+	HH	+
нн НН		19-Mar-98 19-Mar-98		2300			00-Jan-00						+	НН	+
нн НН		19-Mar-98 19-Mar-98		50000			00-Jan-00							HH	
HH		23-Mar-98		< 200		16597	00-Jan-00						+	HH	+
HH		23-Mar-98		2300			00-Jan-00						+	HH	+
НН		23-Mar-98 24-Mar-98		11000			00-Jan-00						+	HH	
НН		26-Mar-98		13000			00-Jan-00							HH	
HH		26-Mar-98		5000			00-Jan-00							НН	<u> </u>
НН		23-Mar-98		< 200			00-Jan-00							НН	<u> </u>
НН		23-Mar-98		3000			00-Jan-00							НН	<u> </u>
НН		30-Mar-98		3000			00-Jan-00						T	НН	
HH		30-Mar-98		< 200			00-Jan-00							НН	
НН		30-Mar-98		< 200			00-Jan-00						T	НН	
НН		31-Mar-98		1300			00-Jan-00						T	НН	
HH		31-Mar-98		3000			00-Jan-00							HH	
НН		31-Mar-98		2600			00-Jan-00						1	НН	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	COMMENT		SOURCE 2	
HH		30-Mar-98		400			00-Jan-00							HH	
НН		30-Mar-98		400			00-Jan-00							HH	
HH		03-Apr-98		13000			00-Jan-00							HH	
HH		03-Apr-98		8000			00-Jan-00							HH	
HH		03-Apr-98		< 200			00-Jan-00							HH	
HH		03-Apr-98		< 200			00-Jan-00							HH	
HH		03-Apr-98		160000			00-Jan-00							HH HH	
HH		17-Mar-98		50000			00-Jan-00								
HH HH		17-Mar-98		> 160000 1700			00-Jan-00 00-Jan-00							HH HH	
HH		01-Apr-98 01-Apr-98		900000			00-Jan-00 00-Jan-00							нн НН	
HH		01-Apr-98		11000			00-Jan-00							нн НН	
HH		01-Apr-98		< 200			00-Jan-00							НН	
HH		02-Apr-98		50000			00-Jan-00							НН	
HH		02-Apr-98		3000			00-Jan-00							НН	
НН		07-Apr-98		1300			00-Jan-00							НН	
HH		06-Apr-98		> 160000			00-Jan-00							НН	
HH		06-Apr-98		1700			00-Jan-00							НН	
HH		22-Apr-98		2200			00-Jan-00							НН	1
HH		22-Apr-98		30000			00-Jan-00							НН	
HH		15-Apr-98		200			00-Jan-00							НН	
НН		15-Apr-98		< 200			00-Jan-00							НН	
НН		15-Apr-98		28000			00-Jan-00							НН	
НН		15-Apr-98		2100			00-Jan-00							НН	
НН		14-Apr-98		30000			00-Jan-00							НН	
НН		14-Apr-98		30000			00-Jan-00							НН	
НН		30-Apr-98		13000			00-Jan-00							НН	
НН		30-Apr-98		800			00-Jan-00							НН	
НН		30-Apr-98		50000			00-Jan-00							НН	
НН		27-Apr-98		30000		16649	00-Jan-00							НН	
НН		27-Apr-98		1700		16675	00-Jan-00							НН	
НН		01-May-98		1300		11188	00-Jan-00							НН	
НН		01-May-98		200		15847	00-Jan-00							HH	
НН		01-May-98		< 200		90010	00-Jan-00							HH	
НН		01-May-98		< 200		90007	00-Jan-00							HH	
НН		01-May-98		1300		16591	00-Jan-00							HH	
HH		29-Apr-98		8000		11387	00-Jan-00							HH	
HH		29-Apr-98		90000		11148	00-Jan-00							HH	
HH		04-May-98		> 160000		90012	00-Jan-00							HH	
НН		04-May-98		1700			00-Jan-00							HH	
HH		04-May-98		24.5	-		00-Jan-00							HH	1
HH		04-May-98		90000	-		00-Jan-00							HH	1
HH		07-May-98		30000			00-Jan-00							HH	
HH		07-May-98		400			00-Jan-00							HH	-
HH		07-May-98		8000			00-Jan-00							HH	
HH		12-May-98		200			00-Jan-00							HH	1
HH		12-May-98		400			00-Jan-00							HH	+
HH		14-May-98		200			00-Jan-00							HH	-
HH		14-May-98		5000			00-Jan-00							HH	-
HH		12-May-98		11000			00-Jan-00							HH	-
HH		12-May-98		30000			00-Jan-00							HH	1
HH		07-May-98		8000			00-Jan-00							HH	1
HH		07-May-98		13000			00-Jan-00							HH	+
HH		11-May-98		< 200			00-Jan-00							HH	1
HH		11-May-98		800			00-Jan-00 00-Jan-00							HH HH	-
HH		15-May-98		24000 200			00-Jan-00 00-Jan-00							HH HH	1
HH		15-May-98		50000										HH	
HH		15-May-98		50000	1	90007	00-Jan-00						1	HH	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	COMMENT		PROGRAM
HH		15-May-98		200			00-Jan-00						HH	
НН		18-May-98		3000			00-Jan-00						HH	
HH		18-May-98		800			00-Jan-00						HH	
HH		18-May-98		1300			00-Jan-00						HH	
HH		18-May-98		3000			00-Jan-00						HH	
HH		18-May-98		1700			00-Jan-00						HH	
HH		21-May-98		3000			00-Jan-00						HH	
HH		21-May-98		5000			00-Jan-00						HH	
HH HH		21-May-98		400 13000			00-Jan-00 00-Jan-00						HH HH	
HH		28-May-98 28-May-98		90000			00-Jan-00						НН	
нн НН		02-Jun-98		1300			00-Jan-00						НН	
HH		02-Jun-98		1700			00-Jan-00						HH	
НН		02-Jun-98		200			00-Jan-00						HH	
НН		03-Jun-98		200			00-Jan-00						HH	
НН		03-Jun-98		< 200			00-Jan-00						НН	
НН		21-May-98		1300			00-Jan-00						НН	
НН		21-May-98		90000			00-Jan-00						НН	
НН		28-May-98		5000			00-Jan-00						НН	
НН		28-May-98		> 160000			00-Jan-00						НН	
НН		01-Jun-98		830			00-Jan-00						НН	
НН		01-Jun-98		28000		11148	00-Jan-00						HH	
НН		07-May-98		900		16593	00-Jan-00						НН	
НН		07-May-98		5000		11387	00-Jan-00						НН	
НН		07-May-98		50000		11148	00-Jan-00						HH	
НН		08-Jun-98		> 160000		16649	00-Jan-00						HH	
НН		08-Jun-98		> 160000		16675	00-Jan-00						HH	
HH		12-Jun-98		400			00-Jan-00						HH	
НН		12-Jun-98		800			00-Jan-00						HH	
HH		15-Jun-98		2200			00-Jan-00						HH	
НН		15-Jun-98		2600			00-Jan-00						HH	
HH		15-Jun-98		6000			00-Jan-00						HH	
HH		15-Jun-98		1400			00-Jan-00						HH	
HH		15-Jun-98		30000		90012	00-Jan-00						HH	
HH		12-Jun-98		610			00-Jan-00						HH	
HH HH		12-Jun-98 08-Jun-98		4300 1400			00-Jan-00 00-Jan-00						HH HH	
HH		08-Jun-98		14000			00-Jan-00						HH	
нн НН		09-Jun-98		110000			00-Jan-00						НН	
НН		11-Jun-98		5000			00-Jan-00						HH	
НН		11-Jun-98		200			00-Jan-00						НН	
НН		11-Jun-98		200			00-Jan-00						HH	
НН		17-Jun-98		> 160000			00-Jan-00						НН	
НН		18-Jun-98		50000			00-Jan-00						НН	
НН		26-Jun-98		1300		90010	00-Jan-00						НН	
HH		26-Jun-98		13000		15847	00-Jan-00						НН	
НН		26-Jun-98		1300			00-Jan-00						НН	
НН		26-Jun-98		1100			00-Jan-00						НН	
HH		26-Jun-98		1100			00-Jan-00						НН	
НН	·	22-Jun-98		> 160000			00-Jan-00						НН	
НН		22-Jun-98		28000			00-Jan-00						HH	
НН	-	24-Jun-98		400			00-Jan-00						НН	
HH		09-Jun-98		90000			00-Jan-00						HH	
HH		09-Jun-98		90000			00-Jan-00						HH	
HH		09-Jun-98		8000			00-Jan-00						HH	
HH		10-Jun-98		1400			00-Jan-00						HH	
HH		10-Jun-98		1700			00-Jan-00						НН	1
НН		22-Jun-98		2300		11347	00-Jan-00						HH	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	COMMENT		PROGRAM
НН		22-Jun-98		3000			00-Jan-00						НН	
НН		22-Jun-98		22000			00-Jan-00						HH	
HH		29-Jun-98		> 160000			00-Jan-00						HH	
HH		29-Jun-98		160000			00-Jan-00						HH	
HH HH		29-Jun-98 08-Jul-98		> 160000 30000			00-Jan-00						HH HH	
нн НН		08-Jul-98		160000			00-Jan-00 00-Jan-00						нн НН	-
НН		30-Jun-98		1700			00-Jan-00						HH	
НН		09-Jul-98		8000			00-Jan-00						НН	
НН		09-Jul-98		1700			00-Jan-00						НН	
НН		09-Jul-98		400			00-Jan-00						НН	
НН		13-Jul-98		400			00-Jan-00						НН	
НН		13-Jul-98		8000			00-Jan-00						НН	
НН		13-Jul-98		8000			00-Jan-00						НН	
НН		13-Jul-98		5000			00-Jan-00						НН	
НН		15-Jul-98		> 160			00-Jan-00						НН	
НН		15-Jul-98		> 160000			00-Jan-00						НН	
НН		15-Jul-98		> 160000			00-Jan-00						НН	
НН		13-Jul-98		8000		11351	00-Jan-00						НН	
HH		13-Jul-98		2100		11356	00-Jan-00						HH	
НН		13-Jul-98		13000		11356	00-Jan-00						HH	
НН		14-Jul-98		200		11142	00-Jan-00						HH	
НН		14-Jul-98		900		11360	00-Jan-00						HH	
НН		16-Jul-98		13000			00-Jan-00						HH	
HH		16-Jul-98		17000			00-Jan-00						HH	
HH		16-Jul-98		8000			00-Jan-00						HH	
НН		20-Jul-98		200			00-Jan-00						HH	
НН		20-Jul-98		900			00-Jan-00						HH	
HH		20-Jul-98		800			00-Jan-00						HH	
HH		20-Jul-98		400			00-Jan-00						HH	
HH		20-Jul-98		3000			00-Jan-00						HH	
HH		22-Jul-98		> 160000			00-Jan-00						HH	
HH		23-Jul-98		160000			00-Jan-00						HH	
HH		31-Jul-98		24000			00-Jan-00						HH	
HH HH		31-Jul-98 03-Aug-98		50000 200			00-Jan-00 00-Jan-00						HH HH	
HH		03-Aug-98		200			00-Jan-00						нн НН	
НН		03-Aug-98		1100			00-Jan-00						НН	
НН		03-Aug-98		3000			00-Jan-00						НН	
НН		03-Aug-98		17000			00-Jan-00						НН	
НН		07-Aug-98		> 160000			00-Jan-00						НН	
НН		07-Aug-98		> 160000			00-Jan-00						НН	
НН		04-Aug-98		3000			00-Jan-00						НН	
НН		04-Aug-98		8000			00-Jan-00						НН	
НН		14-Aug-98		67000		11148	00-Jan-00						НН	
HH		14-Aug-98		4800		11387	00-Jan-00						НН	
НН		20-Jul-98		200			00-Jan-00						НН	
НН		20-Jul-98		1700		11360	00-Jan-00						НН	
НН		22-Jul-98		24000			00-Jan-00						НН	
HH		22-Jul-98		800		11351	00-Jan-00						НН	
НН		22-Jul-98		30000			00-Jan-00						НН	
НН	-	23-Jul-98		400			00-Jan-00						НН	
HH		23-Jul-98		13000			00-Jan-00						HH	
HH		30-Jul-98		1300			00-Jan-00						HH	
HH		30-Jul-98		1700			00-Jan-00						HH	
HH		04-Aug-98		200			00-Jan-00						HH	
HH		04-Aug-98		1700			00-Jan-00						НН	<u> </u>
НН		05-Aug-98		2300		11347	00-Jan-00						HH	

HH 05-Aug-98 HH 05-Aug-98 HH 10-Aug-98 HH 11-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 11-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 17-Aug-98 HH 18-Aug-98 HH 18	ID DATE STOR	T GT VALUE remar	STATION ID END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1 SOURCE	PROGRAM
HH 10-Aug-98 HH 14-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 11-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 24-Aug-98 HH 22-Aug-98 HH 23-Aug-98 HH 24-Aug-98 HH 23-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 25-Sep-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 12-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 12-Aug-98 HH 12-Aug-98 HH 13-Aug-98		3000	11351 00-Jan-00							НН	
HH 14-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 25-Aug-98 HH 27-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 12-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 14-Aug-98 HH 15-Aug-98 HH 15-Aug-98 HH 17-Aug-98 HH 18-Aug-98 HH 18		5000	11356 00-Jan-00							HH	
HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 24-Aug-98 HH 25-Aug-98 HH 27-Aug-98 HH 27-Aug-98 HH 27-Aug-98 HH 27-Aug-98 HH 28-Aug-98 HH 28-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 14-Aug-98 HH 15-Aug-98 HH 17-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 23-Oct-98 HH 13-Nov-98		17000	90012 00-Jan-00							HH	
HH		> 160000	16649 00-Jan-00							HH	
HH 17-Aug-98 HH 21-Aug-98 HH 10-Aug-98 HH 10-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 25-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 12-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 14-Aug-98 HH 15-Aug-98 HH 16-Aug-98 HH 17-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 13-Nov-98		17000	16675 00-Jan-00							HH	
HH		8000 11000	16597 00-Jan-00 90013 00-Jan-00							HH HH	
HH		13000	16591 00-Jan-00							HH	
HH 10-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 12-Aug-98 HH 13-Aug-98 HH 14 12-Aug-98 HH 15-Aug-98 HH 17-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 23-Oct-98 HH 13-Nov-98		800	11142 00-Jan-00							HH	
HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 13-Aug-98 HH 14-Aug-98 HH 15-Aug-98 HH 16-Aug-98 HH 17-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 23-Oct-98 HH 13-Nov-98		8000	11360 00-Jan-00							HH	
HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 12-Aug-98 HH 13-Aug-98 HH 14-Aug-98 HH 15-Aug-98 HH 16-Aug-98 HH 17-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 25-Sep-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 13-Nov-98		3000	11347 00-Jan-00							НН	
HH 13-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 12-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 23-Oct-98 HH 13-Nov-98		1300	11351 00-Jan-00							НН	
HH 17-Aug-98 HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 16 23-Oct-98 HH 17-Aug-98 HH 18-Aug-99 HH		24000	11356 00-Jan-00							НН	
HH 17-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 24-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 23-Oct-98 HH 123-Oct-98 HH 13-Nov-98	17-Aug-98	1700	11142 00-Jan-00							НН	
HH		5000	11360 00-Jan-00							НН	
HH		5000	11188 00-Jan-00							НН	
HH 24-Aug-98 HH 11-Aug-98 HH 12-Aug-98 HH 25-Sep-98 HH 25-Sep-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 123-Oct-98 HH 23-Oct-98 HH 13-Oct-98 HH 13-Oct-98 HH 13-Oct-98 HH 13-Nov-98		5000	15847 00-Jan-00							НН	
HH	24-Aug-98	2300	90010 00-Jan-00							HH	
HH 11-Aug-98 HH 13-Aug-98 HH 13-Aug-98 HH 23-Oct-98 HH 123-Oct-98 HH 23-Oct-98 HH 13-Oct-98 HH 13-Oct-98 HH 13-Nov-98		11000	11142 00-Jan-00							HH	
HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 18-Aug-98 HH 18-Aug-98 HH 23-Sep-98 HH 25-Sep-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 123-Oct-98 HH 23-Oct-98 HH 13-Oct-98 HH 13-Oct-98 HH 13-Nov-98		5000	11360 00-Jan-00							НН	
HH 11-Aug-98 HH 11-Aug-98 HH 11-Aug-98 HH 13-Aug-98 HH 03-Sep-98 HH 25-Sep-98 HH 25-Sep-98 HH 22-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 123-Oct-98 HH 13-Oct-98 HH 13-Oct-98 HH 13-Oct-98 HH 13-Nov-98	11-Aug-98	2700	93151 00-Jan-00							НН	
HH 11-Aug-98 HH 03-Sep-98 HH 03-Sep-98 HH 25-Sep-98 HH 225-Sep-98 HH 23-Oct-98 HH 13-Oct-98 HH 13-Oct-98 HH 14 23-Oct-98 HH 15-Nov-98 HH 16-Nov-98 HH 17-Nov-98 HH 18-Nov-98		8000	16594 00-Jan-00							HH	
HH 18-Aug-98 HH 03-Sep-98 HH 25-Sep-98 HH 25-Sep-98 HH 28-Sep-99 HH 23-Oct-98 HH 06-Nov-98 HH 13-Nov-98		200	16593 00-Jan-00							HH	
HH 03-Sep-98 HH 25-Sep-98 HH 28-Sep-98 HH 28-Sep-98 HH 23-Oct-98 HH 3-Oct-98 HH 3-Oct-98 HH 3-Oct-98 HH 3-Oct-98 HH 3-Oct-98 HH 3-Nov-98 HH 3-Nov-98 HH 3-Nov-98 HH 13-Nov-98		17000	16594 00-Jan-00							HH	
HH 25-Sep-98 HH 28-Sep-98 HH 23-Oct-98 HH 60-Nov-98 HH 106-Nov-98 HH 106-Nov-98 HH 106-Nov-98 HH 13-Nov-98		> 160000	11387 00-Jan-00							HH	
HH 28-Sep-98 HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98		> 200000	90007 00-Jan-00							НН	
HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98		5000	16675 00-Jan-00							НН	
HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		160000	16649 00-Jan-00							HH	
HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 20-Nov-98		800	11142 00-Jan-00							HH	
HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		400	90010 00-Jan-00							HH	
HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98		> 160000 50000	15847 00-Jan-00 11188 00-Jan-00							HH HH	
HH 23-Oct-98 HH 23-Oct-98 HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 12-Nov-98 HH 13-Nov-98		2200	11360 00-Jan-00							HH	
HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 120-Nov-98 HH 120-Nov-98 HH 20-Nov-98 HH 20-Nov-98		1700	11356 00-Jan-00							HH	
HH 23-Oct-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		3000	90013 00-Jan-00							HH	
HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		9000	16597 00-Jan-00							HH	
HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 05-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		1600	93151 00-Jan-00							НН	
HH 06-Nov-98 HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98		12000	16595 00-Jan-00							НН	
HH 06-Nov-98 HH 06-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98		24000	16594 00-Jan-00							НН	
HH 06-Nov-98 HH 13-Nov-98 HH 23-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		2800	16593 00-Jan-00							НН	
HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		300	16591 00-Jan-00							НН	
HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		43000	16649 00-Jan-00							НН	
HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98	13-Nov-98	34000	11347 00-Jan-00							НН	
HH 13-Nov-98 HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98	13-Nov-98	25000	11351 00-Jan-00							НН	
HH 13-Nov-98 HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98	13-Nov-98	34000	16675 00-Jan-00							HH	
HH 13-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98	13-Nov-98	26000	11387 00-Jan-00							НН	
HH 20-Nov-98		86000	16648 00-Jan-00							НН	
HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98	13-Nov-98	110000	11148 00-Jan-00							HH	
HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		260	11142 00-Jan-00							HH	
HH 20-Nov-98 HH 20-Nov-98 HH 20-Nov-98		99	90010 00-Jan-00							НН	
HH 20-Nov-98 HH 20-Nov-98		500	15847 00-Jan-00							НН	
HH 20-Nov-98		37000	11188 00-Jan-00							НН	
		590	11360 00-Jan-00							HH	
		350	11356 00-Jan-00							НН	
	20-Nov-98	680	90013 00-Jan-00							HH	
HH 20-Nov-98		510	16597 00-Jan-00							HH	
HH 25-Nov-98 HH 25-Nov-98		1000 56000	93151 00-Jan-00 16595 00-Jan-00							HH HH	

Database	TAG	END DATE	STORET	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC.	TYPE	COMMENT	SOURCE 1 2	PROGRAM
НН		25-Nov-98		8200		16594	00-Jan-00							НН	
HH		25-Nov-98		3800			00-Jan-00							HH	
НН		25-Nov-98		270			00-Jan-00							НН	
HH		04-Dec-98		9400			00-Jan-00							НН	
HH		04-Dec-98		1100			00-Jan-00							HH	
HH		04-Dec-98		230			00-Jan-00							HH	
HH		04-Dec-98		3600			00-Jan-00							HH	
HH HH		04-Dec-98 04-Dec-98		> 200000 5900			00-Jan-00 00-Jan-00							HH HH	
нн НН		04-Dec-98		120000			00-Jan-00 00-Jan-00							HH	
HH		11-Dec-98		16000			00-Jan-00							HH	
НН		11-Dec-98		21000			00-Jan-00							НН	
НН		11-Dec-98		14000			00-Jan-00							НН	
НН		11-Dec-98		51000			00-Jan-00							НН	
HH		11-Dec-98		53000			00-Jan-00							НН	
НН		11-Dec-98		45000			00-Jan-00							НН	
НН		11-Dec-98		72000		90013	00-Jan-00							НН	
НН		11-Dec-98		56000			00-Jan-00							НН	
HH		18-Dec-98		2300		93151	00-Jan-00							НН	
НН		18-Dec-98		> 200000		16595	00-Jan-00							HH	
НН		18-Dec-98		16000		16594	00-Jan-00							HH	
НН		18-Dec-98		57000		16593	00-Jan-00							НН	
HH		18-Dec-98		560		16591	00-Jan-00							HH	
HH		23-Dec-98		380			00-Jan-00							HH	
НН		23-Dec-98		720			00-Jan-00							НН	
HH		23-Dec-98		12000			00-Jan-00							НН	
HH		23-Dec-98		2800			00-Jan-00							HH	
HH		23-Dec-98		1100			00-Jan-00							HH	
HH		23-Dec-98		17000			00-Jan-00							HH	
HH		23-Dec-98		59000			00-Jan-00							HH HH	
HH HH		31-Dec-98 31-Dec-98		63			00-Jan-00 00-Jan-00							HH	
HH		31-Dec-98		140			00-Jan-00							НН	
HH		31-Dec-98		15000			00-Jan-00							HH	
НН		31-Dec-98		6000			00-Jan-00							НН	
НН		31-Dec-98		630			00-Jan-00							НН	
НН		31-Dec-98		440			00-Jan-00							НН	
НН		31-Dec-98		38000			00-Jan-00							НН	
PW&E97	BUD9701	06-Jan-97	31616	190		11364								HP	
PW&E97	BUE9701	06-Jan-97	31616			11163								HP	
PW&E97	WOM9701	27-Jan-97	31616	3900		11385								HP	
PW&E97	WOK9701	27-Jan-97	31616	4600		15825								HP	
PW&E97	WOL9721	27-Jan-97	31616	6800		15824								HP	
PW&E97	WOB9702	04-Feb-97	31616	450		15831								HP	
PW&E97	WOC9702	04-Feb-97	31616	490		15830								HP	
PW&E97	WOD9702	04-Feb-97	31616	10000		15829								HP	
PW&E97	WOE9702	04-Feb-97	31616	15000		11390								HP	
PW&E97	WOF9702	04-Feb-97				11391								HP	
PW&E97	WOG9702	04-Feb-97				15828								HP	
PW&E97	WOJ9702	04-Feb-97	31616			15826								HP	
PW&E97	WOM9702	04-Feb-97				11385								HP	
PW&E97	WOK9702	04-Feb-97	31616			15825								HP	
PW&E97	WOL9722	04-Feb-97	31616			15824								HP	
PW&E97	WOB9704	02-Apr-97	31616			15831								HP	
PW&E97	WOC9704	02-Apr-97	31616			15830								HP HP	
PW&E97 PW&E97	WOD9704 WOE9704	02-Apr-97	31616 31616			15829 11390								HP	
PW&E97 PW&E97	WOF9704	02-Apr-97				11390								HP	
I WOLY/	W OF9/04	02-Apr-97	31010	3800	1	11391				1				Hr	L

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START	START TIME	START DEPTH	CALC.	TYPE	COMMENT	SOURCE SOURC	PROGRAM
	WOG9704	02-Apr-97	31616	4400		15828								HP	
PW&E97	WOJ9704	02-Apr-97	31616	2100		15826								HP	
PW&E97	WOM9704	02-Apr-97	31616	10000		11385								HP	_
	WOK9704 WOL9724	02-Apr-97	31616	2500 7794		15825								HP HP	_
	WOL9724 WOB9705	02-Apr-97 07-May-97	31616 31616	490		15824 15831								HP	_
	WOC9705	07-May-97	31616	780		15830								HP	_
PW&E97	WOD9705	07-May-97	31616	440		15829								HP	+
PW&E97	WOE9705	07-May-97	31616	690		11390								HP	
PW&E97	WOF9705	07-May-97	31616	660		11391								HP	
PW&E97	WOG9705	07-May-97	31616	2600		15828								HP	
PW&E97	WOJ9705	07-May-97	31616	3300		15826								HP	
PW&E97	WOM9705	07-May-97	31616	560		11385								HP	
PW&E97	WOK9705	07-May-97	31616	3800		15825								HP	
PW&E97	WOL9725	07-May-97	31616	2245		15824								HP	_
PW&E97	BUF9701	06-Jan-97	31616	700		11363								HP	
	BUG9701 BUH9701	06-Jan-97 06-Jan-97	31616 31616	460 430		15847 11362			+					HP HP	+
PW&E97	BUI9701	06-Jan-97	31616	140		11361								HP	_
	BUJ9701	06-Jan-97	31616	270		11360								HP	+
PW&E97	BUK9701	06-Jan-97	31616	390		11359								HP	1
PW&E97	BUL9701	06-Jan-97	31616	350		15846								HP	
PW&E97	BUM9701	06-Jan-97	31616	320		11357								HP	
PW&E97	BUN9701	06-Jan-97	31616	90		15845								HP	
	BUO9701	06-Jan-97	31616	160		11354								HP	
	BUP9701	06-Jan-97	31616	390		11353								HP	
	BUQ9701	06-Jan-97	31616	370		15844								HP	_
PW&E97 PW&E97	BUA9701	06-Jan-97 06-Jan-97	31616	770 1000		11351 15843								HP HP	_
PW&E97	BUS9701 WOL9701	06-Jan-97	31616 31616	9500		15824								HP	+
	BUV9701	06-Jan-97	31616	2000		11345								HP	+
	BUW9701	06-Jan-97	31616	790		15841								HP	+
PW&E97	BUX9701	06-Jan-97	31616	720		15840								HP	
PW&E97	BUD9702	03-Feb-97	31616	200		11364								HP	
PW&E97	BUE9702	03-Feb-97	31616	12000		11163								HP	
PW&E97	BUF9702	03-Feb-97	31616	3000		11363								HP	
	BUG9702	03-Feb-97	31616	2000		15847								HP	
	BUH9702	03-Feb-97	31616	3500		11362								HP	_
	BUI9702	03-Feb-97 03-Feb-97	31616	700		11361			+					HP HP	+
	BUJ9702 BUK9702	03-Feb-97 03-Feb-97	31616 31616	360 330		11360 11359								HP	+
	BUL9702	03-Feb-97	31616	300		15846								HP	_
	BUM9702	03-Feb-97	31616	370		11357								HP	+
	BUN9702	03-Feb-97	31616	140		15845								HP	-
	BUO9702	03-Feb-97	31616	180		11354								HP	
PW&E97	BUP9702	03-Feb-97	31616	460		11353								HP	
PW&E97	BUQ9702	03-Feb-97	31616	330		15844								HP	
	BUA9702	03-Feb-97	31616	660		11351								HP	
	BUS9702	03-Feb-97	31616	890		15843								HP	
	WOL9702	03-Feb-97	31616	7500		15824				 				HP	
	BUV9702	03-Feb-97	31616	2400 800		11345				1		-		HP HP	_
	BUW9702 BUX9702	03-Feb-97 03-Feb-97	31616 31616	800		15841 15840		+ +		1				HP HP	+
	BUD9703	31-Mar-97	31616	1400		11364		1		1				HP	+
	BUE9703	31-Mar-97	31616	410		11163								HP	+
	BUF9703	31-Mar-97	31616	1500		11363								HP	+
	BUG9703	31-Mar-97	31616	5200		15847								HP	
	BUH9703	31-Mar-97	31616	5600		11362								HP	

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY CALC		COMMENT	SOURCE 2	
PW&E97	BUI9703	31-Mar-97	31616	4000		11361								HP	
PW&E97	BUJ9703	31-Mar-97	31616	2500		11360								HP	
PW&E97	BUK9703	31-Mar-97	31616	7900		11359								HP	
PW&E97	BUL9703	31-Mar-97	31616	5400		15846								HP	
PW&E97 PW&E97	BUM9703 BUN9703	31-Mar-97 31-Mar-97	31616 31616	6300 4600		11357 15845								HP HP	
	BUO9703	31-Mar-97	31616	7300		11354								HP	
PW&E97	BUP9703	31-Mar-97	31616	6800		11353								HP	
PW&E97	BUQ9703	31-Mar-97	31616	15000		15844								HP	
PW&E97	BUA9703	31-Mar-97	31616	16000		11351								HP	
PW&E97	BUS9703	31-Mar-97	31616	4500		15843								HP	
PW&E97	WOL9703	31-Mar-97	31616	12000		15824								HP	
PW&E97	BUV9703	31-Mar-97	31616	17000		11345								HP	
PW&E97	BUW9703	31-Mar-97	31616	28000		15841								HP	<u> </u>
PW&E97	BUX9703	31-Mar-97	31616	6693		15840								HP	1
PW&E97	BUD9705	05-May-97	31616	180		11364								HP	
PW&E97 PW&E97	BUE9705 BUF9705	05-May-97	31616 31616	140 130		11163 11363								HP HP	
PW&E97	BUG9705	05-May-97 05-May-97	31616	340		15847								нг HP	
PW&E97	BUH9705	05-May-97	31616	6900		11362								HP	
PW&E97	BUI9705	05-May-97	31616	4900		11361								HP	
PW&E97	BUJ9705	05-May-97	31616	3700		11360								HP	
PW&E97	BUK9705	05-May-97	31616	500		11359								HP	
PW&E97	BUL9705	05-May-97	31616	520		15846								HP	
PW&E97	BUM9705	05-May-97	31616	560		11357								HP	
PW&E97	BUN9705	05-May-97	31616	430		15845								HP	
PW&E97	BUO9705	05-May-97	31616	240		11354								HP	
PW&E97	BUP9705	05-May-97	31616	430		11353								HP	
PW&E97	BUQ9705	05-May-97	31616	210		15844								HP	1
PW&E97	BUA9705	05-May-97	31616	3700	BM	11351							BM	HP	
PW&E97 PW&E97	BUS9705 WOL9705	05-May-97 05-May-97	31616 31616	380 2700		15843 15824								HP HP	
PW&E97	BUV9705	05-May-97	31616	3500		11345								HP	
PW&E97	BUW9705	05-May-97	31616	27000		15841								HP	
PW&E97	BUX9705	05-May-97	31616	530		15840								HP	
PW&E97	BUD9706	22-Jun-97	31616	3600		11364								HP	
PW&E97	BUE9706	22-Jun-97	31616	3100		11163								HP	
PW&E97	BUF9706	22-Jun-97	31616	1100		11363								HP	
PW&E97	BUG9706	22-Jun-97	31616	3300		15847								HP	
PW&E97	BUH9706	22-Jun-97	31616	3700		11362								HP	1
PW&E97	BUI9706	22-Jun-97	31616	3100		11361								HP	
PW&E97	BUJ9706	22-Jun-97	31616	2400		11360								HP	
PW&E97	BUL9706	22-Jun-97	31616	2600		15846								HP	-
PW&E97	BUM9706	22-Jun-97	31616	2700		11357								HP	
PW&E97 PW&E97	BUN9706 BUO9706	22-Jun-97 22-Jun-97	31616 31616	2100 2800		15845 11354								HP HP	
PW&E97	BUP9706	22-Jun-97 22-Jun-97	31616	2200		11354								нг HP	<u> </u>
	BUQ9706	22-Jun-97		6000		15844								HP	
	BUA9706	22-Jun-97	31616	5400		11351							BM	HP	
	BUS9706	22-Jun-97	31616	1300		15843								HP	
PW&E97	WOL9706	22-Jun-97	31616	3500		15824								HP	
PW&E97	BUV9706	22-Jun-97	31616	3400		11345								HP	
PW&E97	BUW9706	22-Jun-97	31616	1800		15841								HP	
PW&E97	BUX9706	22-Jun-97	31616	2645.8		15840								HP	1
PW&E97	BUA9707	16-Jul-97	31616	10500		11351						1	BM	HP	
	BUD9707	16-Jul-97	31616	740		11364								HP	
	BUE9707	16-Jul-97	31616	580		11163						1		HP	
PW&E97	BUF9707	16-Jul-97	31616	2100		11363								HP	1

Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END START DEPTH DATE	START TIME	START DEPTH	CATEGORY	CALC.	TYPE	COMMENT	SOURCE SOURC	PROGRAM
	BUG9707	16-Jul-97	31616	3400		15847									HP	
	BUH9707	16-Jul-97	31616	2500		11362									HP	
PW&E97	BUI9707	16-Jul-97	31616	7400		11361									HP	
PW&E97	BUJ9707	16-Jul-97	31616	6700		11360									HP	
PW&E97 PW&E97	BUK9707 BUL9707	16-Jul-97 16-Jul-97	31616 31616	4600 3400		11359 15846									HP HP	-
PW&E97	BUM9707	16-Jul-97	31616	8300		11357									HP	-
PW&E97	BUN9707	16-Jul-97	31616	900		15845									HP	-
PW&E97	BUO9707	16-Jul-97	31616	870		11354									HP	
PW&E97	BUP9707	16-Jul-97	31616	20000		11353									HP	
PW&E97	BUQ9707	16-Jul-97	31616	830		15844									HP	
PW&E97	BUS9707	16-Jul-97	31616	3300		15843									HP	
PW&E97	WOL9707	16-Jul-97	31616	2400		15824									HP	
PW&E97	BUV9707	16-Jul-97	31616	380		11345									HP	
PW&E97	BUW9707	16-Jul-97	31616	890		15841									HP	
PW&E97	BUX9707	16-Jul-97	31616	145000		15840									HP	
PW&E97 PW&E97	BUD9709 BUE9709	15-Sep-97	31616	934 950		11364 11163									HP HP	
PW&E97	BUF9709	15-Sep-97 15-Sep-97	31616 31616	890		11363									HP	
PW&E97	BUG9709	15-Sep-97	31616	710		15847									HP	
PW&E97	BUH9709	15-Sep-97	31616	2700		11362									HP	+
PW&E97	BUI9709	15-Sep-97	31616	2800		11361									HP	
PW&E97	BUJ9709	15-Sep-97	31616	8500		11360									HP	
PW&E97	BUK9709	15-Sep-97	31616	2800		11359									HP	
PW&E97	BUL9709	15-Sep-97	31616	2500		15846									HP	
	BUM9709	15-Sep-97	31616	5800		11357									HP	
PW&E97	BUN9709	15-Sep-97	31616	5400		15845									HP	
PW&E97	BUO9709	15-Sep-97	31616	6000		11354									HP	
PW&E97 PW&E97	BUP9709 BUQ9709	15-Sep-97 15-Sep-97	31616 31616	4400 4800		11353 15844									HP HP	
	BUA9709	15-Sep-97	31616	7800		11351								BM	HP	
PW&E97	BUS9709	15-Sep-97	31616	8000		15843								DIVI	HP	-
PW&E97	WOL9709	15-Sep-97	31616	4100		15824									HP	
PW&E97	BUV9709	15-Sep-97	31616	2800		11345									HP	
PW&E97	BUW9709	15-Sep-97	31616	1300		15841									HP	
PW&E97	BUX9709	15-Sep-97	31616	3550		15840									HP	
	BUD9710	06-Oct-97	31616	383		11364									HP	
PW&E97	BUE9710	06-Oct-97	31616	25000		11163									HP	_
PW&E97 PW&E97	BUF9710 BUG9710	06-Oct-97 06-Oct-97	31616 31616	22000 34000		11363 15847									HP HP	
PW&E97	BUH9710	06-Oct-97	31616	33000		11362									HP	
	BUI9710	06-Oct-97	31616	21000		11361									HP	_
PW&E97	BUJ9710	06-Oct-97	31616	13000		11360									HP	+
PW&E97	BUK9710	06-Oct-97	31616	12000		11359									HP	
PW&E97	BUL9710	06-Oct-97	31616	11000		15846									HP	
PW&E97	BUM9710	06-Oct-97	31616	15000		11357									HP	
PW&E97	BUN9710	06-Oct-97	31616	8800		15845									HP	
PW&E97	BUO9710	06-Oct-97	31616	12000		11354									HP	
PW&E97	BUP9710	06-Oct-97	31616	12000		11353									HP	
	BUQ9710	06-Oct-97	31616	7700		15844								DM	HP HP	+
PW&E97 PW&E97	BUA9710 BUS9710	06-Oct-97 06-Oct-97	31616 31616	12000 23000	DIVI	11351 15843								BM	HP HP	+
PW&E97 PW&E97	WOL9710	06-Oct-97	31616	34000		15843									HP	+
PW&E97	BUV9710	06-Oct-97	31616	23000		11345									HP	+
PW&E97	BUW9710	06-Oct-97	31616	28000		15841									HP	+
PW&E97	BUX9710	06-Oct-97	31616	9540		15840									HP	
	BUD9711	03-Nov-97	31616	450		11364									HP	
PW&E97	BUE9711	03-Nov-97	31616	270		11163									HP	

														dot #020 0 00 12 1/ Work Order			
Database	TAG	END DATE	STORET CODE	GT LT VALUE	remark	STATION ID	END TIME	END DEPTH	START DATE	START TIME	START DEPTH	CATEGORY CALC	TYPE	COMMENT	SOURCE 1	SOURCE 2	PROGRAM
PW&E97	BUF9711	03-Nov-97	31616	160		11363										HP	
PW&E97	BUG9711	03-Nov-97	31616	360		15847										HP	
PW&E97	BUH9711	03-Nov-97	31616	170		11362										HP	
PW&E97	BUI9711	03-Nov-97	31616	290		11361										HP	
PW&E97	BUJ9711	03-Nov-97	31616	200		11360										HP	
PW&E97	BUK9711	03-Nov-97	31616	230		11359										HP	
PW&E97	BUL9711	03-Nov-97	31616	310		15846										HP	
PW&E97	BUM9711	03-Nov-97	31616	340		11357										HP	
PW&E97	BUN9711	03-Nov-97	31616	480		15845										HP	
PW&E97	BUO9711	03-Nov-97	31616	420		11354										HP	
PW&E97	BUP9711	03-Nov-97	31616	520		11353										HP	
PW&E97	BUQ9711	03-Nov-97	31616	260		15844										HP	
PW&E97	BUA9711	03-Nov-97	31616	270	BM	11351								BM		HP	
PW&E97	BUS9711	03-Nov-97	31616	5400		15843										HP	
PW&E97	WOL9711	03-Nov-97	31616	5200		15824										HP	
PW&E97	BUV9711	03-Nov-97	31616	980		11345										HP	
PW&E97	BUW9711	03-Nov-97	31616	950		15841										HP	
PW&E97	BUX9711	03-Nov-97	31616	340		15840										HP	
PW&E97	WOB9701	27-Jan-97	31616	380		15831										HP	
PW&E97	WOC9701	27-Jan-97	31616	530		15830										HP	
PW&E97	WOD9701	27-Jan-97	31616	12000		15829										HP	
PW&E97	WOE9701	27-Jan-97	31616	19000		11390										HP	
PW&E97	WOF9701	27-Jan-97	31616	7500		11391										HP	
PW&E97	WOG9701	27-Jan-97	31616	5100		15828										HP	
PW&E97	WOJ9701	27-Jan-97	31616	2800		15826										HP	

APPENDIX D

QUALITY ASSURANCE PROGRAM PLAN (QAPP)

Total Maximum Daily Loads for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou Quality Assurance Project Plan Revision 4

University of Houston Houston, TX 77204-4003

Total Maximum Daily Load Program
Texas Natural Resource Conservation Commission
P.O. Box 13087, MC - 150
Austin, Texas 78711-3087

Effective Period June 2001 to May 2002

Questions concerning this quality assurance project plan should be directed to:

Hanadi Rifai
University of Houston Project Manager
4800 Calhoun
Houston, Texas 77204-4003
(713) 743-4271
rifai@uh.edu

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 3
Section A
Page 2

A1 Approval Page

Total Maximum Daily Loads for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou

Texas Natural Resource Conservation Commission Office of Compliance and Enforcement Compliance Support Division

Carol Batterton, Director Compliance Support Division

Stephen Stubbs, Quality Assurance Manager

Sharon Coleman, TMDL Quality Assurance Specialist

Monitoring Operations Division

David Sullivan, Section Manager Monitoring Data Management and Analysis

Office of Environmental Policy, Analysis, and Assessment Strategic Assessment Division

Julia Rathgeber, Director Strategic Assessment Division

Chuck Mueller, Manager Strategic Implementation Plans Section

Program Manager TMDL Team

Andrew Sullivan, Project Manager TMDL Team

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 3
Section A
Page 4

University of Houston/PBS&J

Hanadi Rifai, Project Manager University of Houston

Paul Jensen, Project Manager PBS&J

Adrienne Boer, Quality Assurance Officer PBS&J

Note: The University of Houston/PBS&J Quality Assurance Officer will secure written documentation (such as the letter in Appendix H) from each sub-tier project participant (e.g., subcontractors, other units of government, laboratories) stating the organization's awareness of and commitment to requirements contained in this quality assurance project plan and any amendments or revisions of this plan. The Quality Assurance Officer will maintain the documentation as part of the project's quality assurance records, and will ensure that the document is available for review.

A2 Table of Contents	
A1 Approval Page	2
A2 Table of Contents	
A3 Distribution List	
List of Acronyms.	
A4 Project/Task Organization	12
Figure 1. Organization Chart	
A5 Problem Definition.	
A6 Project/Task Description and Schedule	
A7 Quality Objectives and Criteria for Measurement Data	 20
Table 1. Data Quality Objectives for Measurement Data	∠0 22
A8 Training Requirements/Certifications	
B1 Sampling Process Design	
B2 Sampling Methods Requirements	
Table 2. Field Sampling and Handling Procedures	
B3 Sampling Handling and Custody Procedures	
B4 Analytical Methods Requirements	
B5 Quality Control Requirements	33
B6 Instrument/Equipment Testing, Inspection and Maintenance Requirements	
B7 Instrument Calibration and Frequency	
B8 Inspection/Acceptance Requirement for Supplies and Consumables	3/
B9 Data Acquisition Requirements	
B10 Data Management	38
C1 Assessments and Response Actions	
Table 3. Assessments and Response Actions	
C2 Reports to Management	
D1 Data Review, Validation	
D2 Validation and Verification Methods	
D3 Reconciliation with User Requirements	43
Table 4. Data Review, Verification, and Validation Procedures	
Appendix A. Work Plan.	46
Table 5. Impairments of Designated Uses to be Addressed in this TMDL Project	
Table 6. Data to be Included into TRACS	
Figure 2. Monitoring Plan Timeline	58
Appendix B. Sampling Process Design and Monitoring Schedule	59
Table 7. Monitoring Sites and Frequencies	60
Figure 3. Monitoring Locations for Point Source Sampling.	
Figure 4. Pilot Areas for Illegal Discharges Monitoring.	
Figure 5. Sampling Locations for Runoff Monitoring.	
Figure 6. Monitoring Locations for Dynamics Testing	6/
Figure 7. Monitoring Locations for Sediment Sampling	68
Appendix C. Field Data Reporting Form	
Appendix D. Chain-of-Custody Form	
Appendix E. Data Management Plan	
Figure 8. Data Management Plan.	
Appendix F. Monitoring Systems Review Checklist	
Appendix G. Data Review Checklist.	78
Appendix H. Example letter to document adherence to the QAPP	80

Page 6

A3 Distribution List

Texas Natural Resource Conservation Commission P.O. Box 13087 Austin, Texas 78711-3087

Office of Compliance and Enforcement Compliance Support Division

Sharon Coleman, TMDL Quality Assurance Specialist MC-176 (512) 239-1831

Monitoring Operations Division

Water Data Manager MC-165

Office of Environmental Policy, Analysis, and Assessment Strategic Assessment Division

Andrew Sullivan, TMDL Project Manager MC-150 (512) 239-4587

TNRCC Field Operations Division Region 12 5425 Polk Ave., Ste. H Houston, TX 77023-1486

Steve Smith, TMDL Liaison (713) 767-3693

University of Houston 4800 Calhoun, Room N107D Houston, TX 77204-4003

Hanadi Rifai, Project Manager (713) 743-4271

Monica Suarez, Data Manager (713) 743-0753

PBS&J 206 Wild Basin Road, Suite 300 Austin, TX 78746-3343 TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 3
Section A
Page 7

Paul Jensen, Project Manager (512) 329-8342 ext. 9584

Adrienne Boer , Quality Assurance Officer (512) 329-8342

Note: The University of Houston Data Manager will provide copies of this project plan and any amendments or revisions of this plan to each sub-tier project participant, e.g., subcontractors, other units of government, laboratories. The University of Houston/PBS&J Quality Assurance Officer will document receipt of the plan by sub-tier participants and maintain this documentation as part of the project's quality assurance records. This documentation will be available for review.

List of Acronyms

AVS Acid Volatile Sulfide

BAT Best Available Technology

BCT Best Conventional Technology

BMP Best Management Practice

BPJ Best Professional Judgement

CBOD₅ 5-day Carbonaceous Biochemical Oxygen Demand

CFR Code of Federal Regulations

CFU Colony-Forming Unit of bacteria

COC Chain of Custody

COD Chemical Oxygen Demand

CRM Certified Reference Material

CRP Clean Rivers Program

CSO Combined Sewer Overflow

CWA Clean Water Act

DMP Data Management Plan

DO Dissolved Oxygen

DOC Dissolved Organic Carbon

DOO Data Quality Objective

EC Escherichia coli

EPA Environmental Protection Agency

FC Fecal coliform

FDA Food and Drug Administration, US

FR Federal Register

FRPD Relative Percent Deviation of Field samples

GC Gas Chromatography

GEMS Geographic Information and Management System (City of Houston)

GPS Global Positioning System

HCFCD Harris County Flood Control District

HCPC Harris County Pollution Control

H&HS Health and Human Services (City of Houston)

IC Ion Chromatography

LA Load Allocation

LC Loading Capacity

LDPE Low Density Polyethylene

LIMS Laboratory Information Management System

LRPD Relative Percent Deviation of Laboratory samples

MAL Minimum Analytical Level, equivalent to EPA's Minimum Level

MDL Method Detection Limit

MOS Margin of Safety

MPN Most Probable Number

MS Mass Spectrometry

MSD Matrix Spike Duplicate

NCMP National Coastal and Marine Policy

National Estuary Program

NEP

NIST National Institute of Science and Technology

NOAA National Oceanic and Atmospheric Administration

NPDES National Pollutant Discharge Elimination System

NPS Nonpoint Source

PES Performance Evaluation Sample

POTW Publicly Owned Treatment Works

PW&E Public Works and Engineering (City of Houston)

QA/QC Quality Assurance/Quality Control

QAM Quality Assurance Management

QAO Quality Assurance Officer

QAPP Quality Assurance Project Plan

QAS Quality Assurance Specialist

OMP Quality Management Plan

RPD Relative Percent Deviation

RWA Receiving Water Assessment

SOP Standard Operating Procedure

SPM Suspended Particulate Matter

SRM Standard Reference Material

STORET Storage and Retrieval

SWQM Surface Water Quality Monitoring

TDS Total Dissolved Solids

TMDL Total Maximum Daily Load

$TMDL\ for\ Fecal\ Pathogens\ in\ Buffalo\ Bayou\ and\ Whiteoak\ Bayou\ QAPP$

Revision No. 3 Section A

Page 11

TNRCC Texas Natural Resource Conservation Commission

TOC Total Organic Carbon

TPDES Texas Pollutant Discharge Elimination System

TRACS Texas Regulatory and Compliance System

TSD Technical Support Document

TSS Total Suspended Solids

TSWQS Texas Surface Water Quality Standards

USGS United States Geological Survey

WBS Waterbody System

WLA Wasteload Allocation

WQMP Water Quality Management Plan

WMT Watershed Management Team

WWTP Wastewater Treatment Plant

A4 Project/Task Organization

TNRCC Compliance Support Division

Sharon Coleman TMDL Quality Assurance Specialist

Assists the TNRCC Project Manager in QA related issues. Reviews the QAPP to ensure projects meet stated objectives. Conveys quality related problems to an appropriate TNRCC manager. Coordinates or performs audits, as deemed necessary and using wide variety of assessment guidelines and tools. Provides a point of contact at the TNRCC to resolve QA issues.

Monitoring Operations Division

Water Data Manager

Receives quality-assured data in specified electronic format and loads these data into the Texas Regulatory and Compliance System (TRACS) database. Maintains records of data submission and returns incorrect or erroneous submissions TMDL Project Manager for resolution. Serves as Monitoring Operations data management customer service representative for the TNRCC Project Manager. Provides training to the TNRCC TMDL Project Manager to ensure proper data submittal.

Strategic Assessment Division

TNRCC TMDL Program Manager

Responsible for oversight of the TNRCC TMDL Program. Oversees the development of QA guidance for the TMDL Team to be sure it is within pertinent frameworks of the TNRCC. Reviews and approves all TMDL Projects, QA audits, corrective actions, reports, work plans, and contracts. Enforces corrective action, as required, where QA protocols are not met. Ensures that all TNRCC TMDL personnel are fully trained, and TMDL projects are adequately staffed.

Andrew Sullivan TNRCC TMDL Project Manager

Responsible for ensuring that the project delivers data of known acceptable quality, quantity, and type on schedule to achieve project objectives. Provides the primary point of contact between the University of Houston/PBS&J and the TNRCC. Tracks deliverables to ensure that tasks in the work plan are completed as specified in the contract. Assists TNRCC QAS in technical review of the QAPP. Responsible for verifying that the QAPP is followed by the University of Houston/PBS&J. Notifies the TNRCC QAS of particular circumstances, which may adversely affect the quality of data derived from the collection and analysis of samples.

Field Operations Division

Steve Smith TNRCC Regional Office TMDL Liaison

Assists in the development of the water quality monitoring plan. Ensures that the water quality monitoring plan in Appendix B adequately represents the local water quality conditions that may account for the observed impairment. Works with the University of Houston/PBS&J to resolve problems with water quality monitoring. Maintains contact with TNRCC Project Manager to ensure coordination of issues.

University of Houston/PBS&J

Hanadi Rifai University of Houston Project Manager

The University of Houston Project Manager is responsible for ensuring that tasks and other requirements in the contract are executed on time and with the quality assurance/ quality control requirements in the system as defined by the contract and in the QAPP; assessing the quality of subcontractor/participant work; submitting accurate and timely deliverables to the TNRCC Project Manager; and coordinating attendance at conference calls, training, meetings, and related project activities with the TNRCC. Responsible for verifying that the QAPP is followed by the University of Houston and sub-tier participants. Responsible for verifying that the project is producing data of known and acceptable quality. Responsible for ensuring adequate training and supervision of all activities involved in generating analytical data, corrective action taken as well as facilitating internal audits.

Paul Jensen PBS&J Project Manager

Responsible for ensuring that tasks performed by PBS&J are executed on time and with the quality assurance/ quality control requirements in the system as defined by the contract and in the QAPP; submitting accurate and timely deliverables to the University of Houston Project Manager; and coordinating attendance at conference calls, training, meetings, and related project activities with the

University of Houston. Responsible for verifying that the project is producing data of known and acceptable quality. Responsible for ensuring adequate training and supervision of all activities involved in generating analytical data, corrective action taken as well as facilitating internal audits.

Adrienne Boer

Quality Assurance Officer

Responsible for coordinating development and implementation of the University of Houston/PBS&J's QA program. Responsible for writing and maintaining QAPPs. Responsible for maintaining records of QAPP distribution, including appendices and amendments. Responsible for maintaining written records of sub-tier commitment to requirements specified in this QAPP. Responsible for identifying, receiving, and maintaining project quality assurance records. Responsible for compiling and submitting the QA report. Responsible for coordinating with the TNRCC QAS to resolve QA related issues. Notifies the University of Houston Project Manager and TNRCC Project Manager of particular circumstances which may adversely affect the quality of data. Responsible for the validation of data prior to the submission of data to the TNRCC. Coordinates the research and review of technical QA material and data related to water quality monitoring system design and analytical techniques. Conducts laboratory inspections. Develops, facilitates, and conducts monitoring systems audits. Responsible for performing and documenting a minimum 10% validation and verification of all data collected in accordance with Table 4 and acquired data procedures after each task is performed.

Monica Suarez University of Houston Data Manager

Responsible for the acquisition, verification, and transfer of data to the TNRCC. Oversees data management for the study. Performs data quality assurances prior to transfer of data to TNRCC. Responsible for transferring data to the TNRCC in the acceptable format. Ensures that the database review checklist is filled out and data submitted with appropriate codes and data.

Tina Petersen University of Houston Field Supervisor

Responsible for supervising all aspects of the sampling and measurement of surface waters and other parameters in the field. Responsible for the acquisition of water samples and field data measurements in a timely manner that meet the quality objectives specified in Section A7 (Table 1), as well as the requirements of Sections B1 through B8. Responsible for field scheduling, staffing, and ensuring that staff is appropriately trained as specified in Sections A6 and A8. Coordinates any joint monitoring with the TNRCC Project Manager and TNRCC Regional Office TMDL Liason. Reports status, problems, and progress to the University of Houston Project Manager.

Deborah Roberts University of Houston Laboratory Manager

Responsible for supervision of laboratory personnel involved in generating analytical data for this project. Responsible for ensuring that laboratory personnel involved in generating analytical data have

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 3
Section A

Page 15

adequate training and a thorough knowledge of the QAPP and all SOPs specific to the analyses or task performed and/or supervised. Responsible for oversight all operations ensuring that all QA/QC requirements are met and documentation related to the analysis is completely and accurately reported. Enforces corrective action, as required.

Deborah Roberts

University of Houston Laboratory Quality Assurance Officer

Monitors the implementation of the QAM/QAP within the laboratory to ensure complete compliance with QA objectives as defined by the contract and in the QAPP. Conducts in-house audits to identify potential problems and ensure compliance with written SOPs. Responsible for supervising and verifying all aspects of the QA/QC in the laboratory. Performs validation and verification of data before the report is sent to the contractor. Insures that all QA reviews are conducted in a timely manner from real-time review at the bench during analysis to final pass-off of data to the QA officer.

Ka-Leung Lee PBS&J Data Manager

Responsible for the acquisition, verification, and transfer of data to the University of Houston. Performs data quality assurances prior to transfer of data to the University of Houston. Ensures that the database review checklist is filled out and data submitted with appropriate codes and data. Provides the point of contact for the University of Houston Data Manager to resolve issues related to the data.

Martin Heaney PBS&J Field Supervisor

Responsible for supervising all aspects of the sampling and measurement of surface waters and other parameters in the field. Responsible for the acquisition of water samples and field data measurements in a timely manner that meet the quality objectives specified in Section A7 (Table 1), as well as the requirements of Sections B1 through B8. Responsible for field scheduling, staffing, and ensuring that staff is appropriately trained as specified in Sections A6 and A8. Coordinates any joint monitoring with the TNRCC Project Manager and TNRCC Regional Office TMDL Liason. Reports status, problems, and progress to the PBS&J Project Manager.

Steve Grychka North Water District Lab Services, Laboratory Manager

Responsible for supervision of laboratory personnel involved in generating analytical data for this project. Responsible for ensuring that laboratory personnel involved in generating analytical data have adequate training and a thorough knowledge of the QAPP and all SOPs specific to the analyses or task performed and/or supervised. Responsible for oversight all operations ensuring that all QA/QC requirements are met and documentation related to the analysis is completely and accurately report. Enforces corrective action, as required.

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 3
Section A
Page 16

Steve Grychka North Water District Lab Services, Laboratory Quality Assurance Officer

Monitor the implementation of the quality assurance management plan within the laboratory to ensure complete compliance with QA objectives as defined by the contract and in the QAPP. Conduct inhouse audits to identify potential problems and ensure compliance with written SOPs. Responsible for supervising and verifying all aspects of the QA/QC in the laboratory. Perform validation and verification of data before the report is sent to the contractor. Insures that all QA reviews are conducted in a timely manner from real-time review at the bench during analysis to final pass-off of data to the QA officer.




Figure 1. Organization Chart

A5 Problem Definition

The TNRCC implements the statewide approach for watershed management in Texas to improve the efficiency, effectiveness, and continuity of water quality management programs. The approach, which is summarized in *The Statewide Watershed Management Approach for Texas: The TNRCC's Framework for Implementing Water Quality Management* (TNRCC, 1997), establishes the state's process for managing water quality. It focuses on assessing watershed conditions for all waters of the state and implementing solutions where improvement is necessary. The primary goal of the approach is to ensure that management efforts provide a safe, clean, affordable water supply and healthy aquatic ecosystems for Texas.

The Total Maximum Daily Load Program, a major component of the approach, addresses impaired or threatened streams, lakes, and estuaries (water bodies). The primary objective of the TMDL Program is to restore and maintain the beneficial uses of impaired or threatened water bodies. The Federal Clean Water Act $\S303(d)$ list identifies "impaired" water bodies not meeting applicable water quality standards for their designated uses and requiring development of Total Maximum Daily Loads (TMDLs) for contaminants of concern. In general, a TMDL is the total amount of a pollutant that a water body can assimilate and still meet state water quality standards. The term also refers to the assessment necessary to establish an acceptable pollutant load for an impaired water body and to allocate the load between contributing point, nonpoint, and natural background sources of pollutants in the watershed. Thus, water quality monitoring and other assessment activities are an integral part of the TMDL.

Segments 1013, 1014 and 1017 have been identified in the 303(d) list as impaired due to elevated levels of fecal coliforms that can negatively impact contact recreaction. Consequently, a TMDL study for fecal pathogens in Buffalo and Whiteoak Bayous is being developed. As part of the bacteria TMDL project, the University of Houston and PBS&J will collect field data on concentrations and dynamics of fecal pathogens in the segments of concern to assess sources, current contamination levels and trends. The monitoring will have four main components, which are monitoring of point sources under dryweather conditions, assessment of illicit discharge locations, sampling of moderate run-off in tributaries and main stream for model calibration, and analysis of bacteria dynamics in the bayous.

This QAPP addresses the monitoring program for the TMDL project. The purpose of the QAPP is to clearly delineate the tasks, management structure, and policies which will be used to implement the QA requirements necessary to document the reliability and validity of environmental data. The QAPP is reviewed by the TNRCC to ensure that data generated for the purposes described above are scientifically valid and legally defensible. This process will insure that all data submitted to the statewide database have been collected and analyzed in a way that guarantees its reliability and therefore can be used in TMDL development, stream standards modifications, permit decisions, and water quality assessments.

A6 Project/Task Description and Schedule

See Appendix A for the work plan tasks and schedule of deliverables for this project. This QAPP covers the water quality monitoring tasks described in the work plan. No decisions will be made by the project team based on the data collected. These data, and data collected by other organizations (e.g. USGS, TNRCC, etc.), will be subsequently analyzed and used by the TNRCC for TMDL development.

See Appendix B for sampling locations and scheduling for the monitoring to be conducted under this QAPP.

Revisions to the QAPP

Until the work described is completed, this QAPP shall be revised as necessary and reissued annually on the anniversary date, or revised and reissued within 120 days of significant changes, whichever is sooner. The last approved versions of QAPPs shall remain in effect until revised versions have been approved, if revised version has been submitted for review before expedition of approved version. If the entire QAPP is current, valid, and accurately reflects the project goals and the organization's policy, the annual re-issuance may be done by a certification that the plan is current, to include a copy of new, signed approval pages for the QAPP.

Expedited Changes

Expedited Changes to the QAPP may be approved to reflect changes in project organization, tasks, schedules, objectives, and methods, address deficiencies and non-conformance, improve operational efficiency; and accommodate unique or unanticipated circumstances. Requests for expedited changes are directed from the University of Houston Project Manager to the TNRCC Project Manager in writing. They are effective immediately upon approval by the TNRCC Project Manager and Quality Assurance Specialist, or their designees. Expedited changes to the QAPP and the reasons for the changes shall be documented, and revised pages shall be initialed by the TNRCC Project Manager and QAS and University of Houston Project Manager, then distributed to all persons on the QAPP distribution list by the University of Houston/PBS&J QAO.

Expedited changes shall be reviewed, approved, and incorporated into a revised QAPP during the annual revision process or within 120 days of the initial approval in cases of significant changes.

Personnel and Equipment Requirements

See Sections A8 and B6.

Assessment Techniques

See section C1 for a listing of project assessments.

Quality Assurance Records

See section A9 for a listing of project quality assurance documents and records.

A7 Quality Objectives and Criteria for Measurement Data

The project objective is to collect data that comply with TNRCC rules for surface water quality monitoring programs, to support decisions related to bacteria TMDL development for the Buffalo and Whiteoak Bayous. Fecal coliform (FC) and *Escherichia coli* (EC), the official bacterial indicators for past and current Texas water quality standards, will be measured in several locations across segments 1013, 1014 and 1017. Conventional water chemistry and field-measured parameters (e.g. pH, temperature, DO, turbidity, conductivity, salinity, NH₃-N, and PO₄-P) as well as flow severity, TSS will also be measured to find any correlation among these parameters and to understand how levels of the bacterial indicators change with flow. In addition, samples collected at point sources (at a point following the chlorine contact chamber as it is flowing over the weir) will be analyzed for residual chlorine. EC will also be measured in some sediment samples to try to establish a baseline of bacterial contamination in the sediments. The measurement performance criteria to support the project objective are specified in Table 1.

Precision

The precision of laboratory data is a measure of the reproducibility of a measurement when an analysis is repeated. It is strictly defined as a measure of the closeness with which multiple analyses of a given sample agree with each other. Precision is assessed by replicate analyses, by repeated analyses of a stable standard. Precision is specified by the relative percent deviation of the results.

RPD =
$$\{(X_1 - X_2) / \hat{a}(X_1 + X_2) / 2\tilde{n} \} * 100$$

For microbiological analyses, the method to be used for calculating precision is the one outlined in Standard Methods 20th Edition section 9020 B.8.b.

$$RPD_{bacteria} = (log X_1 - log X_2)$$

The RPD_{bacteria} should be lower than $3.27~SR_{log}/n$, where R_{log} is the difference in the natural log of duplicates for the first 15 positive samples.

Performance control limits for analytical measurements are specified in Table 1. Performance limits for field duplicates are defined in Section B5.

Accuracy

Accuracy is a statistical measurement of correctness and includes components of systemic error. A measurement is considered accurate when the value reported does not differ from the true value. Accuracy is verified through the analysis of laboratory matrix spikes and certified reference materials are specified in Table 1. Performance limits for blank analyses are discussed in Section B5.

Representativeness

A small part of the data collected under the TMDL Program will be considered representative of ambient water quality conditions. Representativeness is a measure of how accurately a monitoring program reflects the actual water quality conditions. The representativeness of the data is dependent on 1) data quality objectives, 2) the sampling locations, 3) the number of samples collected, 4) the number of years and seasons when sampling is performed, 5) the number of depths sampled, and 6) the sampling procedures. Appropriate site selection and sampling of all pertinent media (water, sediment, and biota) and use of only approved analytical methods will assure that the measured data represent the conditions at the site. The goal for meeting total representation of the water body is tempered by the availability of time and funding and the objectives of the data collection. Representativeness will be measured with the completion of sample collection in accordance with the approved QAPP.

Comparability

Only approved procedures, as described in this QAPP, will be used for field sampling and laboratory analyses to assure the comparability of the data. In addition, for an accurate analysis to be conducted, reporting units will be consistent for the dataset, accepted rules for rounding figures will be applied, and data will be reported in a standard format as specified in the Data Management Plan (Appendix E).

Completeness

The completeness of the data is basically a relationship of how much of the data are available for use compared to the total potential data. Ideally, 100% of the data should be available. However, the possibility of unavailable data due to accidents, insufficient sample volume, broken or lost samples, etc. is to be expected. Therefore, it will be a general goal of the project that 90% data completion is achieved.

Revision No. 3

Section A Page 22

Table 1 - Data Quality Objectives for Measurement Data

PARAMETER	UNITS	METHOD TYPE	METHOD	METHOD DESCRIPTION	STORET	MAL	PRECISION of laboratory duplicates (RPD)	ACCURACY of matrix spikes % Recovery	ACCURACY CRM	PERCENT COMPLETE
Field Parameter	rs		1				. ,	•		
рН	pH units		EPA 150. land TNRCC SOP		00400	1.0	10	NA	NA	90
DO	mg/L		EPA 360. land TNRCC SOP		00300	1.0	10	NA	NA	90
Conductivity	mS/cm		EPA 120. land TNRCC SOP		00094	1	10	NA	NA	90
Temperature	° Celcius		EPA 170. land TNRCC SOP		00010	NA	10	NA	NA	90
Flow	cfs		TNRCC SOP		00061	NA	10	NA	NA	90
Flow Severity	1-no flow, 2-low, 3-normal, 4-flood, 5-high, 6-dry	TNRCC SOP	TNRCC SOP ²		01351	NA	NA	NA	NA	90
Conventional pa	arameters									
TSS	mg/L	gravimetric	EPA 160.2		00530	4.0	20	NA	NA	90
TOC	mg/L	oxidation	EPA 415.2		00680	0.1	20	80-120	NA	90
Residual chlorine	mg/L	DPD colorimetric	Std. Methods 400-Cl G/ HACH Method 8021		50060	0.01	20	80-120		90
Ammonia-N	mg/L	Colorimetric, salicylate	HACH Methods 10023(low range) and 10031 (high range			0.02	20	80-120		90

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP

Revision No. 3

Section A

Page 23

										Page.
PARAMETER	UNITS	METHOD TYPE	METHOD	METHOD DESCRIPTION	STORET	MAL	PRECISION of laboratory duplicates (RPD)	ACCURACY of matrix spikes % Recovery	ACCURACY CRM	PERCENT COMPLETE
o-Phosphorous	mg/L	colorimetric, absorbic acid	EPA 365.3/ HACH Method 8048		00671	0.01	20	80-120		90
Turbidity	NTU	nephelometric	EPA 180.1		82079		20	NA		90
Carbonaceous Biochemical Oxygen Demand	mg/L	potentiometri c	Std. Methods 5210-B		80082		25	NA		90
FC in water	cfu/100 mL	membrane filter, mFC	Std. Methods 9222-D	membrane filter, mFC	31616	1	3.27* SRlog/n	NA		90
EC in water	MPN/100 mL	Alternate Direct	IDEXX Colilert	IDEXX MPN Quantitray 2000	31699	1	3.27* SRlog/n	NA		90
EC in sediment ³	cfu/100 g	Resuspension in water with subsequent mTEC		membrane filter, mTEC	31702	1	3.27* SRlog/n	NA		90
Sediment grain size analysis	% dry weight 0.0039- 0.0625 mm	TNRCC SOP	Fract.separatio n/gravimetric determination		82008	NA	NA	NA		90
Sediment grain size analysis	% dry weight < 0.0039 mm	TNRCC SOP	Fract.separatio n/gravimetric determination		82009	NA	NA	NA		90
Sediment grain size analysis	% dry weight 0.0625- 2 mm	TNRCC SOP	Fract.separatio n/gravimetric determination		89991	NA	NA	NA		90

¹ Due to the dependence of rainfall occurrence at certain times, runoff samples will have a lesser percent of completeness ² TNRCC. 1999. Surface Water Quality Monitoring Procedures, pp. 2.16-2.17

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP

Revision No. 3

Section A

Page 24

³ Bacteria will be transferred from the sediment sample to an aqueous phase and subsequently analyzed using membrane filtration.

A8 Training Requirements/Certifications

UH/PBS&J personnel will be fully trained in all methods and procedures required in this QAPP. Documentation of any training classes will be maintained.

A9 Documentation and Records

The documents that describe, specify, report, or certify activities, requirements, procedures, or results for this project and the items and materials that furnish objective evidence of the quality of items or activities are listed.

Document/Record	Location	Retention	Form
QAPP, amendments, and appendices	Univ. of Houston	5 years	Paper
QAPP distribution documentation	Univ. of Houston	5 years	Paper
Field notebooks or field data sheets	Univ. of Houston	5 years	Paper
Field equipment calibration/maintenance logs	Univ. of Houston	5 years	Paper
Chain of custody records	Univ. of Houston.	5 years	Paper
Field SOPs	Univ. of Houston	5 years	Paper
Bacteriological field samples logs	Univ. of Houston	5 years	Paper
Media/incubation logs	Lab	5 years	Paper
Laboratory sample reception logs	Lab	5 years	Paper
Laboratory QA manuals	Lab	5 years	Paper
Laboratory SOPs	Univ. of Houston	5 years	Paper
Laboratory internal/external standards	Lab	5 years	Paper
Laboratory instrument performance	Lab	5 years	Paper
Laboratory initial demonstration of capability	Lab	5 years	Paper
Laboratory procedures	Lab	5 years	Paper
Instrument raw data files	Lab	5 years	LIMS Electronic
Instrument readings/printouts	Lab	5 years	Paper
Laboratory data reports	Univ. of Houston.	5 years	Paper
Laboratory data verification for integrity,			
precision, accuracy and validation	Lab	5 years	Paper
Laboratory equipment maintenance logs	Lab	5 years	Paper
Laboratory calibration records	Lab	5 years	LIMS Electronic
Laboratory corrective action documentation	Lab	5 years	Paper
University of Houston data base verification	Univ. of Houston	5 years	Electronic
Lead Organization data quality assurance/			
Quality control verification/validation	Univ. of Houston	5 years	Paper
Copy of data collected by other organizations	Univ. of Houston	5 years	Paper/Electronic
Training records	Univ. of Houston	3 years	Paper
Progress report/final report/data	U of H/TNRCC	3 years	Paper/Electronic

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak
Bayou QAPP
Revision No. 3
Section A
Page 26

The TNRCC may elect to take possession of records at the conclusion of the specified retention period.

Special Reporting Formats

The University of Houston/PBS&J will use the formats from the TNRCC SWQM Program. Special reporting formats are included in the SWQM *Data Management Reference Guide*.

Case Narrative

A case narrative is not required for this project.

References

American Public Health Association, American Water Works Association, and Water Pollution Control Federation, 1999. *Standard Methods for the Examination of Water and Wastewater*. Eds. L. Clesceri, A. Eaton, and A. Greenberg. 20th Edition. American Public Health Association, Washington. DC.

TNRCC, 1999a. Data Management Reference Guide, Surface Water Quality Monitoring (or most current version).

TNRCC, 1999b. Surface Water Quality Monitoring Procedures Manual, GI-252, June 1999.

TNRCC, 1999c. Program Guidance & Reference Guide FY 2000-2001, Texas Clean Rivers Program.

Note: when references are made to documents that are not attached to the QAPP, the Project Manager of the University of Houston assumes responsibility for compliance of the documentation with the QAPP requirements.

B1 Sampling Process Design

See Appendix B for sampling process design information and monitoring tables associated with data collected under this QAPP.

B2 Sampling Methods Requirements

Field Sampling Procedures

The University of Houston and PBS&J will follow the field sampling procedures for field, biological, and conventional chemical parameters documented in the *TNRCC Surface Water Quality Monitoring Procedures Manual* (1999a) and the TNRCC *Receiving Water Assessment Procedures Manual* (1999b). Water samples will be collected manually in new, unused Whirlpak bags containing sodium thiosulfate for bacterial analysis. Additionally, water will be collected in 2-liter sterile glass bottles and transferred to a 1-L bottle to perform the respective field analyses, two 50 mL-bottles for TOC analysis (if pertinent), and two half-liter LDPE bottles for TSS analysis. Additionally, duplicate water samples will be collected in one gallon- cubitainers for CBOD₅ analysis, when appropriate. Sediment samples will be collected with a clean, washed Ekman dredge (pre-rinsed with native water) and the unconsolidated material at the top scraped off into a 500 g-pint glass jars for bacterial analyses. Additional procedures for field sampling outlined in this section reflect specific requirements for sampling under this TMDL Project and/or provide additional clarification.

Sample Volume, Container Types, Minimum Sample Volume, Preservation Requirements, and Holding Time Requirements.

Table 2. Field Sampling and Handling Procedures

Parameter	Matrix	Container	Preservation	Sample Volume	Holding Time
o-phosphorus	water	Pre-cleaned glass bottles	To be analyzed in the field		-
Ammonia- Nitrogen	water	Pre-cleaned glass bottles	To be analyzed in the field		-
Residual chlorine	water	Pre-cleaned glass bottles	To be analyzed in the field		-
CBOD₅	water	Gallon cubitainer	4° C, add 1 g/L FAS crystals if residual chlorine present	1000 mL	48 hours
TSS	water	Pre-cleaned LDPE bottle	4° C, dark	400 mL	7 days
TOC	water	Pre-combusted borosilicate glass bottle	4° C, dark, pH<2 with H ₂ SO ₄	40 mL	28 days

ection B	
Page 28	

Parameter	Matrix	Container	Preservation	Sample Volume	Holding Time
Turbidity	water	Pre-cleaned glass bottles	To be analyzed in the field		
FC	water	Sterile Whirlpak bags	4° C, dark	250 mL	6+2 hours 1
EC	water	Sterile Whirlpak bags	4° C, dark	250 mL	6+2 hours ¹
EC	sediment	Pint glass jars with teflon liners	4° C, dark	500 g	6+2 hours ¹
Grain size analysis	sediment	Pint glass jars with teflon liners		500 g	

¹ This holding time represents 6 field hours and 2 lab hours

Processes to Prevent Cross Contamination

Procedures outlined in the TNRCC Surface Water Quality Procedures Manual describe the necessary steps to prevent cross-contamination of samples. These include such things as direct collection into sample containers, when possible; clean sampling techniques for metals; and certified containers for organics. Field QC samples as discussed in Section B5 are collected to verify that crosscontamination has not occurred.

Documentation of Field Sampling Activities

Field sampling activities are documented on field data sheets as presented in Appendix C. Flow work sheets, multi-probe calibration records, and records of bacteria analyses (if applicable) are part of the field data record. For all visits, station ID, location, sampling time, date, and depth and sample collector's name/signature are recorded. Values for all measured field parameters are recorded. Detailed observational data are recorded including water appearance, weather, biological activity, stream uses, unusual odors, specific sample information, missing parameters, days since last significant rainfall, and flow severity.

Recording Data

For the purposes of this section and subsequent sections, all personnel follow the basic rules for recording information as documented below:

- 1. Legible writing in indelible, waterproof ink with no modifications, write-overs or cross-outs;
- 2. Correction of errors with a single line followed by an initial and date;
- 3. Closeouts on incomplete pages with an initialed and dated diagonal line.

Deviations from Sampling Method Requirements or Sample Design, and Corrective Action

Examples of deviations from sampling method requirements or sample design include but are not limited to such things as inadequate sample volume due to spillage or container leaks, failure to preserve samples appropriately, contamination of a sample bottle during collection, storage temperature and holding time exceedance, sampling at the wrong site, etc. Any deviations will invalidate resulting data. Samples should be discarded and re-collected.

B3 Sampling Handling and Custody Procedures

Chain-of – **Custody** – The COC system described in this QAPP replaces the "tag" system as described in the SWQM Manual.

Proper sample handling and custody procedures ensure the custody and integrity of samples beginning at the time of sampling and continuing through transport, sample receipt, preparation, and analysis.

A sample is in custody if it is in actual physical possession or in a secured area that is restricted to authorized personnel. The COC form is used to document sample handling during transfer from the field to the laboratory and among contractors. The following information concerning the sample is recorded on the COC form (See Appendix D).

- 1. Date and time of collection
- 2. Site identification
- 3. Sample matrix
- 4. Number of containers
- 5. Preservative used or if the sample was filtered
- 6. Analyses required
- 7. Name of collector
- 8. Custody transfer signatures and dates and time of transfer
- 9. Name of laboratory admitting the sample
- 10. Bill of lading (if applicable)

The Chain of Custody will be attached to the Field Data Sheets.

Sample Labeling

Samples are labeled on the container (or on a label) with an <u>indelible</u>, waterproof marker. Label information includes the site identification, the date and time of sampling, and preservative added (if applicable).

Sample Handling

For all the analyses to be conducted, the sample containers will not be pre-rinsed.

FC analysis in water

Whirlpak bags containing sodium thiosulfate ($Na_2S_2O_3$) will be used to collect the FC samples to prevent interference by residual chlorine. Samples (in duplicate for point sources and illegal discharges) will be sealed and carried in ice chests from the point of collection (see Appendix A for a description of the point where the samples will be collected from) to the University of Houston laboratory/North Water District Laboratory Services. In addition, a bottle containing DI water will be packed with the samples for further checking of temperature. As soon as the samples are received, the temperature tester will be open and the temperature measured and recorded in a laboratory logbook. If the temperature exceeds 4° C, the samples will be discarded. Sample filtration will be initiated at most six hours after the sample is collected. To insure that the holding time criterion is met, the laboratory data manager will receive a copy of the field log format and will log in the samples at the laboratory including both time of collection and time of reception of each sample. If the time of reception exceeds six hours the sample will be discarded and a new sample will have to be collected at the respective location.

Filtering will start as soon as possible after the samples are logged in at the laboratory but in all cases in less than two hours. A new record will be added to the lab log format to indicate the time at which filtration is initiated. If the lab holding time exceeds 2 hours, or the overall holding time exceeds 8 hours, the sample will be discarded and re-collected. Samples will be left on ice until filtration is initiated. Sample size will be dictated based upon experience. It is anticipated that the average FC number will be between 1,000 to 10,000 cfu/100 mL. It is required that the sample volume yields between 20 and 60 cfu/ 100 mL. Based upon this expectation, sample size will need to be between 0.00002 mL to 0.001 mL to yield the optimum number of colonies. If the sample size is less than 1mL, dilutions will be prepared serially using sterile phosphate buffered water dilution blanks. Samples will be shaken vigorously at least 25 times prior to preparation of dilutions. Three different dilutions will be filtered of one sample (1:1, 1:10, and 1:100, or as determined after looking at historical data for each location), and three replicates will be prepared of each dilution. When sample aliquots of less than 20 mL are to be filtered, 10 mL of sterile buffer water will be added to the funnel before filtration.

Once a sample is filtered, incubation will be started. Prior to loading the incubator, the temperature will be set to 35 ± 0.5 °C. The incubation temperature as well as the time at which incubation started will be recorded in the lab logbook. Samples will be removed from the incubator after at least 22 hours of incubation and in any case prior to 26 hours of incubation. The time at which the samples are removed from the incubator will be recorded in the lab logbook. If the incubation time exceeds 26 hours, the sample will be discarded and a new sample will have to be collected. Counting will be initiated as soon as all the dilutions from one sample are removed from the incubator. Plates with too few (less than 20) or too many (more than 100) colonies will be discarded, but in any case they will be recorded in the lab logbook.

EC analysis in water

Whirlpak bags containing sodium thiosulfate ($Na_2S_2O_3$) will be used to collect the EC samples to prevent interference by residual chlorine. Samples (in duplicate for point sources) will be sealed and carried in ice chests from the point of collection to the laboratory or place where sealing and incubation are performed. The laboratory data manager will receive a copy of the field log format and will log in the samples at the laboratory including both time of collection and time of reception of each sample, as well as the temperature measured from the tester (see earlier paragraph). If the temperature exceeds $4^{\circ}C$,

the samples will be discarded. Sample preparation (reagent addition, pouring into tray and sealing) will be initiated at most six hours after the sample is collected. To insure that the holding time criterion is met, the laboratory data manager will receive a copy of the field log format and will log in the samples at the laboratory including both time of collection and time of reception of each sample. If the time of reception exceeds six hours the sample will be discarded and a new sample will have to be collected at the respective location. Three different dilutions will be prepared of one sample (1:1, 1:10, and 1:100, or as determined after looking at historical data for each location) and three replicates will be prepared of each dilution. Sealed samples will be placed in an incubator at 35°C, the starting incubation time and temperature will be recorded in the lab logbook. Samples will be removed from the incubator after 24 hours of incubation. The time at which the samples are removed from the incubator will be recorded in the lab logbook. If the incubation time exceeds 24 hours, the sample will be discarded and a new sample will have to be collected. Counting will be initiated as soon as all the dilutions from one sample are removed from the incubator.

EC analysis in sediment

Pint glass jars with teflon liners will be used to collect sediment samples. Duplicate samples will be sealed and carried in ice chests from the point of collection to the University of Houston laboratory. The laboratory data manager will receive a copy of the field log format and will log in the samples at the laboratory including both time of collection and time of reception of each sample, as well as the temperature measured from the tester (see earlier paragraph). The indirect enumeration of microorganisms from a sediment sample will involve transferring the organisms from the sample into a water phase. Water sample preparation will be initiated at most six hours after the sample is collected. To insure that the holding time criterion is met, the laboratory data manager will receive a copy of the field log format and will log in the samples at the laboratory including both time of collection and time of reception of each sample. If the time of reception exceeds six hours the sample will be discarded and a new sample will have to be collected at the respective location. The sediment-to-water transference will start as soon as possible after the samples are logged in at the laboratory but in all cases in less than two hours and will follow the procedure outlined below:

- 1. Weigh 10 g of the sediment sample into a 250 mL Erlenmeyer flask. Lable the flask with the corresponding sample ID.
- 2. Add 100 mL of sterile buffered dilution water (Std. Methods 9050C.1) to each flask.
- 3. Place flasks in an orbital shaker and mix on a medium setting for one hour.
- 4. Allow the samples to settle for 30 minutes and decant the liquid for analysis.
- 5. Prepare serial dilutions (10⁻², 10⁻³, 10⁻⁴, and 10⁻⁵) using sterile buffered dilution water (Std. Methods 9050C.1).

Filtering will start as soon as possible after the water samples are prepared. Sample size will be dictated based upon experience. It is anticipated that the average EC number will be between 1,000 to 50,000 cfu/100 g. Three different dilutions will be filtered of one sample (1:10, 1:100, and 1:1000, or as determined after looking at historical data for each location), and three replicates will be prepared of each dilution. Once a sample is filtered, incubation will be started. Prior to loading the incubator, the temperature will be set to 30°C. The incubation temperature as well as the time at which incubation started will be recorded in the lab logbook. After two hours, the incubation temperature will be raised to

44.5°C, the time and temperature will be recorded in the lab logbook. Samples will be removed from the incubator after at least 22 hours of incubation and in any case prior to 26 hours of incubation. The time at which the samples are removed from the incubator will be recorded in the lab logbook. If the incubation time exceeds 26 hours, the sample will be discarded and a new sample will have to be collected. Counting will be initiated as soon as all the dilutions from one sample are removed from the incubator. Plates with too few (less than 20) or too many (more than 100) colonies will be discarded, but in any case they will be recorded in the lab logbook.

TSS and TOC

Pre-cleaned LDPE bottles and pre-cleaned borosilicate glass bottles will be used to collect samples for TSS and TOC analyses, respectively. Sulfuric acid will be added at the field to the TOC bottles until pH is less than or equal to 2. Duplicate samples will be sealed and carried in ice chests from the point of collection to the University of Houston laboratory/North Water District Laboratory Services. The laboratory data manager will receive a copy of the field log format and will log in the samples at the laboratory including both time of collection and time of reception of each sample, as well as the temperature measured from the tester (see earlier paragraph). pH measurements will be taken from the samples to be analyzed for TOC, and the value will be recorded in the logbook; if pH exceeds 2, the sample will be discarded. Both TSS and TOC samples will then be transferred to the cold room and the temperature of the thermostat will be recorded (should be less than or equal to 4°C). Samples collected during a one-week period (i.e. Monday through Friday) will be analyzed soon after the last sample is taken. To insure that the holding time criterion is met, a new record will be added to the lab log format to indicate the date and time at which analyses were initiated.

Carbonaceous BOD₅

Gallon cubitainers will be used to collect the samples for CBOD₅ tests. If residual chlorine is detected, 1 g/L of FAS crystals will be added to the samples. Duplicate samples will be sealed and carried in ice chests from the point of collection to the North Water District Laboratory. Sample crews will make every effort to deliver samples for analysis within 6 hours of collection. The laboratory data manager will receive a copy of the field log format and will log in the samples at the laboratory including both time of collection and time of reception of each sample, as well as the temperature measured from the tester (see earlier paragraph). To insure that the holding time criterion is met, a new record will be added to the lab log format to indicate the date and time at which sample preparation was initiated. Sample analysis will be initiated as soon as possible but in no case will it start after 24 hours of collection. A new record will be added to the lab log format to indicate the time at which sample preparation is initiated. If the overall holding time exceeds 24 hours, the sample will be discarded and re-collected. Samples will be left on ice until sample preparation is initiated.

Failures in Chain-of-Custody and Corrective Action

All failures associated with chain-of-custody procedures are immediately reported to the University of Houston Project Manager. These include such items as delays in transfer, resulting in holding time violations; violations of sample preservation requirements; incomplete documentation, including signatures; possible tampering of samples; broken or spilled samples, etc. The University of Houston Project Manager, in consultation with the PBS&J Project Manager will determine if the procedural

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 4
Section B
Page 33

violation may have compromised the validity of the resulting data. Any failures that have reasonable potential to compromise data validity will invalidate data, and the sampling event should be repeated. The resolution of the situation will be reported to the TNRCC in the quarterly progress report. Corrective action reports will be maintained by University of Houston/PBS&J QAO.

B4 Analytical Methods Requirements

The analytical methods are listed in Table 1 of Section A7. The analyses cited in the table are approved in "Standard Methods for the Examination of Water and Wastewater." Laboratory SOPs are consistent with method requirements. Copies of laboratory SOPs are retained by the University of Houston and are available for review by the TNRCC.

Standards Traceability

All standards used in the laboratory are traceable to certified reference materials. Standards preparation is fully documented and maintained in a standards logbook. Each documentation includes information concerning the standard identification, starting materials, including concentration, amount used and lot number, date prepared, expiration date and preparer's initials or signature. The reagent bottle will be labeled in a way that will trace the reagent back to preparation.

Alternative Methodologies

Only data collected under TNRCC approved analytical methodologies as specified in this QAPP will be submitted to the TNRCC. Changes to the methodologies specified in this document (modifications of EPA approved methods, new methods, etc.) are changes to the QAPP, which is described in Section A6. Approval may involve equivalency testing, etc. Amended work will only begin after the TNRCC Project Manager and QAS have approved the modified procedures.

Failures or Deviations in Analytical Methods Requirements and Corrective Actions

Failures in analytical methods requirements involve, but are not limited to such things as instrument malfunctions, failures in calibration, blank contamination, quality control samples outside QAPP defined limits, etc. In many cases, the field technician or lab analyst will be able to correct the problem. If the problem is resolvable by the field technician or lab analyst, then they will document the problem on the field data sheet or laboratory record and complete the analysis. If the problem is not resolvable, then it is conveyed to the Laboratory Supervisor, who will make the determination and notify the University of Houston/PBS&J QAO. If the analytical system failure may compromise the sample results, the resulting data will not be reported to the TNRCC as part of this study. The nature and disposition of the problem is reported on the data report that is sent to the University of Houston Project Manager. The University of Houston Project Manager will include this information on the Quarterly Report, which is sent to the TNRCC Project Manager.

B5 Quality Control Requirements

Sampling Quality Control Requirements and Acceptability Criteria

The minimum Field QC Requirements are outlined in the *TNRCC Surface Water Quality Monitoring Procedures Manual* and Table 4 under Field Supervisor and staff tasks. The field staff should complete a documented review of 100% of the field data for compliance with QC requirements and the University of Houston/PBS&J will complete a documented review of a minimum of 10% of the field data. Specific requirements are outlined below. Field QC Samples are reported with the data report. See Section C2.

Bottle and Equipment Blanks (Filter/acid blanks) - An equipment blank is a sample of reagent water poured into a sample bottle, or poured over or pumped through a sampling or analysis device. It is collected in the same type of container as the environmental sample, preserved in the same manner and analyzed for the same parameter. In addition to regularly collected bottle and equipment blanks, laboratory equipment blanks are prepared at the laboratory where collection materials are cleaned between uses. These blanks document that the materials provided by the laboratory are free of contamination. The QC check is performed before each set of equipment is sent to the field, and before each new batch of samples to be analyzed in the laboratory . The analysis of equipment blanks should yield values less than the MAL. When target analyte concentrations are very high, blank values must be less then 5% of the lowest value of the batch.

Field duplicates - A field duplicate is defined as a second sample (or measurement) from the same location, collected in immediate succession, using identical techniques. This applies to all cases of routine surface water collection procedures, including in-stream grab samples, bucket grab samples (e.g., from bridges), pumps, and other water sampling devices. Duplicate samples are sealed, handled, stored, shipped, and analyzed in the sample manner as the primary sample. Precision of field duplicate results is calculated by the relative percent difference (FRPD) as defined by 100 times the difference (range) of each duplicate set, divided by the average value (mean) of the set. For duplicate results, X_1 and X_2 , the FRPD is calculated from the following equation:

FRPD =
$$\{(X_1 - X_2) / \hat{a}(X_1 + X_2) / 2\tilde{n} \} * 100$$

For bacteria, the logarithms of the actual counts are used in this formula.

Field duplicates will be collected at a frequency of 10% or higher. The FRPD between field duplicates should be less than 20%. If the FRPD of the field duplicates exceeds 20%, the laboratory should communicate this to the sampling team so that the source of error can be identified and corrective measures taken before the next sampling event.

Field Blanks - Field blanks consist of analyte-free de-ionized water that is taken to the field and transferred to the appropriate container in precisely the same manner as a sample during the course of a sampling event. They are used to assess the contamination from field sources such as air borne materials, containers, and preservatives. The analysis of field blanks should yield values less than the

Minimum Analytical Level. When target analyte concentrations are high, blank values should be less then 5% of the lowest value of the batch. Field blanks will be collected at a frequency of 10% or greater.

Laboratory Measurement Quality Control Requirements and Acceptability Criteria

Detailed laboratory QC requirements are contained within each individual method and Laboratory Quality Assurance Manuals. The minimum requirements that all participants abide by are stated in Table 4 under Laboratory Supervisor and Staff and below. Lab QC sample results are reported with the data report (see Section C2).

Laboratory duplicate - Laboratory duplicates are used to assess precision. A laboratory duplicate is prepared by splitting aliquots of a single sample (or a matrix spike or a laboratory control standard) in the laboratory. Both samples are carried through the entire preparation and analytical process. Laboratory duplicates are analyzed on 10% of samples analyzed. Acceptability criteria are outlined in Table 1 of Section A7.

Precision is calculated by the relative percent difference (LRPD) of lab duplicate results as defined by 100 times the difference (range) of each duplicate set, divided by the average value (mean) of the set. For duplicate results, X_1 and X_2 , the LRPD is calculated from the following equation:

LRPD =
$$\{(X_1 - X_2)/(\dot{a}(X_1 + X_2)/2)\} * 100$$

For bacteria, the logarithms of the actual counts are used in this formula.

Laboratory Control Standard (LCS) - A laboratory control sample is analyte-free water spiked with the analyte of interest prepared from standardized reference material. The laboratory control standard is generally spiked into laboratory pure water at a level less than or equal to the mid-point of the calibration curve for each analyte. The LCS is carried through the complete preparation and analytical process. The LCS is used to document the accuracy of the method due to the analytical process. LCSs are generally run at a rate of one per batch. Acceptability criteria are laboratory specific and usually based on results of past laboratory data. LCSs are routinely incorporated into the analysis program. The analysis of LCSs is a measure of accuracy and is calculated by Percent Recovery %R is defined as 100 times the observed concentration, divided by the true concentration of the spike.

The formula used to calculate percent recovery, where %R is percent recovery; SR is the observed spiked sample concentration; SA is the spike added:

$$R = (SR/SA) * 100$$

Matrix spikes (MS) and matrix spike duplicates- A matrix spike is an aliquot of sample spiked with a known concentration of the analyte of interest. A matrix spike duplicate (MSD) is a second matrix spike prepared in exactly the same manner. Percent recovery of the known concentration of added

analyte is used to assess accuracy of the analytical process. The spiking occurs prior to sample preparation and analysis. Matrix spike samples and matrix spike duplicates are routinely prepared and analyzed at a rate of 10% of samples processed. The MS is spiked at a level less than or equal to the midpoint of the calibration or analysis range for each analyte. The MS is used to document the accuracy of a method due to sample matrix and not to control the analytical process. Acceptability criteria are outlined in Table 1 of Section A7 and is calculated by Percent Recovery. Percent Recovery (%R) is defined as 100 times the observed concentration, minus the sample concentration, divided by the true concentration of the spike. Acceptance criteria are defined in Table 1 of Section A7.

The formula used to calculate percent recovery, where %R is percent recovery; SSR is the observed spiked sample concentration; SR is the sample concentration; and, SA is the spike added; is:

$$R = {(SSR - SR)/SA} * 100$$

Method Blank- A method blank is an analyte-free matrix to which all reagents are added in the same volumes or proportions as used in the sample processing and analyzed with each batch. The method blank is carried through the complete sample preparation and analytical procedure. The method blank is used to document contamination from the analytical process. Method blanks will be run before the start of fecal analysis, and following each sample. For the other analyses (TOC and TSS), deionized water will be run through the machines every five samples. The analysis of method blanks should yield values less than the Minimum Analytical Level. For very high level analyses, blank value should be less then 5% of the lowest value of the batch.

Additional method specific QC requirements - Additional QC samples are run (e.g., surrogates, internal standards, continuing calibration samples, interference check samples) as specified in the methods. The requirements for these samples, their acceptance criteria, and corrective action are method-specific.

Failures in Quality Control and Corrective Action

Sampling QC excursions are evaluated by the University of Houston/PBS&J Project Managers, in consultation with the University of Houston/PBS&J QAO. In that differences in field duplicate sample results are used to assess the entire sampling process, including environmental variability, the arbitrary rejection of results based on pre-determined limits (e.g. FRPD > 20%) is not practical. Therefore, the professional judgement of the University of Houston/PBS&J Project Managers and QAO will be relied upon in evaluating results. Rejecting sample results based on wide variability is a possibility. Notations of field duplicate excursions and blank contamination are noted in the quarterly report and the final QC Report.

Corrective action will involve identification of the cause of the failure where possible. Response actions will typically include re-analysis of questionable samples. In some cases, a site may have to be resampled to achieve project goals.

Laboratory measurement quality control failures are evaluated by the laboratory staff. The disposition

of such failures and conveyance to the TNRCC are discussed in Section B4 under Failures or Deviations in Analytical Methods Requirements and Corrective Actions.

B6 Instrument/Equipment Testing, Inspection and Maintenance Requirements

All sampling equipment testing and maintenance requirements are detailed in the *TNRCC Surface Water Quality Monitoring Procedures Manual*. Equipment records are kept on all field equipment and a supply of critical spare parts is maintained by the University of Houston/PBS&J Field Supervisor, or designee.

All laboratory tools, gauges, instrument, and equipment testing and maintenance requirements are contained within laboratory QAM(s). Testing and maintenance records are maintained and are available for inspection by the TNRCC. Instruments requiring daily or in-use testing may include, but are not limited to, water baths, ovens, autoclaves, incubators, refrigerators, and laboratory pure water. Critical spare parts for essential equipment are maintained to prevent downtime. Maintenance records are available for inspection by the TNRCC. The University of Houston Project Manager assumes responsibility for compliance of the QAM Quality Assurance Management Plan from the laboratory with the QAPP requirements.

B7 Instrument Calibration and Frequency

Field Equipment calibration requirements are contained in the *TNRCC Surface Water Quality Monitoring Procedures Manual*. Post calibration error limits and the disposition resulting from error are adhered to. Data not meeting post-error limit requirements invalidates associated data collected subsequent to the pre-calibration and are not submitted to the TNRCC.

Detailed laboratory calibrations are contained within the QAM(s). The laboratory QAM identifies all tools, gauges, instruments, and other sampling, measuring, and test equipment used for data collection activities affecting quality that must be controlled and, at specified periods, calibrated to maintain bias within specified limits. Calibration records are maintained and are available for inspection by the TNRCC. Equipment requiring periodic calibrations include, but are not limited to, thermometers, pH meters, balances, incubators, turbidity meters, and analytical instruments. Calibration records are available to the TNRCC for review. The University of Houston Project Manager and the Laboratory Managers assume responsibility for compliance of the QAM Quality Assurance Management Plan from the laboratory with the QAPP requirements.

B8 Inspection/Acceptance Requirement for Supplies and Consumables

Each new batch of supplies are tested before use to verify that they function properly and are not contaminated. The laboratory QAM provides additional details on acceptance requirements for laboratory supplies and consumables.

B9 Data Acquisition Requirements

Appendix B of this QAPP includes sampling by the U. S. Geological Survey (USGS). Flow data will be acquired from USGS gages on Buffalo and Whiteoak Bayous during the period of study (Source Codes GS/GS). These data are not covered under this QAPP and will not be reported to the TNRCC Data Manager by the University of Houston/PBS&J. However, data collected by the above organization that meet the data quality objectives of this project may be useful in satisfying the data and informational needs of the TMDL, and are included in Appendix B for that reason.

In addition, rainfall data will be obtained from the Harris County Flood Control District (HCFCD) monitoring network for the period July 2001 to December 2001 and from the City of Houston Public Works and Engineering (SC1/SC2: HG/HP) for the same time period. These data will be used for calibrating a fate and transport model of fecal pathogens in the Buffalo and Whiteoak Bayous and will not be reported to the TNRCC Data Manager.

Data Validation

Data management is an important part of QA for data collection activities. Part of the measurement objective for this plan is to use the collected data (ambient and non-ambient) to calibrate a suitable model to quantify the fate and transport of the indicator bacteria and to determine the maximum permissible loading to Buffalo and Whiteoak Bayous that will meet contact recreation criteria. All acquired data will be reviewed and verified for integrity and continuity, reasonableness, and conformance to project requirements (sampling procedures, analytical methods, representativeness, and accuracy) and then validated against the DQOs. The validation process shall include verification of the sampling design and execution (location, dates, time, procedures, etc), sample handling procedures (preservation, holding times, chain-of-custody, etc), laboratory procedures (sample identification, analytical methods, equipment maintenance, etc.), and analytical results (project and quality control samples). The results of the validation process shall be compared with the applicable requirements in the QAPP to determine if the data can be used. The validation, comparison, and final determination must be documented and the documentation must be maintained with other project record and available for audit or inspection. Only those data that are ambient measurements, which are supported by appropriate QC data and meet the DQOs defined for this project will be considered acceptable, and will be reported for entry into the Surface Water Quality Monitoring (SWQM) portion of the Texas Regulatory and Compliance System (TRACS) database.

B10 Data Management

Data Management Protocols are addressed in the Data Management Plan, which is in Appendix E of the document.

References

TNRCC, 1999a. Data Management Reference Guide, Surface Water Quality Monitoring (or most current version).

TNRCC, 1999b. Surface Water Quality Monitoring Procedures Manual, GI-252, June 1999.

TNRCC, 1999c. Receiving Water Assessment Procedures Manual, GI-253, June 1999.

Note: when references are made to documents that are not attached to the QAPP, the Project Manager of the University of Houston assumes responsibility for compliance of the documentation with the QAPP requirements.

C1 Assessments and Response Actions

The following table presents the types of assessments and response action for data collection activities applicable to the QAPP.

Table 3. Assessments and Response Actions

Assessment Activity	Approximate Schedule	Responsible Party	Scope	Response Requirements
Status Monitoring Oversight, etc.	Continuous	University of Houston Project Manager	Monitoring of the project status and records to ensure requirements are being fulfilled. Monitoring and review of contract laboratory performance and data quality	Report to TNRCC in Quarterly Report. Ensure project requirements are being fulfilled.
Laboratory Inspections	Dates to be determined by the TNRCC lab inspector	TNRCC Laboratory Inspector	Analytical and quality control procedures	30 days to respond in writing to the TNRCC to address corrective actions
	Annually	University of Houston/PBS&J QAO	employed at the laboratory and the contract laboratory	Implements corrective action. Report sent to TNRCC QAS
Monitoring Systems Audit	Dates to be determined by TNRCC	TNRCC QAS	The assessment will be tailored in accordance with objectives needed to assure compliance with the QAPP.	30 days to respond in writing to the TNRCC to address corrective actions
	Annually	University of Houston/PBS&J QAO	Field sampling, handling and measurement; facility review; and data management as they relate to the TMDL Project	Report sent to TNRCC QAS. Resolves any deficiencies.
Performance Evaluation Samples	Annually	University of Houston/PBS&J QAO	Checks competency of the laboratory and the contract laboratory to perform analyses	Report sent to TNRCC QAS. Resolves any deficiencies. Verifies satisfactory performance with second set of PES

Corrective Action

The University of Houston Project Manager is responsible for implementing and tracking corrective action procedures as a result of audit findings. Records of audit findings and corrective actions are maintained by both the TNRCC TMDL Program and the University of Houston/PBS&J Quality Assurance Officer.

If audit findings and corrective actions cannot be resolved, then the authority and responsibility for terminating work is specified in the TNRCC QMP and in agreements or contracts between participating organizations.

C2 Reports to Management

Laboratory Data Reports

Laboratory data reports contain the results of all specified QC measures listed in section B5, including but not limited to equipment blanks, filter and reagent blanks, field blanks, laboratory duplicates, laboratory control standards, calibrations, and matrix spikes. This information is reviewed by the University of Houston/PBS&J QAO and compared to the pre-specified acceptance criteria to determine acceptability of data before forwarding to the University of Houston Project Manager. This information is available for inspection by the TNRCC.

Reports to TNRCC Project Management

All reports detailed in this section are contract deliverables and are transferred to the TNRCC in accordance with contract requirements.

Quarterly Progress Report - Summarizes the University of Houston/PBS&J's activities for each task; reports problems, delays, and corrective actions; and outlines the status of each task's deliverables.

Monitoring Systems Review Checklist and Report of Significant Corrective Actions - Following the annual audits performed by the University of Houston/PBS&J, the monitoring systems audit checklist along with recommendations and corrective actions is sent to the TNRCC.

Reports by TNRCC Project Management

Contractor Evaluation - The University of Houston participates in a Contractor Evaluation by the TNRCC annually for compliance with administrative and programmatic standards.

D1 Data Review, Validation, and Verification Requirements

For the purposes of this document, verification means the processes taken to confirm by examination and provision of objective evidence that specified QAPP/project requirements, including documentation and technical criteria, have been fulfilled. Validation means those processes taken independently of the data-generation processes to confirm by examination and provision of objective evidence of the quality control acceptability of all the processes involved in the production of environmental data. Integrity means the processes taken to assure that no falsified data will be reported.

All data obtained from field and laboratory measurements will be reviewed and verified for conformance to project requirements, and then validated against the data quality objectives which are listed in Section A7. Only those data which are supported by appropriate quality control data and meet the data quality objectives defined for this project will be considered acceptable, and will be reported to the TNRCC for entry into TNRCC's water quality database. All other data will be rejected.

The procedures for verification and validation of data are described in Section D2, below. The University of Houston/PBS&J Field Supervisors are responsible for ensuring that field data are properly reviewed and verified for integrity. The Laboratory Supervisor is responsible for ensuring that laboratory data are scientifically valid, defensible, of acceptable precision and accuracy, and reviewed for integrity. The University of Houston Data Manager will be responsible for ensuring that all data are properly reviewed and verified, and submitted in the required format to the project database. The University of Houston/PBS&J QAO is responsible for documented validation of a minimum of 10% data for each task. Finally, the University of Houston Project Manager, with the concurrence of the PBS&J Project Manager, is responsible for validating that all data to be reported meet the objectives of the project and are suitable for reporting to TNRCC.

D2 Verification and Validation Methods

All data will be verified to ensure they are representative of the samples analyzed and locations where measurements were made, and that the data and associated quality control data conform to project specifications. The staff and management of the respective field, laboratory, and data management tasks are responsible for the integrity, validation and verification of the data each task generates or handles throughout each process. The field and laboratory tasks ensure the verification of raw data, electronically generated data, and data on chain-of-custody forms and hard copy output from instruments.

Verification, validation and integrity review of data will be performed using self-assessments and peer review, as appropriate to the project task, followed by technical review by the manager of the task. The data to be verified (listed by task in Table 4) are evaluated against project specifications (Section A7) and are checked for errors, especially errors in transcription, calculations, and data input. Potential outliers are identified by examination for unreasonable data, or identified using computer-based statistical software. If a question arises or an error or potential outlier is identified, the manager of the task responsible for generating the data is contacted to resolve the issue. Issues which can be corrected are corrected and documented electronically or by initialing and dating the associated paperwork. If an

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 4
Section D
Page 43

issue cannot be corrected, the task manager consults with higher level project management to establish the appropriate course of action, or the data associated with the issue are rejected.

The University of Houston Project Manager and the University of Houston/PBS&J QAO are each responsible for validating that the verified data are scientifically valid, defensible, of known precision, accuracy, integrity, meet the data quality objectives of the project, and are reportable to TNRCC. One element of the validation process involves evaluating the data again for anomalies. The University of Houston/PBS&J QAO or Project Manager may designate other experienced water quality experts familiar with the water bodies under investigation to perform this evaluation. Any suspected errors or anomalous data must be addressed by the manager of the task associated with the data, before data validation can be completed.

A second element of the validation process is consideration of any findings identified during the annual monitoring systems audit conducted by the TNRCC QAS assigned to the project. Any issues requiring corrective action must be addressed, and the potential impact of these issues on previously collected data will be assessed. Finally, the University of Houston Project Manager, with the concurrence of the University of Houston/PBS&J QAO, validates that the data meet the data quality objectives of the project and are suitable for reporting to TNRCC.

D3 Reconciliation with User Requirements

No decisions will be made by the project team based on the data collected. These data, and data collected by other organizations (e.g., USGS, TNRCC, etc.), will be subsequently analyzed and used by the TNRCC for TMDL development, stream standards modifications, permit decisions, and water quality assessments.

Page 44

Table 4 Data Review, Verification, and Validation Procedures

Data to be Verified	Field Supervisor and Staff	Laboratory Supervisor and Staff	Data Manager	UH Project Manager/ QAO Task *
Collection and analysis techniques consistent with SOPs and QAPP	V	V	√	V
Field QC samples collected for all analytes as prescribed in the TNRCC SWQM Procedures Manual	√			√
Field documentation(e.g. biological, stream habitat) complete	\checkmark			\checkmark
Instrument calibration data complete	V	V		V
Bacteriological records complete	√	√		√ V
Sample documentation complete	V	V	V	V
Field QC results within acceptance limits	V			V
Field QC results attached to DB check list			√	\checkmark
Sample identifications	$\sqrt{}$	$\sqrt{}$	V	$\sqrt{}$
Chain of custody complete/acceptable	$\sqrt{}$	$\sqrt{}$	V	$\sqrt{}$
Sample preservation and handling	$\sqrt{}$	√F, L	V	
Holding times	$\sqrt{}$	√F, L	V	$\sqrt{}$
Instrument calibration data	\checkmark	$\sqrt{}$	√F	√
QC samples analyzed at required frequencies	$\sqrt{}$	$\sqrt{}$	√F	V
QC samples within acceptance limits	V	$\sqrt{}$	√	V
Internal/external standards	V	V	V	V
Instrument readings/printouts	V	V	V	V
Calculations	V		V	√
MALs for lab analyses		√	√	√
Laboratory data verification for integrity, precision, accuracy and validation		V		V

Page 45

Data to be Verified	Field Supervisor and Staff	Laboratory Supervisor and Staff	Data Manager	UH Project Manager/ QAO Task *
Laboratory data reports		$\sqrt{}$	V	$\sqrt{}$
Data entered in required format	$\sqrt{}$	$\sqrt{}$	$\sqrt{}$	V
TNRCC ID number assigned			$\sqrt{}$	V
Valid STORET codes	\checkmark	$\sqrt{}$	V	\checkmark
Absence of transcription error	\checkmark	$\sqrt{}$	V	V
Source codes 1, 2, and 3 used correctly			V	V
Reasonableness of data	V	V	√	V
Electronic submittal errors	√	√	√	V
Sampling and analytical data gaps		$\overline{\qquad}$		
Database Check List				

 $[\]mbox{\sc *University}$ of Houston/PBS&J Project Manager/QAO will monitor only 10% of data for QA/QC purpose

All other entities are required to inspect 100% of the data prior to approval

F = Field (Only field related)

L = Laboratory

Appendix A. Monitoring Plan

MONITORING DATA FOR SOURCE IDENTIFICATION AND QUANTIFICATION

Introduction

Segments 1013 and 1014 of Buffalo Bayou and Segment 1017 of Whiteoak Bayou in Houston, Texas are among the most fecal contaminated water bodies in Texas as indicated by the frequency and magnitude of exceedances of FC-based water quality criteria for contact recreation (see Tables 5a through 5c). The overall project will result in the completion of a Total Maximum Daily Load (TMDL), which will be submitted to TNRCC for approval by the Commission. In addition, the project will also provide several allocation scenarios which the TNRCC will use in the development of an implementation plan in support of the TMDL.

As part of the TMDL project the University of Houston and PBS&J will collect field data on concentrations and dynamics of fecal pathogens in the segments of concern to assess sources, current contamination levels and trends. This QAPP addresses those monitoring activities.

Project Description

The Buffalo and Whiteoak Bayou systems have been and continue to be monitored for a range of conventional water quality parameters. Data from four different sources (USGS, TNRCC, City of Houston PW&E and City of Houston H&HS) were acquired as part of the tasks outlined in the first work order of the bacteria TMDL project (University of Houston and PBS&J, 2000a,b). The monitoring data have been analyzed and indicate that the bayous maintain relatively high concentrations of indicator bacteria even under dry weather conditions when essentially all of the flow is composed of treated and disinfected wastewater. The expectation for disinfected wastewater would be low bacteria levels.

The main reasons for monitoring under the bacteria TMDL project are to understand and document the sources of these elevated bacteria levels so that development of appropriate control measures that can be implemented to bring bacteria levels into compliance with the contact recreation criteria. A second reason is to better understand the processes affecting bacteria concentrations in the bayous, such as survival in the water and sediment, possible regrowth/reactivation, and inputs from the sediments. A third reason for monitoring is to obtain better data to calibrate a water quality model of the system. The monitoring program covered by this QAPP includes four major components:

- Monitoring of point sources under dry-weather conditions,
- Searches for illicit discharges in both sewered and unsewered areas,
- Sampling of moderate runoff in main stream for model calibration, and
- Analyses of concentration dynamics in the bayous.

Revision No. 4 Appendix A

Page 47

Table 5a. Impairments of Designated Uses to be Addressed in this TMDL Project

Basin: San Jacinto River Basin Segment ID: 1013 Segment Name: Buffalo Bayou Tidal

Impaired Uses: Contact Recreation, Aquatic Life Year of Most Recent 305(b) Assessment: 1998

Assessment Period: 1993-1997	Station	0	Exceedances of the Criterion by Month per Total Number of Samples by Month During the 5-year Assessment Period												Average	Suspected Source from 305(b)
Assessment Method	ID	J	F	M	A	M	J	J	A	S	o	N	D			
FC > 400	11345	0/0	3/3	0/0	0/0	3/3	0/0	0/0	4/4	0/0	0/0	2/2	0/0	12/12	35155 cfu/dl	Urban NPS
FC > 400	11351	0/0	1/1	0/0	0/0	1/1	0/0	0/0	1/1	0/0	0/0	0/0	0/0	3/3	59330 cfu/dl	Urban NPS

Table 5b. Impairments of Designated Uses to be Addressed in this TMDL Project

Basin: San Jacinto River Basin Segment ID: 1014 Segment Name: Buffalo Bayou Above Tidal

Impaired Uses: Contact Recreation, Aquatic Life Year of Most Recent 305(b) Assessment: 1998

Assessment Period: 1993-1997	Station												All months	Average	Suspected Source from 305(b)	
Assessment Method	ID	J	F	M	A	M	J	J	A	S	o	N	D			
FC > 400	11358	0/0	1/1	0/0	0/0	2/2	0/0	0/0	1/1	0/0	0/0	0/0	0/0	4/4	17090 cfu/dl	Municipal PS Urban NPS
FC > 400	11362	0/0	2/3	0/0	0/0	3/4	0/0	0/0	4/4	0/0	0/0	1/1	0/0	10/12	17855 cfu/dl	Municipal PS Urban NPS

Table 5c. Impairments of Designated Uses to be Addressed in this TMDL Project

Basin: San Jacinto River Basin Segment ID: 1017 Segment Name: Whiteoak Bayou Above Tidal

Impaired Uses: Contact Recreation, Aquatic Life Year of Most Recent 305(b) Assessment: 1998

Assessment Period: 1993-1997	Station	Exceedances of the Criterion by Month per Total Number of Samples by Month During the 5-year Assessment Period													Average	Suspected Source from 305(b)
Assessment Method	ID	J	F	M	A	M	J	J	A	S	o	N	D			
FC > 400	11387	0/0	2/2	0/0	0/0	3/3	0/0	0/0	3/3	0/0	0/0	1/1	0/0	9/9	19465 cfu/dl	Municipal PS Urban NPS
FC > 400	11388	0/0	1/1	0/0	0/0	1/1	0/0	0/0	1/1	0/0	0/0	0/0	0/0	3/3	56330 cfu/dl	Municipal PS Urban NPS
FC > 400	11398	0/0	1/3	0/0	0/0	3/4	0/0	0/0	3/3	0/0	0/0	0/1	0/0	7/11	7400 cfu/dl	Municipal PS Urban NPS

Point Source Monitoring

In dry weather essentially all of the flow in these urban bayous is from point source discharges. Therefore, our search for understanding of water bacteria levels will start with these water sources. These discharges are required to maintain a chlorine residual of 1 mg/L for at least 20 minutes and plants larger than 1 MGD are required to dechlorinate down to a concentration of <0.01 mg/L. These requirements must be met in wet weather conditions when the plants are at maximum permitted flows (these requirements must be met at all times, although they are most difficult to meet during wet weather events). In practice, the chlorine contact time is much longer in dry weather and low flows. If all of these requirements were met, in theory there should be very low levels of indicator bacteria in the effluents. Since the effluents essentially are the bayou flows in dry weather, low bacteria levels should be the norm. However, sampling done as part of a recent Greens Bayou Intensive Survey (City of Houston Public Works and Engineering Department, 1999) showed discharged FC concentrations higher than 200 cfu/dL, with 2 of 12 samples exhibiting FC counts near 10,000 cfu/dL. Similarly, data from inspections conducted by HCPC between 1998 and 2000 showed that 25 out of 29 measurements (for a total of 18 small plants in the Buffalo and Whiteoak Bayous) exceeded the limit of 200 cfu/dL, with 14 samples showing FC levels higher than 10,000 cfu/dL.

One of the problems with smaller plants may be poor control over the chlorination process. While the City of Houston (COH) plants in these stream segments have a sophisticated system to regulate the dosage of disinfectant and the sodium bisulfite dechlorination agent, that is not true for many of the smaller facilities. That lack of automatic control, plus the fact that these plants are checked infrequently, may mean that high levels of indicator bacteria are not at all uncommon. In Whiteoak and Buffalo, there are 76 and 44 domestic WWTP with flows lower than 1 MGD, respectively releasing close to 38 and 12% of the median flow in these bayous (45 and 90 cfs, respectively).

To investigate and document this situation a program of point source monitoring that will include early morning and mid-morning sampling of a broad range of plants over the course of a 6-month period is proposed. This sampling effort will cover all the minor domestic wastewater treatment plants (flow less than 1 MGD) discharging to Buffalo and Whiteoak Bayous. A total of 120 wastewater dischargers will be sampled (see Appendix B for sampling location and scheduling).

A sampling crew (2 people) will leave early in the morning to sample two small plants by 0800, and then will deliver the samples to the lab. This round of samples will characterize the discharge at the low point in the diurnal flow cycle. Samples will be collected at a point following the chlorine contact chamber as it is flowing over the weir. The sampling will include doing a field measurement of residual chlorine, estimating the flow, estimating conventional chemical parameters (see Table 1) and collecting water samples for laboratory analyses. Each of the samples will be analyzed for FC and EC along with TSS at the University of Houston laboratory. The methods that will be employed by the University of Houston lab are:

FC	M9222D	Membrane filtration
EC	IDEXX	IDEXX MPN Quantitray 2000
Total Suspended Solids	E160.2	Filtration dry weight

The EC analyses will be performed using the IDEXX Colilert method that is a separate test from the FC analysis, which may result in EC counts higher than the FC data.

To sample the high flow period, the crew will repeat the trip in mid-morning, getting the samples to the lab by early afternoon. This process will continue during dry weather until all the plants had been sampled and those plants that showed high bacteria values had been resampled (the highest 20).

Illicit Discharges

This component will include sampling of stormsewers discharging into the bayous under dry-weather conditions to identify illicit discharges to the bayous via stormsewers that may come from a sanitary sewer problem of some type or outright unpermitted wastewater discharges. This work will include review of monitoring in the bayous to identify locations where a sudden increase in indicator bacteria occurs, and checking on stormsewers to find flow. In dry weather the stormsewers should be dry so flow could be an illicit discharge.

In general terms, this effort will be undertaken by two-person teams that will work in dry weather only. They will be equipped with maps of the stormsewer system and the locations of the outfalls. Prior to sampling the teams will walk along the bayous and main tributaries to perform reconnaissance of the stormsewer infrastructure. During this reconnaissance effort, the teams will identify how many outfalls are discharging into the bayous and confirm their presence in the GIMS database so that their properties can be determined (diameter, length, material, and age). If an outfall is not found in the GIMS maps, it will be noted with its diameter and material. Geographic locations will be verified using Global Positioning System (GPS) to the extent possible and practical. GPS activities will be conducted using a Motorola LGT 1000 equipped with Starlink MRB-2A radio beacon receiver to correct for selective availability. This equipment has a real time correction providing accuracy of 5 meters.

Once all the outfalls have been located and identified, the sampling activities will start. The sampling points will be based on locatable outfalls discharging under dry-weather conditions. A maximum of 60 points will be sampled for this component. For sampling in the Buffalo Bayou, a canoe will be used to both expand the sampling area and insure detailed coverage. It is expected that in a seven-day period, the area from Eldridge Parkway Bridge to Shepherd Street Bridge could be covered and with a canoe to transport sampling equipment and personnel, 98% of all the outfalls could be located and sampled. Further, for sampling of the remaining segments of Buffalo Bayou as well as sampling of Whiteoak Bayous and the tributaries to both bayous, the crews will walk pilot areas determined after field reconnaissance. The criteria to select those areas include diameter of the stormsewers (sampling will focus mainly on large diameter lines since they represent large drainage areas and this should offer the most coverage for potential dry weather flow) and age of the lines. Appendix B contains a map of the preliminary pilot areas.

The sampling crew will first determine if there is flow, and then determine if there is a residual chlorine level indicating a drinking water leak of some type. If it is chlorinated water, no further work will be done other than the flow estimate. If the flow is significant it should be reported as a water leak. If the water is not chlorinated, two different criteria will be applied to determine whether samples will be collected for

bacterial and TSS analyses. First, the presence of ammonia using a field test kit will be assumed as an indicator of fecal contamination and, therefore, samples will be collected. Second, the observation of Sphaerotilus will be considered a trigger for sample collection. Sphaerotilus is a non-fungus aerobic bacteria that prefers habitats with slowly running fresh water contaminated with sewage and grows attached to submerged plants, rods, and other solid objects. Sphaerotilus will appear submerged in the flow and attached to a hard surface. The color of the growth is a gray to white hue (see Standard Methods for additional information). The sampling crew will also measure the approximate dimensions of the flow and estimate the velocity. The samples will be iced and the team will move to the next stormsewer outfall. By 1400 the team will head to the University of Houston lab arriving in time for the bacteria samples to begin filtration.

Based on available data, two preliminary pilot areas have been identified (See Appendix B); however, these sampling areas may change as the field recognition is conducted. Appendix B includes the sampling schedule for the illicit discharges monitoring.

Runoff Event Monitoring

Concentrations of indicator bacteria in runoff tend to be very large, several orders of magnitude greater than the criteria developed for swimming areas in fair weather. For safety as well as bacteria reasons, the main project emphasis needs to be on lower flow conditions. However, there is also a need to consider some runoff events simply because they are often small enough to have a very small effect on flow in the main stem of the bayous, and thus become part of the "background" levels. Accordingly, this monitoring program will include at least three smaller rain events in each watershed.

Runoff event monitoring will be conducted at the USGS locations on each bayou (e.g. Whiteoak Bayou at Heights and Buffalo at West Belt or Piney Point) so that flow data will be available for acquisition (see Section B9 for data validation). USGS Station 08074200 (Whiteoak at Alabonson) appears to be defective because its record shows a consistent base flow of about 400 cfs; therefore, this station is discarded for runoff sampling. Nor will Buffalo at Mckee (08074610) and Whiteoak at Main (08074598) be sampled as they are stage record gages and flow is not monitored. The sampling crews will deploy to the USGS gages and collect samples with pre-sterilized buckets from the bridges. Two non-USGS stations on Whiteoak Bayou and one on Buffalo Bayou will also be sampled and flow will be measured. Samples will be analyzed for conventional parameters in the field and for FC and EC by North Water District Laboratory Services. In parallel, we will obtain rainfall data from the HCFCD network as well as the City stations.

Events will be limited to those that could be sampled during daylight hours. Samples will be collected as soon as possible on the rising limb of the hydrograph, and then at roughly 3-hr intervals till dark. To track the expected decline in bacteria levels on the falling limb, samples will be collected the next morning and then at 12-hr intervals for the next two days. See Appendix B for the location of the monitoring sites.

Concentration Dynamics in the Bayous

Once a disinfected discharge enters the bayous it becomes subject to a very different set of environmental conditions. After chlorine has been eliminated by contact with organic matter and sediments, it may be possible for indicator bacteria to either reactivate (assuming they were stunned but

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 4
Appendix A
Page 53

not killed by the disinfectant) or regrow (assuming some cells survived and there was sufficient nutrients to support growth of the cells that also perform well on the FC or EC tests). Either mechanism, or some other mechanism not well defined, can result in higher stream levels than are typically seen in wastewater effluents.

To study these regrowth or resupply dynamics, we propose a series of field and laboratory experiments where we seek to isolate various mechanisms and document changes and rates. There will be three main elements: in-stream dynamics (normal rates of change), rates of change influenced by freshwater (regrowth), and rates of change affected by resupply from stream sediments.

The in-stream dynamics tests will comprise a series of *in-situ* chambers placed in Buffalo and Whiteoak bayous. The chambers will be attached to round floats so the edge of the chamber is above the water surface, but the water inside the chamber will be exposed to the air and true ambient conditions. The floats will be tethered or anchored so that they could be easily sampled. To avoid contamination from bird droppings, the floats will be fitted with a clear plastic "umbrella". It is recognized that if a significant flow increase occurs, the containers will be lost. Duplicate EC subsamples will be collected from each chamber the first morning and evening after installation of the chambers and the morning and evening following installation. In addition, routine probe parameters will be monitored from the collected samples. Each set of chambers will have a control, either in the ambient water (water collected from the stream approximately tracking the water initially sampled as it moved downstream under the influence of sediment and intervening sources) or a chamber without additions. A DI water blank will be prepared for each batch of bags. Chamber conditions will be varied to further examine the exact dynamics occurring at the bayous. Some of the variations in chamber conditions are as follows: post-rain versus dry conditions, effluent mixes versus natural site water to assess regrowth, and effluent or site water mixed with channel sediments to obtain an indication of the effect of solids content on rates. Tracking the bagged and water samples will provide an indication of the growth and dieoff rates as influenced by daynight light intensity, sediment levels, organic strength and isolation from the sediment. Appendix B includes a map with the proposed locations for this component. We expect this testing process to evolve with model calibration and development, with model needs guiding the testing decisions. Data obtained from the dynamics studies will not be considered ambient monitoring and will not be submitted to the TNRCC database.

For the regrowth studies, bayou water samples will be collected under dry weather conditions from upstream, effluent and from the mixing zone downstream from four large domestic wastewater treatment plants (preliminary locations are mapped on Appendix B). The samples will be collected in new plastic garbage sacks (presumed to be free of significant bacterial contamination). All samples will be checked in the field for residual chlorine. Dechlorination will be performed if necessary. An aliquot of each water sample will be analyzed for N and P forms, TOC, CBOD₅, and TSS by North Water District Laboratory Services. Duplicate subsamples will be collected at the start and tested for bacterial levels. The collected effluent and upstream water will be mixed together to simulate the downstream mixing zone. This would yield two sets of bottles, with one set from the downstream mixing zone and one simulating the same conditions. The samples will be taken back to the laboratory where conditions such as sunlight and temperature could be controlled and gentle mixing will be provided with a small flow of air. Subsamples will then be withdrawn after a one to two day period and analyzed for EC levels with

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP
Revision No. 4
Appendix A
Page 54

IDEXX. If significant increases in bacteria concentrations are noted, regrowth of shocked cells may be occurring. If the mixing zone concentrations increases, and no bacteria are detected in the effluent, this might suggest that nutrients in the effluent were stimulating growth in bacteria from upstream.

Resupply of bacteria from sediments will be assessed by collecting sediment grab samples at locations removed from point sources and mixing a predetermined amount (1 mL, 10 mL, and 100 mL) of sediment unconsolidated surface mud with 1L of previously collected and autoclaved stream water. Three aliquots will be made from each water-sediment mixture. A control using DI water will be used as well. The water-sediment mixtures will be shaken and then an initial portion of each sample will be poured off for EC analysis. The bottles will be maintained near bayou water temperatures in low light conditions and resampled after the first and second days for EC and routine probe parameters. It is expected that differences in the initial level of bacteria concentrations will be proportional to the initial sediment addition. Further increases in bacteria concentrations following incubation would be evidence of bacteria resupply. The results of the experiment should not be affected by low dissolved oxygen occurring after 1-2 days. Additional tests will be conducted by allowing the top of the bottles to be open to ensure DO similar to bayou levels, and EC analysis will be conducted again.

Standard statistical tests for means and variance using Excel spreadsheets will be used to analyze the data to identify significant trends in data obtained from the dynamics tests.

Finally, to determine baseline sediment concentrations, EC levels will be measured in up to 20 sediment samples. Analyses of sediment samples will be conducted only if the results from the dynamics test show that resuspension is a significant source of EC into the Buffalo and Whiteoak Bayous. Preliminary locations for sediment sampling are included in Appendix B. This locations, however, may change depending on model segmentation and needs. In addition to EC analysis, sediment samples will be analyzed to obtain particle size data.

Data Analysis

The product of the sampling exercise will be a quantification of FC, EC, and TSS as well as conventional field parameters. We will then be able to analyze data to assess potential sources of contamination as well as the weather- and time-based trends, and possible correlations between bacterial counts and other chemical parameters, and to set-up and calibrate a fate and transport model of fecal pathogens in the Buffalo and Whiteoak Bayous.

Data Submittal

The following data will be submitted to be entered into the TRACS database:

Table 6. Data to be	e included into '	TRACS
		Project Component

		-			i				Pa
		I.1	I.2	п	Ш	IV.1	IV.2	IV.3	IV.4
Field Parameters									
pH	pH units	N	N	N	Y	N	N	N	N/A
DO	mg/L	N	N	N	Y	N	N	N	N/A
Conductivity	mS/cm	N	N	N	Y	N	N	N	N/A
Temperature	° Celcius	N	N	N	Y	N	N	N	N/A
Flow	cfs	N	N	N	Y	N	N	N	N/A
Flow Severity	1-no flow, 2-low, 3-normal, 4- flood, 5-high, 6-dry	N	N	N	Y	N	N	N	N/A
Conventional Parame	eters								
TSS	mg/L	N	N	N	Y	N/A	N	N/A	N/A
TOC	mg/L	N/A	N/A	N/A	N/A	N/A	N	N/A	N/A
Residual chlorine	mg/L	N	N	N	N/A	N/A	N	N/A	N/A
Ammonia-N	mg/L	N	N	N	N/A	N/A	N/A	N/A	N/A
o-Phosphorous	mg/L	N	N	N	N	N	N	N	N/A
Turbidity	NTU	N	N	N	Y	N	N	N	N/A
CBOD ₅	mg/L	N/A	N/A	N/A	N/A	N/A	N	N/A	N/A
FC in water	cfu/100 mL	N	N	N	Y	N/A	N/A	N/A	N/A
EC in water	MPN/100 mL	N	N	N	Y	N	N	N	N/A
EC in sediment ³	cfu/100 g	N/A	N/A	N/A	N/A	N/A	N/A	N	Y
Sediment grain size analysis	% dry weight 0.0039-0.0625 mm	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Y
Sediment grain size analysis	% dry weight < 0.0039 mm	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Y
Sediment grain size % dry weight analysis 0.0625- 2 mm		N/A	N/A	N/A	N/A	N/A	N/A	N/A	Y

N = No; Y = Yes; N/A = not applicable (parameter will not be measured)

Appendix E outlines the requirements for data submittal to the TRACS database.

Schedule

Testing will begin in July 2001. Sampling and testing will continue for 9 months. A report describing the testing procedures and results will be prepared two months after testing is finished or as specified in the approved work order. Figure 2 depicts the proposed timeline for the work done under this QAPP.

References

- City of Houston Public Works and Engineering Department. (1999). "Greens Bayou Intensive Survey and Wasteload Evaluation Final Report." Prepared for the Texas Clean Rivers Program, Houston-Galveston Area Council, Houston, TX.
- University of Houston and PBS&J. (2000a). "Total Maximum Daily Load for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou Quarterly Report No. 1." Prepared for the Texas Natural Conservation Commission, Houston, TX.
- University of Houston and PBS&J. (2000b). "Total Maximum Daily Load for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou Quarterly Report No. 2." Prepared for the Texas Natural Conservation Commission, Houston, TX.

COMPONENT Week starting on	Jul-01 2 9 16 23 30	Aug-01	Sep-01	Oct-01	Nov-01	Dec-01	Jan-01	Feb-02	Mar-02
I.1 Point Sources - First Round					3 12 17 20		7 17 21 20	7 11 10 20	7 11 10 22
I.2 Point Sources - Second Round									
II. Illegal Discharges									
III. Runoff									,
IV.1 Dynamics									
IV.2 Dynamics - Regrowth									
IV.3 Dynamics - Resuspension									
IV.4 Dynamics - Sediment Baseline									
Reporting									

Figure 2. Monitoring Plan Timeline

Appendix B. Sampling Process Design and Monitoring Schedule

Sample Design Rationale

The sample design is based on the program requirements of the Total Maximum Daily Load Program. The TNRCC, and the University of Houston/PBS&J through contract with the TNRCC, has been tasked with providing data and information to characterize water quality conditions, to identify the presence or absence of impairments of designated water body uses, and to support water quality modeling, site-specific water quality standard revisions, the load allocation, and other TMDL data and information needs. As part of the TMDL stakeholder involvement process, the University of Houston coordinates closely with the TNRCC and other TMDL participants to ensure an adequate water monitoring strategy to supply informational needs for modeling, assessment, load allocation, and decision-making.

Site Selection Criteria

This data collection effort involves monitoring point and non-point source data for the purpose of aiding TMDL development. This study will collect ambient and non-ambient data, a small portion of which will be entered to the statewide surface water quality database. The criteria employed for selecting sites included: presence on the 303(d) list, probability of elevated FC and EC concentrations, proximity to USGS stations (runoff samples), representativeness of particular land uses in a watershed, accessibility and safety. All monitoring activities will be developed in coordination with the TNRCC.

Monitoring Sites

A list of the stations to be sampled under this QAPP is included in Table 7, and Figures 3 to 7 show the locations of the sampling sites.

Critical vs. non-critical measurements

FC and EC results are critical to the success of the TMDL project.

Monitoring Schedule Buffalo Bayou and White Oak Bayou TMDL Project Segment ID: 1013, 1014 and 1017

-		Segment 1D: 1013, 1014 and 1017	·					1				Monitorin	g frequenci	es (per monitorir	ng program)			
Sampling	Segment	Site description	Permit number/	Sample ID	Scheduled Date	Completed Date	SC1/	Prog					8 1	Wet	Residual		CBOD ₅	
Componenta			Station ID				SC2	Code	Flow	FC	EC	TSS	TOC	chemistryb	chlorine	Ammonia		Grain size
I.1	1017	HARRIS CO FWSD 061	10876-002	S2	07/24	07/24	tbd/UH	DL	2 ^c	2°	2°	2°		2 ^c	2 ^c			
I.1	1017	HARRIS CO MUD 170	12121-001	S4	07/24	07/24	tbd/UH tbd/UH	DL	2°	2°	2° 2°	2°		2°	2 ^c 2 ^c			
I.1 I.1	1017 1017	HARRIS CO FWSD 061 TIFCO INDUSTRIES	10876-001 12465-001	S1 S3	07/24 07/25	07/24	tbd/UH	DL DL	2° 2°	2° 2°	2°	2° 2°		2 ^c 2 ^c	2°			
I.1	1017	NORTHW HARRIS CO MUD 029	12795-001	S5	07/26	07/26	tbd/UH	DL	2 ^e	2°	2°	2 ^c		2°	2 ^c			
I.1	1017	HARRIS CO MUD 006	11273-001	S6	07/26	07/26	tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	WEST HARRIS CO MUD 010	14072-001	S7	07/27		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1017	SUPERIOR DERRICK SERV	12443-001	S8	07/27	07/27	tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1017	SMITH, WILLIAM - William Smith Mobile Home F	12573-001	S15	07/27	07/27	tbd/UH	DL	2 ^e	2 ^e	2 ^e	2 ^e		2 ^c	2 ^c			
I.1	1017	WHITE OAK BEND MUD	11979-002	S9	07/30	07/30	tbd/UH	DL	2 ^e	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1017	REID ROAD MUD 001	11563-001	S10	07/30	07/30	tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1017	WEST HARRIS CO MUD 21 WWTF	13623-001	S12	07/31	07/31	tbd/UH	DL	2 ^c	2°	2°	2°		2°	2 ^c			
I.1	1017	RIEDEL, ANTHONY	13939-001	S13	08/01		tbd/UH	DL	2°	2°	2°	2 ^c		2°	2°			
I.1	1017	HERON LAKE ESTATES WWTF	13433-001	S11	08/01 08/01	08/01	tbd/UH	DL	2°	2° 2°	2°	2 ^c 2 ^c		2°	2° 2°			
I.1 I.1	1017 1017	ABB VETCO GRAY INC CREEKSIDE UTILITIES	11651-001 11375-001	S14 S26	08/01	08/01	tbd/UH tbd/UH	DL DL	2° 2°	2°	2° 2°	2°		2 ^c 2 ^c	2°			
I.1	1017	HANOVER LAND CO.	11797-001	S16	08/02	06/01	tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	CB&I CONSTRUCTORS, INC.	11389-001	S19	08/02	08/02	tbd/UH	DL	2°	2°	2 ^c	2°		2 ^c	2°			
I.1	1017	KONECRANES LANDEL	13912-001	S20	08/02	08/02	tbd/UH	DL	2 ^e	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	OCEANEERING INTL. INC.	12466-001	S39	08/03	08/03	tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	WEATHERFORD SPENCER RD WWTF	14070-001	S41	08/03	08/03	tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1017	CHAMP'S WATER CO.	11005-001	S17	08/06		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1017	HARRIS CO MUD #119	12714-001	S18	08/06		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	WYMAN-GORDON FORGINGS	01402-002	S51	08/07	08/07	tbd/UH	DL	2 ^e	2 ^e	2 ^e	2 ^e		2 ^c	2 ^c			
I.1	1014	WEST HARRIS CO MUD #15	12223-001	S52	08/07	08/07	tbd/UH	DL	2 ^e	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1017	SMITH, BOB	13509-001	S22	08/08		tbd/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS CO MUD 250	12685-001	S65	08/08	08/08	tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS CO MUD 155	12726-001	S60	08/08	08/08	tbd/UH	DL	2 ^c	2°	2°	2 ^c		2°	2 ^c			
I.1	1017	C&P UTILITIES	12342-001	S21	08/08		tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	MOORPARK VILLAGE	13727-001	S24	08/09 08/09		tbd/UH	DL	2° 2°	2° 2°	2° 2°	2 ^c 2 ^c		2° 2°	2 ^c 2 ^c			
I.1 I.1	1017 1014	HARRIS CO METRO UD CHIMNEY HILL MUD	13673-001 12304-001	S23 S62	08/09	08/09	tbd/UH tbd/UH	DL	2°	2°	2°	2° 2°		2° 2°	2° 2°			
I.1	1014	HARRIS CO MUD 102	11523-001	S72	08/10	08/10	tbd/UH	DL DL	2°	2°	2°	2°		2°	2°			
I.1	1014	HORSEPEN BAYOU MUD	12128-001	S70	08/10	08/10	tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	ROLLING FORK PUD	11188-001	S25	08/13	00/10	tbd/UH	DL	2 ^e	2 ^e	2°	2°		2°	2 ^c			
I.1	1014	HARRIS CO MUD 167	12834-001	S56	08/13	08/13	tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	MAYDE CREEK MUD	11969-001	S83	08/13	08/13	tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1017	HARRIS CO MUD 130	12574-001	S33	08/14		tbd/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^c	2 ^c			
I.1	1017	HARRIS CO MUD 023	11485-001	S27	08/14		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1017	SUNBELT FWSD	11670-001	S28	08/14		tbd/UH	DL	2 ^e	2 ^e	2 ^e	2 ^e		2 ^c	2 ^c			
I.1	1014	NORTHWEST HARRIS CO MUD 16	11935-001	S77	08/14		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1017	RESTAURANT SERVICE	13983-001	S30	08/15		tbd/UH	DL	2 ^e	2 ^e	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	FRY ROAD MUD	11989-001	S84	08/15		tbd/UH	DL	2°	2°	2°	2 ^c		2°	2°			
I.1	1014	WEST HARRIS CO MUD 017	12247-001	S82	08/15		tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	MCDONALDS CORP.	13807-001	S29	08/15		tbd/UH	DL	2°	2°	2°	2° 2°		2°	2° 2°			
I.1 I.1	1017 1017	WEST HARRIS CO MUD 011 VANCOUVER MANAGEMENT	13689-001 11051-001	S32 S31	08/16 08/16		tbd/UH tbd/UH	DL DL	2° 2°	2° 2°	2° 2°	2° 2°		2° 2°	2° 2°			
I.1 I.1	1017	HARRIS CO MUD 247	12681-001	S31 S34	08/16		tbd/UH tbd/UH	DL	2°	2°	2°	2°		2° 2°	2° 2°			
I.1	1017	NCI BUILDING SYSTEMS	12552-001	S35	08/20		tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	NCI BUILDING SYSTEMS	12552-001	S36	08/21		tbd/UH	DL	2°	2°	2°	2 ^c		2°	2°			
I.1	1014	ADDICKS UD	11696-002	S89	08/22		tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	COOPER CAMERON CORP.	13578-001	S38	08/22		tbd/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2 ^c	2 ^c			
I.1	1014	WEST PARK MUD	12346-001	S88	08/22		tbd/UH	DL	2 ^c	2°	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	ADAMOLI, JAMES	12811-001	S37	08/22		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	ROBINSON, J. WAYNE	12830-001	S40	08/23		tbd/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2°	2 ^c			
I.1	1017	AQUASOURCE UTILITY	11193-001	S42	08/27		tbd/UH	DL	2 ^c	2°	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1017	HOUSTON-WESTWAY UD	10495-139	S44	08/28		tbd/UH	DL	2 ^e	2 ^e	2 ^e	2 ^c		2°	2 ^c			
I.1	1017	AQUASOURCE UTILITY	12222-001	S43	08/28		tbd/UH	DL	2°	2°	2°	2°		2°	2 ^c			
I.1	1017	TRAMMELL CROW	13996-001	S46	08/29		tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1017	FAIRBANKS PLAZA SHOPPING	12139-001	S45	08/29		tbd/UH	DL	2°	2°	2°	2° 2°		2 ^c 2 ^c	2°			
I.1	1014	HARRIS CO MUD 157	11906-001	S47	08/30	I	tbd/UH	DL	2 ^e	2-	2 ^c	2"		I 2"	2 ^c	l	ı l	

Monitoring Schedule Buffalo Bayou and White Oak Bayou TMDL Project Segment ID: 1013, 1014 and 1017

			ъ	Ī								Monitori	ng frequenci	ies (per monitori	ng program)			
Sampling	Segment	Site description	Permit number/	Sample ID	Scheduled Date	Completed Date	SC1/	Prog						Wet	Residual		CBOD ₅	
Componenta			Station ID				SC2	Code	Flow	FC	EC	TSS	TOC	chemistryb	chlorine	Ammonia		Grain size
I.1	1014	HARRIS COJUVENILE BOOT CAMP	13921-001	S48	08/30		tbd/UH	DL	2°	2°	2°	2°		2 ^c	2°			
I.1 I.1	1014 1014	HARRIS CO MUD 196 REMINGTON MUD 001	12447-001 13328-001	S49 S50	09/03 09/03		tbd/UH tbd/UH	DL DL	2°	2° 2°	2° 2°	2° 2°		2 ^c 2 ^c	2 ^c 2 ^c			
									2° 2°						2° 2°			
I.1	1014 1014	NORTHW HARRIS CO MUD 012	11991-001 11792-002	S54	09/05		tbd/UH tbd/UH	DL	2°	2° 2°	2° 2°	2° 2°		2°	2°			
I.1 I.1	1014	HARRIS CO MUD 105 HARRIS CO MUD 127	12209-001	S53 S55	09/05 09/06		tbd/UH	DL DL	2°	2°	2°	2°		2°	2°			
I.1	1014	HARRIS CO MUD 284	12949-001	S58	09/00		tbd/UH	DL	2°	2°	2°	2°		2°	2 ^c			
I.1	1014	ROLLING CREEK UD	12949-001	S57	09/10		tbd/UH	DL	2°	2°	2°	2°		2°	2°			
I.1	1014	HARRIS CO MUD #149	11836-001	S59	09/10		tbd/UH	DL	2 ^c	2°	2°	2°		2°	2 ^c			
I.1	1014	SPENCER ROAD PUD	11472-001	S61	09/11		tbd/UH	DL	2°	2°	2°	2°		2 ^c	2°			
I.1	1014	SASSON, ELI	11414-001	S63	09/12		tbd/UH	DL	2 ^c	2 ^e	2 ^e	2°		2°	2 ^c			
I.1	1014	VERRY, RICHARD	12310-001	S64	09/13		tbd/UH	DL	2 ^c	2°	2 ^e	2°		2°	2 ^c			
I.1	1014	PETERSEN, JAMES	12398-001	S66	09/17		tbd/UH	DL	2 ^c	2°	2 ^c	2°		2°	2 ^c			
I.1	1014	529 #35, LTD	13484-001	S67	09/18		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2°		2°	2 ^c			
I.1	1014	VARCO SHAFFER	03994-001	S68	09/18		tbd/UH	DL	2 ^c	2°	2°	2 ^c		2°	2°			
1.1	1014	AIR LIQUIDE AMERICA	13959-001	S69	09/19		tbd/UH	DL	2 ^c	2 ^e	2 ^e	2 ^c		2 ^c	2 ^c			
I.1	1014	TOSHIBA INTERNATIONAL	03153-002	S71	09/20		tbd/UH	DL	2 ^c	2 ^e	2 ^c	2°		2°	2 ^c			
I.1	1014	HARRIS CO MUD 185	12124-001	S73	09/24		tbd/UH	DL	2 ^c	2°	2 ^e	2 ^c		2°	2 ^c			
I.1	1014	HARRIS CO MUD 276	12927-001	S74	09/24		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2°		2°	2 ^c			
I.1	1014	FRIEDMAN, STEPHEN	13778-001	S75	09/25		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	LANGHAM CREEK UD	11682-001	S76	09/25		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS CO MUD 166,257,276	12474-001	S78	09/26		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	WEST HARRIS CO MUD 007	12140-001	S80	09/27		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS CO MUD 071	11917-001	S79	09/27		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	TEX-SUN PARKS	12189-001	S81	10/01		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS CO MUD 238	12802-001	S86	10/03		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	KATY ISD	12110-001	S85	10/03		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	WESTLAKE MUD 001	11284-001	S87	10/04		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	WEST HOUSTON AIRPORT	12516-001	S90	10/08		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	WESTON MUD	12412-001	S92	10/09		tbd/UH	DL	2^{c}	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	WILLIAMSBURG REGIONAL	11598-001	S91	10/09		tbd/UH	DL	2^{c}	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	TRANSWESTERN KATY FREEWAY	11632-001	S94	10/10		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS COUNTY-BEAR CK	11883-001	S93	10/10		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	CASTLEWOOD MUD	12356-001	S95	10/11		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS CO. MUD #345	12682-001	S96	10/11		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HOUSTON-PARK TEN	10495-135	S97	10/12		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS CO MUD 216	12406-001	S98	10/12		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	GREEN TRAILS MUD	10932-001	S99	10/15		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	NOTTINGHAM COUNTRY MUD	12427-001	S100	10/15		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	NOTTINGHAM COUNTRY MUD (WTP)	12233-001	S102	10/16		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	HARRIS COUNTY-CULLEN	12355-001	S101	10/16		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2°	2 ^c			
I.1	1014	ASEP AMERICA, INC.	12132-001	S103	10/17		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	AIVAZIAN, GEORGE	13764-001	S104	10/17		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	BAYOU CLUB OF HOUSTON	12289-001	S105	10/18		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c		1	1
I.1	1017	TOWER MANAGEMENT SERV	12479-001	S106	10/18		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2 ^c		2 ^c	2 ^c		1	1
I.1	1017	WHITE OAK OWNERS ASSOC.	12370-001	S107	10/22		tbd/UH	DL	2 ^c	2°	2 ^c	2 ^c		2 ^c	2 ^c			
I.1	1014	FORT BEND CO MUD 034	12498-001	S108	10/22		tbd/UH	DL	2 ^c	2°	2 ^c	2 ^c		2 ^c	2 ^c		1	1
I.1	1014	COOPER CAMERON CORP	12805-001	S110	10/23		tbd/UH	DL	2 ^c	2 ^c	2 ^c	2°		2 ^c	2°			
I.1	1014	FORT BEND CO MUD 037	13775-001	S109	10/23		tbd/UH	DL	2 ^c	2°	2 ^c	2 ^c		2 ^c	2 ^c		1	1
I.1	1014	HARRIS-FT BEND CO MUD	12298-001	S112	10/24		tbd/UH	DL	2 ^c	2°	2 ^c	2 ^c		2 ^c	2 ^c		1	1
I.1	1014	HARRIS-FORT BEND COS MUD	13228-001	S111	10/24		tbd/UH	DL	2°	2°	2°	2°		2 ^c	2 ^c			
I.1	1014	CINCO MUD 001	12858-001	S114	10/25		tbd/UH	DL	2 ^c	2°	2°	2°		2 ^c	2°		1	1
I.1	1014	BIG OAKS MUD	13674-001	S113	10/25		tbd/UH	DL	2 ^c	2°	2°	2°		2 ^c	2°		1	1
I.1	1014	FT BEND CO MUD 050	13245-001	S116	10/29		tbd/UH	DL	2°	2°	2°	2°		2 ^c	2°			
I.1	1014	RLG REALTY HOLDINGS	13021-001	S115	10/29		tbd/UH	DL	2°	2°	2°	2°		2°	2°		1	1
I.1	1014	GRAND LAKES MUD #4	13172-002	S117	10/30		tbd/UH	DL	2°	2°	2°	2°		2 ^c	2°		1	1
I.1	1014	CINCO MUD 001	13558-001	S118	10/30		tbd/UH	DL	2°	2°	2°	2 ^c		2°	2°			
I.1	1014	GINTER REAL ESTATE	13218-001	S120	10/31		tbd/UH	DL	2°	2°	2°	2 ^c		2 ^c	2°	-		
I.1	1014	HOUSTON AREA DEVELOPMENT	14011-001	S119	10/31	12/00	tbd/UH	DL	2°	2°	2°	2 ^c		2 ^c	2°	-		
I.2	1017	20 POINT SOURCES (HIGHEST LEVELS)	tbd	T1 / T20	11/01	12/08	tbd/UH	DL	2						2			<u> </u>
II	1017	PILOT AREA 1 - WHITEOAK	30 locations tbd	I1 to I30	09/03	02/01	tbd/UH	DL	1 dry	1 dry	1 dry	1 dry	l	1 dry	1 dry	1 dry	I	l


Monitoring Schedule Buffalo Bayou and White Oak Bayou TMDL Project Segment ID: 1013, 1014 and 1017


	Permit				6-111	Completed					Monitoring frequencies (per monitoring program)							
Sampling Component ^a	Segment	Site description	number/ Station ID	Sample ID	Scheduled Date	Completed Date	SC1/ SC2	Prog Code	Flow	FC	EC	TSS	TOC	Wet chemistry ^b	Residual chlorine	Ammonia	CBOD ₅	Grain size
II	1014	PILOT AREA 2 - BUFFALO	30 locations tbd	I31 to I60	09/03	02/01	tbd/UH	DL	1 dry	1 dry	1 dry	1 dry	100	1 dry	1 dry	1 dry		Grain Size
III	1017	W. TIDWELL AVE.	15831	R7	07/02	08/31	tbd/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet	rury	rury		
III	1014	SHEPHERD DR.	11351	R4	07/02	08/31	tbd/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet				
III	1017	HEIGHTS BLVD.	11387	R5	07/02	08/31	tbd/PB	DL	10 1101	10 wet	10 wet	10 wet		10 wet				
III	1017	HEIGHTS BLVD.	11387	R5	07/02	08/31	GS/GS	DL	10 wet									
III	1014	PINEY POINT RD	11358	R3	07/02	08/31	tbd/PB	DL		10 wet	10 wet	10 wet		10 wet				
III	1014	PINEY POINT RD	11358	R3	07/02	08/31	GS/GS	DL	10 wet									
III	1014	WEST BELT	11360	R2	07/02	08/31	GS/GS	DL	10 wet									
III	1014	DAIRY ASHFORD RD.	11362	R1	07/02	08/31	tbd/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet				
III	1017	JONES RD.	11398	R6	07/02	08/31	tbd/PB	DL	10 wet	10 wet	10 wet	10 wet		10 wet				
III	1014	WEST BELT	11360	R2	07/02	08/31	tbd/PB	DL		10 wet	10 wet	10 wet		10 wet				
IV.1	1017	JONES RD.	11398	D3	08/06	12/21	tbd/PB	DL			5 dry			5 dry				
IV.1	1014	WEST BELT	11360	D2	08/06	12/21	tbd/PB	DL			5 dry			5 dry				
IV.1	1014	SAN FELIPE ST.	11357	D1	08/06	12/21	tbd/PB	DL			5 dry			5 dry				
IV.1	1017	WATONGA	15830	D4	08/06	12/21	tbd/PB	DL			5 dry			5 dry				
IV.2	1014	HOUSTON-WEST DISTRICT WWTP	10495-030	RG4	08/06	12/21	tbd/PB	DL	3 dry		3 dry	1 dry	1 dry		3 dry		1 dry	
IV.2	1017	HARRIS COUNTY MUD 170	12121-001	RG1	08/06	12/21	tbd/PB	DL	3 dry		3 dry	1 dry	1 dry		3 dry		1 dry	
IV.2	1014	HOUSTON-NORTHWEST WWTP	10495-076	RG2	08/06	12/21	tbd/PB	DL	3 dry		3 dry	1 dry	1 dry		3 dry		1 dry	
IV.2	1017	MEMORIAL VILLAGES WA	10584-001	RG3	08/06	12/21	tbd/PB	DL	3 dry		3 dry	1 dry	1 dry		3 dry		1 dry	
IV.3	1014	WEST BELT	11360	RS2	08/06	12/21	tbd/PB	DL			1 dry ^d			1 dry				
IV.3	1017	JONES RD.	11398	RS3	08/06	12/21	tbd/PB	DL			1 dry ^d			1 dry				
IV.3	1017	WATONGA	15830	RS4	08/06	12/21	tbd/PB	DL			1 dry ^d			1 dry				
IV.3	1014	SAN FELIPE ST.	11357	RS1	08/06	12/21	tbd/PB	DL			1 dry ^d			1 dry				
IV.4	1017	JONES RD.	11398	SE12	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	WEST BELT	11360	SE5	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	ELDRIDGE RD.	11363	SE2	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1017	W. T C JESTER AVE.	15828	SE15	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1017	WATONGA	15830	SE13	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	BRIAR FOREST AVE.	15846	SE6	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1017	HEIGHTS BLVD.	11387	SE17	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	DAIRY ASHFORD RD.	11362	SE3	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	SAN FELIPE ST.	11357	SE8	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	WILCREST DR.	11361	SE4	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1017	W. 43RD ST.	15829	SE16	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	VOSS RD.	11356	SE10	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	SHEPHERD DR.	11351	SE9	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	PINEY POINT RD.	11358	SE7	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1017	ELLA BLVD.	11391	SE14	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	BARKER DAM	11142	SE1	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1017	W.TIDWELL AVE.	15831	SE18	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	1014	SAN JACINTO AVE.	15842	SE11	09/03	12/21	tbd/UH	DL			1 dry							1 dry
IV.4	tbd	tbd		SE20	09/03	12/21	tbd/UH	DL			1 dry			1				1 dry
IV.4	tbd	tbd		SE19	09/03	12/21	tbd/UH	DL			1 dry							1 dry


tbd = to be determined


b Wet chemistry analyses include DO, pH, turbidity, conductivity, and PO4--P


c Two samples taken during the same day (one in the morning and the other at midday) for the first sampling round. If levels are high, then it may be monitored a second time











Appendix C. Field Data Reporting Form

FIELD DATA SHEETS FECAL PATHOGENS STUDY

Project	Name/Lo	cation										
Job Nui	mber											
Sample												
(signature Date	Time	Station ID/ Sample ID	Location	DO	pН	Temp.	Flow	Flow Severity ¹	Residual chlorine	NH ₃ -N	PO ₄ -P	Observations ²
ĺ										ĺ		

¹ 1-no flow, 2-low, 3-normal, 4-flood, 5-high, 6-dry
² Water appeareance, weather, biological activity, stream uses, unusual odors, specific sample information, missing parameters, days since last significant rainfall, and flow severity if applicable.

Appendix D. Chain-of-Custody Form

University of Houston 4800 Calhoun Road, Room N107D Houston, Texas 77204-4003

(713)743-4271

CHAIN OF CUSTODY RECORD

Project Name:					# of containers		Ar	nalyses Re	quired		Sample ID	
Station ID	Date	Time (24hr)	Matrix	Description		FC	EC	тос	TSS	CBOD ₅		
Collected by: (signature)			Date:	Time:	Received by: (signature)		Date:	Time:		Laborator	y remarks:	
Relinquished by (signature)	7 :		Date:	Time:	Received by: (signature)		Date:	Time:				
Relinquished by (signature)	7:		Date:	Time:	Received by: (signature)		Date:	Time:		Lab log #		
Relinquished by (signature)	':		Date:	Time:	Received by: (signature)		Date:	Time:		Laborator	y Name:	

Appendix E. Data Management Plan

Personnel

Andrew Sullivan is responsible for managing this project for the TNRCC. He will be responsible for receiving the data and database review checklist from Monica Suarez of the University of Houston, reviewing the database review checklist for completeness, and conveying the data in the required format.

Dr. Hanadi Rifai is responsible for managing the project for the University of Houston. She is responsible for ensuring that data is managed by the University of Houston and its subcontractors according to this data management plan and QAPP.

Dr. Paul Jensen is responsible for managing the water quality data for PBS&J and ensuring that the data comply with this QAPP. He will submit the evaluated data to the University of Houston.

Adrienne Boer is responsible for reviewing the water quality data from University of Houston/ PBS&J and the laboratories, performing all quality control checks on the data, converting the data to the required format, archiving the data, backing up the data, and transferring the data to Andrew Sullivan of the TNRCC.

The University of Houston/North Water District Laboratory Services Laboratory Managers are responsible for ensuring that the data resulting from laboratory analyses for this project is managed according to the lab QMPs and this QAPP.

David Sullivan is responsible for receiving the project data from Andrew Sullivan, performing automated data quality diagnostic checks, and adding the data to the TNRCC database.

Systems Design – Data will be entered into, stored in, and transmitted between personal computers operating on Microsoft Windows 95/98/NT, and using common commercially-available software. QuattroPro 6.01, Microsoft Access 97, or Corel Paradox 8 will be used as databases, and data files created by these software programs will be transmitted between computers via e-mail. The TNRCC database hardware and software are described elsewhere and available from the TNRCC Data Manager.

Data Dictionary

Tag_id	A7	This field is the key between the event and results tables and is 7 characters long.
_		The first character(s) is the prefix code for the submitting agency.
Station	A9	This is a combination of the segment_id and the sequence of a site within a
		segment Stationid A5 This is a unique id that identifies each sampling station. This
		number is generated by the TNRCC.
Enddate	A10	The date the sample was collected in the form of MM/DD/YYYY
Endtime	A5	The time the sample was collected in military format (HH:MM)
Enddepth	A6	This is the depth in meters at which the sample was collected.
Startdate	A10	This field is only required for composite samples and is the beginning date in the
		form of MM/DD/YYYY

Page 72

		Page 72
Starttime	A5	This field is only required for composite samples and is the beginning time (in military format) at which the sample was collected (HH:MM)
Startdepth	A6	This field is only required for composite samples and is the depth nearest surface (in meters) at which the sample was collected.
Category	A1	This field is only required for composite samples and should correspond to the following codes: T is for time composites S is for space composites (i.e.depth) B is for both space and time composites F is for flow weighted composites
Calculatn	A1	This field is no longer used and should be left blank
Type	A2	This field is only required for composite samples and should correspond to the
		following codes: CN for continuous ## where ## is the number of grabs in the composite GB where the number of grabs is unknown
Comment	A135	This is a text field where record of any observational data is included with the sample
Source1	A2	The TNRCC assigned code for the submitting agency.
Source2	A2	An optional field that may be used to further identify the sample
Program	A2	A field that further identifies the sample. This field may be used to tie targeted monitoring to specific permits.
STORET code	e A5	This is a five digit code which identifies the substance or measurement.
Gtlt	A1	If the value is above the detection limit then this field should contain an . If the value is below the detection limit then this field should contain an <.
Value	A8	This is the test result and should be reported in units according to the storet description

The following table outlines the codes that will be used when submitting data under this QAPP.

Name of Monitoring Entity			
	Source Code 1	Source Code 2	Program Code
University of Houston	U of H	UH	DL
PBS&J	PBS&J	PB	DL

Note: Source codes need to be obtained prior to submission of data.

STORET codes for data collected under this project include the following:

00094 CONDUCTIVITY (MS/CM)

00010	TEMPERATURE (DEGREE CELSIUS)
00061	FLOW (CFS)
00300	DISSOLVED OXYGEN (MG/L)
00400	pH (pH UNITS)
00530	RESIDUE, TOTAL NONFILTRABLE (MG/L)
00671	ORTHOPHOSPHOROUS (MG/L)
00680	TOTAL ORGANIC CARBON (MG/L)
01351	FLOW: 1=NO FLOW, 2=LOW, 3=NORMAL, 4=FLOOD, 5=HIGH, 6=D
31616	FECAL COLIFORM, MEMBR FILTER, M-FC BROTH (#/100 ML)
31699	E. COLI, IDEXX COLILERT (MPN/100ML)
31702	E. COLI, BOTTOM DEPOSITS (CFU/100 G)
82079	TURBIDITY (NTU)
80082	5 DAY CARBONACEOUS BIOCHEMICAL OXYGEN DEMAND (MG/L)
50060	CHLORINE, TOTAL RESIDUAL (MG/L)

Data Management Plan Implementation – Implementation of the data management plan is displayed graphically on Figure 8. Field data will be recorded on field data reporting forms, then conveyed to Monica Suarez, who will enter them into a database file. All values in the electronic file will be compared to the paper forms after entry. Field data forms will be maintained at the University of Houston for five years.

The results of TSS, CBOD₅, TOC, FC, and EC tests at the University of Houston/ North Water District Laboratory Services will be provided on paper forms, then entered into an electronic database file by Monica Suarez. After this operation, each value in the database is compared to the value on paper for accuracy.

If any calculations are made, at least 10% will be checked by hand for accuracy. Monica Suarez will convert the electronic file to Corel Paradox format for the TNRCC, and following manual accuracy checks, archive copies of each file to CD-ROM format. The Corel Paradox data file, along with a database review checklist, will be then transferred to the TNRCC Project Manager by e-mail. After approving the database review checklist, the TNRCC Project manager will convey the file to the TNRCC Data Manager. The TNRCC Data Manager will run the TNRCC automated screening procedure on the file to check for errors and outliers, then forward the results to the TNRCC Project Manager. Upon approval of the TNRCC Project Manager, the TNRCC Data Manager will add this data to the TNRCC TRACS database.

Quality Assurance/Control - See Section D of this QAPP.

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QAPP

Revision No. 4


Appendix E

Page 74

Backup/Disaster Recovery – Data files stored on the network servers at the University of Houston, PBS&J, North Water District Laboratory Services, and TNRCC computer systems are routinely backed up. After a summary report is produced at the University of Houston, it will then be saved to a CD-ROM for distribution and archive at the University of Houston offices. Copies of the field data reporting forms and laboratory paper records will be maintained, at the University of Houston and the North Water District Laboratory Services, respectively, for a period of five years as additional insurance against data loss.

Archives/Data Retention - Complete original data sets are archived on permanent media (zip disk or CD-ROM) and retained on-site by the University of Houston for a retention period specified in the original QAPP approved by the TNRCC Project Manager.

Figure 8. Data Management Plan



Appendix F

Page 76

Appendix F. Monitoring Systems Review Checklist

This checklist is part of the QA/QC and should be used by the University of Houston/PBS&J QAO when performing monitoring systems audits in order to assure compliance with this QAPP. This checklist applies to field sampling, handling and measurement, and data management as they relate to the bacteria TMDL project.

Field Sampling			
		Ö, x, or N/A	
A.	Are collection techniques consistent with SOPs and QAPP?		
B.	Is field documentation complete?		
C.	Were field QC samples collected for all analytes required in this QAPP?		
D.	Was the chain of custody properly filled out?		
E.	Were the samples properly identified?		
F.	Were the samples properly preserved and transported?		
. .			
Labora	tory Systems		
A.	Are analysis techniques consistent with SOPs and QAPP?		
B.	Is laboratory documentation complete?		
C.	Were holding times verified?		
D.	Were the samples properly handled and stored?		
Data M	[anagement		
A.	Are field paper records properly maintained?		
B.	Are laboratory logbooks properly filled out?		
C.	Were data entered to database in required format?		
D.	Were valid STORED codes used?		
E.	Were digitized data compared to paper records?		
F.	Were checks on correctness of analysis or data reasonableness performed?		
Ö =	Yes		

TMDL for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou QA	PP
Revision No	o. 3
Appendix	x F
Page	77

QAO Signature: Date:			
Comments (attach README.TXT file if applicable):			
Date Range:			
Date Submitted to TNRCC:			
necessary):			

Appendix G. Database Review Checklist

This checklist is part of the QA/QC and should be used by the TMDL University of Houston/PBS&J database managers and other entities handling the monitoring data in order to review data processing methods before submittal to the TNRCC. This checklist applies to data collected under a quality assurance project plan and is confined to only those items, which the data manager routinely reviews.

Field Data Review

 $\ddot{0}$, x, or N/A

- A. QC samples (field duplicates) collected for all analytes as prescribed in the TNRCC SWQM Procedures Manual?
- D. Are field duplicate and blank results acceptable?
- E. _Are field QC results attached to this review?
- D. Field documentation includes the following:
 - (1) Identification of individual(s) collecting sample(s)?
 - (2) Sample ID number and site location?
 - (3) Sample collection date, depth, and time?
 - (4) Site observations (i.e. weather, unusual flow, etc)?
 - (5) Unusual occurrences that may affect water quality?
 - (6) Sample collection problems?
- G. Chain of custody record properly filled out and available for review?

Data Format and Structure

- A. Are there any duplicate *Tag Id* numbers?
- B. Are the *Tag* prefixes correct?
- C. Are all *Tag Id* numbers 7 characters?
- D. Are TNRCC station location (SLOC) numbers assigned?
- E. Are sampling *Dates* in the correct format, DD/MM/YYYY?
- F. Is the sample *Depth* greater than 0.3 meters?
- G. Is the *Comment* field filled in where appropriate?
- H. Source Code 1, 2 and Program Code used correctly?
- I. Is the sampling date in the *Results* file the same as the one in the *Events* file?
- J. Values represented by a valid parameter (STORET) code with the correct units?
- K. Are there any duplicate measurements for the same *Tag* and *STORET*?
- L. Are there any invalid symbols in the Greater Than/Less than (GT/LT) field?
- M. Are there any measurements in the *Results* file that are not in the *Events* file?
- N. Is the sampling *Time* based on the 24 hour clock (e.g. 13:04)?
- $\ddot{\mathbf{0}} = \mathbf{Yes}$ $\mathbf{x} = \mathbf{No}$ $\mathbf{N/A} = \mathbf{Not}$ applicable

Appendix G

Page 79

DATABASE REVIEW CHECKLIST (cont'd)

Data Quality Review			Ö, x, or N /A
A. B. C. D. E.	Checks on correctness of For FC densities the values reported Have at least 10% of the For FC densities the	ose in the QAPP?	
$\ddot{0} = \mathbf{\tilde{0}}$	Ves $\mathbf{x} = \mathbf{No}$	N/A = Not applicable	
Explain ar	y answers that may indica	ate a problem with the data (attach another page if necessary):	
Date Subr	nitted to TNRCC:		
TAG Serie	es:		
Date Rang	e:		
Data Sour	ce:		
Comment	s (attach README.TXT	file if applicable):	
Data Ma	nager Signature:	Date:	

Appendix H. I	Example letter to document sub-tier participant adherence to the QAPP
TO:	(name) (lead organization)
FROM:	Hanadi Rifai University of Houston
RE: QAPP for	Total Maximum Daily Loads for Fecal Pathogens in Buffalo Bayou and Whitoak Bayou
Please sign and	return this form by (date) to:
	onmental Engineering Rd., Room N107D 7204-4003
the QAPP desc	receipt of the QAPP for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou. I understand ribes quality assurance, quality control, and other technical activities that I must implement to lts of work performed will satisfy stated performance criteria.
Signature	Date

APPENDIX E

SLIDES PRESENTED AT STAKEHOLDER MEETINGS

Technical Presentation at January 25, 2001 Meeting

Total Maximum Daily Load for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou

University of Houston PBS&J

What is a TMDI?

"A TMDL is the total amount of a pollutant a water body can assimilate and still meet state water quality standards." (TNRCC, 1999)

TMDL Allocation Components

- Identify problem
- Identify water quality target
- Evaluate watershed and water quality conditions
- Assess pollutant sources (point, non-point, natural background)
- · Allocate pollutant loads

TMDL Implementation Plan Components

- Description of pollution control actions
- Development of schedule for implementation of pollution control actions
- Assurances of load allocation goal achievement
- Determination of legal authority
- · Formulation of follow-up plan
- Definition of measurable outcomes to evaluate plan implementation

The 303(d) List

Water bodies identified as impaired or threatened are compiled into the 303(d) list, named after the relevant section of the Clean Water Act (CWA). Currently, this list is developed and submitted to EPA.

303(d) List for Relevant Water Bodies


Buffalo
Bayou


Average mercury exceeds human health criterion for saltwater fish
Bacteria levels exceed contact recreation levels
Mean copper concentrations do not support aquatic life
Whiteoak
Bayou


Bacteria levels exceed contact recreation levels
Mean lead concentrations do not support aquatic life


Major tasks


- Stakeholder/Public education and involvement
- Assess current levels and trends of bacterial indicators of fecal pathogens in the bayous
- Assess major sources, transport, and fate of bacterial indicators of fecal contamination
- Apply models to elucidate the sources and major processes controlling observed levels of FC
- Develop a QAPP for additional data collection
































92-1999 FC Data at High-Flow			
	# data	Geomean (cfu/dL)	Stdev. Log data
Buffalo Bayou	(Q>1,000 cfs)		
Main stem	298	997	0.84
Tributaries	94	2,997	1.05
Whiteoak Bayo	u (Q>300 cfs)	
Main stem	67	9,711	0.63
Tributaries	47	36,372	0.67







FC Self-Reporting Data in Buffalo and Whiteoak Bayous Buffalo Bayou Maximum Average 1998 10 7 Whiteoak Bayou Maximum Average 437 22

19992000


Buffalo Bayou		
<u>Maximum</u>	Average	
10	7	
40	15	
2	2	


Whiteoak Bayou		
<u>Maximum</u>	<u>Average</u>	
437	22	
154	28	
211	54	


Daily Maximum (cfu/dL)
Source: EPA PCS Database


Point Source Fecal Coliform Load


Avg. conc. Avg. conc. **Estimated** minor major Bayou PS load dischargers dischargers (cfu/yr) (cfu/dL) (cfu/dL) 3.26x10¹⁴ 2,114 Buffalo 2 Whiteoak 2,114 54 2.14x10¹⁴ Major dischargers Q>1 MGD














Summary of Findings

- Nine potential sources
- Runoff dominates in wet weather and contributes during smaller rains
- Point sources dominate dry weather flow with disinfection uncertain
- Sewer leaks exist but flow is small
- More data and modeling needed for quantitative understanding

Future Monitoring Efforts

- Point Sources-AM & PM sampling
- Stormsewers-Check for dry weather flow and sample
- Smaller runoff events
- Bacteria dynamics
 - rates of change day-night
 - effects of sediment and organic levels
 - regrowth tests

Key Points and Issues

- Complexity--Bacteria levels are affected by several sources and processes; a model is required to analyze
- Model and data should develop together
- Water Quality Target needs to be addressedlevels in runoff far too high for contact recreation so what flow level is appropriate target?


Technical Presentation at March 8, 2001 Meeting


Total Maximum Daily Load for Fecal Pathogens in Buffalo Bayou and Whiteoak Bayou


University of Houston PBS&J


Maior tasks


- Stakeholder/Public education and involvement
- Assess current levels and trends of bacterial indicators of fecal pathogens in the bayous
- Assess major sources, transport, and fate of bacterial indicators of fecal contamination
- Apply models to elucidate the sources and major processes controlling observed levels of FC
- Develop a QAPP for additional data collection























Concentration dynamics in the Bayous

- Regrowth
- Rates of change
- •Resupply from stream sediments

Modeling task

HSPF selected because it models:

- •Build-up and washoff of water quality constituents in the watershed.
- Quality routing by means of advection and mixing
- •In-stream first-order decay (and regrowth)
- Scour and deposition of sediments

Model data needs

- precipitation and meteorological data
- watershed land use/land cover characteristics
- hydrography and channel characterization
- quality data

